SOLICITATION NUMBER: GS-04P-15-EW-D-0088

SERVICE: BUILDING OPERATIONS & MAINTENANCE AND JANITORIAL & RELATED SERVICES

LOCATIONS:

Alto Lee Adams Sr, US Courthouse (FL0030ZZ) O&M Only
101 South US Highway 1
Fort Pierce, FL 34950 111,306
rsf

Claude Pepper Federal Building (FL0061ZZ) O&M Only
51 SW 1St Ave
Miami, FL 33130
259427 rsf

Brickell Plaza Federal Building (FL0079ZZ) O&M Only
909 SE 1st AVE
Miami, FL 33130
145440 rsf

US Courthouse (FL0089ZZ) O&M Only
299 E Broward Blvd
Ft Lauderdale, FL 33301
169093 rsf

James L King Federal Justice Building (FL1021ZZ) O&M Only
99 NE 4th St
Miami, FL 33130
264768 rsf

Sydney M. Arnovitz U.S. Courthouse (FL0019ZZ) O&M, Janitorial, Landscape
301 Simonton St.
Key West, FL 33040 53248 rsf

PERIOD OF PERFORMANCE: Base Year of 1 Feb 2016 – 31 Jan 2017 with potential for four one-year option periods.

SOLICITATION ISSUE DATE: June 9, 2015

Amendment 1: June 10, 2015, inclusion of missing pages
Amendment 2: July 10, 2015, changes to Past Performance Criteria
Amendment 3: July 16, 2015, Responses to Questions
Amendment 4: July 20, 2015, Postpone RFP

Amendment 5: September 23, 2015, Revised Statement of Work dated August 25, 2015

OFFER RECEIPT DATE and TIME: October 7, 2015, 2015 4:00 p.m. EST

SOLICITATION TABLE OF CONTENTS

(Sections A through M)

A. SOLICITATION/CONTRACT FORM

A.1. STANDARD FORMS

B. SERVICES, ORDERING AND PRICES

B.1. DESCRIPTION OF SERVICES
B.2. BID/OFFER/BASIC SERVICES BENCHMARK DATA
B.3. ALTERNATE BID/OFFER FOR ADDITIONAL SERVICES
B.4. PRICING OF OPTIONS FOR CONTRACT SERVICES

C. DESCRIPTION/SPECIFICATION/STATEMENT OF WORK

INTRODUCTION
C.1. SCOPE OF WORK
C.1.1 The Contractor Shall:
C.1.2 The Contractor Shall:
C.1.3 Excluded from this scope are:
~~*C.1.4 Items Typically Subcontracted*~~
C.2. DEFINITIONS
C.2.1 Acceptance
C.2.2 Above Standard Services
C.2.3 Acts Of God
C.2.4 Additional Services
C.2.5 Advance Meters
C.2.6 Advance Metering Systems
C.2.7 Approval
C.2.8 Architectural and Structural
C.2.9 Basic Services
C.2.10 Building
C.2.11 Building Automation System (BAS)
C.2.12 Building Operating Plan RESERVED
C.2.13 Commissioning RESERVED
C.2.14 Commissioning (Ongoing) RESERVED
C.2. 15 Computerized Maintenance Management System (CMMS)
C.2.16 Consumable Parts
C.2.17 Contracting Officer (CO)
C.2.18 Contracting Officer Representative (COR)
C.2.19 Contract Award Date
C.2.20 Contract Services Start Date
C.2.21 Contract Phase-in/ Transition Period
C.2.22 Contractor
C.2.23 Contractor's Hours Other Than Normal Working/Duty Hours
C.2.24 Controls and Control System
C.2.25 Critical Equipment
C.2.26 Defective Services
C.2.27 Emergency
C.2.28 Emergency Callback
C.2.29 Environmentally Sustainable
C.2.30 Existing Deficiency List Report
C.2.31 Exterior

C.2.32 Federal Holidays
C.2.33 Federal Executive Holiday, Unanticipated
C.2.34 Fire Protection and Life Safety Systems
C.2.35 GSALink RESERVED
C.2.36 Guiding Principles for Sustainable Existing Buildings
C.2.37 GSA Green Purchasing Program (GPP)
C.2.38 Government Furnished Equipment (GFE)
C.2.39 Indefinite Quantity
C.2.40 Maintenance Repair
C.2.41 Miscellaneous Work
C.2.42 Modification of Contract
C.2.43 Negligence
C.2.44 Non Agency Specific Equipment
C.2.45 Non-Reimbursable Repair
C.2.46 Normal Working Hours
C.2.47 Occupant Emergency Plan (OEP)
C.2.48 Open System
C.2.49 Operations
C.2.50 Overtime Services
C.2.51 Performance Based Contracting
C.2.52 Performance Work Statement (PWS)
C.2.53 Phase in
C.2.54 Phase out Transition Period
C.2.55 Predictive Maintenance
C.2.56 Preventive Maintenance (Scheduled and Unscheduled)
C.2.57 Product Preference
C.2.58 Quality Assurance Surveillance Plan (QASP)
C.2.59 Quality Control Plan
C.2.60 Repair
C.2.61 Reimbursable Repair
C.2.62 Sequence of Operations
C.2.63 Service Request
C.2.64 Standard Services
C.2.65 Stewardship
C.2.66 Supervisor, On-site
C.2.67 Technical Proposal
C.2.68 Tour
C.2.69 Vertical Transportation Systems
C.2.70 Watch
C.3. REFERENCES
C.4. EXISTING DEFICIENCY INSPECTION/INITIAL DEFICIENCY LIST
C.4.1 Initial Inspection
C.4.2 Initial Deficiency List
C.5. STARTUP PHASE/TRANSITION PHASE
C.5.1 Transition Phase Startup
C.5.2 Start up Work Schedule
C.5.3 Adjustments and Corrections
C.6. PHASEOUT TRANSITION PERIOD
C.7. PUNCH LIST COMPLETION AND WITHHOLDING OF FINAL PAYMENT
C.8. GENERAL AND ADMINISTRATIVE REQUIREMENTS
C.8.1 Minimum Staffing and Ability to Contact and Communicate with the CO
C.8.2 Contractor Communication Equipment
C.8.3 Onsite Records

C.8.4 Service Request and Administrative Support
C.8.5 Use of CMMS
C.8.6 Quality Control Program
C.8.7 Government Quality Assurance Program
C.8.7.1 Contract Performance
C.8.7.2 Methods
C.8.7.3 Records and Files
C.8.7.4 Cooperation – Inspections
C.8.7.5 Contractor Performance Assessment Reporting System (CPARS)
C.9. BUILDING OPERATING PLAN RESERVED
C.9.1 Building Operating Plan
C.9.2 Components of the Building Operating Plan (BOP)
C.10. EQUIPMENT INVENTORY
C.10.1 Occupant Agency Program Equipment
C.11. MONTHLY PROGRESS REPORTS
C.12. PERFORMANCE EVALUATION AND REVIEW
C.12.1 General:
C.12.2 GSA/Contractor Meetings:
C.12.3. GSA/Contractor/Tenant Meetings:
C.13. EQUIPMENT CONDITION ASSESSMENT
C.14. OCCUPANT FEEDBACK PROGRAM
C.15. REFERENCE LIBRARY
C.16. REVIEW OF DESIGN DOCUMENTS
C.17. BUILDING MANAGEMENT SUPPORT SERVICES (MISCELLANEOUS HOURS)
C.18. INSPECTION ASSISTANCE FOR SPACE BUILDOUTS
C.19. EMERGENCY SHUTDOWN INSTRUCTIONS AND TOUR CHECKLISTS RESERVED
C.20. LABELING OF ELECTRICAL CIRCUITS
C.21. OPERATIONAL REQUIREMENTS
C.21.1 General
C.21.2 Extended Operating HoursRESERVED
C.21.3 Continuity Of Operations (Coop)
C.21.4 Emergency Operating Plan
C.21.5 Tenant Environment
C.21.6 Energy and Water Efficiency
C.21.7 Contact After Normal Hours
C.21.8 Normal Tenant Working Hours
C.21.9 Building Information
C.22. SYSTEM PERFORMANCE STANDARDS OR PROCEDURES
C.22.1 Smart Buildings
C22.2 Integrated Building Systems
C.23. SERVICE REQUEST
C.23.1 General
C.23.2 Emergency Service Request
C.23.3 Emergency Call Back (after hours)
C.23.4 Urgent Service Request Response
C.23.5 Routine Service Request Response
C.23.6 Overtime Services
C.24. TOURS
C.24.1 General
C.24.2 Operating Logs and Tour Check Sheets
C.24.3 Tour Frequencies
C.24.4 Condensate Drip Pans
C.24.5 Monitoring Of Central Plant Equipment

C.25. Demand Response Programs
C.26. Curtailment
C.27. BAS Alarm Response (ALL buildings in this contract)
C.28 Advance Metering Program (AMP)(FL0061ZZ, FL0079ZZ, FL0089ZZ, FL1021ZZ)
C.28.1 Verification and Calibration
C.29. Protection And Damage
C.30. Negligence
C.31. Key Control
C.31.1 Locksmith Services
C.32. Disruptive Or Hazardous Tools
C.33. Disruption To Utilities, Lighting, Or Space Conditioning
C.34. Plumbing and Restrooms
C.35. Maintenance Program
C.35.1 General
C.35.2 Maintenance Standard
C.35.3 Application of Diagnostic Software
C.35.4 BAS Control Systems
C.35.5 Smart Building Technology
C.35.6 Ongoing Commissioning /Re-Tuning RESERVED
C.36. Water Treatment
C.36.1 General
C.36.2 Tolerances
C.36.3 Initial Report and Development of Program
C.36.4 Cooling Tower Management Plan
C.36.5 Corrosion Monitoring
C.36.5 Monthly Testing
C.37. Diesel Fuel, Oil Analysis And Oil Changes
C.37.1 Periodic Oil Analysis
C.37.2 Oil and Refrigerant Additives
C.37.3 Generator Oil
C.37.4 Diesel Fuels
C.38. Lamps And Ballasts
C.39. Architectural And Structural Systems Maintenance
C.39.1 General
C.39.2 Maintenance and Repair
C.39.3 Repair and Replacement Work
C.39.4 Painting
C.39.5 Interior Signage and Directories RESERVED
C.39.6 Finishes Maintenance
C.39.7 Historic Building Preservation
C.39.8 Vertical Transportation and Associated Elevator Equipment
C.39.9 Flag Procedures
C.40. Repairs
C.40.1 General
C.40.2 Non-Reimbursable Repairs
C.40.3 Reimbursable Repairs
C.40.4 Miscellaneous Work RESERVED
C.40.5 Repair Shared Liability Example:
C.40.6 Approval of Work
C.40.7 Invoicing
C.40.8 Ordering Repairs from Outside Source
C.40.9 Force Majeure (Uncontrollable Events)
C.40.10 Warranties

C.40.11 Quality of Materials and Replacement Parts

C.41. SAFETY AND ENVIRONMENTAL MANAGEMENT

C.41.1 General
C.41.2 Scheduling and Recordkeeping
C.41.3 Refrigerants
C.41.3.1 Control and Certification
C.41.3.2 Certified Handlers
C.41.4 AIR QUALITY MANAGEMENT DISTRICT (AQMD) Operating Permits
C.41.5 Fuel Storage Tanks
C.41.5.1 Underground and Above Ground Storage Tanks
C.41.5.2 Underground/Above Ground Storage Tanks
C.41.5.3 Who Needs to be Trained
C.41.6 Solid Waste Audit RESERVED
C.41.7 Polychlorinated Biphenyl (PCB) Control RESERVED
C.41.8 Facility Hazards
C.41.8.1 Hazardous Waste
C.41.9 Workplace Safety
C.41.10 Electrical Safety
C.41.11 Fall Protection
C.41.12 Powered Platforms
C.41.13 Lockout/Tagout
C.41.14 Confined Spaces
C.41.15 Asbestos Management
C.41.16 Hazardous Materials
C.41.16.1 MSDS
C.41.16.2 Disposition of Hazardous Waste
C.41.16.3 Environmental Report
C.41.16.4 Recycled Content Product Purchase Annual Reporting
C.41.16.5 Non-Bio-based Products
C.41.16.6 Bio-Based Products
C.41.17 Boiler/Pressure Vessel Operation and Inspection Standards
C.41.17.1 Boiler Operation and Inspections
C.41.17.2 Inspections and Tests
C.41.17.3 Backflow Prevention Devices
C.41.17.4 Potable Water Systems
C.41.18 Labeling and Signage
C.41.19 Roof Anchorage Points

C.42. FIRE PROTECTION AND LIFE SAFETY EQUIPMENT AND SYSTEMS

C.42.1 General
C.42.2 Fire Alarm System Services
C.42.3 Fire Alarm System Testing
C.42.4 Fire Alarm System Maintenance
C.42.5 Fire Alarm System Central Station Monitoring
C.42.6 Water-Based Fire Suppression Systems
C.42.7 Fire Doors and Other Opening Protective
C.42.8 Fire and Combination Fire/Smoke Dampers
C.42.9 Smoke Doors and Other Opening Protective
C.42.10 Smoke Dampers
C.42.11 Portable Fire Extinguishers
C.42.12 Non-Water-Based Fire Extinguishing Systems
C.42.13 Smoke Control Systems
C.42.14 Emergency and Standby Power Systems
C.42.15 Emergency Lighting Systems and Exit Signage

C.43. MAINTENANCE AND REPAIR OF VERTICAL TRANSPORTATION SYSTEMS
C.44 RESERVED
C.45. CUSTODIAL PROGRAM
C.45.1.Objectives and Scope
C.45.2. Cleaning Hours:
C.45.3. Building Information Data Sheet Estimates:
C.45.4. The Contractor Shall
C.45.5. Green Cleaning
C.45.5.1. Green Reporting
C.45.6. LEED EB RESERVED
C.45.7. Standard Services
C.45.7.1. Interior
C.45.7.2. Performance Standards
C.45.7.3. Floor Care
C.45.7.4. Bare Floors
C.45.7.5. Carpet and Rugs RESERVED
C.45.7.6. Floor Mats and Runners
C.45.7.7. Restrooms, Shower Rooms, Locker Rooms, and Holding Cells
C.45.7.8. Fixtures
C.45.7.10. Walls
C.45.7.11. High Cleaning
C.45.7.12. Dusting
C.45.7.13. Trash, Wastebaskets, and Ash Receptacles
C.45.7.14. Recyclables
C.45.7.15. Elevator, Escalators, and Stairways
C.45.7.16. Plate Glass
C.45.7.17. Window Washing RESERVED
C.45.7.18. Blinds and Coverings (Not including Drapes, Curtains, and Unique Coverings) RESERVED
C.45.7.19. Policing
C.45.7.20. Interior and Atrium Plants (Government Plants) RESERVED
C.45.7.21. Concessions
C.45.7.22. Postal Space RESERVED
C.45.7.23. Fitness Centers, Health Units, and Laboratories (RESERVED)
C.45.8. Exterior
C.45.8.1. Performance Standards
C.45.8.2. Plate Glass
C.45.8.3. Window Washing RESERVED
C.45.8.4. Canopies
C.45.8.5. Hard Surface Areas
C.45.8.6. Ash Receptacles and Trash Containers
C.45.8.7. Surfaces (signs, vending machines, tables, etc.)
C.45.8.8. Parking Structures, Parking Lot(s), and Dock Areas
C.45.8.9. Graffiti Removal RESERVED
C.45.8.10. Excrement Removal (Human, avian and rodent) RESERVED
C.45.8.11. Policing Outside Areas
C.45.8.12. Snow and Ice Removal RESERVED
C.45.8.13. Grounds Maintenance
C.45.8.13.1. Landscape Waste Management RESERVED
C.45.8.13.2. Grounds Maintenance Services
C.45.8.13.3. Composting RESERVED
C.45.8.13.4. Trees and Shrubs
C.45.8.13.5. Mulching
C.45.8.13.6. Mowing and Edging

C.45.8.13.7. Leaf Removal
C.45.8.13.8. Over Seeding, Dethatching, and Plugging RESERVED
C.45.8.13.9. Fertilization
C.45.8.13.10. Flowerbeds and Plants
C.45.8.13.11. Soil and Ground Cover
C.45.8.13.12. Unimproved Grounds RESERVED
C.45.8.13.13. Fence Lines RESERVED
C.45.8.13.14. Weeds
C.45.8.13.15. Irrigation
C.45.8.13.16. Watering
C.45.8.13.17. Adjust, Clean, and Set Automatic Controllers RESERVED
C.45.8.13.18. Integrated Pest Management Plan
C.45.8.13.19. Plant Replacements
C.45.9. Above Standard Services
Services with Quality Standards
C.45.9.1. Carpet Extraction (Public & Private Areas)
C.45.9.2. Window Washing
C.45.9.3. Blinds and Coverings (Not Including Drapes, Curtains, and Unique Coverings)
C.45.9.4. Pressure Washing and Steam Cleaning
C.45.9.5. Tree Thinning
C.45.9.6. Government Furnished Trees and Plants (Planted in Ground or Planters) RESERVED
C.45.9.7. Snow and Ice Removal for Areas Requiring Chemicals & Tools and Heavy Equipment
C.45.9.8 Excrement Removal (Human, avian and rodent)
C.45.9.9 Graffiti Removal
C.45.9.10 Composting
C.45.9.11 Trees and Shrubs
C.45.10. Service Calls
C.45.14. Trash and Solid Waste Disposal and Removal
C.45.14.1. Extent of Work
C.45.14.2. Solid Waste Records and Reports
C.45.15. Recycling
C.45.15.1. Extent of Work
C.45.15.2. Recyclable Materials Disposition
C.45.15.3. Recycling Containers
C.45.15.4. Recyclables
C.45.15.4.1. The Contractor Shall
C.45.15.4.2. Restriction on Use
C.45.15.4.3. Recycling Proceeds RESERVED
C.45.15.4.4. Recycling Records and Reports
C.45.16. Integrated Pest Management
C.45.16.1. Preventive Pest Maintenance
C.45.16.2. Initial Pest Assessment
C.45.16.3 RESERVED
C.45.16.4. General
C.45.16.5. Pest Included and Excluded
C.45.16.5. Pest Control Plan
C.45.16.6. Pesticide Application
C.45.16.7. Structural and Procedural Recommendations
C.45.16.8.Record Keeping
C.45.16.9.Manner and Time to Conduct Service
C.45.16.10. Insect Control
C.45.16.11 Rodent Control
C.45.16.12. Safety and Health

C.45.17 Child care Center RESERVED
C.45.18 Cleaning Schedules

D. PACKAGING & MARKING

D.1. PAYMENT OF POSTAGE AND FEES
D.2. MARKING

E. INSPECTION & ACCEPTANCE

E.1. THE ROLE OF GOVERNMENT PERSONNEL AND RESPONSIBILITY FOR CONTRACT ADMINISTRATION
E.1.1 Contractor Responsibility
E.1.2 Contracting Officer
E.1.3 Contracting Officer's Representatives
E.1.4 Government Quality Assurance
E.1.5 Occupant Complaint Program
E.1.6 FAR 52.246-4 Inspection of Services-Fixed-Price (Aug 1996).
E.1.7 FAR 52.246-16 Responsibility for Supplies (APR 1984).
E.1.8 Failure to Perform

F. DELIVERIES OR PERFORMANCE

F.1 PLACE OF PERFORMANCE
F.2. TERM OF CONTRACT
F.2.1 Term of the Contract
F.2.2 Option to Extend the Term of the Contract
F.3. REPORTING REQUIREMENTS
F.3.1 Plans, Schedules and Report Format Submission Requirements
F.3.2 Other Reports

G. CONTRACT ADMINISTRATION DATA

G.1. PAYMENTS
G.2. UNEXPECTED BUILDING CLOSURE
G.3. WITHHOLDING MONIES FOR NON-SUBMISSION OF WORK SCHEDULES
G.4. WITHHOLDING MONIES FOR NON-SUBMISSION OF REPORTS
G.5. APPLICATION OF CRITERIA FOR DEDUCTIONS (NON-PERFORMANCE
G.6. REDUCTION AND ADDITION OF SPACE
G.7. ADDITIONS AND DELETIONS OF BUILDINGS

H. SPECIAL CONTRACT REQUIREMENTS

H.1. SECURITY
H.1.1 GSAM 552.237-71 QUALIFICATIONS OF EMPLOYEES (MAY 1989)
H-1.2.SUITABILITY DETERMINATIONS
H-1.3. COMPLIANCE WITH SECURITY REQUIREMENTS
H.1.4. Suitability Determinations
H.1.5. Compliance with Security Requirements
H.1.6.Standards of Conduct
H.2. IDENTIFICATION CREDENTIAL
H.3. ESCORT REQUIREMENTS
H.4. STANDARDS OF CONDUCT
H.5. REMOVAL FROM CONTRACT WORK
H.6. SENSITIVE BUT UNCLASSIFIED (SBU) BUILDING INFORMATION
H.7. RECORDING PRESENCE
H.8. GOVERNMENT FORMS
H.9. OTHER CONTRACTORS
H.10. ORDINANCES, TAXES, PERMITS, AND LICENSES

H.11. Discrepancy In The Specifications
H.12. Affirmative Procurement Program (APP)
H.12.1 Standards
H.12.2 Reporting
H.12.3 Recycle Content Certification
H.12.4 Green Cleaning Training
H.13. Asbestos Awareness Training
H.14. Uniforms
H.15. Personnel Qualifications For Mechanical Personnel
H.15.1 Personnel Training
H.15.2 Qualifications of Project Manager and Onsite Supervisory Personnel
H.15.3 Qualifications of Technicians
H.15.4 Submission of Resumes for New Employees
H.15.5 State Licensing
H.15.6 Compliance with Federal, State, and Local Codes
H.16. Personnel Qualifications For Custodial Personnel
H.16.1 Training
H.16.1.1 Blood Borne Pathogens
H.16.2 Qualifications of Supervisory Employees
H.16.3 Qualifications of Contractor Personnel
H.17. Furnished Materials
H.17.1 Government-Furnished Materials
H.17.1.1 Use of Government Information Technology
H.17.2 Contractor-Furnished Materials
H.18. Additional Services [Indefinite Quantity Provisions]
H.18.1 General
H.18.2 Price Proposal for Additional Services Work
H.18.3 Pricing
H.18.4 Parts and Materials
H.18.5. Labor
H.18.6 Subcontracts
H.18.6.1 Mark-up Agreement for Architectural/Structure and Maintenance Repair
H.18.7 Cost Documentation
H.18.8 Competitive Bids
H.18.9 Method of Ordering
H.19.Award Fee Reserved
H.20. Strike Contingency Plan (SCP)
H.21. Occupancy Emergency Plan (OEP)
H.22. Contractor Pandemic Plan
H.23. Subcontracting
H.24. Conservation
H.25. LEED-EB

I. Contract Clauses

J. List of Attachments (List of documents, exhibits and Other Attachments)

J.1. Quality Assurance Surveillance Plan (QASP)
J.1.1. Contract Deliverables Reference
J.2. Green Purchase Report
J.3. Solid Waste Audits
J.4. Summary of Environmentally Preferable Product Attributes
J.5. Building Information Sheets
J.6. Monthly Report Template
J.7. Building Operating Plan Template

J.8. SMART BUILDING RESERVED
J.9. WATER TREATMENT STANDARDS
J.10. ENERGY & WATER OPERATIONAL PERFORMANCE TARGETS
J.11. ENERGY & WATER EFFICIENCY USE PLAN RESERVED
J.12. ENERGY AND WATER EFFICIENCY MONTHLY REPORT RESERVED
J.13. ANNUAL ENERGY AND WATER EFFICIENCY REPORT RESERVED
J.14. QUALIFICATIONS OF ELECTRICAL TESTING TECHNICIANS (FTT)
J.15. MISCELLANEOUS BEST PRACTICES
J.16. EQUIPMENT INVENTORY/CMMS
J.17. PREVENTIVE MAINTENANCE SCHEDULE
J.18. SOLID WASTE AND RECYCLING REPORT
J.19. ELEVATOR TOUR LOG RESERVED
J.20. UNDERGROUND STORAGE TANK (UST/AST)
J.21. ON-BOARDING AND OFF-BOARDING CONTRACT EMPLOYEES REQUIRING ACCESS TO GSA IT SYSTEMS PROCEDURES – CONTRACTOR INFORMATION WORKSHEET (CIW)
J.22. CUSTODIAL SURVEILLANCE FORMS
J.23. BUILDING EXTERIOR AND HARDSCAPE PLAN
J.24. EROSION SEDIMENT CONTROL
J.25. WAGE DETERMINATIONS

K. REPRESENTATIONS, CERTIFICATIONS, AND OTHER STATEMENTS OF BIDDERS/OFFERERS

L. INSTRUCTIONS FOR SUBMITTING PROPOSAL

L.1 52.204-7 SYSTEM FOR AWARD MANAGEMENT (JUL 2013)
L.2 52.215-1 INSTRUCTIONS TO OFFERORS--COMPETITIVE ACQUISITION (JAN 2004)
L.3 52.222-24 PREAWARD ON-SITE EQUAL OPPORTUNITY COMPLIANCE EVALUATION (FEB 1999)
L.4 52.237-1 SITE VISIT (APR 1984)
L.5 52.216-1 TYPE OF CONTRACT (APR 1984)
L.6 52.233-2 SERVICE OF PROTEST (SEP 2006)
L.7 52.252-1 SOLICITATION PROVISIONS INCORPORATED BY REFERENCE (FEB 1998)
L.8 552.252-5 AUTHORIZED DEVIATIONS IN PROVISIONS (DEVIATION FAR 52.252-5) (SEP 1999)
L.9 INSPECTION OF FACILITY
L.10. INSTRUCTIONS FOR SUBMITTING PROPOSAL
L.11. CONTENTS OF TECHNICAL PROPOSAL
L.11.1 Minimum Performance Standard
L.11. 2 MANAGEMENT APPROACH
L.11. 3 PAST PERFORMANCE
L.12. INFORMATION TO BE INCLUDED IN PRICE PROPOSAL
L.12.1 General
L.12.2 Specific Instructions For Price Proposal
L.13. NOTICE TO JOINT VENTURES
L.14. SERVICE CLASSIFICATION AND SIZE STANDARD
L.15. OFFERORS INTERESTED IN MORE THAN ONE PROPOSAL
L.16. PREPARATION, RECEIPT AND OPENING OF PROPOSAL
L.17. SMALL BUSINESS ASSISTANCE
L.18. MINIMUM PERFORMANCE STANDARDS
APPENDIX I

M. EVALUATION FACTORS FOR AWARD

M.1. FAR 52.217-5 EVALUATION OF OPTIONS (JUL 1990)
M.2. FAR 52.232-15 PROGRESS PAYMENTS NOT INCLUDED (APR 1984)
M.3. UNBALANCED OFFERS

M.4. FACTORS FOR AWARD

A. Basis of Award

B. Lowest Price Technically Acceptable Evaluation Process

C. Technical Factors

M.5. FORMULA FOR EVALUATING – PRICE PROPOSALS

M.6. PRICE EVALUATION FACTORS

A.**A.**

SOLICITATION/CONTRACT FORM

A.1. STANDARD FORMS

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. Contract ID Code	Page of Pages	
	1	15

2. AMENDMENT MODIFICATION NO.	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. (if applicable)
005	SEP 23, 2015	4PMOM-14-0016	

6. ISSUED BY	CODE	7. ADMINISTERED BY (If other than item 6)	CODE
GSA ,PBS, ACQUISITION DIVISION SERVICES BRANCH (4PQS) 77 FORSYTH STREET, ROOM T8 ATLANTA GA 30303	EW000		

8. NAME AND ADDRESS OF CONTRACTOR (NO., Street, Country, State and ZIP Code)	(x)	9A. AMENDMENT OF SOLICITATION NO.
	X	GS-04P-15-EW-D-0088
		9B. DATED (SEE ITEM 11) JUN 09, 2015
		10A. MODIFICATION OF CONTRACT/ORDER NO.
		10B. DATED (SEE ITEM 13)
CODE / FACILITY CODE		

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in item 14. The hour and date specified for receipt of offers ☒ is extended, ☐ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing items 8 and 15, and returning __1__ copies of amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OR OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment your desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

See Schedule

13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

Check One	
	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor ☐ is not, ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible)

See Attachment Page.

Except as provided herein, all terms and conditions of the document referenced in item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)	16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)

15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
_____ (Signature of person authorized to sign)		_____ (Signature of Contracting Officer)	

The purpose of Amendment 005 is to re-establish Solicitation GS-04P-15-EW-D-0088 as well as Amendments 001, 002, 003, and 004.

Amendment 005 hereby incorporates the following:

1. All previous statements of work are hereby rescinded. Statement of Work dated August 25, 2015, is hereby incorporated. All revisions are indicated in the Statement of Work by yellow highlighting and/or strikethroughs.
2. The period of performance is hereby changed to:
   Base Period: 1 Feb 2016 – 31 Jan 2017
   Option I: 1 Feb 2017 – 31 Jan 2018
   Option II: 1 Feb 2018 – 31 Jan 2019
   Option III: 1 Feb 2019 – 31 Jan 2020
   Option IV: 1 Feb 2020 – 31 Jan 2021
3. Wage Determinations are hereby updated with the following:
   a. WD 2005-2111 Rev 17 dated July 8, 2015
   b. WD 2005-2119 Rev 17 dated July 8, 2015
4. Due date for proposals is extended to 4:00 pm Eastern on October 7, 2015. All previous proposals ***WILL NOT BE EVALUATED FOR AWARD***. All interested offerors are to submit revised proposals based on Statement of Work dated August 25, 2015.

Amendments 001, 002,003,004 and 005 are to be signed and a copy returned with your offer.

ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME.

SCHEDULE Continued

ITEM NO.	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
	Provide O&M, Janitorial and Landscaping services to the FB-CT Key West Florida - Bldg # FL0019ZZ. Provide O&M services for buildings FL0061ZZ, FL0079ZZ, FL1021ZZ, FL0089ZZ and FL0030ZZ.				
0001	O&M Services FL0019ZZ SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2016 to 01/31/2017	**12.00**	MO		
0002	Janitorial FL0019ZZ SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2016 to 01/31/2017	**12.00**	MO		
0003	O&M services for the US Courthouse Ft. Pierce Florida Building # FL0030ZZ. SHIP TO: New Fort Pierce Federal Courthouse 101 South U.S. Highway 1 FT PIERCE FL 34950 Period of Performance: 02/01/2016 to 01/31/2017	**12.00**	MO		
0004	O&M Services for the Claude Pepper FB FL0061ZZ. SHIP TO: 51 SW FIRST AVENUE MIAMI FL 33130-1608 Period of Performance: 02/01/2016 to 01/31/2017	**12.00**	MO		
0005	O&M Services for the Brickell FB FL0079ZZ SHIP TO: 909 SE FIRST AVE. MIAMI FL 33131-3030 Period of Performance: 02/01/2016 to 01/31/2017	**12.00**	MO		
0006	O&M Services for FB/CT FT. LAUDERDALE, FL0089ZZ SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2016 to 01/31/2017	**12.00**	MO		
0007	O&M Services for the James King FB FL1021ZZ SHIP TO: 99 NE FOURTH ST MIAMI FL 33132-2131 Period of Performance: 02/01/2016 to 01/31/2017	**12.00**	MO		
0008	Hourly rate for Overtime services SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE	**0.00**	HR		

SCHEDULE Continued

ITEM NO.	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
	SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2016 to 01/31/2017				
0009	Hourly rate for Miscellaneous Labor SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2016 to 01/31/2017	**0.00**	HR		
0010	Hourly rate for Emergency Call Back SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2016 to 01/31/2017	**0.00**	HR		
0011	Hourly rate for Architectural Structural Repairs SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2016 to 01/31/2017	**0.00**	HR		
0012	Additional Services: Janitor SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2016 to 01/31/2017	**0.00**	HR		
0013	Overtime Services: Janitor SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2016 to 01/31/2017	**0.00**	HR		
0014	Provide overhead/fee percentage for work performed by the prime contractor only. SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2016 to 01/31/2017	**0.00**	%		
0015	Provide a Profit percentage for additional services for work performed by the prime contractor only. SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423	**0.00**	%		

SCHEDULE Continued

ITEM NO.	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
	MIAMI FL 33130 Period of Performance: 02/01/2016 to 01/31/2017				
0016	Provide a Subcontractor Oversight Fee Percentage for additional services for work performed by a subcontractor only. SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2016 to 01/31/2017	**0.00**	%		
0017	Provide a per square foot price for Carpet Cleaning Services for FL0019ZZ. SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2016 to 01/31/2017	**0.00**	SF		
1001	O&M Services FL0019ZZ SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2017 to 01/31/2018	**12.00**	MO		OPT
1002	Janitorial FL0019ZZ SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2017 to 01/31/2018	**12.00**	MO		OPT
1003	O&M services for the US Courthouse Ft. Pierce Florida Building # FL0030ZZ. SHIP TO: New Fort Pierce Federal Courthouse 101 South U.S. Highway 1 FT PIERCE FL 34950 Period of Performance: 02/01/2017 to 01/31/2018	**12.00**	MO		OPT
1004	O&M Services for the Claude Pepper FB FL0061ZZ. SHIP TO: 51 SW FIRST AVENUE MIAMI FL 33130-1608 Period of Performance: 02/01/2017 to 01/31/2018	**12.00**	MO		OPT
1005	O&M Services for the Brickell FB FL0079ZZ SHIP TO: 909 SE FIRST AVE. MIAMI FL 33131-3030	**12.00**	MO		OPT

SCHEDULE Continued

ITEM NO.	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
	Period of Performance: 02/01/2017 to 01/31/2018				
1006	O&M Services for FB/CT FT. LAUDERDALE, FL0089ZZ SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2017 to 01/31/2018	**12.00**	MO		OPT
1007	O&M Services for the James King FB FL1021ZZ SHIP TO: 99 NE FOURTH ST MIAMI FL 33132-2131 Period of Performance: 02/01/2017 to 01/31/2018	**12.00**	MO		OPT
1008	Hourly rate for Overtime services SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2017 to 01/31/2018	**0.00**	HR		OPT
1009	Hourly rate for Miscellaneous Labor SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2017 to 01/31/2018	**0.00**	HR		OPT
1010	Hourly rate for Emergency Call Back SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2017 to 01/31/2018	**0.00**	HR		OPT
1011	Hourly rate for Architectural Structural Repairs SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2017 to 01/31/2018	**0.00**	HR		OPT
1012	Additional Services: Janitor	**0.00**	HR		OPT

SCHEDULE Continued

ITEM NO.	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
	SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2017 to 01/31/2018				
1013	Overtime Services: Janitor SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2017 to 01/31/2018	**0.00**	HR	_____	OPT _____
1014	Provide overhead/fee percentage for work performed by the prime contractor only. SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2017 to 01/31/2018	**0.00**	%	_____	OPT _____
1015	Provide a Profit percentage for additional services for work performed by the prime contractor only. SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2017 to 01/31/2018	**0.00**	%	_____	OPT _____
1016	Provide a Subcontractor Oversight Fee Percentage for additional services for work performed by a subcontractor only. SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2017 to 01/31/2018	**0.00**	%	_____	OPT _____
1017	Provide a per square foot price for Carpet Cleaning Services for FL0019ZZ SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2017 to 01/31/2018	**0.00**	SF	_____	OPT _____
2001	O&M Services FL0019ZZ SHIP TO: 301 SIMONTON ST.	**12.00**	MO	_____	OPT _____

SCHEDULE Continued

ITEM NO.	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
	KEY WEST FL 33040-6890 Period of Performance: 02/01/2018 to 01/31/2019				
2002	Janitorial FL0019ZZ SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2018 to 01/31/2019	**12.00**	MO		OPT
2003	O&M services for the US Courthouse Ft. Pierce Florida Building # FL0030ZZ. SHIP TO: New Fort Pierce Federal Courthouse 101 South U.S. Highway 1 FT PIERCE FL 34950 Period of Performance: 02/01/2018 to 01/31/2019	**12.00**	MO		OPT
2004	O&M Services for the Claude Pepper FB FL0061ZZ. SHIP TO: 51 SW FIRST AVENUE MIAMI FL 33130-1608 Period of Performance: 02/01/2018 to 01/31/2019	**12.00**	MO		OPT
2005	O&M Services for the Brickell FB FL0079ZZ SHIP TO: 909 SE FIRST AVE. MIAMI FL 33131-3030 Period of Performance: 02/01/2018 to 01/31/2019	**12.00**	MO		OPT
2006	O&M Services for FB/CT FT. LAUDERDALE, FL0089ZZ SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2018 to 01/31/2019	**12.00**	MO		OPT
2007	O&M Services for the James King FB FL1021ZZ SHIP TO: 99 NE FOURTH ST MIAMI FL 33132-2131 Period of Performance: 02/01/2018 to 01/31/2019	**12.00**	MO		OPT
2008	Hourly rate for Overtime services SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130	**0.00**	HR		OPT

SCHEDULE Continued

ITEM NO.	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
	Period of Performance: 02/01/2018 to 01/31/2019				
2009	Hourly rate for Miscellaneous Labor SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2018 to 01/31/2019	**0.00**	HR		OPT
2010	Hourly rate for Emergency Call Back SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2018 to 01/31/2019	**0.00**	HR		OPT
2011	Hourly rate for Architectural Structural Repairs SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2018 to 01/31/2019	**0.00**	HR		OPT
2012	Additional Services: Janitor SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2018 to 01/31/2019	**0.00**	HR		OPT
2013	Overtime Services: Janitor SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2018 to 01/31/2019	**0.00**	HR		OPT
2014	Provide overhead/fee percentage for work performed by the prime contractor only. SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2018 to 01/31/2019	**0.00**	%		OPT
2015	Provide a Profit percentage for additional services for work performed by the prime contractor only. SHIP TO:	**0.00**	%		OPT

SCHEDULE Continued

ITEM NO.	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
	MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2018 to 01/31/2019				
2016	Provide a Subcontractor Oversight Fee Percentage for additional services for work performed by a subcontractor only. SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2018 to 01/31/2019	**0.00**	%	_____	OPT _____
2017	Provide a per square foot price for Carpet Cleaning Services for FL0019ZZ SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2018 to 01/31/2019	**0.00**	SF	_____	OPT _____
3001	O&M Services FL0019ZZ SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2019 to 01/31/2020	**12.00**	MO	_____	OPT _____
3002	Janitorial FL0019ZZ SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2019 to 01/31/2020	**12.00**	MO	_____	OPT _____
3003	O&M services for the US Courthouse Ft. Pierce Florida Building # FL0030ZZ. SHIP TO: New Fort Pierce Federal Courthouse 101 South U.S. Highway 1 FT PIERCE FL 34950 Period of Performance: 02/01/2019 to 01/31/2020	**12.00**	MO	_____	OPT _____
3004	O&M Services for the Claude Pepper FB FL0061ZZ. SHIP TO: 51 SW FIRST AVENUE MIAMI FL 33130-1608 Period of Performance: 02/01/2019 to 01/31/2020	**12.00**	MO	_____	OPT _____
					OPT

SCHEDULE Continued

ITEM NO.	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
3005	O&M Services for the Brickell FB FL0079ZZ SHIP TO: 909 SE FIRST AVE. MIAMI FL 33131-3030 Period of Performance: 02/01/2019 to 01/31/2020	**12.00**	MO		
3006	O&M Services for FB/CT FT. LAUDERDALE, FL0089ZZ SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2019 to 01/31/2020	**12.00**	MO		OPT
3007	O&M Services for the James King FB FL1021ZZ SHIP TO: 99 NE FOURTH ST MIAMI FL 33132-2131 Period of Performance: 02/01/2019 to 01/31/2020	**12.00**	MO		OPT
3008	Hourly rate for Overtime services SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2019 to 01/31/2020	**0.00**	HR		OPT
3009	Hourly rate for Miscellaneous Labor SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2019 to 01/31/2020	**0.00**	HR		OPT
3010	Hourly rate for Emergency Call Back SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2019 to 01/31/2020	**0.00**	HR		OPT
3011	Hourly rate for Architectural Structural Repairs SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423	**0.00**	HR		OPT

SCHEDULE Continued

ITEM NO.	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
	MIAMI FL 33130 Period of Performance: 02/01/2019 to 01/31/2020				
3012	Additional Services: Janitor SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2019 to 01/31/2020	**0.00**	HR		OPT
3013	Overtime Services: Janitor SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2019 to 01/31/2020	**0.00**	HR		OPT
3014	Provide overhead/fee percentage for work performed by the prime contractor only. SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2019 to 01/31/2020	**0.00**	%		OPT
3015	Provide a profit percentage for additional services for work performed by prime contractor only. SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2019 to 01/31/2020	**0.00**	%		OPT
3016	Provide a Subcontractor Oversight Fee Percentage for additional services for work performed by a subcontractor only. SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2019 to 01/31/2020	**0.00**	%		OPT
3017	Provide a per square foot price for Carpet Cleaning Services for FL0019ZZ SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2019 to 01/31/2020	**0.00**	SF		OPT

SCHEDULE Continued

ITEM NO.	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
4001	O&M Services FL0019ZZ SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2020 to 01/31/2021	**12.00**	MO		OPT
4002	Janitorial FL0019ZZ SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2020 to 01/31/2021	**12.00**	MO		OPT
4003	O&M services for the US Courthouse Ft. Pierce Florida Building # FL0030ZZ. SHIP TO: New Fort Pierce Federal Courthouse 101 South U.S. Highway 1 FT PIERCE FL 34950 Period of Performance: 02/01/2020 to 01/31/2021	**12.00**	MO		OPT
4004	O&M Services for the Claude Pepper FB FL0061ZZ. SHIP TO: 51 SW FIRST AVENUE MIAMI FL 33130-1608 Period of Performance: 02/01/2020 to 01/31/2021	**12.00**	MO		OPT
4005	O&M Services for the Brickell FB FL0079ZZ SHIP TO: 909 SE FIRST AVE. MIAMI FL 33131-3030 Period of Performance: 02/01/2020 to 01/31/2021	**12.00**	MO		OPT
4006	O&M Services for FB/CT FT. LAUDERDALE, FL0089ZZ SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2020 to 01/31/2021	**12.00**	MO		OPT
4007	O&M Services for the James King FB FL1021ZZ SHIP TO: 99 NE FOURTH ST MIAMI FL 33132-2131 Period of Performance: 02/01/2020 to 01/31/2021	**12.00**	MO		OPT
4008	Hourly rate for Overtime services	**0.00**	HR		OPT

SCHEDULE Continued

ITEM NO.	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
	SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2020 to 01/31/2021				
4009	Hourly rate for Miscellaneous Labor SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2020 to 01/31/2021	**0.00**	HR		OPT
4010	Hourly rate for Emergency Call Back SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2020 to 01/31/2021	**0.00**	HR		OPT
4011	Hourly rate for Architectural Structural Repairs SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2020 to 01/31/2021	**0.00**	HR		OPT
4012	Overtime Services: Janitor SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2020 to 01/31/2021	**0.00**	HR		OPT
4013	Additional Services: Janitor SHIP TO: 301 SIMONTON ST. KEY WEST FL 33040-6890 Period of Performance: 02/01/2020 to 01/31/2021	**0.00**	HR		OPT
4014	Provide overhead/fee percentage for work performed by the prime contractor only. SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2020 to 01/31/2021	**0.00**	%		OPT

SCHEDULE Continued

ITEM NO.	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
4015	Provide a Profit percentage for additional services for work performed by the prime contractor only. SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2020 to 01/31/2021	**0.00**	%		OPT
4016	Provide a Subcontractor Oversight Fee Percentage for additional services for work performed by a subcontractor only. SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2020 to 01/31/2021	**0.00**	%		OPT
4017	Provide a per square foot price for Carpet Cleaning Services for FL0019ZZ SHIP TO: MIAMI SERVICE CENTER 51 SW FIRST AVENUE SUITE 423 MIAMI FL 33130 Period of Performance: 02/01/2020 to 01/31/2021	**0.00**	SF		OPT

B. SERVICES, ORDERING AND PRICES

This solicitation contains a work statement for a performance-based service. This means that the Government has described WHAT is to be accomplished, not HOW to accomplish it, and states a basis for determining whether finished work meets the Government quality requirements. It does not state detailed procedures for accomplishing the work unless there are safety, security or communication requirements.

It is the responsibility of the contractor to ensure that their bid/proposal/offer price reflects the costs associated with their proposed plans, schedules and programs in their technical proposal as **the technical proposal including staffing will be incorporated and made a part of any resulting contract.**

The contractor will be required to maintain a quality control program to ensure that the requirements of this contract are met. This program shall be created for identifying and correcting deficiencies in the quality of services before the performance becomes unacceptable.

B.1. Description Of Services

The Contractor shall provide all management, supervision, labor, materials, supplies and equipment (except as otherwise provided), and shall plan, schedule, coordinate and assure effective performance of all services described herein. The Contractor will be required to provide management, operations and maintenance related services during the initial twelve (12) months of service in accordance with the requirements of this solicitation and prices for basic and alternate services.

The resultant award will contain **4** (four) twelve month Option periods, which may be exercised upon 30 days written notice to the Contractor. Evaluation of options does not obligate the government to extension of the contract term past the initial year (s) of service.

B.2. Bid/Offer/Basic Services Benchmark Data

General Services Administration will utilize the BOMA Experience Exchange Report (BEER) Benchmark Data and Regional market analysis to determine a reasonable per square foot cost for these services. https://www.bomaeer.com/BOMA/main_landing.aspx#bookmark

B.3. Alternate Bid/Offer For Additional Services

Offerors must quote a price **per man-hour** for providing additional services when ordered by the Contracting Officer (CO) in addition to the services specified as "basic services" in Section C. This additional services provision is to be used to satisfy the Government's short-term non-recurring need for service.

All orders will be confirmed by issuance of a GSA Form 300, Order for Supplies or Services. The GSA Form 300 will describe the service provided and will establish the hours of service for which the Contractor will be compensated, as per the contract.

B.4. Pricing Of Options For Contract Services

Offerors shall price the option requirements for the four (4) 12-month periods. The minimum hourly wages and fringe benefits established by the U.S. Department of Labor Wage Determination(s), Executive Order 13658 Establishing a Minimum Wage for Contractors are located in section J for your reference.

C. DESCRIPTION/SPECIFICATION/STATEMENT OF WORK

August 25, 2015

INTRODUCTION

This is a Performance Based Service Contract which focuses on the needs of the customer rather than on how the contractor meets those needs. The success of the contract depends on the satisfaction of the requirements, but also the satisfaction of our shared customer through a partnering effort between the CO or his/her designee and the contractor, Rather than a mere list of activities, this is a written expression of the GSA's expectation of the service to be performed by the contractor. A higher level of effective communication between the Government and contractor is essential for partnering and performance based service contracting to succeed. The success of this contract is shared between the Government and the contractor.

More emphasis is placed on the contractor's internal self-management of quality; not the usual external inspection by Government Inspectors, although that is a part of this contract as well. All parties should act proactively to reduce service cost; therein providing an incentive for the contractor.

The contractor, through innovation, technology, or other means, shall perform the required maintenance of these facilities by following our Guiding Principles for Sustainable Buildings:

1. Employ Integrated Assessment, Operation and Management Principles

a. In conjunction with the CO or his/her designee establish operational performance goals for energy, water, material use and recycling, and indoor environmental quality, and ensure incorporation of these goals throughout the lifecycle of this contract

b. Ensure that operating decisions are carried out with regard to sustainable operations.

c. Meet ASHRAE standards as noted throughout the SOW for thermal comfort and indoor air quality

d. Use low emitting materials for maintenance. In particular, use products that have low pollutant emissions; adhesives, sealants, and solvents.

e. Use products meeting or exceeding EPA's recycled content recommendations for building maintenance. For other products such as ceiling tiles, use materials with recycled content. For more information see EPA's Comprehensive Procurement Guideline website.

f. Use materials with the highest content level per USDA's biobased content recommendations (website) for maintenance of or use in the building.

g. Use environmentally preferable products that have a lesser or reduced effect on human health and the environment, See the Federal Green Construction Guide.

h. Provide salvage, reuse and recycling services for waste generated from building operations, maintenance, and repair and discarded equipment.

i. Eliminate the use of ozone depleting compounds where alternative environmentally preferable products are available consistent with the Clean Air Act.

II. Optimize Energy Performance – GSA is in the process of optimizing energy performance through many means and processes. Operate all equipment to optimize efficiency to reduce energy use and otherwise seek operating costs reductions wherever possible

III. Protect and Conserve Water where possible inside and outside. Metering systems may be

already installed or will be installed in government buildings to aid in reducing consumption.

Where available use EPA's Water Sense-labeled products or other water conserving products, where available.

IV. Be aware that the building(s) and management involved with this contract maybe in the process of establishing processes, instituting plans, and operational procedures to meet energy efficiency goals either through receiving an ENERGY STAR rating, LEEDS or comparable programs. The contractor will play an integral part of obtaining these goals and should be aware of the programs and processes.

V. The policy of GSA is to bring existing buildings into conformity with GSA's Strategic Sustainability Performance Plan (SSPP). The contractor should follow the guidelines set forth in J.4 regarding materials and products purchased during the performance of this contract.

VI The purpose of partnering is to adopt procedures wherein the contract and Government work together in achieving contract objectives. Partnering involves the development of a cooperative management team that seeks to identify compatible interests, and common goals and objectives.

VII. This is a fixed-price contract and while working with the Government in obtaining goals the contractor is motivated to find improved methods of performance in or to increase its profits. Results of an effective partnership should reflect a "mutual win" situation.

C.1. SCOPE OF WORK

C.1.1 The Contractor Shall:

The Contractor shall provide management, supervision, labor, materials, equipment, and supplies and shall be responsible for the efficient, effective, economical, and satisfactory operation, scheduled and unscheduled maintenance, and repair of equipment and systems located within the property line of the Alto Lee Adams Sr, US Courthouse FL0030ZZ; Claude Pepper Federal Building FL0061ZZ; Brickell Plaza Federal Building FL0079ZZ; US Courthouse FL0089ZZ; James L King Federal Justice Building FL1021ZZ; and the Sydney M. Arnovitz U.S. Courthouse FL0019ZZ to include the following:

a. Air-conditioning equipment and systems.
b. Air-handling/distribution equipment and systems.
c. Electrical systems and equipment, lighting and switchgear systems.
d. Energy management control systems (EMCS) where applicable,
e. Building Automation System (BAS) where applicable (where BAS/ ECMS systems are connected to the GSA network, the Contractor's employees will need to obtain a GSA ENT account to access systems) and heating, ventilation, exhaust systems and air conditioning (HVAC) systems and equipment.
f. Heating, ventilation, and air conditioning (HVAC) systems and equipment.
g. Plumbing and domestic water equipment and systems to include domestic water fountains and coolers, decorative ponds and exterior fountains.
h. Sanitary sewage equipment and systems.
i. Storm drainage equipment and systems - reduce storm water pollution by minimizing discharges and runoff to the storm sewer system and environment.

j. Fire protection and life safety systems and equipment including detection, notification, and communication systems as well as monitoring service, including sprinkler systems, standpipes, backflow preventors, water storage tanks, fire extinguishers, etc.
k. Special suppression systems (i.e., wet chemical, dry chemical, FM-200, Inergen, Halon, etc.)
l. All control systems that are within the scope of this Contract. All Building Automation Systems (BAS), Public Address Systems, and Computerized Lighting Systems that are within the scope of this Contract (BAS, and Computerized software maintenance is excluded).
m. Smoke control systems (i.e., building, atrium, stair pressurization, elevator ventilation, etc.)
n. Kitchen hood and exhaust systems
o. Fire doors and windows (including hinges, closers and latching hardware)
p. Non agency security system (locks, gates/arms, hydraulic bollards, keypads, card readers, cameras, magnetic locks, etc…) and its components (hardware only).
q. Architectural and structural systems, fixtures, and equipment within the site (to the property line).
r. Service request desk operations as identified in Section C.8.4 to include record keeping using a computerized maintenance management system (CMMS) if available or by other means as well as other administrative functions
s. Maintenance of landscape irrigation systems to include controllers, pumps, timers, and sprinkler nozzles.
t. Dock levelers and roll-up and sliding garage doors.
u. Parking Lots, parking lot surfaces, sidewalks and illumination.
v. DSL, Modems, and other information systems periphery used to include the communication and data lines necessary to operate the fire alarm monitoring, building automation system and web based access to CMMS.
w. Locks, keycard systems, vehicle barrier systems and static and dynamic bollard systems
x. Elevator and vertical transportation systems, including locks and keycard systems. Elevator Service (Changing of Light Bulbs/Ballast in the Elevator Cars is the responsibility of the O&M Contractor as well as Emergency Phone testing. The O&M contractor is NOT responsible for actually changing light bulbs in elevator pits and hoistways however, supplying the bulbs/ballast is required.)
y. The Contractor shall complete roofing system investigations and repairs.
z. The Contractor shall maintain and repair U.S. flag pole, lighting and pulley system.
aa. The Contractor shall maintain kitchen/concessions area drains and grease traps.
bb. The Contractor shall maintain conveying equipment, parking control equipment, and loading dock equipment.
cc. photovoltaic, Flozone, Pulspure, Ozonators

Additional services may be ordered at the discretion of the Government for work relating to the operations, maintenance and repair or upgrade of the covered facilities, but not covered in the basic services of the contract, as described in this document.

C.1.2 The Contractor Shall:

a. Be responsible to make the management and operational decisions to meet the quality standards required under this contract.
b. Use innovation, technology and other means and methods to develop and perform the most efficient services for the building.
c. Implement an effective Quality Control Plan (QCP).
d. Implement an effective service call system, as specified under the Special Requirements section of this contract that results in prompt, professional, and courteous resolution of tenant concerns.
e. Keep the Contracting Officer (CO) informed of current status of the work being performed, provide work schedules, provide a major equipment and critical system break down or impairment form, and provide other pertinent information needed by the CO .
f. Reduce the environmental impacts of work performed under this contract by using, to the maximum extent, environmentally sound practices, processes, and products.
g. Provide training to their employees that will stress stewardship in maintenance practices i.e., the proper use, disposal, recycling of chemicals, dispensing equipment and packaging. Provide documentation that their employees are completing training in the core competences and participating in continual educational training according to the Federal Building Personnel Training Act. Ensure that their employees are properly licensed and/or certified to operate necessary building systems or equipment for which licensed and/or certified personnel are required by federal, state or local law, codes or ordinances (H.15. Personnel Qualifications).
h. Federal Requirements: The Contractor shall comply with all applicable Federal, state and local laws, regulations and codes, including any supplements or revisions. The Contractor shall obtain all applicable licenses training, and permits. If a change in law or regulation requires the Contractor to implement an action that will result in an increase or decrease in Contract price, the Contractor shall implement the required action and within 30 calendar days submit to the CO a price proposal for such change. If the CO determines an equitable adjustment is substantiated a modification to the Contract will be issued.

C.1.3 Excluded from this scope are:

a. Security systems (does not include mechanical components of the door ,closers, keepers, hinges, etc)
b. Government telecommunication systems.
c. Equipment owned and operated by tenant agencies.
d. Furnishings, furniture, portable equipment, office partitions and cubicles unless specifically noted in the inventory (not installed as fixtures).
e. Paper, soap, and hand-sanitizer dispensing equipment in restrooms.
f. Kitchen appliances and equipment (NOTE: kitchen exhaust ductwork above the ceiling, grease traps with associated piping, and any fire suppression or fire alarm equipment are included in the scope).
g. Equipment owned by servicing public utilities.

h. Upgrade of software supported IT software or software licenses (to include building automation systems (BAS), security systems, advance metering systems and lighting control systems.
i. Fitness center equipment.
j. Additional services as needed by various agencies.

Additional services may be ordered at additional cost to the Government for work relating to the operations, maintenance and repair or upgrade of the covered facilities, but not covered in the basic services of the contract, as described in this document.

~~**C.1.4 Items Typically Subcontracted**~~

~~The following systems are typically subcontracted work and are recommended to be inclusive in the subcontract plan:~~

1. ~~Chillers/Chiller Controls systems~~
2. ~~Boilers/Boiler Controls Systems~~
3. ~~Diesel Generators~~
4. ~~Hydraulic and electrical Bollards, Plates, gates and security systems~~
5. ~~Fire/Life safety Systems and components~~
6. ~~Swithgear maintenance and testing~~
7. ~~Infrared Analysis~~
8. ~~Boiler and unfired pressure vessel maintenance and inspection~~
9. ~~Building Automation Systems~~
10. ~~Energy Management Systems~~
11. ~~Automatic Doors~~
12. ~~Roofing~~
13. ~~Window washing~~
14. ~~Carpet extraction~~

C.2. DEFINITIONS

C.2.1 Acceptance

"Acceptance" means an authorized representative of the Government has inspected and agreed that the work meets all requirements of this contract, to include documentation requirements.

C.2.2 Above Standard Services

Above Standard Services are services not covered in the monthly price of the contract. Contractor prices include all applicable labor, materials, supplies, equipment (except as otherwise provided), supervision, and management.

C.2.3 Acts Of God

These are unanticipated grave natural disasters or other natural phenomenon of an exceptional, inevitable, and irresistible character; the effects of which could not have been prevented or avoided by the exercise of due care or foresight.

C.2.4 Additional Services

"Additional services" are services that the Contractor will provide at an additional cost to the Government, to include all labor, supervision, supplies and materials specifically identified as

being outside the provisions of the basic services and included in the offeror's overall pricing. These services may be provided during or after normal working hours.

C.2.5 Advance Meters

Advanced meters are those that have the capability to measure and record interval data (at least hourly for electricity), and communicate the data to a remote location in a format that can be easily integrated into an advanced metering system.

C.2.6 Advance Metering Systems

A system that collects time-differentiated energy usage data from advanced meters via a network system on either an on-request or defined schedule basis. The system is capable of providing usage information on at least a daily basis and can support desired features and functionality related to energy use management, procurement, and operations, U.S. Department of Energy, EERE: Guidance for Electric Metering in Federal Buildings, (February 3, 2006).

C.2.7 Approval

"Approval" means the Government has reviewed submittals, deliverables, and administrative documents (e.g., insurance certificates, installation schedules, planned utility interruptions, etc.) and has determined the documents conform to contract requirements.

C.2.8 Architectural and Structural

"Architectural and structural" systems include all building structure, envelope, building improvements and finishes, and site improvements (e.g., paving, walkways, asphalt, etc.) to the property line.

C.2.9 Basic Services

The "basic services" of the contract consist of the recurring contract requirements for which the Contractor is paid as a base price, i.e., the requirements established by the contract statement of work and related general and administrative requirements that do not contain provisions for separate reimbursement.

C.2.10 Building

A reference to "facility" and "site" is interchangeable with "building". A man made structure or edifice which services are performed within or on the exterior of the formation and is intended to support or shelter any use or continuous occupancy.

C.2.11 Building Automation System (BAS)

The "building automation system" is a system controlling and monitoring building HVAC, and possibly other systems, to include all device, field, and global controllers; instrumentation; networking infrastructure; computers and peripherals; software; programming; database files; and licenses.

C.2.12 Building Operating Plan RESERVED

~~The "building operating plan" is a mandatory plan that the Contractor prepares for Government approval that describes the Contractor's program for operating and maintaining the building, to include both normal circumstances and contingencies.~~

C.2.13 Commissioning RESERVED

~~A practice used to optimize and verify performance of fundamental building systems.~~

C.2.14 Commissioning (Ongoing)RESERVED

~~The practice of optimizing system performance by continuing to fine-tune equipment so will result in actively preventing problems for the lifetime of the building. GSA's Ongoing Commissioning efforts will focus on maintaining the facility in the optimized state resulting from TBC and Re/Retro Commissioning efforts. GSA will achieve this through its relationship with its service providers (Operations and Maintenance/Custodial/Repair and Alterations/IT/Utilities) and the use of technology (networked systems/Advanced Meters/Smart Buildings).~~

C.2. 15 Computerized Maintenance Management System (CMMS)

A "computerized maintenance management system" is a database and application software package that automates the O&M and repairs record keeping requirements. A CMMS is designed to enhance efficiency and effectiveness of maintenance activities. Typical features include planning, scheduling and monitoring of work orders and maintenance needs.

The National CMMS (N-CMMS) is a central repository (Database) for all maintainable GSA Assets. The N-CMMS provides a mandatory, Agency-Wide means and method for processing and reporting all maintenance work done for GSA regardless of Region or Contractor.

C.2.16 Consumable Parts

"Consumable parts" or components are parts or components that customarily require regular replacement rather than repair in a maintenance program and shall be disposed of properly. Examples include oil, grease, belts, filters, ballasts, lamps, etc.

~~The Contractor is responsible for any consumables (including fuel) used during day-to-day operation of a generator, i.e., exercising the generator, testing, etc. Operation of a generator for an extended period or due to a power loss would be treated as a reimbursable expense. If the operation of the generator is caused by Contractor negligence, the Contractor shall be liable for the full cost of refueling, any other provisions notwithstanding~~

C.2.17 Contracting Officer (CO)

Contracting Officer (CO) has the overall responsibility for the administration of this contract. The CO alone, without delegation, is authorized to take actions on behalf of the Government to amend, modify or deviate from the contract terms, conditions, requirements, specifications, details and/or delivery schedules. However, the CO may delegate certain other responsibilities to authorized Government representatives.

C.2.18 Contracting Officer Representative (COR)

Contracting Officer's Representatives (COR) shall be appointed by letter from the CO. CORs will be the primary Government representatives for the administration of Contract, shall have proper training and experience in inspecting contracts, but will not have the authority to modify the contract.

C.2.19 Contract Award Date

Contract award date" as used in this document refers to the date the contracting officer signs the contract.

C.2.20 Contract Services Start Date

"Contract service start date" as used in this document refers to the first day after completion of any phase in/transition period and the performance of O&M services for the period of this contract begins.

C.2.21 Contract Phase-in/ Transition Period

"Contract phase-in/Transition Period" as used in this document refers to the first day after completion of any phase in/transition period after award and prior to performance of O&M services for the period of this contract.

C.2.22 Contractor

"Contractor" as used in this document refers to the firm awarded this contract.

C.2.23 Contractor's Hours Other Than Normal Working/Duty

Hours Hours other than those identified as Normal Working

Hours.

C.2.24 Controls and Control System

A "control system" is any low-voltage control, communication and monitoring system, including but not limited to stand alone devices, field and global controllers; instrumentation; networking infrastructure; computers and peripherals; software; programming; database files; and licenses. Examples are the BAS, Advance Metering System (AMS), and lighting control systems. Fire protection systems and security systems are excluded from this definition for purposes of this contract and are defined separately. Gateway devices and mapping software and files for data interchange between a control system and a fire protection or security system are considered part of the control system.

C.2.25 Critical Equipment

Any equipment or system used for safeguarding of life and property. Equipment needed to give adequate security to areas subject to compromise; to eliminate health, fire, or safety hazards; or to protect valuable property or equipment. Equipment used in direct support of the overall GSA mission that, if not operational, would reduce the effectiveness of GSA's ability to sustain tenants in a property; equipment that supports the property or prevents a breakdown of essential equipment operations or housekeeping functions.

C.2.26 Defective Services

A unit of service that does not conform with specified contract requirements.

C.2.27 Emergency

The term "Emergency" includes bombings, and bomb threats, civil disturbances, fires, explosions, electrical failure, loss of water pressure, building flooding, sanitary and sewer line stoppage, chemical and gas leaks, medical emergencies, hurricanes, tornadoes, floods, and earthquakes. The term does not apply to civil defense matters such as potential or actual enemy attacks.

C.2.28 Emergency Callback

An "emergency callback" is a service request or other request for service placed outside of normal working hours and of such a nature that response cannot wait for the resumption of the next day's normal working hours.

C.2.29 Environmentally Sustainable

Products or services that have a lesser or reduced effect on human health and the environment when compared with competing products or services that serve the same purpose. This comparison may consider raw materials acquisition, production, manufacturing, products and chemicals, packaging, distribution, reuse, operation, maintenance, or disposal of the product or service. Attributes of environmentally sustainable products include those that are energy efficient, water-efficient, biodegradable, environmentally preferable, non-ozone depleting, contain recycle content, non or less toxic, EPA-designated and biobased.

C.2.30 Existing Deficiency List Report

The "existing deficiency list report" or "existing deficiency list" is a list of deficiencies that may exist in the equipment and systems covered by this performance work statement, as well as the Contractor's itemized price (including, but not limited to, labor, materials, overhead, and profit) for correcting each deficiency. The purpose of this inspection shall be to discover and list in an existing deficiency list report all deficiencies that may exist in the equipment and systems covered by this performance work statement, as well as the Contractor's itemized price in accordance with the requirements of this specification for correcting each deficiency.

C.2.31 Exterior

This includes entrances; landings; steps; sidewalks; parking areas; arcades; courts; planters; lawns; irrigation systems; fountains; security bollards; gates; fences; flagpoles; building-mounted, pole, and ground lighting; etc. located adjacent to the facility extending to the legal property line.

C.2.32 Federal Holidays

"Federal holidays" for the purposes of this contract are New Year's Day, Martin Luther King Day, President's Day, Memorial Day, Independence Day, Labor Day, Columbus Day, Veterans' Day, Thanksgiving Day, and Christmas Day. When Federal holidays fall on weekends, a weekday is typically designated as the holiday. Holidays that fall on Saturday are observed on the previous Friday and holidays that fall on a Sunday are observed on the following Monday. Veterans' Day is always on the 11th of November and Thanksgiving is always the 3rd Thursday of November.

C.2.33 Federal Executive Holiday, Unanticipated

Unanticipated holidays declared by the president will count as Federal holidays. As long as the Contractor pays employees as if it were an anticipated Federal holiday, the Contractor will be paid for the unanticipated holiday as if it were a normal Federal Holiday.

C.2.34 Fire Protection and Life Safety Systems

"Fire protection and life safety systems " are systems and equipment installed in the building to (1) detect fire and products of combustion, (2) notify building occupants and emergency responders, (3) initiate smoke control and management systems (4) initiate fire suppression systems, (5) control or suppress fires and (6) facilitate or enhance emergency egress. These systems also may

communicate with other major building systems for fire and smoke control, elevator recall, and utilities control. Life safety systems and equipment includes emergency lighting, exit signage, special egress door locking arrangements, and exit stair markings.

C.2.35 GSALink

Note: The buildings contained in this contract are part of GSA Link initiative and as a result of this a separate contractor will be monitoring the BAS system and reporting anomalies to the GSA property manager who will have the O&M contractor investigate as part of the Service call requirements of the contract.

C.2.36 Guiding Principles for Sustainable Existing Buildings

A practice of using processes that is environmentally responsible and resource-efficient throughout a building's life-cycle. The goal is to minimize and offset consumption of energy, water, and other resources and to eliminate all waste and pollution in building operations and activities. The result is to reduce the environmental impact of the Federal government, which will expand and complement the building design economy, utility, durability, and comfort. The common objective is to reduce the overall impact of the building environment on human health and the natural environment by:

a. Improving energy efficiency and reductions in greenhouse gas emissions.
b. Reducing water consumption intensity.
c. Acquiring green products and services.
d. Implementing pollution prevention measure, including reduction or elimination of the use of toxic and hazardous chemicals and materials.
e. Implementing cost-effective waste prevention and recycling programs.
f. Increasing diversion of solid waste.

C.2.37 GSA Green Purchasing Program (GPP)

The GPP which includes the Green Purchasing Plan specifies requirements to promote the purchase of environmentally sustainable products and services.

C.2.38 Government Furnished Equipment (GFE)

Any required computer or server hardware (i.e. PC, laptop) and peripherals (i.e. mouse, keyboard, monitor) and/or routing and switching equipment, used to provide GSA network connectivity, must be government-furnished and must be provided by the GSA.

C.2.39 Indefinite Quantity

"Indefinite quantity" provisions permit the Government to order additional work, in addition to the basic services, and upon acceptance permit additional payment to the Contractor.

C.2.40 Maintenance Repair

Work required preventing a breakdown of a piece of equipment or system, or put equipment or systems back in service after a breakdown or failure.

C.2.41 Miscellaneous Work

"Miscellaneous work" is additional labor that is performed at the request of the agency at no additional cost to the Government (i.e., they are part of basic services). The Contractor may also have to provide consumable materials to complete the request. Miscellaneous work is treated as a

Service Call and is included in the Basic Operations and Maintenance price quoted per month on the bid sheet. During normal duty hours minor tasks related to routine, day-to-day operational requirements requested by the which will consist of, but not be limited to: making door keys; changing locks; hanging pictures, maps and bulletin boards; trimming door bases; and othersimilar functions as directed. Miscellaneous work shall be accomplished in the same time frame as routine service calls unless otherwise directed by the CO . The Contractor will be paid at the hourly rate quoted for after normal duty hours only if authorized by the CO in advance for specific activities.

C.2.42 Modification of Contract

Modification is a bilateral or unilateral change in the terms of a contract.

C.2.43 Negligence

"Negligence" is the failure to use due care under the circumstances. It is the doing of some act which a person of ordinary prudence would not have done under similar circumstances or failure to do what a person of ordinary prudence would have done under similar circumstances.

C.2.44 Non Agency Specific Equipment

Equipment owned or controlled by the tenant agency and not GSA.

C.2.45 Non-Reimbursable Repair

A "non-reimbursable repair" is a repair that is the Contractor's responsibility with no additional reimbursement from the Government.

C.2.46 Normal Working Hours

"Normal working hours" is the hours of building operations under most circumstances when all services shall be provided to all occupants.

C.2.47 Occupant Emergency Plan (OEP)

The lead agency in each building is responsible for development and enforcement of the building's "Occupant Emergency Plan" (OEP). The OEP details what the building tenants shall do in case of an emergency. The plan identifies floor wardens, shelter in place locations etc. The Contractor shall support all OEP efforts to the fullest extent possible.

C.2.48 Open System

An "open systems" solution is based on industry standard open protocols. This environment and solution is typically designed, procured, installed and maintained in a manner that provides the building owner with as many competitive configuration options as possible while maintaining the integrity of the supported manufacture system. The solution must be procured and installed so that the result delivers device level interoperability amongst different manufactures residing on a common network. In addition, the solution must be maintained with no future need for the original (installing) contractor. Additions, modifications, and retrofits can easily, without significant additional cost, be made to the system without dependence on the original installing contractor nor require substantial engineering or other technical development. Contractors shall specify Open Systems solutions where feasible and reasonably possible.

C.2.49 Operations

"Operations" is the continual process of using building equipment systems to accomplish their function, optimize building performance, and improve energy efficiency. Operations includes

analysis of requirements and systems capabilities, operating controls and control systems, responding to service requests, touring and observing equipment performance and condition,

adjusting equipment, identifying needed maintenance and repairs to equipment, and maintaining lubrication and chemical treatments, etc.

C.2.50 Overtime Services

Overtime services are the operation and maintenance services provided at times other than those defined as "normal tenant working hours".

C.2.51 Performance Based Contracting

The procurement strategy that seeks to issue technical requirements that set forth outcomes for performance instead of specific requirements on how to perform the service. This strategy shifts the risk of performance to the Contractor by allowing the Contractor to design the methods of achieving desired results as defined by the performance quality standards established by the Government.

C.2.52 Performance Work Statement (PWS)

The Performance Work Statement details the work requirement and can be referred to as the specification.

C.2.53 Phase in

“Contract Phase in” as used in this document refers to the period the contractor has to develop and submit for approval required plans, schedules and submittals prior to beginning performance of O&M services.

C.2.54 Phase out Transition Period

“Contract Phase out Transition Period” as used in this document refers to the last 30 calendar days of the performance of O&M services.

C.2.55 Predictive Maintenance

“Predictive maintenance” is a program of maintenance activities in which scheduling of maintenance derives from monitoring the operating condition, or changes in the operating condition, of equipment being maintained.

C.2.56 Preventive Maintenance (Scheduled and Unscheduled)

“Scheduled preventive maintenance” is a program of maintenance activities performed based on a fixed schedule or on equipment runtimes. “Unscheduled preventive maintenance” is all work performed including adjustments and procedures necessary to sustain the proper operation of all building equipment and systems pending a scheduled procedure.

C.2.57 Product Preference

(See Exhibit 4 Summary of Environmental Sustainable Product Attributes)

Use of “environmentally sustainable” products is mandatory for performance of this contract. As such, products identified as “environmentally sustainable” will be selected over those which do not carry such designations. The following factors should be considered when selecting products: environmental performance, cost performance, bio-based, recycled content, biodegradability, technical performance, and availability.

C.2.58 Quality Assurance Surveillance Plan (QASP)

The QASP is the Government's surveillance method of monitoring and evaluating the Contractor's performance under a Performance Based Statement of Work (PBSOW)

C.2.59 Quality Control Plan

The "quality control plan" (QCP), is the Contractor's complete written system for identifying and correcting deficiencies in the quality of services before the level of performance becomes unacceptable. Preparation of this document is the responsibility of the Contractor.

C.2.60 Repair

A "repair" is an act of restoring inoperable, dysfunctional or deteriorated equipment, systems, or material to a fully functional, non-deteriorated state. Repairs usually involve some combination of labor and replacement parts, components or materials.

C.2.61 Reimbursable Repair

A "reimbursable repair" is a repair that is reimbursable to the Contractor, in whole or in part, in accordance with the provisions in this document.

C.2.62 Sequence of Operations

A "sequence of operations" is the control logic used to operate a system normally put into effect through a control program.

C.2.63 Service Request

A "service request" is a response to a GSA, tenant, or agency request or a response to an observation that some equipment, system or material covered by the contract is inoperable, dysfunctional, deteriorated, or not within normal operating parameters, or that performance standard of the contract is not being met. A service request shall be considered as any corrected maintenance action that requires three (3) hours or less of in-house labor and no more than $200.00 in parts and materials. Service request response involves analysis of the problem and adjustment of operating or monitoring controls or other immediate corrective action. A requirement to perform a repair may result from the analysis stage of a service request. Service requests may be generated automatically from interfaces to BAS or diagnostic software.

C.2.64 Standard Services

Standard services are defined as all services that are included in the monthly price or as defined in the Contract document. Prices are to include all applicable labor, materials, supplies, training/certifications, equipment (except as otherwise provided), supervision, and management.

C.2.65 Stewardship

The act of stewardship is to take the responsibility for managing, conducting or supervising the quality, state or condition of a commercial building. A Stewardship program in addition to caring for the building, its occupants and visitors includes among other things a sense of shared responsibility, occupant participation and communications amongst building management, O&M personnel, cleaning personnel, occupants, contractors and others who have an impact on/in the building.

C.2.66 Supervisor, On-site

The term "on-site supervisor" means a person designated in writing by the Contractor who has authority to act for the contract on a day-to-day basis at the work site.

C.2.67 Technical Proposal

Technical proposal" means all documentation (regardless of the form or method of the recording) of a technical nature submitted by the contractor in response to contract requirements.

C.2.68 Tour

~~A "tour" is generally a scheduled walkthrough of equipment rooms and installations including computer rooms, restrooms, etc. by Contractor operating personnel for the purpose of ensuring that equipment is running properly, ensuring that equipment rooms are in good order and without safety hazards, and making any necessary adjustments to operating controls or to lubricate equipment. A tour may also involve a combination of such physical visits in addition to using automated systems for the monitoring of equipment and systems. Equipment log sheets are a part of the tour plan/program. All tours are "inspection" work orders in the CMMS and will comply with all work order requirements.~~

A tour may involve a combination of ~~such~~ physical visits in addition to using automated systems for the monitoring of equipment and systems. Equipment log sheets are a part of the tour plan/program. All tours are "inspection" work orders in the CMMS and will comply with all work order requirements.

C.2.69 Vertical Transportation Systems

"Vertical transportation systems" include elevators, escalators, dumbwaiters, lifts, etc.

C.2.70 Watch

A "watch" involves performing certain tasks required for the operation of the HVAC equipment (central systems over 300 tons), boilers, compressors, and related equipment in a centralized location. Watches include, but are not limited to starting equipment, checking at designated intervals all operating equipment in the area, recording readings, shifting equipment and loads, making adjustments at the central control center, taking water samples, making tests, and adding chemicals as required.

C.3. REFERENCES

The following publications are incorporated by reference as setting quality, performance, and design standards for work required in this document. Unless a specific date is provided, references are for the current edition published at the time of issue of the solicitation, to include any addenda or errata published by the issuing organization. The Contractor is responsible for obtaining all referenced documents at its expense, with the exception of the most current Public Buildings Service Operations and Maintenance Standards (most current), the Facilities Standards for the Public Buildings Service (PBS P100), and the U.S. Courts Design Guide, which will be provided by the Government.

- Public Buildings Service Operations and Maintenance Standards Dated 2012 or later
- Facilities Standards for the Public Buildings Service (PBS P100)
- U.S. Courts Design Guide

- SMACNA Sheet Metal and Air Conditioning Contractors National Association HVAC Systems Testing, Adjusting & Balancing
- AHERA Asbestos Hazard Emergency Response Act
- ASHRAE Guideline 1HVAC Commissioning Process

- ASHRAE Guideline 4 Preparation of Operating and Maintenance Documentation for Building Systems
- ANSI/ASHRAE Standard 15 Safety Code for Mechanical Refrigeration
- ANSI/ASHRAE Standard 34 Number Designation and Safety Classification of Refrigerants
- ANSI/ASHRAE Standard 55, Thermal Environmental Conditions for Human Occupancy
- ANSI/ASHRAE Standard 62, Ventilation for Acceptable Indoor Air Quality
- ANSI/ASHRAE Standard 100, Energy Conservation in Existing Buildings/Commercial
- ANSI/ASHRAE Standard 111, Practices for Measurement, Testing, Adjusting, and Balancing of Building Heating, Ventilation, Air-Conditioning, and Refrigeration Systems;
- American Society of Mechanical Engineers ASME A17.1/CSA B44, Safety Code for Elevators and Escalators
- American Society of Mechanical Engineers ASME A17.2, Inspector's Manual for Elevators
- ASME Boiler and Pressure Vessel Code
- ASME CSD-1 Control and Safety Devices of Automatically Fired Boilers
- National Board of Boiler and Pressure Vessel Inspectors, National Board Inspection Code
- OSHA 29 CFR 1910 and 29 CFR1926
- Clean Air Act
- Clean Water Act
- EPA Green Book
- EPA Purple Book
- GSA SEMS Sustainable Environmental Management System (GSA.GOV/SEMS)
- International Building Code
- International Fire Code
- International Plumbing Code
- International Mechanical Code
- NETA Maintenance Testing Specification for Electrical Power Distribution Equipment and Systems
- NFPA 10, Standard for Portable Fire Extinguishers
- NFPA 12, Standard on Carbon Dioxide Extinguishing Systems
- NFPA 12A, Standard on Halon 1301 Fire Extinguishing Systems
- NFPA 13, Standard for the Installation of Sprinkler Systems
- NFPA 14, Standard for the Installation of Standpipe and Hose Systems
- NFPA 17, Standard for Dry Chemical Extinguishing Systems
- NFPA 17A, Standard for Wet Chemical Extinguishing Systems
- NFPA 20, Standard for the Installation of Stationary Pumps for Fire Protection
- NFPA 22, Standard for Water Tanks for Private Fire Protection
- NFPA 24, Standard for the Installation of Private Fire Service Mains and Their
- Appurtenances
- NFPA 25, Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection Systems
- NFPA 70, National Electrical Code (NEC)
- NFPA 70E,Standard for Electrical Safety in the Workplace
- NFPA 72, National Fire Alarm and Signaling Code

- NFPA 85, Boiler and Combustible Systems Hazards Code
- NFPA 92, Standard for Smoke Control Systems
- NFPA 96, Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations
- NFPA 101, Life Safety Code
- NFPA 105, Standard for the Installation of Smoke Door Assemblies and Other Opening Protectives
- NFPA 110, Standard for Emergency and Standby Power Systems
- NFPA 111, Standard on Stored Electrical Energy Emergency and Standby Power Systems
- NFPA 2001, Standard on Clean Agent Fire Extinguishing Systems
- NICET (National Institute for Certification in Engineering Technologies publications and issuances
- NIOSH (National Institute for Safety and Health publications and issuances
- DOE/EE-0157, International Performance Measurement and Verification Protocol
- NEMA TP-1,National Electrical Manufacturers Association, Guide for Determining Energy Efficiency for Distribution Transformers
- NEMA MG-1. National Electrical Manufacturers Association, Motors and Generators
- NEMA Application Guide for AC Adjustable Speed Drive Systems
- ANSI/IWCA I-14.1, Window Cleaning Safety Standard
- Safe Drinking Water Act, PL 99-339, as amended
- Title 40 CFR, Part 761, PCBs in Electrical Transformers
- Title 40 CFR, 141.43, Sections A and D, Environmental Protection Agency Safe Drinking Water
- Title 40 CFR part 273, Universal Waste Rule
- ANSI/ASME A17.1 Safety Code for Elevators and Escalators
- OSHA 29 CFR 1910.1200, 29 CFR 1910.146, 29 CFR 1910.147, 29 CFR 1910.1030, 29 CFR 1910.1001, 29 CFR 1910.178
- Guideline 3-1990 and Addendum, or latest version, FAR 52.223-2, ARI Standard 700-1988, or latest edition, and Appendix A to 40, CFR, Part 82, Subpart F.
- Resource Conservation and Recovery Act
- Toxic Substances Control Act
- National Historic Preservation Act of 1966
- National Park Service Technical Preservation Services - Preservation Briefs (Entire Series) located at http://www.nps.gov/history/hps/tps/briefs/presbhom.htm
- North American Technician Excellence (N.A.T.E.) Core Service with any Service Specialty) http://www.natex.org/technicians/what-tests-to-takekates/kates-specialty-exams/
- HVAC Excellence Professional - the following three certifications : Light Commercial Air Conditioning, Gas Heat, and Green Awareness Certification http://www.hvacexcellence.org/ProfessionalLevel.aspx
- UA Star HVAC Mastery http://www.ua.org/HVACR.asp
- Public Law 94-344(Joint Resolution to Codify and Emphasize Existing Rules and Customs Pertaining to The Display and Use of The Flag of the United States Of America)
- ~~Technology Policy for PBS Owned Building Monitoring and Control Systems (https://sharepoint.pbs.gsa.gov/pbs/energyit/ESI/Library%20of%20docs%20saved%20on%20t~~

~~his%20site/ImplementationGuide/Technology%20Policy%20for%20PBS-Owned%20Buildings%20Monitoring%20and%20Control%20Systems_4.5.11.pdf)~~

- ~~Building Technologies Technical Reference Guide (https://sharepoint.pbs.gsa.gov/pbs/energyit/ESI/Library%20of%20docs%20saved%20on%20this%20site/ImplementationGuide/Building%20Technologies%20Technical%20Reference%20Guide_FINALDRAFT_6.7.11.doc~~
- Telecommunications Distribution Design Guide.
- http://www.dep.state.fl.us/waste/categories/tanks/

C.4. EXISTING DEFICIENCY INSPECTION/INITIAL DEFICIENCY LIST

The existing deficiency inspection and list is meant to identify and document all deficiencies that exist in the equipment and systems covered by this performance work statement, but that will not be repaired during routine preventative maintenance and includes the Contractor's itemized price (including, but not limited to labor, materials, overhead, and profit) for correcting each deficiency. This inspection is required to be documented in the CMMS.

C.4.1 Initial Inspection

The Contractor and the CO or his/her designee shall make a complete and systematic initial inspection together during the startup or transition phase of the contract that will include all mechanical, electrical, fire protection and life safety systems, environmental systems, including but not limited to USTs and structural storm water Best Management Practices (BMP's) (including drains, oil/water separators, etc.) and utility systems and equipment, windows, doors, and other structural features for which maintenance and repairs are covered by this performance work statement. The purpose of this inspection shall be to discover and list in an existing deficiency list report all deficiencies that may exist in the equipment and systems covered by this performance work statement, as well as the Contractor's itemized price (including, but not limited to labor, materials, overhead, and profit) for correcting each deficiency. The contractor shall not be required to provide pricing for all deficiencies found and shall provide pricing for only those items the CO or his/her designee require.

The Government may elect to have all or any part of this work performed by the Contractor (at the price or prices quoted), by Government employees, or by other Contractors. The existing deficiency list report shall not include any items that would be replaced, repaired, or adjusted during the performance of a service request or normal preventive or predictive maintenance, , including general cleaning of equipment and space.

The Contractor shall be responsible for making immediate adjustments or corrections that fall within the scope of routine preventive or predictive maintenance or routine services as defined in Section C. required by this contract at no additional cost to the Government. This includes but is not limited to making adjustments to controls; adjusting the BAS software, e.g., correcting set points; reloading programs; restoring equipment being operated manually to automatic operation (this does not include changing established sequences of operation or programming sequences); applying lubricants; cleaning fan housings, fans, coils, dampers, air handling unit (AHU) sections, and equipment rooms and replacing consumable parts or components.

The deficiency inspection shall commence on a mutually agreeable date no later than five (5) calendar days after contract start date and be completed within fourteen (14) calendar days.

C.4.2 Initial Deficiency List

The Contractor shall submit an initial deficiency list report not later than 60 days after start of the Contract to the CO . Any dispute between the Government and the Contractor as to classification of initial deficiency list report items will be resolved under the Disputes Clause in this document. The Contractor's itemized estimates for correcting each deficiency shall remain in effect for 60 calendar days after submission of the initial deficiency list report.

Deficiencies discovered after the submission of the initial deficiency list report will not be considered pre-existing for purposes of this Contract, unless equipment is operational and cannot be secured and inspected. Any piece of equipment or system that cannot be inspected shall be highlighted at the beginning of the deficiency list stating why it cannot be secured and inspected. An estimate of when the Contractor reasonably expects to be able to inspect the piece of equipment shall be provided. When an existing deficiency in an item is corrected, the Contractor shall assume full responsibility for the subsequent repair of the item as covered under the terms of this Contract at no additional cost to the Government. Nothing in this existing deficiency inspection/initial deficiency list clause shall be construed as diminishing the obligations imposed by this Contract upon the Contractor to operate any deficient item (to the extent operable) or to adjust or maintain any such item.

Any piece of equipment or system that cannot be inspected shall be highlighted at the beginning of the deficiency list stating why it cannot be secured and inspected. An estimate of when the Contractor reasonably expects to be able to inspect the piece of equipment shall be provided.

Deferring repair acceptance will be handled on a case-by-case bases during the start-up period based on previous preventative maintenance performed and conditions in previous test reports.

C.5. STARTUP PHASE/TRANSITION PHASE

C.5.1 Transition Phase Startup

~~The Contractor shall provide transition startup services within 30 calendar days prior to the Contract start date to assist transitioning between Contractors. The purpose of this phase is to permit a transition that is seamless to the tenants and to assess the condition of the building and incomplete maintenance work at the time of Contractor transition. During this period the Contractor shall complete all activities necessary to conduct all contract requirements on the Contract start date. These activities include but are not limited to the following:~~

~~a. Establish sub-contractor agreements and submit a list of Sub-contractors to the CO or his/her designee for approval.~~

~~b. Conduct interviews and hire new employees to include incumbent personnel.~~

~~c. Purchase tools, equipment, and supplies.~~

~~d. Develop a list of supplies and chemicals the contractor intends to utilize and submit MSDS sheets to the CO or his/her designee for approval. No chemicals shall be brought on the premises without prior approval.~~

~~e. Complete and submit all paperwork necessary for security clearances for employee personnel and sub-contractors as necessary.~~

~~f. Purchase employees uniforms.~~

~~g. Update equipment inventory database and startup permanent government provided CMMS. Complete the government-furnished CMMS training.~~

~~h. Update the preventive maintenance schedule. The new preventive maintenance schedule shall be based off of the last time PMs were performed.~~

~~i. Purchase necessary communication equipment (i.e. cell phones, fax machines, office phones etc...) and set-up e-mail addresses and IT support. Establish phone lines and service for fire alarm dialer.~~

The Contractor shall perform transition of this contract during the period from the date of award to the start of performance of O&M services. The purpose of this phase is to permit a transition that is seamless to the tenants and to assess the condition of the building and incomplete maintenance work at the time of Contractor transition. During this period the Contractor shall complete all activities necessary to conduct all contract requirements on the Contract start date. These activities include but are not limited to the following:

a. Establish sub-contractor agreements and submit a list of Sub-contractors to the CO or his/her designee for approval.

b. Conduct interviews and hire new employees to include incumbent personnel.

c. Purchase tools, equipment, and supplies.

d. Develop a list of supplies and chemicals the contractor intends to utilize and submit MSDS sheets to the CO or his/her designee for approval. No chemicals shall be brought on the premises without prior approval.

e. Complete and submit all paperwork necessary for security clearances for employee personnel and sub-contractors as necessary.

f. Purchase employees uniforms.

g. Complete the government-furnished CMMS training when applicable.

h. Establish a system for tracking and recording preventive maintenance (PM) actions. The government will provide the current PM schedule and all PM actions shall be based on current schedule. The PM schedule shall remain in place until such time the N-CMMS is on line.

i. Purchase necessary communication equipment (i.e. cell phones, fax machines, office phones etc...) and set-up e-mail addresses and IT support. Establish phone lines and service for fire alarm dialer.

j. Update the Quality Control plan submitted in contractor's technical proposal to a site specific plan.

k. Establish a service call system for tracking and recording service requests. The service call system shall remain in place until such time the N-CMMS is on line.

l. Develop and submit a site specific Work Place Safety Plan in accordance with the requirements of C.41.8

m. Submit a Strike Contingency Plan to the CO or his/her designee for approval.

C.5.1.2 Transition Phase Startup Implementation of Government Owned Computerized Maintenance Management System (National CMMS)

The Contractor shall transition to the NCMMS upon notification by GSA that the NCMMS is ready to proceed.

a. The contractor will perform only as an end user in the NCMMS. ALL system programming is the burden of the government.

b. The NCMMS is the system of record for the equipment/asset list, preventive maintenance schedule, and work orders. All data in the NCMMS belongs to GSA, and the government may use NCMMS for reports, quality assurance, and data calls. Additionally, Contractor shall provide reports, data, etc, when requested by the CO or his/her designee.

c. The Contractor shall provide within _180 days transition, (GO LIVE) startup services prior to the assist transitioning *to GSA's National CMMS.* The purpose of this phase is to permit a transition that is seamless to the tenants and to assess incomplete maintenance work at the time of implementation. The contractor is to provide the current schedule of maintenance and assist in creating the preventive maintenance schedule and entering data of past performance of maintenance for each piece of equipment.

d. During the transition period the Contractor shall:
(1) Validate/update NCMMS copy of equipment inventory.

(2). Within 90 days of contract start, begin Start up/Implement Government Owned CMMS. Verify and update equipment inventory for accuracy. Print and Install QR code labels Complete the government-furnished CMMS training when applicable.

(3) Utilize the incumbent preventive maintenance schedule and plan the maintenance to be

performed for the first 6 months manually while transitioning into the government owned CMMS. Implement the new preventive maintenance schedule in the NCMMS once the inventory has been downloaded . The new preventive maintenance schedule shall be based off of the last time PMs were performed.

(4) Provide preventive maintenance schedules to National CMMS team using GSA template. Cross-check PM schedules and guides used by contractor versus PM guides and schedules in NCMMS. The new periodic maintenance schedule and guides shall be based off of the last time PMs were performed and in accordance with the requirements of the contract.

(5) Complete the government-furnished 1-day (8 hour) CMMS training for CMMS administrator (1 person per contract at management level). Complete the 1 day (8 hour) CMMS training for scheduler and end user (1 person per contract). Training may be accomplished in segments over separate periods of time. Training will be initially conducted at the closest GSA office to the contract project management office of the contract.

(6) Coordinate with the Contracting Officer or his/her designee and submit CIW for ENT access to ensure all users will have access to the system in the government enterprise in keeping with para H.1.1.(b) GSAM 552.237-71 QUALIFICATIONS OF EMPLOYEES (MAY 1989) of the contract.

(7) Provide preventive maintenance schedules and history of preventive maintenance.

(8) Provide list of users who will be entering or scheduling service calls, creating reports, performing maintenance data entry, dispatching work orders, and approving actions within the CMMS.

(9) Provide cross reference on the NCMMS excel equipment inventory from contractor designated equipment naming/serial to NCMMS equipment naming/serial designation.

After GO LIVE the Contractor shall:

(GLa). Use the NCMMS to provide current contract monthly submittal requirements, such as monthly reporting and identify completion of scheduled work orders, contract reports of accomplishment of services instead of the current manual reporting where able to replace with NCMMS functions and provide to the CO .

(GLb). Audit the NCMMS inventory in an ongoing basis, and annotate in the NCMMS equipment needed to be added or changed. Provide change recommendations and make changes as directed by the implementation process and at the direction of the CO or CO's designee via the NCMMS.

(GLc). Maintain accurate equipment data in NCMMS including Equipment ID, Equipment Type, Equipment Description, Asset Identification Code, Manufacturer, Model

Number, Serial Number, Equipment Status, Building Number, and Location (including floor, room, and location description).

~~(GLd). Create and install QR coding emblems on each piece of equipment over this performance period of the following 12 months as each equipment receives a regularly scheduled preventive maintenance/test/or scheduled repair. This application requires the contractor to utilize the contractor provided printer, print, laminate and apply the code to the equipment initially and replace as needed over the term of the contract. The software web based app will be provided by the government when it becomes available.~~

C.5.2 Start up Work Schedule

Within 15 calendar days of contract award the Contractor shall submit a workschedule and staffing plan.

C.5.3 Adjustments and Corrections

The Contractor shall be responsible for making immediate adjustments or corrections that fall within the scope of routine preventive maintenance required by this Contract at no additional cost to the Government. This includes, but is not limited to: making adjustments to controls; adjusting the BAS software, e.g., correcting set points; reloading programs; restoring equipment being operated manually to automatic operation (this does not include changing established sequences of operation or programming sequences); applying lubricants; cleaning fan housings, fans, coils, dampers, air handling unit (AHU) Sections, and equipment rooms; and replacing consumable parts or components.

Not later than the end of the startup phase, the Contractor shall identify for the Government all alarm points with originating point identification information (device ID, point number, description), so that the Government, at its discretion, may arrange for automatic generation of work orders from alarm conditions.

C.6. PHASEOUT TRANSITION PERIOD

When this contract expires or is otherwise terminated, the Contractor shall cooperate with the incoming contractor during a phase-out period. For planning purposes, the Contractor shall assume a phase-out period of **one month**.

During this phase-out period, the Contractor shall:

a. Assist the CO and incoming Contractor for a seamless transition in operations and maintenance with no adverse effect on the building tenants;

b. Provide GSA and the successor Contractor with access to all records and official documentation (both hard copies and electronic as applicable) required by this Contract;
c. Provide training to the successor Contractor on methods of accessing and programming the building automation system (BAS) and other control systems; and
~~d.~~ Show the successor Contractor where all archived programs and systems literature are maintained. ~~On the last performance day of the Contract, the Contractor shall turn over to the CO all keys and identification badges or cards.~~
e. Coordinate and complete disposal, cleanup, and transfer of all materials according to applicable laws.
f. Provide all data records (database files, spreadsheets, etc.) relating to building systems, assets, work orders, permits, work activities, etc. to GSA. GSA owns all data compiled under this Contract or ancillary to this Contract.
g. On the last performance day of the contract, the Contractor shall turn over to the CO or his/her designee all keys and identification badges or cards.

It is the responsibility of the Contractor to maintain the items listed and to provide information and/or instruction to the succeeding Contractor.

(1) CURRENT BUILDING OPERATING PLAN
(2) KEY CUSTODY AND CONTROL – Key and Door List, Blank and Cut Keys
(3) BUILDING AUTOMATION AND CONTROL – Operating Procedures, System Data, Set points and Controls, and Records and Logs
(4) EQUIPMENT/BUILDING SYSTEMS – Manuals/Schematics and Blueprints
(5) MAINTENANCE MANAGEMENT DOCUMENTATION - Annual Preventive Maintenance Schedule, Inventory of Equipment, Guide Cards/History Cards, Boiler Certificates/Reports, Unfired Pressure Vessel Certificates/Reports, Water Analysis Reports
(6) MAINTENANCE REPAIRS - History of all Repairs Under Contract for Mechanical Equipment and Systems and Architectural and Structure
(7) SUBCONTRACTORS LIST - List of Sub-Contractors Used
(8) OTHER DOCUMENTATION – Any other documentation developed pertinent to the buildings under this contract
(9) TELEPHONE LINES AND NUMBERS - Monitoring of building systems shall continue without interruption. All information is to be turned over to succeeding contractor who will assume payment for the service the day the new contract begins. The incoming contractor shall coordinate with the incumbent contractor for the release of all phone lines and assist with the smooth transition of all existing services.
(10) SAFETY PLANS (Lockout/tag out, etc.)

C.7. Punch List Completion And Withholding Of Final Payment

The Government may create a deficiency list of unmet Contractual requirements at or near the time of termination of the Contract. The Government may employ the services of another Contractor in the development of the list and upon completion provide the Contractor with a copy of work not completed, to include the monetary value the Government has assigned for each item. The Government retains sole discretion over whether to charge the Contractor for the monetary value

of the list in whole or in part or to request corrections by the Contractor. If the Government elects to request corrections by the Contractor, the Contractor shall have until the end of the Contract period to perform such corrections and may invoice for funds withheld on acceptance of the corrections by the Government. Nothing in this Section shall be construed to limit the Contractor's liability or restrict the Government from reporting unsatisfactory or problematic performance by the Contactor.

NOTE: In the event the contract is extended the government reserves the right to re-perform the closeout inspection days prior to the end of the extension period.

C.8. General And Administrative Requirements

C.8.1 Minimum Staffing and Ability to Contact and Communicate with the CO

The Government has determined the MINIMUM maintenance staff levels and skill sets (Trades). These staffing levels as determined by the Government are limited to hourly full time (40 Hours per week FTE) productive employees and trades. The management staff shall be determined by the contractor. The contractor is cautioned that these levels are MINIMUM levels only and this does not limit or restrict the contractor from providing additional hourly full time or part time productive employees. The MINIMUM staffing levels are as follows:

Building 1 (FL0030ZZ) 111306rsf
1 - HVAC (Research Facility)

Building 2 (FL0061ZZ)259427rsf
2.5- HVAC (Research Facility)

Building 3 (FL0079ZZ)145440rsf
1.5 - HVAC (Research Facility)

Building 4 (FL0089ZZ)169093rsf
1.5 - HVAC (Research Facility)

Building 5 (FL1021ZZ)264768rsf
2.5 - HVAC (Research Facility)

Building 6 (FL0019ZZ) 53,000 rsf
1 - HVAC (Research Facility)
1 - Janitorial

The Contractor must provide staff to ensure services are continued without disruption to the tenant. The Contractor must ensure employees maintain communications access with the CO or his/her designee to allow contact by the Government at all times during normal working hours and to effectively communicate with Government personnel.

The Contractor must immediately notify the CO or his/her designee and other designated Government

representative of any recognized safety hazard that might severely affect the building occupants.

The onsite technicians must have sufficient skills to immediately respond to a variety of service requests involving multiple trades, including the operation of building control and energy management systems. Operators must be certified where applicable.

Outside of normal working hours, the Contractor must maintain some designated form of communication with on-call staff to allow the Government to contact such on-call staff at any time for emergency response.

The Contractor must provide staff as necessary to meet all requirements of the contract.

Personnel must be properly licensed and certified to work on building systems or equipment for which licensed and or certified personnel are required by Federal, State, or local law, codes, or ordinances.

The skill sets for the staff shall be as stipulated in the Department of Labor Service Contract Act Directory of Occupations (Fifth Edition) or as otherwise directed in this SOW.

The Contractor shall:

a. Provide the minimum qualified staff and onsite technicians to ensure services are continued without disruption to the tenant. The Contractor must be able to respond immediately to a variety of service requests involving multiple trades, including the operation, troubleshooting, and maintenance of building control and energy management systems. Technicians shall be certified and properly licensed to work on buildings systems, where applicable, in accordance with Federal, State, or Local laws, codes, or ordinances. See paragraph H.15 Personnel Qualifications for additional information.

   (1) Project Manager - The project manager is a person, designated in writing by the Contractor, who has complete authority to act for the Contractor in every detail during the term of the Contract. The Project Manager shall have the authority to accept notices of deductions, inspection reports and all other correspondence on behalf of the Contractor. The Project Manager's physical location and availability shall be approved by the CO .

   (2) Onsite Supervisor - The onsite supervisor is a person, designated in writing by the Contractor, who has complete authority to act for the Contractor on a day-to-day basis at the work site. The onsite supervisor shall have the authority to direct the workforce and the work to be accomplished under this Contract on behalf of the Contractor. The onsite supervisor's physical location shall be at the work site. When multiple shifts are required, the Contractor shall designate a minimum of one onsite supervisor for each shift. These individuals may be classed as working supervisor if so desired by the Contractor and may perform the functions of mechanic and supervisor concurrently.

b. Maintain communication with the Government during normal duty hours and after hours for emergencies. (See Section C.8.2, Communication Equipment).
c. Immediately notify the CO of any recognized safety hazard that might severely affect the building occupants.
d. Develop and submit to the within 15 calendar days after Contract award a list of key personnel and emergency contact information (which may include subcontractor contacts, as applicable).

e. Shall have all Contract employees, including subcontractor employees, sign in and out, upon entering or exiting the building using a log established at each building for security and Contract administration purposes.

C.8.2 Contractor Communication Equipment

The Contractor shall provide key operational personnel (managers, supervisors, and duty mechanics) with portable electronic means to communicate with GSA for service requests, emergencies, status of projects, etc. Electronic communication methods may include the following:

a. Text messaging device. The Contractor is responsible for all costs associated with the text messaging device. Examples are two-way pager, cell phone with text messaging, smart phones, etc. **Devices shall be capable of receiving and sending e-mail documents with attachments.**

b. Fax. Receiving and sending faxes is acceptable as a secondary communication method for locations that have problems with wireless device signal strength. However, delaying faxes because of combined usage of voice and fax on the same line is not acceptable.

c. Electronic Mail shall be established and monitored on a 24 hour basis in order to receive or communicate with the CO or his/her designee customer agency and tenant needs.

C.8.3 Onsite Records

The Contractor shall ensure that all records required by the Contract, or produced in performance of work under the Contract, are maintained in an organized manner onsite in electronic format and are made available to the Government when requested. The Contractor shall receive, maintain and gather data, as well as other materials including records and manuals, related to the support and operation of Government facilities. The Government retains ownership of all databases, information, and other materials received or developed by the Contractor in support of this Contract at all times.

C.8.4 Service Request and Administrative Support

The Contractor shall operate a service request and administrative support function during normal working hours, to act as a central point of contact for the Government and building occupants to take service requests, and track and maintain service request records in the CMMS. This includes service requests for work not under the scope of this Contract (i.e., performing a central service request desk function for the facility, regardless of who is responsible for responding to the service request).

C.8.5 Use of CMMS

GSA's goal is to use Government-furnished CMMS systems in all locations as practicable. Currently there is a project to establish a national CMMS in all regions. When this occurs the Contractor will be required to transfer all data from the CMMS system database to the Government as specified by the CO . The method and format for the transfer will be determined by the on a task by task basis. Contractor shall provide reports to the CO as requested and in a format and media as requested. Contractor shall transition (see CMMS Definitions) to the N-CMMS upon notification by GSA that the N-CMMS is ready to proceed. Contractor will have 180 days to complete this transition and begin use of the N-CMMS. Contractor will be responsible for delivering all Contractor furnished CMMS data to GSA in an electronic format compatible with GSA's N-CMMS Universal Donor Database.

C.8.6 Quality Control Program

A site-specific Quality Control Plan (QCP) shall be developed and submitted for approval to the CO 15 calendar days after contract award date prior to the start of the Contract. Upon approval, the Contractor shall implement the QCP to ensure Contract compliance, and to ensure that potential problems with building equipment and systems are identified, documented in a CMMS if applicable, and resolved prior to failure. An acceptable QCP shall include, at a minimum, inspections by onsite supervisory personnel and by one or more qualified outside parties. The contractor shall provide ~~quarterly~~ annual on-site inspections by qualified Corporate/Regional personnel not performing services at any of the facilities covered by this contract. The system of checklists, inspection methodology, and frequencies shall be documented by the Contractor and submitted to the CO after each site visit. The Contractor shall maintain a Local file of all quality control inspections conducted by the Contractor, including the corrective actions taken and submit copies of quality control inspections monthly in the Monthly Progress Report. All documentation shall be made available to the Government upon request during the term of the

Contract. The QCP shall include, at a minimum, the program of outside inspections, work orders sampling methodology, and a program for verifying compliance with each Contract requirement.

NOTE: The Quality Control plan shall be prepared by the Contractor and provided to the CO as part of the offeror's technical package for review. This Quality Control plan is not required to be site specific rather a plan and processes that the company utilizes to address all the items listed below.

The QCP is a living document and may be subject to change depending on the needs of the contract. When the QCP is revised the Contractor is required to provide an updated QCP to the CO or his/her designee for acceptance.

The QCP shall include the following, as a minimum:

A. How the Contractor will control quality of supplies and services.

B. How project management, inspections, plan implementation, process improvement changes, correction of deficiencies, and green compliance will be accomplished.

C. An inspection plan or checklist tailored to the specific building(s) being maintained and serviced under this contract. The inspection plan or checklist shall detail how services at the work site shall be inspected to ensure that the outcome of the work meets all the quality standards set forth in the Contract and shall include, but is not limited to:

- Date of inspection performed
- Location of inspection
- Description of findings
- Description of action(s) taken (if necessary)
- Signature and date of completion

D. A training program to ensure that Contractor employees are capable of successfully accomplishing all work task(s) under this contract.

E. How Contractor shall monitor deficiencies of work output in relation to the performance standards, methods of informing employees of deficiencies in their area(s) of responsibility, and a process to ensure that the deficiencies are corrected and do not reoccur.

C.8.7 Government Quality Assurance Program

The Government may inspect the Contractor using a quality assurance program through random inspections, scheduled inspections, or any other method of inspection that the Government determines reflects the actual successful performance of this Contract. As part of the Government's quality assurance program, the Government may:

a. Review and, if warranted, reject any reports or other submittals required from the Contractor.
b. Review performance and service records, including, if applicable, but not limited to monthly progress reports, BAS data, CMMS data, Advance metering System, (AMS) data and any computerized or hardcopy records maintained by the Contractor documenting performance under this Contract, and require correction of any unsatisfactory conditions noted.

c. Determine the adequacy of the Contractor's quality control program and documentation and the overall success of this program. The Government may order improvements if it determines the programs are insufficient or ineffective.
d. Obtain tenant satisfaction survey information and require improvements in service on the basis of such information to the extent such results correlate with deficiencies in Contract requirements.
e. Conduct random and routine physical inspections of facility equipment and systems, to include programs and files maintained on computers and Contractor onsite offices and work areas, and require correction of deficiencies noted.
f. Perform inspections with Government personnel or independent third party inspectors.

C.8.7.1 Contract Performance

Contractor performance will be evaluated on the basis of the performance success or deficiencies, success or failure in meeting other Contract requirements, and the Contractor's record of correcting deficiencies when noted. While corrective actions will be noted, a record of significant performance deficiencies may lead to a performance evaluation that is less than satisfactory even if the Contractor takes corrective action.

C.8.7.2 Methods

The use or nonuse of any quality assurance methods (e.g., a measurement and verification (M&V) program) by the Government will not constitute a waiver of or excuse from Contract requirements. The Government may implement or change quality assurance measures at any time during the term of the Contract.

C.8.7.3 Records and Files

All records and files that this Contract requires the Contractor to maintain shall be made readily accessible to Government representatives, including third party Contract inspectors, on request. All records and files utilized or generated during the course of the Contract by the Contractor, including all standard operating procedures and building operating plans, shall become the property of the Government (this excludes employee personnel files and company financial information).

C.8.7.4 Cooperation – Inspections

The Contractor shall instruct all onsite personnel to cooperate with the Government or third party Contract inspector requests for records access and information. This includes answering honestly and comprehensively all questions related to performance of work. The Contractor shall provide personnel to enable inspectors, including third party Contract inspectors, to perform inspections of equipment. The Contractor shall notify the CO at least 2 weeks in advance when critical equipment is to be opened and available for inspection by the Government. The Contractor shall open and operate the equipment for observation by all inspectors at no additional cost to the Government provided the Government requests the service at least 48 hours in advance. Most inspections will be performed during normal working hours. However, the Contractor shall provide personnel to enable access for inspectors who need to conduct observation and testing after normal hours to avoid possible disruption to tenants.

C.8.7.5 Contractor Performance Assessment Reporting System (CPARS)

GSA uses the **CPARS** or similar performance measuring system to formally evaluate the Contractors performance. Evaluations are generally conducted annually or more frequently on or about the anniversary date of the contract and also at the end of the contract period.

C.9. BUILDING OPERATING PLAN "RESERVED"

~~C.9.1 Building Operating Plan~~

~~The Contractor shall revise or prepare and submit for approval to the CO , not later than the end of the startup or transition phase or by 90-calendar days after contract start date, a building operating plan outlining their operating and general maintenance procedures for all major building equipment and systems (See Section C.9.2., Components of the Building Operating Plan, below). The purpose of the building operating plan is to be a standalone document that is a vehicle for the Contractor to document their plan for operating and maintaining the building and it is also a repository for several documents required throughout the Contract. One of the objectives of this plan is that if key personnel are not available then authorized staff should be able to refer to the BOP and manage and operate the building. The BOP contains critical information such as: who to contact, emergency procedures, energy plan, hours of operation, locations of emergency shut off valves, the location of OEP, COOP, Drawings, and equipment Inventory. The Contractor shall execute the Contract requirements in accordance with the approved building operating plan. The Contractor shall coordinate with the CO in developing the components of the plan in accordance with the building operating plan template provided by the CO . The building operating plan shall be submitted as an electronic file (MS Word) with regular updates that reflect current personnel, subcontractors, equipment, systems, and operating procedures. The Contractor shall annually review and update the building operating plan and submit an electronic file (MS Word or searchable PDF) of the complete updated building operating plan on the anniversary of the Contract start date of each Contract year. If the Contractor fails to submit a satisfactory building operating plan at the end of the startup phase, the Government may suspend payments until a satisfactory plan is submitted.~~

~~The building operating plan may be based on, or derived from, the existing building operating plan and other existing documents. However, all components shall be reviewed and updated. Deficiencies in the existing plan do not excuse deficiencies in the new plan.~~

~~C.9.2 Components of the Building Operating Plan (BOP)~~

~~The components of the building operating plan are not additional requirements but a compilation of requirements stated throughout the SOW. Some of the information/documents will be provided by the CO to complete this plan, such as OEP, COOP, drawings, etc. The building operating plan shall contain:~~

- ~~a. Contact information (Local and corporate).~~
- ~~b. Description of staffing, responsibilities, and work schedules.~~
- ~~c. Standard operating procedures for operating building systems, to include at a minimum:~~
  - ~~1) Startup and shutdown times and procedures relative to various environmental conditions.~~

2) Procedures to accommodate tenant overtime utility requests. Provide listings of mechanical equipment, hours of operation and separate procedures for heating and cooling.
3) Energy Conservation, Management and Control Systems, Peak load demand management procedures (if applicable).
4) Other operating strategies to maximize efficiency and minimize energy consumption.
5) Descriptions of major mechanical equipment and sequences of operations for equipment systems such as schedules, settings, start-ups, shut-down, control sequences, etc.
6) Locations of all major utility shutoffs, including gas, electric, and water.
7) Locations of all electric rooms and a narrative of the areas served by each to include emergency generators, substations and transformers, equipment that is on the emergency generator

d. Architectural and Structural systems maintenance (façade, roof, gutters, drains, windows etc)
e. Tour and watch locations, sign-in and documentation procedures.
f. Maintenance schedules, procedures, and a reference to which preventive or predictive maintenance standards or guides the Contractor will use. For fire protection and life safety systems include specific references to which inspection, testing, or maintenance shall be performed each week, month, quarter, semi-annually, annually, 5 years, etc., in a format for the applicable NFPA code or standard.
g. List of test equipment to be maintained onsite to support troubleshooting, sensor calibrations, etc.
h. Vertical Transportation, if applicable, escalators, elevators, dumb waiters or note Contractor information.
i. A description of how building equipment data is maintained and updated. Service request and repair procedures, to include staffing and procedures for the service requests, during operating hours, after hours, and emergency function, if applicable.
j. Safety, Security, Disaster Emergency Response, Recovery and Reporting Procedures Reference the location or incorporate contingency plans for:
1) Loss of the Contractor's onsite personnel (i.e., strike, walkout, injury, abrupt resignation).
2) Civil disturbance or major security threat.
3) Natural disasters, bombing, or other event that damages the building's structure or utilities.
4) Floods, including flooding caused by plumbing breaks.
5) Hazardous materials including asbestos, lead paint, leaks or spills, water management
6) Utilities curtailment plans and shut off locations.
7) Inoperability and impairment of fire protection and life safety systems (including fire watch and impairment procedures (e.g., red tags, etc.).
8) Location of fire alarm control unit/fire control room/instructions to operate PA system in emergency if applicable.
9) Location of incoming municipal fire protection water supply

10) Location of fire sprinkler riser rooms
11) Location of fire pump.
12) Location of sump and sewage ejector pumps and emergency procedures.
13) Pressure booster and reducing stations, back flow preventers.
14) Underground Storage Tanks.
15) Confined Space Locations.
16) Portable Fire Extinguisher Locations
17) Defibrillator Locations
18) Radon mitigation program if applicable.

k. Other contingency plans as necessary to support the Government's Continuity of Operations (COOP), Occupant Emergency (OEP), and Shelter in Place planning for the site. Description of environmental regulatory requirements such as Air Quality Management District and include rules that apply to equipment in the building, which permits are necessary, inspection and certification requirements and other essential information. Identify how the administrative and technical requirements will be managed for the timely accomplishment of all Contract requirements.

l. Assignments of Responsibilities: Identify personnel with Quality Control Plan functions and the personnel with authority to commit funds, and the dollar level of that authority for this Contract.

m. Description of demand response or utility curtailment programs in which the building participates, to include communications protocols and curtailment activities.

n. Location of equipment inventory list.

If the Contractor fails to submit a satisfactory building operating plan at the end of the 90-calendar days from contract start date, the Government shall suspend payments until a satisfactory plan is submitted.

C.10. EQUIPMENT INVENTORY

Omissions on existing inventory do not relieve the Contractor from the responsibility for the maintenance of the equipment. The Contractor may request equitable adjustment pertaining to physical changes in building equipment and equitable adjustments shall be submitted to the CO for consideration.

The Contractor shall:

a. Maintain and update the building equipment inventory and equipment labeling.
b. Maintain equipment inventory and maintenance records in a CMMS.
c. Maintain the same asset identification system currently used for new and replacement equipment unless a national asset identification standard is provided. Some asset identification systems include bar-coding, Radio Frequency Identification (RFID), or other equipment tagging.
d. Collect and maintain an inventory of: (1) all equipment of types that require maintenance or certifications pursuant to the PBS Maintenance Standards or applicable code requirements, (2) equipment which is operated through a sequence of operations, (3) electronic controllers and network devices, (4) sensors, (5) Agency owned sensors , if applicable.

e. Collect and maintain the following equipment data: Equipment ID, Equipment Type, Equipment Description, Asset Identification Code, Manufacturer, Model Number, Serial Number, Equipment Status, Building Number, and Location (Exhibit J. 15).
   1) The Contractor shall provide all data to GSA in a format approved by the CO with certification that the inventory is complete and accurate. For facilities where the GSA provides a CMMS, the government-provided CMMS is the required format for providing inventory data.
   2) The Contractor shall annually certify that the Maintained Building Equipment Inventory is up-to-date and submit the certified inventory to the CO .
   3) The Contractor shall update equipment data when equipment is added, removed, or retrofitted as part of a project, or discovered by GSA or the Contractor.
   4) The Contractor shall review and update equipment records including asset information, maintenance records and preventive maintenance records any time maintenance is performed on a piece of equipment.
   5) The Contractor shall report to the CO changes to the asset inventory and preventative maintenance schedule within five working days of collecting and gathering equipment information.

If the updated inventory data does not meet contract requirements, action to reduce the contract amount in proportion to the failure to meet contract requirements will commence.

During the first year of performance the contractor shall physically visit all equipment while performing maintenance and obtain all pertinent name plate data and update the equipment inventory list to ensure the list is complete and accurate. The contractor shall submit this data on the start date of the first option year and **annually thereafter.** The contractor shall submit all additions/deletions of equipment inventory in the **monthly progress reports.** This inventory list of each item shall include descriptive information including but not limited to:

(a) Manufacturer name and date, type, model and serial number

(b) Specifications for the equipment, length, size, volume or electrical capacities (e.g. gallons, liters, amp rating, voltage, tonnage, horse power, CFM, BTUs per hour, etc.)

The contractor shall be responsible for updating and maintaining a current inventory on-site. The contractor will perform Preventative Maintenance on all equipment, even if the equipment is missing from the successor contractors and/or Government's furnished inventory.

Requests for equitable adjustment pertaining to physical changes in building equipment shall be submitted to the CO.

C.10.1 Occupant Agency Program Equipment

(1) The Contractor is responsible for operation, maintenance, or repair of occupant agency program equipment, with the exception of the following:

Computers	Paper pulpers
Office furniture	Laboratory equipment
Office machines	Special purpose incinerators
Mail handling equipment	Personally owned appliances

Printing plant equipment	Agency-installed alarms, CCTVs, etc.

(2) The Contractor **is** responsible for operation and maintenance and service calls **ONLY** of equipment identified as Occupant Agency Program Equipment.

(a) Any repairs shall be immediately reported to the CO. Work shall not be performed until the Contractor and the CO has reached an agreement on the price to accomplish the project. This requirement may be waived by the CO in the case of an emergency. The Contractor shall submit to the CO a detailed cost breakout to perform the work. This breakout shall include the labor hours by trade or by the various types of work to be performed on the project, and an itemized listing of the cost of supplies, materials and any overhead. The Contractor shall compute the labor costs using the bid unit hourly rate for maintenance repair services specified in the Pricing bid sheets.

(b) The Government reserves the right to furnish any or all parts and/or materials required for a particular repair as Government furnished equipment. If the Contractor furnishes the parts and/or materials, the price to be paid shall be on the basis of established catalog or list prices in effect at that time, less applicable discounts. In no event shall such price be in excess of the Contractor's sale price to his most favored customers for the same item in like quantity, or the current market price, whichever is lower.

C.11. MONTHLY PROGRESS REPORTS

~~The Contractor shall develop a monthly progress report using CMMS data, describing the status of maintenance and operations as of the last day of the performance month. The report shall be submitted to the by the 5th working day of the subsequent month. This report shall include:~~

- ~~a. Work Order status of all types of maintenance, repairs, service calls (highlight overdue and tenant complaints), to include deferred, completed, and active (include estimated completion date), by type of work i.e., reimbursable, repair, and work orders resulting from testing and inspections, and any equipment out of service.~~
- ~~b. Explanation of any equipment, designed to be controlled by the BAS, operating in manual mode as of the end of the performance month, and of any other overrides to sequences of operations in effect as of the end of the performance month.~~
- ~~c. Operating schedule changes (manual or programmed)~~
- ~~d. Description of any lost time accidents or other safety problems, including incidents involving hazardous materials that occurred during the performance month~~
- ~~e. Copies of quality control inspections performed during the month attached to the report.~~
- ~~f. Building Management Support Services (utility hours/miscellaneous work) provided during the month.~~
- ~~g. Copy of arrival and departure reports~~
- ~~h. Monthly water treatment test results~~
- ~~i. Recalibration documentation of advanced metering equipment.~~
- ~~j. When testing/inspections on critical equipment is performed, the Contractor shall submit results with the monthly progress report~~

~~k. Refrigerant Inventory Log to include type and amount of refrigerant used during the month including the leakage rate information on all equipment containing refrigerant.~~

~~l. The Contract shall record the fuel levels monthly and report findings in the Monthly Progress Report~~

~~m. Assist the CO in the review of energy performance trends as of the end of the performance month and description of likely causes of significant changes from the same month 1 year prior.~~

~~n. Check and record diesel fuel levels~~

~~o. Log of irrigation usage~~

The Contractor shall develop a monthly progress report using CMMS data, describing the status of maintenance and operations as of the last day of the performance month. The report shall be submitted to the COR by the 10th working day of the subsequent month. This report shall include:

a. Description of any lost time accidents or other safety problems, including incidents involving hazardous materials that occurred during the performance month
b. Monthly water treatment test results
c. When testing/inspections on critical equipment is performed, the Contractor shall submit results with the monthly progress report
d. Refrigerant Inventory Log to include type and amount of refrigerant used during the month including the leakage rate information on all equipment containing refrigerant.
e. Check and record diesel fuel levels
f. Changes to Equipment inventory

C.12. PERFORMANCE EVALUATION AND REVIEW

The Contractor shall meet with the CO and other Government representatives, at the discretion of the CO , to review contract performance.

C.12.1 General:

The CO will coordinate performance evaluation meetings with the Contractor and/or tenants. The written minutes of these meetings will be prepared and distributed by the CO or designee and will not be the responsibility of the contractor. The Contractor shall acknowledge receipt of the minutes (within 10 working days), and will have the opportunity to provide comments.

GSA/Contractor Meetings:

An initial step in avoiding disputes and claims is to settle minor problems and misunderstandings at the lowest possible level. Accordingly, the Contractor or the Contractor's on-site representative shall meet with the CO frequently, but not less than twice each month during the first **(3)** three months of the contract. Thereafter, meetings shall be as often as necessary at the discretion of the CO , but not less than once per month. A mutual effort shall be made to resolve all problems identified during these meetings.

Specific topics to be addressed by the CO/COR during the regular monthly meeting to determine Contractor responsiveness may include such areas as: effectiveness of Quality Control Plan; corrective action plans; proposal submittals for extra services; and the management of subcontractor problems impacting overall contract performance/service delivery.

C.12.3. GSA/Contractor/Tenant Meetings:

Meetings will also be held between the Contractor, selected building tenants and the CO on a monthly basis for the first three months and thereafter on a schedule agreed to by the participants. The purpose of these meetings will be to discuss the contractor's performance, areas of deficiencies, and areas of satisfaction and tenant needs or concerns.

The CO should establish points of contact with tenant agencies to assist in monitoring contractor service delivery. These agency points of contact should be kept informed of building services program activities with an added emphasis or focus on specific customer feedback and tenant facility requirements.

The minutes of GSA/Contractor/Tenant meetings and the results of tenant surveys should provide sufficient performance data record to make sound business decision(s) when considering a contract renewal or new contract awards.

C.13. Equipment Condition Assessment "reserved"

~~During the performance of the requirements of this Contract the Contractor shall note the condition and efficiency of building equipment and systems on an ongoing basis in the CMMS. Any equipment or systems that the Contractor determines are reaching the end of their life cycle shall be brought to the attention of the CO .~~

~~When requested, the Contractor shall complete and submit to the CO an itemized equipment condition assessment with their recommendation for equipment or system upgrades or replacements (that has reached end of their life cycle), including a text description of each recommended upgrade or replacement and their life cycle cost analysis that shall include estimated project cost. The equipment condition assessment reports shall be produced in Word, Excel, or PDF format, as directed by the CO , and submitted electronically as an email attachment delivered to the CO .~~

C.14. Occupant Feedback Program

"Reserved" (Region 4 relies on Customer Service Satisfaction feedback for this)

C.15. Reference Library

The Contractor shall maintain a comprehensive reference library that includes building design or record documents, renovation or equipment retrofit design or record documents, maintenance reference documents, applicable NFPA codes and standards, fire protection system as-built drawings, fire protection system operations and maintenance manuals with copies of approved submittals, fire protection system parts list, fire protection system zoning scheme, fire protection system sequence of operation matrix, HVAC Operations Manual (if one has been developed), building operating plan, energy and other building technical studies, hazardous materials surveys, and other documents necessary to document the design, function, and condition of the building. The Contractor shall safeguard this information in accordance with the provisions of Section H.6., Sensitive but Unclassified Building Information (SBU).

C.16. Review Of Design Documents

Utilizing the most qualified onsite personnel familiar with the operations of the facilities covered under the scope of this Contract, the Contractor shall review design and construction project

documents as requested by the CO . The purpose of this review is to allow the Contractor to comment on any negative impact the proposed project may have on their ability to efficiently operate the building equipment or systems. When requested to perform these services, the Contractor will be compensated for the actual time required spent. The Contractor should also be allowed to provide input or propose ideas that may improve the operations and provide value engineering.

C.17. BUILDING MANAGEMENT SUPPORT SERVICES (MISCELLANEOUS HOURS)

The Contractor shall provide reasonable and competent assistance during normal working hours to GSA personnel ~~or other GSA Contractors~~ performing energy studies, engineering studies, building condition evaluations, fire protection facility surveys, project designs within the building, and other access needs. Such assistance shall include escorting government investigatory personnel through spaces in the building in accordance with building security requirements, explaining the operation and condition of equipment and systems to investigatory government personnel, and providing access to trend data, maintenance records, reference library materials, and other pertinent building technical data to investigatory government personnel. The CO or their designee shall inform the Contractor as far in advance as possible of the actual date and time these services are needed. When requested to perform these services for other personnel or contractors the O&M Contractor will be compensated for the actual time required to escort these personnel at the hourly rate specified in Section B of this Contract. ~~Report number of hours provided in the Monthly Progress Report C.11~~

C.18. INSPECTION ASSISTANCE FOR SPACE BUILDOUTS

When tenant improvement or space alteration work is completed in the building, the CO may request that the Contractor inspect the space to verify that all offices have appropriately zoned air supply and return ductwork and diffusers, appropriately zoned lighting circuits, and all zone HVAC/lighting controls have been adjusted appropriately and labeling of breakers in electrical panels and outlet cover circuit designations are complete.

Obvious problems or conditions that may potentially affect the efficient operation of the building or create a negative impact on the tenant shall be immediately reported to the CO .

C.19. EMERGENCY SHUTDOWN INSTRUCTIONS AND TOUR CHECKLISTS "RESERVED"

~~Emergency shutdown instructions (including contact name and telephone numbers) and tour inspection checklists and Lock-Out Tag-Out procedures shall be posted by the Contractor in all mechanical rooms and or electrical rooms, as applicable to the equipment in the given room. Such instructions and checklists shall be posted in an accessible and conspicuous location. All instructions and checklist will be recorded in the Building Operation Plan.~~

C.20. LABELING OF ELECTRICAL CIRCUITS

The contractor shall not be responsible for tracing existing circuits that are not currently identified in panel schedules however, the contractor shall be required to label un-labeled circuits found during the course of performing trouble shooting or other maintenance actions. The contractor shall ensure that up-dated panel schedules are presented in a typed format vice "pen and inked" changes to ensure confidence for future technicians that depend on the information being correct.

~~The labeling of the electrical circuits shall be maintained up to date. When another Contractor (not the O&M Contractor) adds or modifies electric circuits the O&M Contractor shall inform the CO the compliance of annotating the changes to the panel and the update to the single line diagrams~~

using the original electronic file format.

C.21. OPERATIONAL REQUIREMENTS

C.21.1 General

The Contractor shall provide building operations services for all systems covered by this Contract, so as to maintain uninterrupted utilities services, and environmental conditioning to tenants during normal working hours, and at other times as described in this document, so as to preserve the asset value of the facility and its systems and to otherwise minimize operating costs to the Government without compromising other Contract objectives or requirements. The Contractor shall be briefed

by the property manager on GSA's policy regarding overtime utilities to better understand what is considered standard and above standard services. Some or all of these requirements are to be documented or referenced in the Building Operating Plan, see Paragraph C.9.2.

C.21.2 Extended Operating Hours RESERVED

[[[Regions shall delete this paragraph provision if not applicable to their facility and mark as "Reserved."]]]

The following areas of the building regularly operate during hours outside of normal working hours; supporting equipment shall be operated and maintained by the Contractor so as to support these extended operating hours.

[[[List the areas and hours of operation.]]]

Areas of the building with extended operating hours may change during the period of the contract. The Contractor will be notified of these changes as soon as possible.

C.21.3 Continuity Of Operations (Coop)

The Contractor shall operate the facility and participate in emergency operations in support as specified in Section H.21. Occupancy Emergency Plan.

C.21.4 Emergency Operating Plan

The Contractor shall be responsible for developing an emergency operations plan within the building operating plan and shall become thoroughly familiar with the Government's occupant emergency plan and other regional plans as applicable. The Contractor's plan shall include the following information: position and contact phone number of each Contractor person, what each position is responsible for in each emergency, general administrative support the Contractor will provide during emergencies and any subcontractor support and contact information.

C.21.5 Tenant Environment

Lighting levels shall be adjusted under the guidance of the CO where they can be adjusted without changing fixtures (e.g., tuning dimmable ballasts, de-lamping). The Contractor should note that while the PBS P100 establishes target lighting levels, light quality, specific tenant requirements, energy conservation, and other individual factors also have an impact on requirements. Environmental standards shall meet ASHRAE Standard 55-2004, Thermal Environmental Conditions for Human Occupancy and ASHRAE 62.1-2007, Ventilation for Acceptable Indoor Air Quality (Guiding Principles) and be maintained throughout normal working hours in the most efficient sequence and equipment startup shall occur efficiently in order to fully attain environmental conditions at the beginning of normal working hours.

The contractor shall comply with the FMR sections; 1002-74.185 and 102-74.195, respectively the

contractor shall meet ASHRAE Standard 55-2004, Thermal Environmental Conditions for Human Occupancy and ASHRAE 62.1-2007, Ventilation for Acceptable Indoor Air Quality (Guiding Principles). The Contractor shall maintain these standards throughout the normal working hours. Equipment start up shall occur efficiently in order to fully attain environmental conditions at the beginning of normal working hours. The contractor shall comply with the ASHREA Standard 55 – 2004 to achieve temperature settings between 74°F and 78°F in the summer months and between 68°F and 72°F in the winter months. These recommended temperature settings apply to the entire building not individual offices. The Contractor shall report significant changes in the operating conditions to the CO . If the standards (ASHRAE Standards 55 and 62) cannot be achieve the Contractor shall submit a written deviation to the CO for approval.

C.21.6 Energy and Water Efficiency

The Contractor shall operate equipment and systems as efficiently as possible without compromising service to the tenants. Failure to operate equipment prudently (e.g., unnecessarily setting demand peaks, simultaneously heating and cooling, operating equipment when not needed, overriding set point unnecessarily, or failing to correct underlying conditions) may result in deductions. The CO will provide the Contractor with Operational Performance Targets for energy and water, where data is available within the first quarter of the award of the Contract.

~~The Contractor shall report annually energy and water usage as compared to the previous year and document energy and water saving initiatives and reasons why performance goals were or were not met. The report shall be submitted to the CO by the 5th working day of the subsequent month. The Contractor is to make full use of available analytic tools (e.g., BAS, AMS, Building Link data) to diagnose problems and identify operational improvements. The Contractor, in coordination with the CO , shall pursue the use of energy efficient replacement parts and equipment items (not limited to Energy Star ® or FEMP designated Energy Efficient products, Water Sense, Design for the Environment products) that will meet or exceed the requirements of this statement of work. In cases where equipment is being replaced or upgraded to high efficiency models the Contractor shall investigate all potential energy rebates that would be advantageous to the government. Any rebates received from a service utility provider shall be assigned to the Government.~~

~~On a monthly basis the contractor shall read all electric, gas, diesel fuel levels, water, cooling tower water make up and lawn sprinkler meters and submit in the monthly progress report.~~

C.21.7 Contact After Normal Hours

The Contractor shall, not later than 15 calendar days after contract award date, provide the CO or his/her designee with telephone numbers which the Government may use at any time to directly contact the Contractor, the Project Manager, any on-site supervisor(s), and assigned mechanical employee(s).

C.21.8 Normal Tenant Working Hours

BUILDING(S)	OFFICIAL TENANT WORKING HOURS	OPEN/CLOSE BUILDING	RAISE/LOWER FLAG
ALL in this contract	7:00 AM - 5:00 PMS	Bldg Security Officer	Bldg Security Officer

The Contractor shall provide the required environmental conditions, specified during the

"normal tenant working hours", for the buildings in accordance with the Building Operating Plans. Personnel responsible for the operation of the heating, ventilation and air conditioning systems may be required to be available earlier or later than specified for normal start up and shut down of HVAC equipment or when requests for overtime utilities or additional services are issued. Contractor shall also be responsible for any necessary operation and prevention of damage to

equipment during on and off duty hours to due to inclement weather, high wind events, or freezing temperatures.

NOTE: In the event the building (s) is closed due to unexpected circumstances (i.e Presidential declaration, inclement weather, etc.) the contractor will be paid for those days provided the employees are compensated and the contractor provides proper documentation to the Contracting Officer.

C.21.9 Building Information

See Building Information Sheets Exhibit 5 of Section J.

C.22. System Performance Standards Or Procedures

RESERVED

C.22.1 Smart Buildings

RESERVED

C22.2 Integrated Building Systems

Assist the Government by ensuring that all relevant equipment vendors, with equipment installed in facility, maintain their respective systems (i.e. HVAC, BAS, Lighting, Advanced Metering, etc.) in accordance with GSA Smart and Sustainable Buildings intended objectives (i.e. open systems running on a single GSA Building Systems data network).

The Contractor shall act as a liaison and facilitate efforts between their respective building-specific monitoring and control system subcontractors and work through the CO GSA with the Information Technology Office (PBS CIO) on issues related to O&M operations.

The Contractor shall make recommendations to the government (as applicable), on improvements to sequences of operations.

C.23. Service request

C.23.1 General

The Contractor shall respond to service requests and initiate corrective actions and identify any repair requirements during normal working hours. The Contractor shall respond to emergency service requests (during normal working hours) and callback (after hours) work requests at all times. The Government (or, where applicable, the tenant Agency) may transmit work orders to the Contractor for service request or emergency service request and callback orally, by email, by creation of a work order by a Government employee or representative, or by generating an automated work order. The Contractor shall respond according to specified service response times.

The Contractor shall log any maintenance problems noted by the mechanic when touring the

building that requires three (3) hours or less of labor and no more than $200.00 in parts and materials.

The Contractor's service call log and/or records shall be maintained at the building site and be available for inspection by GSA inspectors at all times.

C.23.2 Emergency Service Request

Emergency service requests are service requests where the work consists of correcting failures that constitute an immediate danger to personnel or property, including but not limited to: broken water pipes, assist with elevator entrapment (see section C.39.8), electrical power outages, electrical problems that may cause fire or shock, gas or oil leaks, major air conditioning or heating problems, etc., or any work considered by the CO to be of an emergency nature. The Contractor shall respond to emergency service request immediately (within the shortest possible time consistent with the mechanic's location) during normal working hours and within 30 minutes. The Contractor shall remain on the job until the emergency situation has been secured and adequate temporary repairs have been made. Permanent repair shall be governed by the repairs provisions in this document.

C.23.3 Emergency Call Back (after hours)

Emergency call back requests are service requests where the work consists of correcting failures that constitute an immediate danger to personnel or property, including, but not limited to: broken water pipes, stalled elevators with trapped passengers, electrical power outages, electrical problems that may cause fire or shock, gas or oil leaks, major air conditioning or heating problems, etc., or any work considered by the CO to be of an emergency nature. The Contractor shall respond to emergency call back service request (within the shortest possible time consistent with the mechanic's location) after working hours within 1 hour. The Contractor shall remain on the job until the emergency situation has been secured and adequate temporary repairs have been made. Permanent repair shall be governed by the repairs provisions in this document. The Contractor shall provide a written accounting of any emergency call back, to include costs incurred and plan for permanent correction of the problem, to the CO the morning of the next working day.

The contractor <u>will not</u> be paid for emergency call backs in those cases where the nature of the emergency call back is due to failure of equipment or system(s) that the contractor is responsible for under the basic services of the contract. In these cases the contractor shall be responsible for all cost incurred up to the repair threshold. If the nature of the call back is due to conditions beyond the contractors control then the contractor shall be entitled to reimbursement at the hourly rate specified in the bid schedule.

C.23.4 Urgent Service Request Response

Urgent service requests are those service requests where the work consists of correcting failures that interrupt or otherwise adversely impact either GSA operations or building occupant operations, but do not pose immediate danger. Examples of these types of service requests include, but are not limited to, inoperative electrical circuits, temperature complaints, inoperative lighting above a work station, flush valve stuck open, any malfunctions to equipment that affect the operations of building occupants, or any work considered by the CO

to be of an urgent nature. The Contractor shall respond to urgent work requests within 1 hour during normal working hours. The Contractor shall remain on the job until the urgent repairs have been made. Permanent repair shall be governed by the repairs provisions within this document.

C.23.5 Routine Service Request Response

The Contractor shall respond promptly to routine work requests (i.e. plumbing & lighting issues, etc.) and complete the required work within 24 hours of notification. The Contractor shall immediately notify the CO with a written extension when the routine service call cannot be completed within the specified timeframe.

C.23.6 Overtime Services

The Contractor shall ensure that sufficient qualified personnel are available to provide overtime utilities or services.

The Contractor shall not provide any services to tenants other than during normal operating hours unless he is directed to do so by the CO or his/her designed representative. The Contractor shall provide overtime utilities or services when requested, either verbally or in writing, by the CO or his/her designee. The request for overtime utilities or services will normally be made 24 hours in advance, but no less than 1 hour prior to the end of the normal tenant working hours.

When overtime or additional services are provided, the Contractor will be paid at the contract hourly rate as specified in the bid schedule.

C.24. TOURS

~~Procedures must be documented in the building operating plan, see paragraph C.9.2~~

~~C.24.1 General~~

~~The Contractor shall tour major building equipment at set frequencies. Log sheets associated with major operating equipment shall be completed at the time of tours and the information recorded in the CMMS. At the commencement of Contract performance, CO or their designee will direct the Contractor to include on the log sheets established design condition numbers for reference against actual readings at the time tours are performed. Paper log sheets need not be used for equipment monitored and data logged by the BAS, if such monitoring and data logging provides a sufficient database of operating data to allow for analysis of trends in equipment performance and troubleshooting. The Contractor shall document all tours completed in the CMMS. All findings noted during the tour shall be entered as remarks on the tour sheet and a work order shall be initiated for corrective action by the Contractor.~~

~~C.24.2 Operating Logs and Tour Check Sheets~~

~~Operating logs and tour sheets shall be maintained by the Contractor for major equipment. Information recorded on the logs shall be adequate to track the operating hours and performance history of the equipment and the information recorded in the CMMS. Tour check sheets shall be stationed at major points for building tours (for example, air handler rooms). These shall be checked initialed and dated by the Contractor when tours are performed. There shall be either separate tour check sheets for each frequency of inspection or (preferably) different checklist columns on a~~

~~standard tour check sheet for each frequency. Tour sheets shall contain columns for major operating parameters and shall indicate the tolerance bands for acceptable performance, where available.~~

~~C.24.3 Tour Frequencies~~

~~Tours shall on be conducted for fire life safety systems.~~

~~All equipment tours shall be performed by HVAC personnel that have been accepted as qualified by the CO or his/her designee at a minimum. All tours shall be conducted in a manner that supports effective and efficient building operations.~~

~~**1.** DAILY: Major HVAC equipment (when in operation), including boilers, chillers, cooling towers, pneumatic control air compressors, and air handler rooms. Fire alarm system control panels (fire alarm system control panels shall not have any unwanted trouble conditions). Steam system reducing and regulating stations. Special HVAC for critical functions. **Note: On buildings greater than three stories tours of the AHU's can be accomplished by monitoring their status through the BAS system and visual tours shall be conducted on a monthly basis.**~~

~~2. WEEKLY: Distributed HVAC equipment including package units and external condensers, pumps, motors, sewage ejectors, fire pumps, and generators.~~

~~3. TWICE PER MONTH: Battery systems and uninterruptible power systems (UPS).~~

~~4. MONTHLY: Transformers, secondary electrical rooms, switchgear and primary electrical equipment rooms, and condensate drip pans. A visual tour of the AHU's on buildings greater than three stories. Tour all stairwells, standard and emergency lights.~~

~~C.24.4 Condensate Drip Pans~~

~~The Contractor shall conduct inspections of the condensate drip pans of all air handling units, A/C package units, window A/C units, and other equipment items and or systems that physically have drip pans to ensure that they drain properly. Such inspections shall be conducted in accordance with the tour program and be performed no less frequently than monthly. Pans that are not level or that leak shall be reported to the CO or designee. All drip pans shall be treated with an appropriate biocide to control the growth of algae, etc. If any condensate pans are inaccessible, the Contractor shall notify the CO or their designee immediately.~~

~~C.24.5 Monitoring Of Central Plant Equipment~~

~~Where central plant equipment (chillers and boilers) is not (1) controlled through a sequence of operations programmed in a BAS, and (2) centrally alarmed with alarm paging, operational watch procedures, in addition to tour requirements specified elsewhere in this document, shall be performed as follows:~~

~~a. Monitoring the starting, stopping, and loading of equipment.~~
~~b. Checking all operating equipment in the watch area twice per day with one tour being conducted during start-up and the other during the hottest/coldest part of the workday.~~
~~c. Making adjustments at the central control panel in response to changing operating conditions.~~

C.24.1 General

The Contractor shall only be required to tour equipment associated with fire life safety equipment and shall make annotations and conduct those tours in accordance with applicable NFPA codes. In cases where these tour frequencies are being accomplished by NFPA Preventative Maintenance actions no separate tour shall be required.

C.24.2 Condensate Drip Pans

The Contractor shall conduct inspections of the condensate drip pans of all air handling units, A/C package units, window A/C units, and other equipment items and or systems that physically have drip pans to ensure that they drain properly. Such inspections shall be conducted in accordance with the tour program and be performed no less frequently than monthly. Pans that are not level or that leak shall be reported to the CO or designee. All drip pans shall be treated with an appropriate biocide to control the growth of algae, etc. If any condensate pans are inaccessible, the Contractor shall notify the CO or their designee immediately. At a minimum, while checking condensate pans the contractor shall visually check all other major components of the AHU to include belts, filters, coils, dampers, motors, bearings, shaft, fan blades, etc…

C.24.3 Monitoring Of Central Plant Equipment

Where central plant equipment (chillers and boilers) is not (1) controlled through a sequence of operations programmed in a BAS, and (2) centrally alarmed with alarm paging, operational watch procedures, in addition to tour requirements specified elsewhere in this document, shall be performed as follows:

a. Monitoring the starting, stopping, and loading of equipment when shifting equipment manually
b. Checking all operating equipment in the watch area twice per day with one tour being conducted during start-up and the other during the hottest/coldest part of the workday. Contractor shall log and evaluate all readings on the equipment and take any appropriate actions required to maintain the equipment within proper operating parameters. Any cost associated with these actions shall be as required within the contractors repair liability.
c. Making adjustments at the central control panel in response to changing operating conditions.

~~C.25. Demand Response Programs Reserved~~

~~The Government may participate in any of the available demand response programs or critical peak pricing tariffs administered by utilities, State agencies, or third-party administrators. If the Government participates in such a program and advises the Contractor of the requirements of the program, the Contractor shall cooperate fully in the implementation of the program.~~

~~C.26. Curtailment "Reserved"~~

~~The Contractor shall develop a curtailment program in consultation with the CO or their designee and subject to approval; the program shall be described in the BOP (C.9.2). The Contractor shall implement all approved curtailment measures (which might typically include turning off unnecessary lighting, implementing temperature setback programs, etc.) immediately on notification of a curtailment, in accordance with the plan. Failure to diligently manage systems in accordance with such programs may result in performance deductions for excess costs.~~

~~NOTE: MLK is the only building in this region with curtailment capabilities~~

C.27. BAS Alarm Response (ALL BUILDINGS IN THS CONTRACT)

The Contractor shall maintain all BAS systems using qualified employees. BAS alarms shall be treated as service requests and responded to accordingly. Repetitive or associated alarms may be treated in the aggregate and tracked under the work order system established in the CMMS. Communications for alarms set up for remote notification shall be tested on a recurring basis.

C.28 Advance Metering Program (AMP)(FL0061ZZ, FL0079ZZ, FL0089ZZ, FL1021ZZ)

~~GSA's purpose for installing these meters is to monitor, identify, and implement opportunities to reduce energy usage at the building(s) and, in some cases, to verify that the utility companies are billing correctly. In many cases, the AMS will be connected to the BAS. It shall be the Contractor's responsibility to partner with GSA to fully utilize the AMS to develop and implement strategies that will result in overall energy reductions per Section C.21.6. The Contractor shall have all access to the AMS and be trained in its use as stipulated in ***H.15.3.16, Qualifications of AMS, BAS Technicians.*** The Contractor shall be trained by GSA in its use of advanced meters and shall demonstrate minimum competency in developing energy/water usage graphs and where electric advanced meters are capable of measuring power quality, the contactor shall be sufficiently familiar with the software module to utilize this information when troubleshooting electric power issues such as transients, voltage disturbances, power factors, and harmonics.~~

GSA's purpose for installing these meters is to monitor, identify, and implement opportunities to reduce energy usage at the building(s) and, in some cases, to verify that the utility companies are billing correctly. In many cases, the AMS will be connected to the BAS. It shall be the Contractor's responsibility to partner with GSA to fully utilize the AMS to develop and implement strategies that will result in overall energy reductions. The Contractor shall have all access to the AMS and be trained in its use by GSA Regional Energy group Subject Manger Experts. This training shall be coordinated after award by the CO or his/her designee. Any preventive maintenance actions or failure to the installed AMS equipment to include the server, sensors, UPS, or cabling shall be the responsibility of GSA. The contractor shall notify the CO or his/her designee when failure occurs.

C.28.1 Verification and Calibration "RESERVED"

~~The Contractor shall verify daily (M-F excluding federal holidays) that each of the advanced meters is functioning properly and are communicating to the regional and/or central office server. Any communication failures shall be corrected prior to any loss of data. In the event of a communications failure, the Contractor should refer to both the manufacturers and GSA's troubleshooting guides. The Contractor shall be responsible for the recalibration of the advanced meters in accordance with the manufacturer's recommended frequency or sooner if there is evidence that the meters are not reading correctly. Calibration shall be scheduled in advance along with other building preventive maintenance tasks. Documentation of the recalibration shall be submitted with preventive maintenance reports.~~

C.29. PROTECTION AND DAMAGE

The Contractor shall make reasonable efforts to assist the Government to prevent hazardous conditions and property damage and to maintain security. The Contractor shall promptly report such conditions or activities to the CO or Federal Protective Service (FPS) personnel. The Contractor shall protect Government property, buildings, materials, equipment, supplies, records, and data within the Contractor's control against unauthorized access, loss, or damage and excessive energy consumption. The Contractor shall establish a system for onsite work force personnel to report potentially hazardous conditions in the building to the CO . The Contractor and Contractor's employees and subcontractors shall comply with the GSA's Rules and Regulations Governing Public Buildings and Grounds (as posted in the building) and shall promptly report violations by employees, or as otherwise observed, to the CO or security personnel. The Contractor shall provide reasonable assistance to security or emergency response

personnel as needed.

C.30. NEGLIGENCE

The Contractor shall provide all labor, materials and equipment necessary for the protection of Government personnel, equipment, furnishings, buildings, and facility accessories (such as parking lots, fences, etc.) from damage caused by Contractor's negligence. Any items damaged due to work performed by the Contractor or subcontractor working for the Contractor shall be repaired or replaced to its original condition and finish at no additional cost to the Government.

C.31. KEY CONTROL

The Contractor shall follow the building's key control program. Keys issued to the Contractor or the Contractor's personnel or subcontractors shall be signed for and not transferred to other personnel unless recorded in the key control log. The Contractor is financially liable for the cost of re-keying if keys are lost or not recovered from terminated employees or subcontractors. **No keys shall be issued without CO approval in writing.**

C.31.1 Locksmith Services

The Contractor shall furnish locksmith services for routine installation and removal of lock sets and tumblers, duplication of keys, repair of defective lock sets, opening doors, cabinets, and safes in the event of lost keys, and changing of combinations **on all existing locks**. If the Contractor loses any keys, the Contractor is responsible for changing out or re-keying all affected locks and shall provide the appropriate keys at the Contractor's expense. In the event a master key in the Contractor's possession is lost or duplicated, all locks and keys for that system will be replaced.

All new locks shall fit existing master key systems and be keyed to fit existing keys for the locks being replaced.

All non agency security system locks (card readers, swipe card systems, keyed locks, key pads and its components and changing combination on all push button cipher locks shall be the responsibility of the contractor.

The Contractor shall maintain in a safe and usable condition power doors such as garage and loading ramp doors, revolving doors, sliding or swinging doors, and adjustable loading ramps.

In the event a repair is made and office identification cards and holders are removed the Contractor shall be responsible for its replacement. If the identification cards and holders are damaged and cannot be reused these items will be replaced with items with similar size, quality and appearance in order to provide a uniform appearance throughout the building.

The Contractor shall respond to assist tenant personnel in obtaining access to office space if locked out. Access shall be given to tenant personnel only after securing agency approval.

The contractor shall be responsible for duplication of keys when requested in writing from the CO . The number of keys duplicated during a year shall not exceed 15 per building and any additional keys shall be at the cost of the government.

C.32. DISRUPTIVE OR HAZARDOUS TOOLS

The CO shall approve use of impact tools and power-actuated tools during normal working hours. Burning or welding equipment may be used only with written permission from the property management office or CO . A Welding and Burning Permit (GSA Form 1755 or equivalent)

shall be issued in advance for each day welding or burning is performed.

C.33. Disruption To Utilities, Lighting, Or Space Conditioning

Any work that will disrupt utilities, fire protection and life safety systems, lighting or space conditioning for building tenants shall be scheduled and approved in advance with the CO and is generally required to be performed outside of normal working hours.

C.34. Plumbing and Restrooms

Plumbing systems shall be maintained, repaired, and kept functional to the point of service delivery as defined by the utility company. The Contractor shall ensure all system drains, including storm drainage and roof drains, remain clear and unobstructed. The Contractor shall take any necessary steps to prevent odors emitting from drains or other plumbing systems into occupied space, to include keeping water in traps appropriately maintained. The Contractor shall clear toilet and sink blockages, as necessary. Such requests will be transmitted to the Contractor by the CO through service request procedures.
When replacing plumbing fixtures, use the most reduced water usage device as approved by the CO . (For additional information see: http://www.epa.gov/watersense/)

C.35. Maintenance Program

C.35.1 General

The CO may consult with the Regional SME on Contractor's scheduled PM system to ensure this meets GSA's minimal PM requirements. Where advanced meters are connected through the BAS, the contractor shall verify daily, proper information and data sharing.

The Contractor shall establish an effective system for scheduling and performing scheduled preventive maintenance on all building equipment and systems requiring a preventive maintenance procedure covered under the scope of this Contract. The Contractor shall submit this system to the CO , including the list of items receiving a preventive maintenance procedure as well as the specific maintenance standard or guide describing the preventive maintenance procedure and frequency (see Section C.35.2, Maintenance Standard, below), for approval within is to be submitted in the technical proposal. The contractor shall submit an annual preventive maintenance schedule describing the preventive maintenance frequency and month it will be performed to the CO for approval within **30 calendar days** after contract award date. The contractor shall submit a monthly report of all PM's scheduled and completed during that month.

C.35.2 Maintenance Standard

The contractor shall schedule preventive maintenance on new equipment in the CMMS system when the extended maintenance service is completed by the installer and ensure that all pertinent warranty information and proposed maintenance plans are sufficient to uphold our obligations under the warranties.

As part of the Contractor's established system for scheduling and performing scheduled preventive maintenance (See C.35.1, General, above), the Contractor shall propose to the CO , preventive or predictive maintenance standards or guides for each piece of equipment where the manufacturer/designer recommends preventive maintenance. Minimally, the preventive or predictive maintenance standards or guides proposed by the Contractor shall be based on; manufacturer's recommended maintenance or the most current Public Buildings Service Operations and Maintenance Standards (PM Guide) or guides proposed by Contractor. If the Contractor uses the most current version of the Public Buildings Service Operations and Maintenance Standards (PM guides) then the Contractor assumes responsibility that the PM guides are inclusive of all the required preventive maintenance requirements for equipment and systems in the building. The preventive or predictive maintenance standards proposed by the Contractor may be based on a combination of equipment manufacturer's recommendations, the PBS O&M Standards, (PM Guide), sensor technology, diagnostic software, Contractor's experience and other sources. The equipment requiring Contractor proposed preventive or predictive maintenance standards or guides shall include all of the building equipment when any of the following equipment characteristics apply:

a. The equipment normally requires periodic replacement of consumable components.
b. The equipment normally requires periodic or occasional cleaning.
c. The equipment has moving parts.
d. The equipment is prone to failure before overall obsolescence of the system it serves.
e. The equipment is of a type itemized in the NETA, Maintenance Testing Specifications.
f. The equipment requires inspection, testing, and maintenance in accordance with NFPA codes and standards.
g. The equipment requires maintenance in accordance with any other provision of this Contract.

NOTE: Infrared Surveys shall be conducted every three years (commencing in option period two) to include all switchgear, Motor Control Centers, disconnects, distribution panels, transformers and bus duct and all other critical equipment as stipulated by NFPA 70B. A copy of the infrared survey report shall be submitted electronically to the CO or his/her designee with findings and recommendations. Switch gear testing shall be conducted during the same time frame as the infrared testing and shall meet the requirements of NFPA 70B. Periodic circuit breaker testing shall be accomplished for breakers 400 amperes and above. Lower amperes breakers shall be tested as deemed necessary by the contractor, but at no additional cost to the government.

The Contractor shall not use any Contractor-proposed preventive or predictive maintenance standards or guides or any of the Public Buildings Service Operations and Maintenance Standards guides to perform inspections, testing, and preventive maintenance on fire protection and life safety systems and equipment. The Contractor shall be required to use the NFPA Codes and

Standards specified in this document to perform inspections, testing, and preventive maintenance of fire protection and life safety systems and equipment. In addition, the Contractor shall be required to follow the specific testing and inspection frequencies and methods specified in such NFPA Codes and Standards. The Contractor shall record such inspection and testing services on the appropriate NFPA inspection and testing forms.

Infrared Surveys shall be conducted ~~annually~~ to include all switchgear, Motor Control Centers, disconnects, distribution panels, transformers and bus duct. A copy of the infrared survey report submitted electronically to the CO or his/her designee with findings and recommendations. The periodic circuit breaker testing recommended in NFPA 70B should only be considered to be accomplished for breakers 400 amperes and above. Other breakers should be tested as deemed necessary at the contractor discretion but not at additional cost to the government.

NOTE: In the event of conflict between standards the more rigorous shall apply, to the extent that the standard is appropriate for the particular type and model of equipment. ALL GSA maintenance handbooks or preventive maintenance guides may only be used for informational purposes in the development of site specific PM programs. While the GSA guides and handbooks may be considered in the preparation of the PM Program, the document(s) presented for approval shall be specific to the building(s) and its equipment.

~~All equipment for which scheduled maintenance is to be performed less frequently than annually, i.e., every 2 years, every 3 years, etc., shall be scheduled to receive PM during the initial 12 months of this contract, and repeated at the prescribed intervals thereafter~~.

Eddy current testing on Chillers is not required on either the evaporator or condenser tubes.

Chiller Annuals are not required during the base year of the contract. Oil analysis shall be obtained annually, to include base year, tested and results forwarded to the CO or his/her designee as part of the monthly submittal.

The contractor shall not be responsible for any failures that occur to the chiller that could have been identified via eddy current testing or other analysis normally performed during an OEM annual chiller maintenance procedure.

For all pumps not related to Fire Life Safety (i.e. fire pump, sewage ejector, sump pumps and controls) PM maintenance actions are limited to lubrication of bearings (where required) and visual observation only.

On VAV's and PIU's that do not have filters, preventive maintenance is not required and shall be monitored by the BAS system for proper operation.

On AHU's with multimedia filters, the pre-filters are required to be changed at a minimum periodicity of semi-annual. Post filter changes shall be based on differential pressure readings. On AHU's with single filter media, the filters shall be changed at a minimum periodicity of semi-annual. VAV and PIU with filters shall be changed annually.

C.35.3 Application of Diagnostic Software

RESERVED

C.35.4 BAS Control Systems

Control systems shall be maintained as designed. The Contractor shall be responsible for keeping

building system software functioning and for upgrading/re-installing software on computers or building system controllers as necessary to keep current with manufacturer release levels and GSA IT support policies and procedures. The Contractor shall be responsible for making set point adjustments as necessary and appropriate to meet GSA objectives in building operations plan. This action requires the approval by CO .

The Contractor is also responsible for periodic backups when the OCIO's office does not provide this function. The Contractor is not responsible for upgrading software but should inform GSA of software update revisions and patches. The Government may upgrade or change control system software or reprogram control systems during the performance period of the Contract. If the Government provides operator level training and operator level documentation for the Contractor's use, the Contractor shall not claim additional payment for changing to the new or upgraded software or control programs. The Contractor shall not modify set points, sequences of operation or control programs or run systems manually without prior approval of the CO and regional facilities Subject Matter Experts (SME).

NOTE: ANY CHANGES TO SOFTWARE OR SEQUENCE OF OPERATIONS SHALL BE FIRST APPROVED BY FMSP REGIONAL ENERGY GROUP. (R4-energy-team@gsa.gov)

C.35.4.1 ***BAS Operating Standards***

All computers networked with building monitoring and control systems located inside GSA facilities, or which provide storage of and/or access to GSA data, which includes data related to energy usage, industrial systems controls, physical access controls, lighting controls are required to be hosted exclusively on GSA's physical network and system infrastructure, unless otherwise accepted. The contractor shall maintain the following minimum standards: ***Connecting to the GSA Network – Federal IT regulations regarding Trusted Internet Connection (TIC) in conjunction with PBS and GSA and GSA CIO's IT Policies require all PBS systems needing network connectivity to reside on the GSA network.***

C.35.4.1.1 ***GSA-hosted Systems Requirements***

a. All building monitoring and control systems, applications and devices will be implemented as designated in the P100 (2011 or newer) and the PBS Building Technology Policy. Additionally, all government IT systems are required to meet Federal Information Security Management Act (FISMA) standards for IT security.
b. All building systems software, server and workstations based, will be hosted on Government furnished equipment (GFE)
c. All IP traffic is managed by GSA, and IP addresses as well as all routing and switching equipment will only be furnished exclusively by GSA.
d. All vendors provided software that has an End User License Agreement must be presented to and approved by GSA Office of the General Counsel before that software is purchased.
e. Operations and Maintenance contractors are responsible for supporting all cabled path ways to include copper and fiber cabling, necessary to enable IP network communication among system devices and network components, to include all break/fix requirements. All new cabling, to include break fix, should be done in accordance with PBS Telecommunications Distribution and Design Guide.
~~f. Operations and Maintenance contractor is responsible for software, license and security updates to all vendor provided systems devices.~~
g. Operations and Maintenance contract staff must receive preliminary favorable and ultimately completely favorable adjudication of their National Agency Check with Inquiries clearance in accordance with the HSPD-12 directive to obtain a GSA ENT user credential, which is required for all system access.

h. At no time should a GSA hosted building monitoring and control systems be made accessible to the public internet or via any 3rd party network connection.

C.35.4.1.2 ***Excepted Systems Requirements (not hosted on GSA's system infrastructure) (ALL BUIL:DINGS IN THIS CONTRACT)***

a. An approved antivirus software subscription shall be kept in effect and the software used at all times.

b. All internet connectivity to the building control systems must be approved by GSA's Office of the Chief Information Officer.
c. All vendors provided software that has an End User License Agreement must be presented to and approved by GSA Office of the General Counsel before that software is purchased.
d. Contractor personnel shall be prevented from using the system to connect to Web sites not reasonably related to building operations.
e. Antivirus and spyware scans shall be conducted monthly.
f. The Operations and Maintenance contractor is responsible for keeping all workstation and server operating systems updated, to include Windows (or other operating system), JAVA, Adobe and all other standard software. Critical updates shall be downloaded and installed monthly.

g. Complete data backup to a CD, DVD or flash drive, to include trend logs and control software, shall be conducted whenever a software or programming change is made but no less frequently than monthly.
h. Disk drive maintenance to include defragmentation shall be performed quarterly

~~i. Operations and Maintenance contractor is responsible for software, licenses and security updates to all vendor provided systems devices.~~

C.35.4.2 Reporting

The Contractor is responsible for notifying the Government if a sequence of operations or its implementation as a control program is not producing the desired results or is resulting in unnecessary energy use. The Contractor is responsible for notifying the CO if any systems are running out of sequence or manually. All instances shall be reported to the CO immediately and documented in the monthly report. The Contractor is responsible for retaining an adequate level of expertise to manage the control systems. If the Contractor does not have a manufacturer trained or equivalent BAS operator onsite, the Contractor shall enter into a subcontract, including regular scheduled support (not merely support on a contingency basis), or remote access; with a firm that has these skills.

C.35.5 Smart Building Technology

RESERVED

C.35.6 Ongoing Commissioning /Re-Tuning - RESERVED

~~The Contractor shall conduct the six step Re-Tuning procedure described in the Pacific Northwest National Laboratory (PNNL) (http://retuningtraining.labworks.org/training/lms/). The initial frequency of the Re-Tuning is semi-annually. After completing two Re-Tuning cycles the CO in consultation with the Contractor will determine the appropriate frequency of the Re-Tuning effort based on the size and complexity of the facility.~~

C.36. WATER TREATMENT

C.36.1 General

The Contractor shall provide equipment, chemicals, and services (including application) required to control corrosion, scale, algae, and bacterial growth in all HVAC equipment and systems throughout the building. The Contractor shall be responsible for conformity with all pertinent Local sanitation district regulations, air quality district regulations, and other environmental regulations. Water treatment shall be performed and safety equipment (e.g., emergency eyewash stations) maintained in accordance with OSHA standards. **Water treatment application equipment shall not be on the initial deficiency list.**

C.36.2 Tolerances

Water shall be kept within tolerances indicated in Exhibit 9 Water Treatment.

C.36.3 Initial Report and Development of Program

The Contractor shall perform a comprehensive initial water treatment analysis (laboratory analysis) within 30 calendar days after contract start date to assist in developing the building-specific water

treatment plan. The Contractor shall propose a revised water treatment plan after initial water analysis to be approved by the CO .

C.36.4 Cooling Tower Management Plan

Refer to Exhibit J.9. The Contractor shall perform a comprehensive water treatment per the appendix in Exhibit J.9. This exhibit establishes mandatory standards for water in HVAC and domestic water systems in GSA facilities, along with information related to the intent of the standards and guidelines that in most circumstances can be used to construct a water treatment program.

C.36.5 Corrosion Monitoring

~~The Contractor shall install coupon racks, or an equivalent electronic monitoring system for corrosion, in condenser water loops, heating hot water loops, and the building main chilled water loop, if not already present, not later than 30 calendar days after submission of the water treatment plan (For the primary condenser water system, the installation of the water treatment monitoring system described elsewhere in this document meets this requirement). The Contractor shall propose the type and manufacture of the proposed coupon racks to be installed to the CO for final approval before installation. If coupon racks are present the Contractor may use such existing equipment, but is responsible for bringing it into conformity with all requirements in this document. The minimum quantity of coupons and frequency of inspections shall be described in the water treatment plan. Laboratory analysis of coupons shall be no less frequent than quarterly for major systems (e.g., primary building condenser and chilled water loops, as opposed to specialized systems serving limited areas), and annually for other systems. At a minimum, two coupon racks shall be installed for each loop, and used to monitor mild steel and copper. Coupon racks will be the property of the Government upon installation. The Contractor shall have responsibility for maintaining (and if necessary replacing) the coupon racks for the duration of the Contract. The liability threshold for repairs does not apply to this equipment; the Contractor has full responsibility. Acceptable corrosion rates are established in the most current Public Buildings Service Operations and Maintenance Standards. Molybdenum shall not be used in GSA buildings. See Section C.42.6, Water-Based Fire Protection Systems, which references NFPA 25 for information regarding evaluating corrosion of water-based fire protection systems. Contractors during their inspection of water-based fire protection systems shall verify such systems are free from corrosion.~~

During the second year of the contract, the contractor shall evaluate a minimum of three floors of wet sprinkler branch line piping for signs of obstruction, to include but not limited to, MIC (Microbiologically Influenced Corrosion), zebra mussels, inorganic material such as rust and scale, or other foreign manner (i.e work gloves, weld coupons, welding rods etc…). When investigating the branch lines it's not necessary to check all the piping rather a sample of the piping such as valves, couplings, tees, flow switches, sprinkler heads, or end caps. The contractor shall utilize a qualified sprinkler company trained and certified in obstruction testing to accomplish this requirement. The contractor shall conduct obstruction test on all dry pipe systems. Results from these tests shall be forwarded to the CO and Regional Fire Protection Engineer within 30 days of completion of testing. All such testing shall be performed after hours.

C.36.5 Monthly Testing

The Contractor shall provide a qualified independent water treatment specialist to draw a set of

water samples monthly. Tests shall be performed as described in the water treatment plan. Samples shall be analyzed and a monthly report containing all pertinent information, relative to the conditions found, shall be submitted to the CO with the monthly progress report. In facilities where makeup water is metered, makeup water quantities used shall be tracked and reported. Types and quantities of chemicals used shall be tracked and reported.

C.37. DIESEL FUEL, OIL ANALYSIS AND OIL CHANGES

C.37.1 Periodic Oil Analysis

The Contractor shall establish and implement an oil analysis program incorporating the manufacturer's recommendations. Documentation shall include periodic oil analysis tests to be performed at least annually, diagnostic standards, and thresholds for oil changes. Oil analysis shall be conducted to maintain a consistent methodology for data collection, analysis, and historical trending. Periodic oil analysis shall include, but is not limited to, chillers of 50 tons or greater cooling capacity and emergency generators. Periodic oil analysis shall be performed prior to annual maintenance requirements so that results may be considered in performing maintenance. Oil shall be changed only when oil analysis reports determine it to be necessary. Oil analysis subcontractor shall be identified in the subcontract plan.

When testing is performed, the Contractor shall submit a written report with the next monthly progress report. Where oil analysis indicates a need for corrective action, an appropriate work order shall be created in the CMMS and the appropriate corrective action taken by the Contractor.

C.37.2 Oil and Refrigerant Additives

Oil and refrigerant additives shall not be used.

C.37.3 Generator Oil

Generator oil shall be tested by a qualified third party vendor/subcontractor a minimum of annual and analysis and recommendations provided to CO or his/her designee. Testing shall be performed per ASTM D6595 (Wear Metals in Used Oils) and ASTM D445 or ASTM D72799 (Viscosity). Contractor shall take corrective actions and follow any recommendations provided from the testing facility. NOTE: Changing of oil in the generator is only to be performed based on testing and analysis recommendations from a UL approved laboratory and not to be done arbitrarily in a periodic schedule. Oil filters shall be changed periodically per manufacture recommendation or industry standards.

C.37.4 Diesel Fuels

A. Diesel Fuels: All Fuel tanks will be filled by the Government or the previous contractor at the beginning of the contract period and by the Contractor at the end of the contract period. All periods in between will be reimbursed as follows:

(1) Diesel Fuels: The Contractor shall check and record all diesel fuel tank levels monthly and provide monthly reports as a submittal. The contractor shall notify GSA immediately in the event the tank reaches 70% capacity. The contractor shall have GSA approval prior to refilling the fuel tanks. The government shall reimburse the contractor for all costs for fuel for Generator operations that are not related to routine testing of the Generator such as power outages or utility curtailment contingency operations.

B. Diesel Fuel Testing. Fuel oil shall be tested by a qualified third party vendor/subcontractor a minimum of annual and analysis and recommendations provided to CO . Contractor shall take corrective actions and follow any recommendations provided in the analysis. Fuel oil shall be conditioned and treated to maintain minimum quality standards established in ASTM D396-12 "STANDARD SPECIFICATION FOR FUEL OILS".

C.38. Lamps And Ballasts

The Contractor shall replace failed lamps, to include appropriate ballasts if required, with the most efficient products available in accordance with existing building standards defined by P-100 or CO or authorized representative. In lieu of such standards, lamps shall be replaced with the most efficient products available matching type and color temperature. **All light fixtures in one room shall have the same CRI rating.**

The Contractor shall establish and implement a lamping and ballasts recycling program for fluorescent tubes and light bulbs in accordance with Environmental Protection Agency (EPA) and GSA standards. **All Light Bulbs shall be disposed of as Hazardous waste/recycled.**

The use of bulb crushers is strictly prohibited.

All handling, storage, labeling and disposal of mercury containing tubes and bulbs shall be in compliance with Universal Waste Rule guidelines (http://www.epa.gov/osw/hazard/wastetypes/universal/index.htm)

The Contractor shall maintain the mercury content of all mercury-containing lamps below 75 pictograms per lumen hour, on weighted average, for all mercury-containing lamps acquired for the existing building and associated grounds. Screw-based compact fluorescent lamps may be excluded from this calculation if they meet the voluntary standards by NEMA. If the Contractor cannot find replacement lamps to meet this requirement while maintaining building standard lighting, the Contractor shall immediately bring this to the attention of the CO . The Contractor shall maintain documentation of all purchases of mercury-containing lamps and provide the information within the monthly progress report to the CO .

C.39. Architectural And Structural Systems Maintenance

C.39.1 General

The Contractor shall maintain, repair, replace, modify, and restore all of the architectural and structural components of the building. In general, these components include walls, floors, doors, windows, docks, levelers, lighting, and all items that are part of or otherwise associated with them.

Roof maintenance shall include inspection and removal of debris from the roof. Contractor shall make a temporary repair to stop the leak and prevent water intrusion into the building (Note: major roof repairs (repairs in excess of ~~$2500.00~~ $1,000) are not a part of this contract). The contractor shall provide diagnosis services as necessary to determine the origin of the roof leaks. The cost of the diagnosis services shall be applied towards the ~~$2500.00~~ $1,000 repair threshold. This dollar threshold applies to each individual repair job or replacement that may be required per each piece of equipment.

The Contractor shall conduct routine inspection and maintenance and repair of interior and exterior and architectural and structural systems components. All replacement items and parts shall be either the same quality or better than the manufacturer's original parts.

C.39.2 Maintenance and Repair

The Contractor shall perform all architectural and structural maintenance and repairs or replacements to all equipment, electrical and mechanical systems, structures, architectural finishes, and utilities, located on, within, or beneath, this facility's interior and exterior extending to the legal property line**.** The Contractor shall ensure the building is free of missing components or defects that could affect the

safety, appearance, or intended use of the facility or could prevent any electrical, mechanical, fire protection and life safety, plumbing or structural system from functioning in accordance with its design intent. The Contractor shall use approaches that preserve and protect native plants and wildlife that is entrusted to the Government, and that support habitats for pollinators, including honey bees, native bees, birds, bats, and butterflies, to comply with new Executive Orders

C.39.3 Repair and Replacement Work

Repair and replacement work shall be complete, including touch-up painting and operational checks. The quality of the work shall ensure that repaired areas are fully compatible with and match adjacent surfaces or equipment. All replacement items shall be consistent with design documents and match existing equipment in quality, dimension, and material, quality of workmanship, finish, and color.

C.39.4 Painting

Painting is considered "touch-up," for purposes of this Contract, when it is to repair a specific damaged area of paint. Painting should extend to logical break points such as the floor ceiling corner, doorway etc. to avoid a patched look.

Repainting to correct for normal wear and tear to painted surfaces over time is not required. Restriping of parking areas, driveways, roads, and vehicle inspection areas is required where striping is damaged or worn in a specific location, but not for general wear and tear of a large area over time. Repairs to pavement are required where a specific location is damaged but not where an extensive area is degraded. Painting in mechanical areas needed for OSHA compliance, consistent equipment appearance, or other safety reasons is required. If the Contractor must disturb materials he suspects may contain lead-based paint, the Contractor must immediately report the condition to the CO .

The machinery rooms including floors and the equipment located within the machinery rooms shall be painted as necessary to maintain the appearance of the room and equipment. When painting, the contractor must comply with the ANSI color coding system outlined in the ASNI A13.1, Scheme for the Identification of Piping Systems, and maintain the identity (identification number) of the equipment. ~~Machinery spaces, shops and storerooms shall be scheduled to be cleaned and painted (Floors only) in the initial 12 months of this contract and shall be repeated as required thereafter.~~ When work is performed in these areas, the Contractor's personnel shall clean up all debris and leave the area in a presentable condition. The machinery rooms, including floors and the equipment located within the machinery rooms, shall be painted as necessary to maintain the appearance of the room and equipment**. Floors that have not been previously painted shall not be required to be painted as part of this SOW. Unpainted floors shall be swept and scrubbed as necessary to** maintain a professional and clean appearance. When painting, the Contractor shall have the colors utilized approved by the CO . The contractor shall not paint over name plates in order to maintain the identity (identification information) of the equipment.

C.39.5 Interior Signage and Directories - RESERVED

~~The Contractor shall maintain and update building directories, to include electronic directories and tenant common corridor signage but not electronic directories that belong to our building tenants.~~

~~The Contractor shall repair damaged interior or exterior signage in accordance with the repairs~~

~~provisions in this document. Other changes to interior or exterior signage may be ordered from the Contractor as reimbursable items under the additional services provisions in this document.~~

C.39.6 Finishes Maintenance

The Contractor shall ensure finishes are maintained to the manufacturer's specifications and levels that preserve a professional appearance and the integrity of the protected surface. The Contractor shall provide touch-up paint on repaired surfaces that seamlessly matches the surface and condition prior to degradation and repair.

C.39.7 Historic Building Preservation

The Contractor shall provide services that protect and preserve the historical integrity of the building. The Contractor shall consider any building 50 years old as historically significant, regardless of National Register status. The Contractor shall ensure any alteration of the building performed by the Contractor or their subcontractor protects the architectural integrity and compatibility with existing building structural accoutrements. The Contractor shall consult with the CO and obtain a copy, if available, of the building Historic Building Preservation Plan (HBPP) or Historic Structure Report (HSR) prior to any renovation work performed under this Contract on a building 50 years old or older. It may be possible that an HBPP has not been developed for the buildings at the time of this Contract award. In addition to the HBPP or HSR, the Contractor shall obtain a copy of The Secretary of the Interior's Standards for Rehabilitation and Guidelines for Rehabilitating Historic Buildings. These documents shall be followed for Government purposes in the preservation of buildings. The Contractor and CO shall examine the requirements of any applicable documents for maintenance recommendations and specifications. If a conflict exists between applicable documents and Contract requirements, the Contractor shall not proceed until directed to do so by the CO . The Contractor shall protect any work of art (painting, sculpture, carving, etc.) in the project area or close vicinity from possible damage during any renovation to the structure.

The Contractor shall protect any work of art (painting, sculpture, carving, etc.) in the project area or close vicinity from possible damage during any renovation to the structure.

C.39.8 Vertical Transportation and Associated Elevator Equipment

The Contractor is responsible for maintaining fire protection equipment, dewatering, and systems within hoist ways, pits, elevator lobbies, and elevator machine rooms. The Contractor shall provide assistance in performing elevator testing, including after normal work hour requirements.

The Contractor is responsible for maintaining elevator car lighting system, electrical equipment not directly part of elevator systems, and HVAC systems associated with elevator machine rooms and systems. **The elevator contractor is responsible for replacing the lighting in the machine room and hoistway but the O&M contractor must provide the bulbs and ballast .**

In emergency situations, such as elevator car entrapments, the contractor is not to remove passengers or manipulate elevator equipment. The contractor shall notify GSA and emergency response personnel of any elevator entrapments. All entrapped passengers are to be handled by the elevator maintenance contractor and/or emergency personnel (firefighters, police offices, etc.)

C.39.8.1 Elevator Communications and Alarm Test RESERVED

~~The Contractor is responsible for testing the elevator phones and alarm tests at least once a week where there are 7 elevator units or less in the building. Test shall be performed bi-weekly where there are 8 elevator units or more and shall be divided equally or as best suited. Where there are 8~~

~~units or more, the units may be divided equally with half the units tested during one week and the balance tested during the alternate week. GSA will provide the Elevator Communication and Alarm Test Documentation form to be used by the contractor. Completed Elevator communication and test forms shall be submitted in the monthly progress reports.~~

C.39.9 Flag Procedures

The Contractor will raise, lower, and place at half-staff the United States Flag, Agency pennants, and other flags (POW flag). This service shall be provided when directed by the CO or his/her designee and shall comply with requirements in the Flag Policy at no additional costs to the government.

Raise/lower U.S. flag and the MIA/POW flag per Public Law 94-344 and GSA Flag Policy in properties and instances where contract security, Federal Protective Services, Department of Homeland Security, U.S. Marshal Service, or Court Security Officer does not perform such duties. The raising and lowering of the flag on special occasions and local or national declared events of honor or mourning is considered part of the contract will be reimbursed at miscellaneous labor rate.

Flag flying includes holidays, weekends and all designated days referenced in Public Law 94-344 and is considered as no additional expense to GSA.

C.40. REPAIRS

C.40.1 General

The Contractor shall perform reimbursable and non-reimbursable repairs as described in this document. Repairs are handled on a shared liability basis (See shared liability math example in C.40.3 Reimbursable Repairs). Relatively small value repairs (non-reimbursable repairs) are the responsibility of the Contractor in their entirety, and larger repairs (reimbursable repairs) shall be approved and funded by the Government for the cost amount above the Contractor threshold. If damage is caused by Contactor negligence, the Contractor shall be liable for the full cost of repair, any other provisions notwithstanding. The intent of this Contract is to ensure that most repairs will be accomplished by in-house Contractor personnel. However, the Government recognizes that occasionally there are certain specialized repairs that require specialized skills outside the skill sets of the in house O&M personnel. If the Contractor identifies a repair that they believe is of such a specialized nature that a specialized subcontractor is required to properly complete the repair, the Contractor shall provide written justification in advance, to the CO , for approval of the need to use a subcontractor. The Contractor shall not use subcontractors to perform non-reimbursable repairs unnecessarily or with the intent of driving up the repair cost so the Government shall cover part of it. If approved, the cost of the subcontractor's labor and material will be treated as a repair part and material cost for the purposes of calculating the repair threshold. The subcontractor's cost shall be fair and reasonable and approved in advance by the CO . All repairs shall use supplies, materials, and parts of the highest quality available that are appropriate for the repair of the given equipment or system. Any replacement parts used during the course of this Contract shall be of comparable or higher quality. Energy-consuming items shall be the most efficient in their class. The Contractor shall stock commonly used items and have a network of suppliers that will deliver ordered items without any delay. Any replacement motors shall be of premium efficiency. Whenever motors are replaced, motor size shall be recalculated and replacement motor selection shall reflect the appropriate size.

The Contractor shall be responsible for accomplishing all architectural and structural or

maintenance repairs/replacements where the cost of equipment and materials is expected to be ~~$2,500~~ $1,000 or less. This dollar threshold applies to each individual repair job or replacement that may be required.

Refrigerant is considered a supply and the Contractor shall be responsible for all costs associated with it. This includes but not limited to any new refrigerant and/or reclamation of existing refrigerant associated with any repairs.

In the event of a total loss of refrigerant the contractor will not be responsible for any refrigerant unless it is due to contractor negligence.

C.40.2 Non-Reimbursable Repairs

A non-reimbursable repair is a repair requiring no more than ~~$2,500~~ $1,000 in cost for **repair parts and materials only** but no labor cost is included (including any approved subcontracting costs). Non-reimbursable repairs are entirely the Contractor's responsibility with no reimbursement from the Government.

Non-reimbursable repairs shall be completed within 24 hours of identification of the problem unless an extension is approved by the CO. The work order shall be put into a status field in CMMS to indicate the nature of any delay, with appropriate remarks.

C.40.3 Reimbursable Repairs

Reimbursable repairs will be identified as single incident, not an accumulation of various repairs (bundling). If a repair exceeds the non-reimbursable repair cost threshold established above and has been approved and verified by the CO, it becomes a reimbursable repair. Reimbursable repairs are reimbursable to the Contractor, once approved by the CO, for the portion (shared liability) of the cost exceeding the non-reimbursable threshold of ~~$2,500~~ $1,000 (See repair shared liability example below).

~~C.40.4~~ Miscellaneous Work ~~-RESERVED~~

~~The Contractor shall provide 120 ("in-house" manhours additional services HVAC labor) per building per year and $0 (zero dollars) for parts and supplies per calendar month, per building (hours and dollar amounts per building are not cumulative to succeeding months) when requested by the CO, to accomplish discretionary work in the buildings covered by this Contract. No labor shall be included. The Contractor shall furnish the labor, tools and consumable materials as necessary to perform the work. Miscellaneous work may be required for work that makes use of any of the trades normally employed in performing operations and maintenance services under this Contract and does not include tasks associated with the performance of services covered under the scope of this Contract. The Contractor shall create and process CMMS work orders for all miscellaneous work, and accurately record hours of labor expended.~~

The Contractor shall provide in-house miscellaneous mechanical labor to accomplish discretionary work at any of the buildings covered by this Contract, when provided written requested by the CO or designee. When miscellaneous work is requested, the contractor shall be entitled to reimbursement at the miscellaneous labor rate specified in the bid schedule. The Contractor shall furnish the labor and in-house available tools, as necessary, to perform the work.

C.40.5 Repair Shared Liability Example:

In this example, assume the non-reimbursable repair threshold is ~~$2,500~~ $1,000.
A repair is identified and estimated by the Contractor to cost $3,000.00 **for repair parts and materials only.** The contractor shall not charge labor for his/her employees unless the work must be **unreasonably** performed after hours when the work could be reasonably performed during hours. Work that disturbs tenants such as disruptions of power to large areas or the entire facility, water to the facility or large areas, fire system protection, indoor air quality, creates loud noises, or other work the CO or his/her designee determines, shall be considered **reasonable** to conduct after hours and the contractor shall not be allowed to charge his/her employees labor. If work **must** be performed by a sub-contractor then all cost charged by the sub-contractor may be applied towards the repair threshold.

The CO will verify and approve both the need for the repair and the $3,000.00 estimated cost of repair parts and materials. In this example, the Contractor will pay the first ~~$2500.00~~ $1000.00 of the repair and GSA will pay the remaining ~~$500.00.~~ $2000.00

1. Total estimated approved cost for repair parts and materials to complete repair $3,000.00

2. Contractor's shared liability amount to be subtracted (same amount as the non-reimbursable threshold) - ~~$2500.00~~ $1000.00 NOTE: The contractor must deduct ~~$2500.00~~ $1000.00 prior to applying any approved profit or fees.
3. Total to be paid by GSA to the Contractor for the repair $2000.00 plus profit and fees.

The required completion date for reimbursable repairs shall be established when the CO approves the work, as mutually agreed upon by the COR and the Contractor. The Contractor shall attempt to complete work as promptly as feasible.

Immediately upon identification of a reimbursable repair, the Contractor shall create a work order in the CMMS and defer it by putting it in a "hold" status.

C.40.6 Approval of Work

When the Contractor determines that a repair is needed that exceeds the non-reimbursable repair threshold, the Contractor shall immediately notify the CO . The CO shall issue an order to the Contractor before the Contractor may proceed with the repair. The Contractor may defer performance of the reimbursable repair by placing the corresponding work order into a "waiting for funding" status from the time a valid proposal is given to the CO until the time an order is given to the Contractor. The time during which the work order is thus deferred will not count against the Contractor in calculating timeliness. The CO may prohibit the use of subcontractors if the CO determines the Contractor is unnecessarily driving up the cost of the work and the Contractor's own employees have the skills necessary to perform the work.

C.40.7 Invoicing

The Contractor shall invoice the Government for completed reimbursable repairs authorized.

The Contractor shall invoice the Government for completed reimbursable repairs authorized.
If the Contractor directly purchased parts or components, copies of receipts shall be attached. Reimbursable repairs authorized by task order may be invoiced separately upon completion and acceptance of work. Itemized invoices shall also contain references to CMMS work order

numbers.

C.40.8 Ordering Repairs from Outside Source

The Government reserves the right to order repairs from an outside source. If the repair is a reimbursable repair, the Government will inform the Contractor of the outside source's price, and deduct $1000, or the outside source's price, whichever is less, from the Contractor's payments.

C.40.9 Force Majeure (Uncontrollable Events)

Deficiencies or breakdowns caused by vandalism, misuse, abuse, or acts of God including natural disasters are fully reimbursable. The Contractor will be reimbursed under the additional services provisions described in this document or the Government will have the work performed by other means at no cost to the Contractor.

C.40.10 Warranties

The Contractor shall contact installers or manufacturers, as appropriate, for work that is covered under a warranty and maintain records of warranty service. The Contractor shall avoid actions that would invalidate a warranty, unless authorized by the CO. If an installer or manufacturer fails to comply with the terms of a warranty, the Contractor shall immediately notify the CO.

C.40.11 Quality of Materials and Replacement Parts

Replacement components and materials shall be of similar or better quality than the components replaced, considering energy efficiency, operational characteristics, power quality, control and data acquisition, maintainability, and durability. The CO may require replacement of components with components from the same manufacturer to maintain consistency throughout the building. Materials and parts that are visible to building occupants shall be to building standard and maintain the same appearance as similar materials and parts in the occupied space. Components of control systems shall be replaced so as to maintain the tie-in to the control system with no degradation of data throughput, memory, point capacity, data acquisition, or programmability. Motors shall be replaced with premium efficiency motors as defined by the NEMA MG-1 standard or in compliance with Local utility guide demand-side management rebate guidelines old transformers shall be replaced with NEMA-rated class one efficiency transformers in accordance with the NEMA TP-1 standard. Replacement of variable frequency drives shall be done in accordance with recommendations found in NEMA, Application Guide for AC Adjustable Speed Drive Systems. Energy Star-rated equipment shall be installed where available and when there is no engineering or operational reason not to select an Energy Star product.

C.41. SAFETY AND ENVIRONMENTAL MANAGEMENT

C.41.1 General

The Contractor shall use to the extent practicable, the safest and most environmentally friendly products and processes available. The Contractor shall be cognizant of and comply with all Federal, State, and Local laws and Regulations related to building management (permitting, inspection, testing and personnel safety; control of hazardous substances, certification) to include materials and associated systems used or removed in the performance of this contract. Contractor and shall comply with all such requirements, including record keeping. The Contractor shall comply with all Federal, State, and Local environmental and safety laws and regulations that relate to the maintenance and operation of equipment and systems within the scope of this Contract. The Contractor will be responsible for any fines or penalties levied by any environmental or regulatory authority resulting from their action or inaction,(not actions or inactions from a third party or the government) and may be charged the cost as a performance deduction under the Adjusting Payments clause. The Contractor's maintenance, operations, materials and processes shall use green products and processes including, but not limited to products containing recycled content, environmentally sustainable products and services, bio-based products, and products and services that minimize the use of energy, water, and other resources.

C.41.2 Scheduling and Recordkeeping

The Contractor shall maintain copies of all tests, certifications, permits and other required records, and provide copies to the CO and designee. In addition, all required safety and environmental tests; certifications, permits, and other procedures required in this document shall be scheduled in the CMMS work order system and documented in the CMMS or by other means if a CMMS is not available.

C.41.3 Refrigerants

C.41.3.1 Control and Certification

The Contractor shall control refrigerants and maintain records in accordance with EPA, GSA**,** and air quality management district standards. The Contractor shall take appropriate immediate action and report leaks to the CO .

The Contractor shall maintain and test refrigerant monitors and alarms and purge ventilation systems as part of the maintenance program. Testing shall use appropriate media to test sensors as well as alarm circuitry.

Refrigerant control logs shall be updated as required, and a copy sent to the CO in the monthly progress report. The Contractor shall also maintain a set of logs onsite and make this set of logs available for Government inspection.

C.41.3.2 Certified Handlers

Contractor employees who come into contact with refrigerants in the course of their duties shall be certified to handle such refrigerants. If equipment containing chlorofluorocarbon (CFC) or hydro chlorofluorocarbon (HCFC) refrigerants is removed from operation under this contract, the Contractor shall recover all refrigerant in the equipment, seal it in appropriate storage containers, reclaim and reuse it as directed by the CO , or dispose of it within EPA guidelines. In the event fines or penalties are levied by the EPA or an AQMD, the Contractor may be charged the actual cost assessed government Deduction will be taken from the monthly payments.

C.41.4 AIR QUALITY MANAGEMENT DISTRICT (AQMD) Operating Permits

The Contractor shall be familiar with the requirements of the Local Air Quality Management District (AQMD), and shall ensure operating permits for boilers; generators and other emissions-producing equipment regulated by the district are up to date and have copies available to the CO . In the event of fines or penalties levied by an AQMD, the Contractor may be charged the cost as a performance deduction will be taken from the monthly payments.

C.41.5 Fuel Storage Tanks

The Contractor shall:

a. Comply with all Federal, State, and Local requirements for the periodic inspection, monitoring, permitting, certification, registration, maintenance, personnel training and recordkeeping for underground and/or above ground storage tanks.
b. Comply with any additional responsibilities required by the facility's Spill Prevention, Control and Countermeasure (SPCC) Plan including, but not limited to inspections, training, and recordkeeping if the facility must comply with SPCC requirements. Contractor shall update the SPCC plan as required.
c. Validate the inventory of all tank systems and assess tanks for compliance with current environmental design and installation standards at the commencement of the Contract.
d. Notify the CO not later than the end of the Startup Transition Phase and record within the Existing Deficiency/Initial Inspection Deficiency list observed instances of non-compliance to include but not limited to required registration documentation and monitoring systems.
e. Record the fuel levels monthly and report findings in Monthly Progress Report.
f. Record monthly usage logs and follow all fuel unloading procedures**.**

g. Contractor shall ensure that on-site personnel are trained and certified to the appropriate ***level of Underground Storage Tank Operator training***.

C.41.5.1 Underground and Above Ground Storage Tanks

The Contractor is responsible for complying with all Federal, State, and local requirements for the periodic inspection, monitoring, permitting, certification and maintenance of underground storage tanks.

UST/AST TRAINING REQUIREMENTS

C.41.5.2 Underground/Above Ground Storage Tanks

According to revisions to 40 CFR part 280 (http://www.epa.gov/oust/fedlaws/proposedregs.html) UST operators must be certified by state approved trainers by August 8, 2012. Each state has the authority to design its own training course and requirements may vary. The following is the location for the requirements for the State of Florida, http://www.dep.state.fl.us/waste/categories/tanks/.

UST Operator Training is designed to ensure that UST operators operate their tank systems in a manner that is compliant with state and federal requirements, and that will prevent product releases that could endanger human health and/or the environment.

C.41.5.3 Who Needs to be Trained

Each underground storage tank facility must have a Class A, Class B, and Class C operator designated for that facility. Separate individuals may be designated for each class of operator, or an individual may be designated to more than one of the operator classes. An individual who is designated to more than one operator class must be trained in each operator class for which he or she is designated. Class A or Class B operators will be responsible for making sure their Class C operators are properly trained.

The general description for each class of operator is as follows:

Class A Operator

Person having primary responsibility for on-site operation and maintenance of UST/AST system. Class A operator typically manages resources and personnel, such as establishing work assignments, to achieve and maintain compliance with regulatory requirements.

Class B Operator

Person having daily on-site responsibility for the operation and maintenance of UST/AST system. Class B operator typically implements in the field aspects of operation, maintenance, and associated recordkeeping for an UST system.

Class C Operator

Daily, on-site employees having primary responsibility for addressing emergencies presented by a spill or release from an UST system. Class C operator typically controls or monitors dispensing or sale of regulated substances.

C.41.6 Solid Waste Audit

"Reserved"

C.41.7 Polychlorinated Biphenyl (PCB) Control

"Reserved"

C.41.8 Facility Hazards

The Contractor shall assist in identifying facility health and safety hazards and report all hazards in writing to the CO on GSA Form 3614, GSA Notice of Unsafe/Unhealthful Workplace Conditions. The Contractor shall take immediate action to control hazards that present an imminent danger.

C.41.8.1 Hazardous Waste

The Contractor shall be cognizant of, and comply with, all Federal, State, and local laws and regulations related to the disposal (landfill, sewer discharge, etc.) of hazardous waste and materials used or removed in the performance of the contract or discharged by the building, and shall comply with all such requirements, including record keeping requirements.

Fluorescent lamps, batteries, and other items in any quantity subject to the Universal Waste rules for hazardous waste management and disposal shall be recycled or disposed of properly.

All fluorescent lamps will be recycled. For purposes of this contract, lamp, also referred to as "universal waste lamp," is defined as the bulb or tube portion of an electric lighting device. Examples of common universal waste electric lamps include, but are not limited to, fluorescent, including compact fluorescent lights, green tip style lamps/bulbs, high intensity, discharge, neon, mercury vapor, high pressure sodium, and metal halide lamps.

C.41.9 Workplace Safety

The Contractor shall develop a site-specific occupational safety and health program specifically addressing applicable components of 29 CFR 1910 and 29 CFR 1926. The safety and health program shall be submitted to the CO for review and approval 30 calendar days after contract award date. By approving the program, GSA assumes no responsibility for the Contractor's occupational safety and health program.

C.41.10 Electrical Safety

The Contractor shall comply with National Fire Protection Association (NFPA) 70: National Electrical Code and NFPA 70E: Standard for Electrical Safety in the Workplace, when working on or around electrical equipment or systems or switchgear equipment. The Contractor shall ensure that any and all areas restricted to qualified personnel are secured and properly labeled.

C.41.11 Fall Protection

The Contractor shall develop specific fall protection procedures for work on roofs, equipment, and other areas at elevation. The Contractor shall ensure fall protection equipment is provided to their employees and that employees are adequately trained.

C.41.12 Powered Platforms

The contractor shall inspect, test, and maintain all permanently installed powered platforms in accordance with 29 CFR 1910.66, and provide copies of such certifications to the CO .

C.41.13 Lockout/Tagout

The Contractor shall develop a lockout/tag out program in accordance with 29 CFR 1910.147. The program shall include all anticipated energy sources, including but not limited to, electric City, steam, pressurized fluids, and mechanical energy. The Contractor shall communicate the Lockout/Tagout program to all other affected Contractors. Contractor shall record all identified confined spaces in the CMMS as hazards.

C.41.14 Confined Spaces

The Contractor shall identify and label all confined spaces in accordance with OSHA requirements.
The Contractor shall develop a confined space entry permit system for all permit-required confined spaces within 30 calendar days of commencement of the contract.

Contractor shall record all identified confined spaces in the CMMS as hazards.

C.41.15 Asbestos Management

The Contractor shall be expected to occasionally perform Class III and Class IV asbestos work as defined in 29 CFR 1926.1101. The Contractor shall be prepared to deal with asbestos on a small-scale, short-duration basis to effect emergency repairs and to clean up small spills. The Contractor shall protect building tenants, visitors, and employees from asbestos exposure. The Contractor shall comply with applicable OSHA regulations and all applicable Federal, State, and Local asbestos regulations. The Contractor shall immediately become familiar with, comply with, and recommend any appropriate changes to the Government Asbestos Management Plan for the building. If the Contractor must disturb materials he suspects may contain ACM, the Contractor must immediately report the condition to the CO . Contractor personnel who perform the abovementioned work shall have been appropriately trained in accordance with 40 CFR Part 763.

In the event of ACM fiber release (episode <3 sq ft/3 linear ft), procedures outlined in M-29 of the NIBS manual shall be followed. Fiber release episodes exceeding the above level shall be considered a Major Episode Release and appropriate Emergency Response Procedure shall be followed per NIBS manual and EPA Green Book. ACM abatement >3 sq ft/3 linear ft shall be performed by a licensed ACM abatement contractor and approved by GSA.

ACM warning labels for ACM and non-ACM shall be affixed to all accessible thermal system and other known and unknown ACM per 40 CFR part 763.121 (k((iii).

Works Practices for O&M Contractor for any and all ACM work shall conform to all applicable Federal EPA, OSHA, and DOT Regulations and Standards and State and Local guidelines and laws (see references pages for applicable Asbestos Regulations) for the level of work being conducted and Best Management Practices expected on a daily basis. All ACM issues and work will be reviewed and approved by GSA prior to the work being conducted and final clearance given for post work closeout.

The contractor shall ensure that all his/her mechanical employees have received initial worker training and refresher O&M workplace asbestos training. The contractor must provide proof of the completed training **no later than 90 days** after contract award.

The following building(s) contain Asbestos Containing Materials (ACM's):

Location	Yes/No
(1) Federal Building (FL0019ZZ)	Yes

C.41.16 Hazardous Materials

C.41.16.1 MSDS

The Contractor shall make material safety data sheets (MSDS) available to their employees in accordance with 29 CFR 1910.1200. MSDS shall also be made available to the CO on request. The Contractor shall prepare and submit a hazardous materials inventory as an appendix to the building operating plan. The inventory shall itemize all hazardous materials by specific type as sold with individual MSDS and include information pertaining to approximate quantities of each type and exact locations where hazardous materials are to be stored on the premises.

C.41.16.2 Disposition of Hazardous Waste

Hazardous Wastes not subject to the Universal Wastes Rule shall be managed in accordance with 40 CFR 260. Universal Wastes (fluorescent lamps, certain batteries and pesticides) in any quantity subject to the Universal Waste Rules shall be recycled or disposed of as Hazardous Waste. Preference is given to recycling of intact items.

C.41.16.3 Environmental Report

Reserved

C.41.16.4 Recycled Content Product Purchase Annual Reporting

The Contractor shall provide reports, estimating the percentage of total recovered material used in Contract performance, including, if applicable, the percentage of post-consumer material content, to the CO in compliance with the Contractor schedule.

C.41.16.5 Non-Bio-based Products

The Contractor shall report all non-bio-based products to include: green seal, Design for the Environment (DfE), CPG, and environmental choice, (low VOC, non-ozone depleting) as well as non-green (hazardous/ toxic products).

To facilitate the collection of report data for biobased purchases, the FAR has been amended based on final rule 78 FR 46794, which now requires contractors to submit their biobased reports to https://www.sam.gov/.

C.41.16.6 Bio-Based Products

For categories of items that are EPA-designated (e.g. Comprehensive Procurement Guidelines [CPG]) and USDA designated in the BioPreferred Program (visit http://www.biopreferred.gov/), and all other factors (such as price, performance, and availability) being equal, the contractor shall selected the CPG item. For other purchases, unless the contractor receives an exemption from the Contracting Officer, the contractor shall select USDA designated products over products with other sustainable attributes

The Contractor shall report all USDA-designated bio-based products purchased October 1 - September 30, during the previous fiscal year. Information will include the types and dollars spent on these products. The Contractor shall submit the report to USDA designated location and a copy

to the following email address: PBSbiobasedreporting@gsa.gov no later than October 31 of each year during Contract performance and at the end of Contract performance. In addition, the reports shall be submitted to the environmental point of contact (EPOC) as identified in FAR Clause 52.223.2, and a copy to the CO .

C.41.17 Boiler/Pressure Vessel Operation and Inspection Standards

C.41.17.1 Boiler Operation and Inspections

Boiler operation and inspections shall be in accordance with applicable codes and regulations including but not limited to:

a. ASME Boiler and Pressure Vessel Code.
b. National Board Inspection Code.
c. Environmental Protection Agency and local AQMD requirements.
d. ASME CSD-1, Control & Safety Devices for Automatically Fired Boilers.
e. NFPA 85, Boiler and Combustible Systems Hazards Code.

C.41.17.2 Inspections and Tests

Annual boiler inspections shall include internal and external (operating) inspections and tests described in Chapter 2, Inspection of Boiler and Pressure Vessels, of NBIC. **Boilers shall be inspected at a minimum of annually**. The Contractor shall require the inspector to complete GSA Form 349 (Inspection Report of Boiler) or an equivalent approved form for each boiler inspected. The Contractor shall have unfired pressure vessels with design operating pressure in excess of 60 pounds per square inch (psi) and a capacity in excess of 15 gallons inspected annually. The Contractor shall complete GSA Form 350 (Inspection Report of Unfired Pressure Vessels) or an equivalent approved form for each unfired pressure vessel inspected. A GSA Form 1034 (Certificate of Inspection) or an equivalent approved form shall be completed and posted on or near the equipment. Inspections shall be made by inspectors certified by the National Board of Boiler and Pressure Vessel Inspectors, who shall be employed by an independent firm specializing in boiler and unfired pressure vessel inspections.

The contractor shall provide a copy of the inspection report and certificates as part of his/her monthly submittal. In addition the contractor shall post a copy of the certificate in a professional manner on a wall as close as feasibly possible to the device(s).

C.41.17.3 Backflow Prevention Devices

The Contractor shall maintain all existing backflow prevention devices and certify them as prescribed by Federal, State, and Local laws, ordinances, and regulations. If no Local requirement exists, a certified inspector shall inspect all existing backflow prevention devices on an annual basis, record the inspection as a work order in the CMMS and provide certification of proper operation to the CO . While the Government will generally pass on to the Contractor backflow testing notices received from Local water districts or other Local authorities, the Contractor is responsible for timely completion and submission of such test results regardless of receipt of such notices. In addition to other requirements, backflow prevention devices used on water-based fire suppression systems shall be inspected, tested, and maintained in accordance with NFPA 25.

The contractor shall provide a copy of the inspection report and certificates as part of his/her monthly submittal. In addition the contractor shall post a copy of the certificate in a professional manner on a wall as close as feasibly possible to the device(s).

C.41.17.4 Potable Water Systems

The Contractor shall comply with The Safe Drinking Water Act, PL 99-339, as amended, and the Environmental Protection Agency Safe Drinking Water regulations (40 CFR 141.43, Sections A and D), which address the quantity of lead allowable in new installations or repairs to existing drinking water systems and or plumbing. Potable water systems that are repaired, modified, serviced, or breeched in any way shall be disinfected and flushed as needed prior to returning the system to service. Contractor is required to comply with all Federal, State, and Local codes in the operation, treatment, and testing of potable water systems.

C.41.18 Labeling and Signage

The Contractor shall maintain the labeling of existing equipment, pipes, storage areas, containers, confined space, and workspaces as well as associated signage, in accordance with OSHA standards to ensure labels are visible and not obliterated. Any equipment, pipes, etc., newly installed by the Contractor require labeling and signage per OSHA standards shall be labeled immediately upon completion of the installation and maintained throughout the contract period.

C.41.19 Roof Anchorage Points ~~RESERVED~~

~~The Contractor shall provide for an annual inspection of designated roof anchorage points by qualified personnel. Anchorages shall be inspected in accordance with the anchor manufacturer's requirements and additional requirements contained in the installation certification. Copies of the inspection reports shall be provided to the CO or designee. If an area of suspicion is identified, the anchorage shall be tagged "out of service" and immediately reported to the CO or designee. ANSI/IWCA I-14 may be consulted for further guidance.~~

GSA is responsible for certifying anchorage points on a 10 year basis. Sub-contractors performing any work that require use of roof anchorage points shall include the pricing for annual inspection of these points in their proposals.-If an area of suspicion is identified, the anchorage shall be tagged "out of service" and immediately reported to the CO or designee. ANSI/IWCA I-14 may be consulted for further guidance.

C.42. Fire Protection And Life Safety Equipment And Systems

C.42.1 General

Each of the requirements listed below shall apply to all of the paragraphs in Section C.42:

a. The Contractor is responsible to utilize the latest edition of the applicable NFPA code or standard, in effect at the time of contract award, throughout the term of the contract.
b. The Contractor shall ensure all fire protection and life safety systems and equipment are kept operational at all times, except while being tested or repaired.
c. The Contractor shall ensure all maintenance and preplanned impairments of the fire protection and life safety systems and equipment have been authorized and approved by the CO prior to the Contractor performing any work.
d. The Contractor shall utilize technicians that meet the applicable requirements in Section H15.3.

e. The Government reserves the rights to have the Contractor remove any employee that poses a threat to the health, safety, or security of the building occupants.
f. The Government reserves the rights to conduct any test or inspection it deems necessary to ensure all contract performance requirements are being met.
g. The Contractor shall comply with all appropriate safety code requirements. If the Contractor encounters equipment that is in a condition that may endanger life or property, the Contractor shall immediately notify the CO of the condition requiring immediate action. Within 24 hours following the notification of the CO, the Contractor shall provide to the CO a written report of the hazardous condition and recommended corrective action.
h. The Contractor is responsible for meeting the inspection and testing frequencies, test methods, and documentation requirement for each fire protection and life safety system referenced in the applicable NFPA code or standard.
i. The Contractor is responsible for providing all tools, supplies, and equipment necessary to properly perform inspections, tests, and maintenance of the fire protection and life safety equipment and systems in accordance with applicable NFPA code or standard.
j. The Contractor shall be responsible to leave areas where they perform work neat, clean, and orderly.
k. The Contractor shall document all inspections, test results, and maintenance performed on the suggested inspection, testing, and maintenance forms referenced in the applicable NFPA code or standard. These completed forms shall be included with the Contractor's Monthly Progress Report.
l. Testing and repairs to Fire Life Safety systems requires NICET certifications however, operating any Fire Life Safety System does not require NICET certification (i.e. enabling/disabling points, silencing alarms, resetting panels, isolating sprinkler valves, etc..

Any deficiency identified by the Contractor during a required inspection shall be entered into CMMS as a work order; evidence of correcting such deficiency, unless funding is not available, shall be provided with the subsequent Contractor's Monthly Progress Report after correction action is completed.

C.42.2 Fire Alarm System Services

Services include, but are not limited to; the performance, inspection, testing, and preventive maintenance or repair of a variety of fire alarm and notification systems, equipment and components such as manual alarm devices, smoke and heat detectors, tamper switches, pressure switches, water flow switches, remote and graphic annunciations, main fire alarm panel and components, voice alarm systems, speakers, horns, and other audible and visual devices, wiring circuits and junctions, supervising station alarm system transmission equipment, emergency power supplies and all other ancillary devices that operate related equipment (e.g., HVAC shutdown, dampers, elevator recall, door closing devices and door unlocking devices.

All fire alarm system inspections, tests, maintenance, and repairs performed under this contract shall comply with the NFPA 72, National Fire Alarm and Signaling Code.

Fire alarm system testing, maintenance and repair shall be performed during normal business hours when it does not interfere with building operations. When such testing, maintenance or repair will interfere with building operations; it shall be performed after normal business hours without additional costs to the government, unless approved otherwise by the CO . The Contractor shall

provide a fire watch in areas left unprotected or if the system is out of service for more than 4-hours in a 24 hour timeframe. The fire watch shall remain in place until the fire alarm system is completely restored during the performance of routine service and testing procedures. If the system cannot be restored through no fault of the Contractor's, a fire watch still shall be provided until the system is restored, however the Contactor may seek reimbursement for the fire watch with the COR .

It is essential that the Contractor carefully schedule with the property manager and CO all non emergency shutdowns of the fire alarm system and that back up protection be provided by the Contractor (e.g., arrangement of additional personnel stationed in the areas affected and at the fire alarm system control panel) any time that the fire alarm system is out of service for more than 4 hours. The affected portion of the system shall be tested to ensure that the protection has been properly restored.

In no case shall the fire alarm system be left in a disabled condition without notifying the CO and providing a fire watch.

~~All fire alarms testing, with the exception of interconnected building functions, shall be performed after normal working hours without additional cost to the government. Testing of the interconnected building functions, including, but not limited to all handler shutdown, damper control, elevator recall, egress door unlocking, etc., shall be performed during hours the interconnected equipment is active. The testing of the fire alarm system shall not be considered complete without the testing and verifying the performance of interconnected equipment. Contractor shall provide a fire watch in areas left unprotected or if the system is out of service for more than 4-hours in a 24-hour, until the fire alarm system is completely restored during the performance of routine service and testing procedures. If the system cannot be restored through no fault of the Contractor's, a fire watch still shall be provided until the system is restored, however, the Contractor may seek reimbursement for the fire watch with the CO or their designee.~~

Fire alarm testing, with the exception of Audio Visual devices and Elevator Recall, shall be permitted to be performed during normal working hours. Elevator recall **may** be conducted during hours if coordinated and approved by CO or his/her designee. The contractor shall schedule testing of audio visual devices and elevator recall for after hours. The contractor shall coordinate with GSA property management and FPS before performing any test that allows perimeter doors to be released. Once door release functionality has been tested satisfactory the door bypass can be activated for the remainder of the testing period. The contractor shall provide GSA a minimum of 2 week notice when access to tenant space is required both during and after hours to facilitate ample notice and access coordination with building occupants. **Testing of devices in the elevator shafts, pits, and hoist ways shall be coordinated with the elevator contractor. All costs associated with testing involving the elevator contractor shall be the responsibility of the O&M contractor.** Testing of the interconnected building functions, including, but not limited to all handler shutdown, damper control, elevator recall, egress door unlocking, etc., shall be performed during hours the interconnected equipment is active. The testing of the fire alarm system shall not be considered complete without the testing and verifying the performance of interconnected equipment. Contractor shall provide a fire watch in areas left unprotected or if the system is out of service for more than 4-hours in a 24-hour, until the fire alarm system is completely restored during the performance of routine service and testing procedures. If the system cannot be restored through no fault of the Contractor's, a fire watch still shall be provided until the system is restored, however, the Contractor may seek reimbursement for the fire watch with the CO or their designee.

C.42.3 Fire Alarm System Maintenance

The Contractor shall ensure that the fire alarm system is maintained and operable at all times except while being tested or repaired. It is essential that the Contractor carefully schedule with the building manager all non emergency shutdowns of the fire alarm system and that back up protection be provided by the Contractor (arrangement of additional personnel stationed in the areas affected and at the fire alarm system control panel) any time that the fire alarm system is out of service. In addition, regardless of the duration of the shutdown, the affected portion of the system shall be tested to ensure that the protection has been restored.

C.42.4 Fire Alarm System Central Station Monitoring

The Contractor shall provide and maintain a UL-listed central station monitoring service to monitor all fire alarm transmitters and related equipment. The Contractor shall ensure all fire alarm systems are connected to the monitoring service. During any period when the central station monitoring is not operational, the Contractor shall maintain a fire watch. If the Contractor believes

the central station monitoring failure was through no fault of his own, the Contractor may request reimbursement for the fire watch from the CO .

C.42.5 Water-Based Fire Suppression Systems

Services consist of, but are not limited to; the performance , inspection, testing, and preventive maintenance or repair services of all mechanical devices, including valves, sprinklers, couplings, piping, hose connections, water motor gongs and alerting devices, tamper switches, pressure switches, water flow switches, standpipes, backflow preventers, private fire service mains, water storage tanks, fire pumps, and test headers.

All water-based fire extinguishing system inspections, tests, maintenance, and repairs performed under this contract shall comply with the NFPA 25, Inspection, Testing, and Maintenance of Water-Based Fire Extinguishing Systems.

Water-based fire suppression system testing, maintenance and repair shall be performed during normal business hours when it does not interfere with building operations. When such testing, maintenance or repair will interfere with building operations; it shall be performed after normal business hours without additional costs to the government, unless approved otherwise by the CO . The Contractor shall provide a fire watch in areas left unprotected or if the system is out of service for more than 4-hours in a 24 hour period. The fire watch shall remain in place until the water-based fire suppression system is completely restored to service during the performance of any routine service and testing procedures. If the Contractor believes they were not able to restore sprinkler service due to circumstance outside of their control, the Contractor may request reimbursement for that portion or the fire watch from the CO .

It is essential that the Contractor carefully schedule with the property manager and CO all non emergency shutdowns of the sprinkler system and that back up protection be provided by the Contractor any time the sprinkler system is out of service for more than 4 hours. The affected portion of the system shall be tested to ensure that the protection has been properly restored.

In no case shall any water based fire suppression system be left in a disabled condition without notifying the CO and providing a fire watch.

C.42.6 Fire Doors and Other Opening Protective

Services consist of, but are not limited to, the inspection, testing, and maintenance of all fire-rated door assemblies. All fire-rated door assemblies inspections, tests, and maintenance performed under this contract shall comply with the NFPA 80, Standard for Fire Doors and Other Opening Protectives. Please note that the inspection of fire-rated door assemblies shall also meet the requirements in NFPA 101, Life Safety Code.

C.42.7 Fire and Combination Fire/Smoke Dampers

Services consist of but are not limited to, the inspection, testing, and maintenance of all fire dampers, radiation dampers, and combination fire/smoke dampers. All fire damper, radiation damper, and combination fire/smoke damper inspections, tests, and maintenance performed under this contract shall comply with the NFPA 80, Standard for Fire Doors and Other Opening Protectives. Please note that maintenance of combination fire/smoke dampers shall also meet the requirements contained in NFPA 105, Standard for the Installation of Smoke Door Assemblies and Other Opening Protectives.

C.42.8 Smoke Doors and Other Opening Protective

Services consist of, but are not limited to; the inspection, testing, and maintenance of all smoke door assemblies. All smoke door assemblies inspections, tests, and maintenance performed under this contract shall comply with the NFPA 105, Standard for the Installation of Smoke Door Assemblies and Other Opening Protectives.

C.42.9 Smoke Dampers

Services consist of, but are not limited to, the inspection, testing, and preventive maintenance of all smoke dampers. All smoke damper inspections, tests, maintenance, and repairs performed under this contract shall comply with the NFPA 105, Standard for the Installation of Smoke Door Assemblies and Other Opening Protectives.

C.42.10 Portable Fire Extinguishers

Services consist of, but are not limited to; the inspection, testing, and preventive maintenance of all portable fire extinguishers. All portable fire extinguisher inspections, tests, and maintenance performed under this contract shall comply with the NFPA 10, Standard for Portable Fire Extinguishers. **The contractor shall NOT be responsible for performing multiple year PM actions such as 6 YR maintenance or 12 year hydrostatic testing until the actual calendar year the extinguisher is due for the maintenance.**

C.42.11 Non-Water-Based Fire Extinguishing Systems

Services consist of, but are not limited to, the inspection, testing, and preventive maintenance of the following types of non-water-based fire extinguishing systems:

a. Carbon dioxide extinguishing systems, NFPA 12, Standard on Carbon Dioxide Extinguishing Systems.
b. Halogenated extinguishing systems, NFPA 12A, Standard on Halon 1301 Fire Extinguishing Systems.
c. Dry chemical extinguishing systems, NFPA 17, Standard for Dry Chemical Extinguishing Systems.
d. Wet chemical extinguishing systems, NFPA 17A, Standard for Wet Chemical Extinguishing Systems.
e. Fire extinguishing systems, NFPA 96, Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations.
f. Clean agent fire extinguishing systems, NFPA 2001, Standard for Clean Agent Fire Extinguishing Systems.

C.42.12 Smoke Control Systems

Services consist of, but are not limited to; the inspection, testing, and preventive maintenance of smoke control systems. All smoke control system inspections, tests, maintenance, and repairs performed under this contract shall comply with the NFPA 92, Standard for Smoke Control Systems.

C.42.13 Emergency and Standby Power Systems

Services consist of, but are not limited to; the inspection, testing, preventive maintenance, and exercising of equipment per the manufacturer's recommendations for the following types of emergency and standby power systems:

a. Emergency power supply systems, NFPA 110, Standard for Emergency and Standby Power Systems.
b. Stored electrical energy emergency and standby power systems, NFPA 111, Standard on Stored Electrical Energy Emergency and Standby Power Systems.

C.42.14 Emergency Lighting Systems and Exit Signage

Services consist of, but are not limited to; the inspection, testing, and preventive maintenance of emergency lighting systems, emergency lighting equipment, and exit signage. All emergency lighting systems, emergency lighting equipment, and exit signage inspections, tests, maintenance, and repairs performed under this contract shall comply with the NFPA 101, Life Safety Code.

C.43. Maintenance And Repair Of Vertical Transportation SystemS
RESERVED

C.44 RESERVED

C.45. CUSTODIAL PROGRAM

C.45.1.Objectives and Scope

This contract is a Performance-Based Statement of Work (PBSOW) for custodial and related services for the following locations:

- **Sidney M. Arnovitz FB-CT (FL0019ZZ)**

As a performance-based contract, the requirements are stated in terms of desired results with associated quality standards. The contract shall consist of two major functional areas: standard services, and above standard services.

Custodial services provided by the Contractor are arranged and oversight is provided through one or more of the following entities: GSA's Regional Office, Service Centers, Field Offices, or Local Offices. These entities represent the Property Management organizations that have been adopted by GSA's Regional leadership.

The Contractor shall furnish all personnel, labor, equipment, material, tools, supplies, supervision, management, and services, except as may be expressly set forth as Government furnished, and otherwise do all things necessary to or incident to, perform and provide the work efforts described in this Section.

All references incorporated herein as Web pages (URL's) are accurate as of August 1, 2010, and may be subject to change by their web publisher. Web pages are provided to the Contractor for additional clarity. A change to any Web page specified in this contract does not change or alter the Contract Objectives identified above.

C.45.2. Cleaning Hours:

The performance of the cleaning shall take place between the hours of 7:00 a.m. and 5:00 p.m. The hours shall not be changed unless authorized by the CO or his/her designee.

C.45.3. Building Information Data Sheet Estimates:

The figures contained in the Building Information Data Sheet are estimates. It is the Contractor's responsibility to notify the CO or his/her designee if it is believed that the information provided is incorrect.

C.45.4. The Contractor Shall

1. Be responsible to make the management and operational decisions to meet the quality standards required under this contract.
2. Use innovation, technology and other means and methods to develop and perform the most efficient cleaning services for the building.
3. Implement an effective Quality Control Plan (QCP).
4. Implement an effective service call system, as specified under the Special Requirements section of this contract that results in prompt, professional, and courteous resolution of tenant concerns.
5. Keep the Contracting Officer (CO) or his/her designee informed of current status of the work being performed, provide work schedules and provide other pertinent information needed by the CO or his/her designee.
6. Reduce the environmental impacts of work performed under this contract by using, to the maximum extent, environmentally sound practices, processes, and products.
7. The Contractor shall provide training to its employees that will stress stewardship in cleaning practices i.e., use and disposal and recycling of cleaning chemicals, dispensing equipment and packaging. The most current information on stewardship, training, and other issues can be found in ASTM E1971-98 or at the ASTM website for subjects relating to Stewardship for the Cleaning of Commercial and Institutional Buildings (www.astm.org).
8. The Contractor shall ensure that employees are properly licensed and/or certified to operate necessary building systems or equipment for which licensed and/or certified personnel are required by federal, state or local law, codes or ordinances.

C.45.5. Green Cleaning

The Contractor shall use green cleaning products and processes, and shall demonstrate such capability by submitting a green cleaning plan, in accordance with Submittals Chart for Contract Deliverables in this specification, to the CO or his/her designee that describes methods, materials, and equipment used under the contract. Green cleaning is a planned and organized approach to cleaning that is designed to protect the occupants and workers' health and reduce the impact on human health and the environment. Unlike a traditional cleaning program, a green custodial program takes a holistic approach to building cleaning and goes beyond simple appearances to focus on health and the environmental impacts.

Green cleaning products and processes shall be complaint with the Guiding Principles for Sustainable Buildings (See Exhibit J.13.1). Green products and processes are include, but are not limited to products containing recycled content, environmentally preferable products and services, bio-based products, and products and services that minimize the use of energy, water, and other resources. Dilution control equipment should be employed to Chemical concentrates that require dilutions are preferable compared to ready-to-use products and should be used whenever possible. Ensure correct dilutions of concentrates and to protect workers from exposure to concentrated chemicals. In addition to compliance with these requirements, the Contractor shall follow all

applicable standard industry practices including, but not limited to those published by the National Institute of Building Sciences (NIBS), American Society of Testing Materials (ASTM), Carpet and Rug Institute (CRI), and applicable standards of the Environmental Protection Agency (EPA).

The Contractor shall use safe and environmentally preferable products that are on the EPA's Environmentally Preferable Purchasing List. Products on the cleaning products preference list meet the following: United States Department of Agriculture (USDA) designated bio-based products, Green Seal™ certified (Standard GS-37 for Commercial and Institutional Cleaners, Comprehensive Procurement Guidelines (CPG)), applicable Executive Orders and GS-34 for Degreasers (http://www.greenseal.org/findaproduct/retail_products.cfm). The Contractor shall provide a list of environmental product and equipment to the CO or his/her designee in accordance with Submittals Chart Contract Deliverables in this specification. If cleaning products are not available on EPA's preference list only then can the cleaning Contractor use other type products. In such cases the Contractor shall continue to use to the extent possible the safest and most environmentally friendly products

The success of the green program hinges on the principles of stewardship. Stewardship is the shared responsibility for everyone working together to improve human health and the environment through the Government's cleaning program. The Contractor shall develop stewardship activities that help educate building occupants and present them to the CO or his/her designee. Information on stewardship, training plan, and other issues can be found in ASTM E1971-98, Standard Guide on Stewardship for Cleaning Commercial and Institutional Buildings.

For those categories not covered by the Green Seal Standard's preference will be given to those meeting the California Code of Regulations maximum allowable VOC levels for the appropriate cleaning product category (California Air Resource Board/California Code of Regulations (CCR), Title 17 CCR Section 94509 - (Topic cited: Standards for low VOC cleaning products at www.calregs.com).

C.45.5.1. Green Reporting

Records showing the monthly cost and amount of green cleaning products and materials purchased shall be provided to the CO or his/her designee by the Contractor so that this report can be submitted as required by the Resource Conservation and Recovery Act (RCRA) and EO 13514.

Records showing the monthly cost and amount of non-green cleaning products and materials purchased shall be provided to the CO or his/her designee by the Contractor.

C.45.6. LEED EB RESERVED

C.45.7. Standard Services

C.45.7.1. Interior

The Contractor shall provide interior standard services for the work items listed below.

C.45.7.2. Performance Standards

The Contractor through innovation, technology, or other means shall perform the work in this contract to meet the quality and performance standards in this Section. Evaluations of the

Contractors work shall be based on the standards in this Section and conducted in accordance with the Government's Quality Assurance Surveillance Plan (QASP).

C.45.7.3. Floor Care

The Contractor shall provide a floor maintenance schedule to the CO or his/her designee in accordance with Submittals Chart for Contract Deliverables.

C.45.7.4. Bare Floors

Floors: Floors, base moldings, and grout shall be clean and free of debris including but not limited to dirt, water streaks, mop marks, string, gum, tar, and other foreign matter. The floors shall maintain their natural luster and not have a dull appearance.

Wet mopped floors are to be cleaned using disinfectant cleaner(s) with additional scrubbing, if necessary. These floors shall be slip resistant. Surfaces, baseboards, and corners shall be clean and dry. Walls, baseboards, and other surfaces shall be free of splashing and markings from the equipment. There shall be no visible buildup of finish in corners or crevices.

Mops and cleaning rags shall be cleaned and sanitized before and after a day of use. Mops and cleaning rags used in restrooms, including diapering areas in restrooms and Child Care centers, shall not be used to clean any other areas.

Asbestos Containing Building Material (ACBM): Cleaning of flooring that may contain asbestos material, such as vinyl asbestos tile (VAT), shall comply with the methods prescribed in the National Institute of Building Sciences (NIBS) Guidance Manual, "Asbestos Operations and Maintenance Work Practices". The Contractor shall have a copy of the NIBS Guidance Manual. Upon request, the Government shall make available to the Contractor any asbestos sampling results.

ADP Floors: Damp mopping shall be the only method of wet cleaning for floors in Automated Data Processing (ADP) space.

Asphalt Floors: Damp mopping shall be the only method of wet cleaning for floors containing asphalt material.

Granite and Marble Floors: All applicable floor areas shall be maintained in accordance with industry standards.

Loading Dock Floors: Spill residue and clean-up materials shall be disposed of in accordance with the Environmental Protection Agency (EPA), and/or State and local regulatory agency requirements.

Postal Floors: The quality standard for providing standard service is the same as that described for Postal Space in the Standard Service Section in C.45.7.4.

Stripping: The old finish or wax shall be removed in accordance with standard commercial practices. Spots shall be eliminated. There shall be no evidence of gum, burns, scuffmarks, or wax build-up in corners or crevices. UNDER NO CIRCUMSTANCES SHALL BURNISHING OR DRY STRIPPING METHODS BE USED.

Finishing: Walls, baseboards, and other surfaces shall be free of finish residue and marks from equipment. Floors shall be free of streaks, mop strand marks, and skipped areas. The applied finished area shall have a uniform luster.

Sealing: Sealant must adhere to the floor. Floor areas must be evenly coated with a slip resistant seal.

Wood Floors: There shall be no water solutions used on wood flooring. There shall be no dry stripping methods used on wood flooring.

C.45.7.5. Carpet and Rugs

Spot Cleaning: Carpet surfaces shall be free of removable spots, soiled traffic patterns, dirt, dust, debris, gum, and crusted material.

Vacuuming: Carpet surfaces are to be free of dirt, dust, and other debris. Vacuuming shall be done at a frequency that will protect the integrity of the carpet and prolong wear. The Contractor shall utilize HEPA vacuum cleaners that meet the requirements of the Carpet and Rug Institute "Green Label/Green Label Plus" Testing Program.

C.45.7.6. Floor Mats and Runners

The **Government** shall furnish all mats and runners. T**he Contractor shall furnish all replacement mats and runners.** Replacement mats and runners shall be furnished by the contractor. Types and sizes of mats and runners are identified on the Building Information Sheet in Section J. The CO or his/her designee shall approve all mats and runners.

Mats and runners shall be laid out as specified by the CO or his/her designee at main entrances, main lobbies, and main and secondary corridors at all times, and must have finished edges. Replacement mats and runners shall be of the same type as the original mats and runners. Mats and runners shall be free of removable spots, soiled traffic patterns, dirt, debris, gum, and crusted material. There shall be no areas of deterioration or fuzzing as a result of harsh brushing or scrubbing. They shall receive scheduled cleanings and routine inspections based upon the manufacturer's instructions. Any mats and runners that are found to be non-repairable or cannot be cleaned shall be brought to the attention of the CO or his/her designee so they can be replaced. Mats and runners shall be stored in accordance with the ANSI/ASEE A1264.2-2006 Provision of Slip Resistance on Walking/Working Surfaces Guidelines.

The use of larger mats and runners, where appropriate, as opposed to several smaller mats and runners is preferred to eliminate overlapping and to reduce potential tripping hazards.

Wet or Inclement Weather: In the event of wet or inclement weather mats and runners are used, the mats and runners shall be placed at entrances and at other areas identified by the CO or his/her designee prior to the building occupants reporting to work. Wet or inclement weather mats and runners shall be removed, cleaned, and stored by the Contractor when the CO or his/her designee determines that they are no longer required.

C.45.7.7. Restrooms, Shower Rooms, Locker Rooms, and Holding Cells

Cleaning: Areas shall be cleaned and with a disinfectant cleaner. Fixtures shall maintain a high level of luster and be free of dust, mold, mildew, streaks, and encrustation. Partitions, doors, vents, sills, and walls shall be free of dust, dirt, bodily fluid and waste, and graffiti.

Restrooms shall be free of discarded material and trash shall be emptied to prevent the containers from overflowing.

Dispensers: The **Government** shall provide dispensers. The Contractor shall replenish supplies and fill dispensers as a standard service. The supplies for the provided dispensers shall be compatible with the dispenser's manufacturer's requirements. Supplies used shall be consistent with the Comprehensive Procurement Guideline (CPG) items. Hand soaps shall not contain antibacterial agents except where required by Federal, State, local requirements and health codes. Monies

collected from tampon and sanitary napkin dispensers shall be retained by the Contractor who shall provide and replenish the product at their expense.

Floors: The quality standard for providing standard service is the same as that described for Floor Care in the Standard Service Section in C.45.17.4.

Receptacles: The **Government** shall provide receptacles. The Contractor shall empty, clean, and sanitize sanitary napkin and waste receptacles. Sanitary napkin disposal containers shall be lined with new receptacle bags. Disposal of waste shall be treated the same as Blood Borne Pathogens as specified in 29 CFR 1910.1030 (http://www.access.gpo.gov/nara/cfr/waisidx_06/29cfr1910a_06.html).

C.45.7.8. Fixtures

Clean and Sanitize: Fixtures and surfaces (washbasins, urinals, modesty panels, toilets, shower stalls, etc.) shall be clean with no dust, spots, soil substances, discoloration, mold, build-up, or excess moisture.

Drinking fountains: All fountains shall be free of dirt, watermarks, and all other debris or encrustation. Drinking fountains shall be sanitized and present a lustrous appearance.

C.45.7.9. Surfaces

Horizontal surfaces: All surfaces shall be free of dust, dirt, oil spots, or smudges. Cabinets and desks with papers, computers, and keyboards shall not be disturbed. Surfaces should be damp mopped or wiped with a germicidal cleaner. Contact time should be consistent with the manufacturer's recommendations.

Metal, Brass and Woodwork: Surfaces (including corners, crevices, moldings, ledges, hand rails, grills, doors, door knobs, door frames, kick plates, etc.) shall be free of dust, streaks, spots, hand marks, oil, smudges, dirt, soil substances, encrustation, and streaks.

Glass Cleaning: All glass, clear partitions, mirror surfaces, bookcases, and other glass (within approximately 70'' of the floor) shall be clean and free of dirt, dust, streaks, smudges, watermarks, spots and grime, and shall not be cloudy. There shall be no water spots on the glass or adjacent fixtures and furniture.

C.45.7.10. Walls

Clean Spots and Marks: Wall surfaces shall be free of smudges, marks, dirt, and spots. Cleaning should not cause discoloration.

C.45.7.11. High Cleaning

High Surfaces: Surfaces between 70 inches and 180 inches shall be cleaned, free of dirt, dust and cobwebs. Where glass is present, both sides shall be clean and free of streaks. This does not include removal of vents, tiles, or fixtures.

C.45.7.12. Dusting

Surfaces shall be dust free (i.e. with a preference in using a micro-fiber or damp cloth, or backpack vacuum fitted with the appropriate dusting tools).

C.45.7.13. Trash, Wastebaskets, and Ash Receptacles

Trash: All trash (including restrooms) shall be collected and removed to a location designated by the CO or his/her designee. Trash containers shall be emptied and kept clean, odor-free, and free of dirt, dust, debris, residue, and spilled material. Plastic liners for all trash, debris containers shall not be

torn, worn, or contain residue. All ash receptacles shall be free of dust, ashes, odors, tar, streaks, and tobacco residue.

The Contractor shall notify the CO or his/her designee of any item or material identified by the Environmental Protection Agency (EPA), and State and local regulatory agencies as hazardous waste, hazardous materials, or Universal Waste, observed in the trash receptacles. Typical prohibited wastes include but are not limited to fluorescent light bulbs, thermostats, thermometers, most chemicals, and batteries (40 CFR Parts 260-273).

C.45.7.14. Recyclables

Collection: The Contractor shall provide all labor, equipment, and means to collect and transport recyclable materials from recycling bins and containers located throughout the building to storage and loading areas as designated by the CO or his/her designee and as described in the recycling discussion under standard services.

C.45.7.15. Elevator, Escalators, and Stairways

Door Tracks: Tracks shall be clean and free of dirt, debris, built up grime, dust, smudges, and other extraneous matter.

Exterior and Interior Car Surfaces: Surfaces shall be clean and free of finger marks, smudges, and spills. Carpets and floors shall be free of removable spots, dirt, and debris. Floors requiring a finish shall be maintained at a high luster.

Exposed Surfaces, Treads, Risers and Landings: Stairways, escalators, entrances, landings, railings, risers, ledges, grills, doors, radiators, and surrounding areas shall be free of dirt, dust, litter, and debris.

C.45.7.16. Plate Glass

All glass (to include glass over and in exterior and vestibule doors, all plate glass around entrances, lobbies, and vestibules) shall be clean and free of dirt, grime, streaks, and moisture and shall not be cloudy.

C.45.7.17. Window Washing

Cleaning: The windows shall be clean and free of dirt, grime, streaks, moisture, and shall not be cloudy. Window sashes, sills, woodwork, and other surroundings of glass shall be wiped free of drippings and other watermarks. All windows shall be cleaned annually. Cleaning frequencies that are above standard shall be completed on a reimbursable basis to the Contractor. Cleanings of both sides of the windows shall be coordinated to maximize cost effective operations as directed by the CO or their designee. The Contractor shall comply with ANSI/IWCA I-14.1, and all Federal, State and local regulations.

C.45.7.18. Blinds and Coverings (Not including Drapes, Curtains, and Unique Coverings)

Dusting of Blinds and Coverings: All blinds, coverings, cord tapes, and valances shall be clean and free of dust and spots. Blinds and coverings that are not operating properly shall be reported to the CO or their designee for repair.

C.45.7.19. Policing

Areas: All building areas shall be free of papers, trash, and other discarded material.

C.45.7.20. Interior and Atrium Plants (Government Plants) RESERVED

C.45.7.21. Concessions

Cleaning: All public areas (cafeteria furniture and seating areas, snack bars, and vending machine area) shall be clean, sanitized, and free of spillages, food crumbs, spots, smudges, marks, and soil. Floors shall be maintained in accordance to the floor care standard services requirements of this contract. Cleaning of kitchens and areas behind serving tables, and salad and soup bars are the responsibility of the Concessions Contractor.

C.45.7.22. Postal Space RESERVED

C.45.7.23. Fitness Centers, Health Units, and Laboratories (RESERVED)

C.45.8. Exterior

The Contractor shall provide exterior standard services for the work items listed below.

C.45.8.1. Performance Standards

The Contractor shall provide all resources, labor, tools, equipment, transportation, hauling away and disposal, training, supplies, materials, and oversight to ensure that quality and performance standards are successfully achieved.

C.45.8.2. Plate Glass

All glass (to include spandrel glass, glass over and in exterior and vestibule doors, all plate glass around entrances, lobbies, and vestibules) shall be clean and free of dirt, grime, streaks and moisture, and shall not be cloudy.

C.45.8.3. Window Washing

Cleaning: Windows shall be clean and free of dirt, grime, streaks, and moisture and shall not be cloudy. Window sashes, sills, woodwork, and other surroundings of glass shall be wiped free of drippings and other watermarks. Cleaning frequencies that are above standard shall be completed on a reimbursable basis to the Contractor. Cleanings of both sides of the windows shall be coordinated to maximize cost effective operations as directed by the COR. The Contractor shall comply with ANSI/IWCA I-14.1, and all Federal, State and local regulations.

C.45.8.4. Canopies

Cleaning: All canopies and anything affixed to, or included in the surfaces of canopies shall be clean and free of all dirt, dust, cobwebs, nests, bird excrement, trash, and debris.

C.45.8.5. Hard Surface Areas

Cleaning: All areas (sidewalks, brick areas, hard surfaces, parking areas, garages, docks, moats, platforms, driveways, ramps, lanes, etc.) shall be clean and free of dirt, debris, gum, litter, gravel, weeds, oil, and grease. No residual dirt shall remain after the removal of the debris. Spill residue and clean-up materials shall be disposed in accordance with the Environmental Protection Agency (EPA), and State and local regulatory agency requirements.

C.45.8.6. Ash Receptacles and Trash Containers

Cleaning: All trash shall be collected and removed to a location designated by the CO or his/her designee. Trash containers and ash receptacles shall be emptied and kept clean, odor-free, and free of dirt, dust, ash, cigarette butts, debris, residue, and spilled material. Sand in ash receptacles shall be replenished as necessary. Plastic liners for all trash containers shall not be torn, worn, or contain residue.

C.45.8.7. Surfaces (signs, vending machines, tables, etc.)

Cleaning: Surfaces shall be clean, with no dirt, dust, residue, streaks, spots, soil substances, discoloration, or cloth streaks. Surfaces should be damp mopped or wiped with a germicidal cleaner. Contact time should be consistent with the manufacturer's recommendations. Spill residue and clean-up materials used shall be disposed of properly.

C.45.8.8. Parking Structures, Parking Lot(s), and Dock Areas

Cleaning: Areas shall be cleaned and free of dirt, water, streaks, mop marks, and oil spill(s). Spill residue and clean-up materials shall be disposed in accordance with the Environmental Protection Agency (EPA), and State and local regulatory requirements.

C.45.8.9. Graffiti Removal

Remove graffiti using normal cleaning methods (e.g., normal graffiti removal cleansers or solvents). Graffiti that cannot be removed with such methods shall be reported to the CO or their designee.

C.45.8.10. Excrement Removal (Human, avian and rodent)

Cleaning: All steps, stairs, entrances, sidewalks, arcades, landings, balconies, and ledges shall be cleaned of all excrement while following established safety precautions as outlined in the Center of Disease Control protocols. Knowledge of safety requirements in cleaning areas contaminated by bat, pigeon, or other avian pest excrement is required. The Contractor shall fully train all employees designated to perform these services in accordance with Occupational Safety and Health Administration (OSHA) standards and OSHA approved Federal, State, and local regulations.

C.45.8.11. Policing Outside Areas

Policing: All areas including lawn, grounds, planted areas, sidewalks, hard surfaces, parking areas, garages, docks, platforms, driveways, ramps, lanes, etc) shall be clean of gum, litter, debris, paper, trash, and other discarded material.

Unimproved grounds: All areas shall be cleared of trash, debris, and other discarded material each time the native grasses, weeds, etc. are cut.

Fence Lines: Fence lines shall be cleared of trash, debris, and other discarded material.

C.45.8.12. Snow and Ice Removal RESERVED

C.45.8.13. Grounds Maintenance

C.45.8.13.1. Landscape Waste Management RESERVED

C.45.8.13.2. Grounds Maintenance Services

General: Maintain all plants, trees, shrubs, ground cover, and lawns in a manner that prolongs life and sustains a healthy appearance. The Contractor shall seek to prevent pollution by, among other things, reducing fertilizer and pesticide use, using integrated pest management techniques, recycling green waste, and minimizing runoff. Grounds maintenance services in the standard services and above standard services requirements shall benefit the environment and generate cost savings to the Federal Government by preserving and protecting the native plants and wildlife habitat entrusted to us.

C.45.8.13.3. Composting

To reduce the amount of material being disposed of in landfills, the Contractor is required to compost, to the greatest extent possible, yard waste generated by the Contractor's operations. The Contractor shall not compost material on-site unless authorized by the CO or their designee. The Contractor shall utilize an approved recycling or composting facility or compost the material at the

Contractor's own facility. Where applicable, the Contractor shall work with on site cafeterias and wet stands to recover and compost all possible materials. The Contractor is responsible to pay for composting services for landscaping debris.

C.45.8.13.4. Trees and Shrubs

Maintenance: Tree supports should be kept in good condition and functioning at all times and removed when no longer needed. All trees and shrubs should be fully protected. Tree stakes, tree ties, and guy wire shall be of materials that comparable to those existing on site, and shall be replaced or repaired by the Contractor as needed. Supports or braces are to be repositioned as often as necessary to prevent damage to the tree or shrub trunk. Sand pans can be used for trees and shrubs to protect the plant trunk from the mower, and help to avoid over-watering. Keep shrubs and trees trimmed to present an attractive appearance.

Survey: A certified grounds maintenance professional shall provide a survey of the trees and an evaluation of their condition.

This shall be completed within 30 days from the start date of each year the contract is in effect. The evaluation shall include a plan and price list for any special treatment not covered by this contract. Soil samples shall be taken and analyzed at the Contractor's expense by an approved testing laboratory, from areas where plant health problems occur. Recommendations of the testing laboratory should also be submitted with a plan and price list for any special treatment not covered by this contract. Plans and price lists shall be submitted to the CO or his/her designee.

Tree thinning shall reduce the density of live branches towards developing the natural branching structure. Thinning shall result in an even distribution of branches on individual limbs and throughout the crown to provide free air circulation through the remaining limbs and branches. Not more than 25 percent of the crown should be removed within an annual growing season.

Tree maintenance shall be performed only by arborists or arborist trainees who, through related training or on-the-job experience, or both, are familiar with the practices and hazards of arboriculture and the equipment used in such operations. This standard shall not take precedence over arboricultural safe work practices. Operations shall comply with applicable Occupational Safety and Health Administration (OSHA) standards, ANSI Z133.1, as well as State and local regulations.

Climbing spurs shall not be used when climbing and pruning trees. Tree branches shall be removed in such a manner so as not to cause damage to other parts of the tree or to other plants or property. Branches too large to support with one hand shall be precut to avoid splitting of the wood or tearing of the bark. Where necessary, ropes or other equipment shall be used to lower large branches or portions of branches to the ground.

C.45.8.13.5. Mulching

Contractor shall maintain and replace existing mulch as necessary. Replacement mulch shall be commercial grade shredded hardwood bark, or equivalent. It shall be free of sticks, stones, clods, or other foreign material. A sample of proposed mulch and chips shall be submitted to and approved by the CO or his/her designee prior to use. All areas to be mulched shall be raked, debris removed, edge reestablished, and any excessive mulch buildup worked into existing soil or removed, at the discretion of the CO or his/her designee, prior to mulch application.

C.45.8.13.6. Mowing and Edging

Contractor shall mow and edge all turf areas at a frequency and method that ensures that all areas present an attractive appearance at all times. Mulching mowers shall be used; however, non-mulching mowers are permitted at some sites and shall be approved by the CO or his/her designee. Grass clippings shall be cleared from walkways and roadways and blown onto the grass. As appropriate, grass clippings shall be left in place, composted, or mulched.

C.45.8.13.7. Leaf Removal

The Contractor shall remove leaves, as necessary, to maintain a neat and clean appearance. Throughout the year, the Contractor shall remove minor accumulations due to isolated leaf drop and shall check all storm drain openings on the premises and remove any leaves or debris that have accumulated. Care shall be taken to remove leaves in existing mulched areas to maintain a neat and clean appearance without substantial reduction in mulch depth or damage to herbaceous or woody plant material.

C.45.8.13.8. Over Seeding, Dethatching, and Plugging

Over-seed, dethatch, and plug as necessary to prevent bare areas and promote even growth of turf areas following common and local landscaping practices.

C.45.8.13.9. Fertilization

All lawn, trees, and ground cover shall be fertilized consistent with common local landscaping practices. Application by the Contractor shall employ the best practices to minimize chemical runoff. Fertilizer used shall be of a balanced type that supplies all nutrients required for providing sustainable growth and development. The fertilizer application rate for the trees will be determined by tree type, girth, and height. Prior to application, the Contractor shall schedule time of application with the CO or his/her designee.

C.45.8.13.10. Flowerbeds and Plants

Flowerbeds are to be free from weeds and debris. Replacement plants shall be supplied by the **Contractor and approved by the CO or his/her designee** and shall be arranged in an attractive and professional manner. Preference shall be given to the use of perennials instead of annuals.

C.45.8.13.11. Soil and Ground Cover

Aeration: Soil shall be aerated (frequency is dependent on the type of soil and grass but no less than one aeration-per year) by manual or mechanical methods of piercing the ground to provide an adequate air supply to the soil and promote sustained plant life.

Cultivation: Soil shall be cultivated to ensure the topsoil is loose for the purposes of gas exchange, water penetration, and soil aeration.

Groundcover: All areas shall be maintained to promote healthy and sustained growth. Ground cover must present a neat appearance.

C.45.8.13.12. Unimproved Grounds RESERVED

C.45.8.13.13. Fence Lines

Maintenance: Grass, native grasses, weeds, and other growths at fence lines including Land Ports of Entry, shall be controlled and not exceed (6) six inches in height. Any chemical treatment used must be approved by the CO or their designee prior to use. Application of any chemicals must be accomplished by a Licensed Pest Control Operator. Application of chemicals shall be documented in a record log book on the types of pesticides applied and date(s) of application.

C.45.8.13.14. Weeds

Maintenance: All areas (excluding unimproved grounds) are to be free of weeds and unwanted growth.

C.45.8.13.15. Irrigation

Initial Deficiency Walk-Through: The Contractor shall conduct a walk-through and inspect all irrigation systems (sprinklers, rain and freeze sensors, and drip systems) and submit a list of all damages to those systems to the CO or his/her designee.

C.45.8.13.16. Watering

Watering: All watering cycles shall be conducted at times that minimize inconvenience to the building occupants and visitors, and maximize percolation. Entrances and Exits shall not be wet during the arrival and departure of occupants and visitors. Watering shall be accomplished using a drip, soaker hose, or other water-saving irrigation system devices. The Contractor shall operate watering systems that use automatic timers coupled with rain/freeze sensors, in an efficient manner that considers local weather and local mandates. During periods of water restrictions, watering guidelines by the local water district shall apply. The Contractor shall not be responsible for the replacement of landscaping materials that die as a result of a lack of proper access to water during these periods of water restrictions by municipalities.

Hand Watering: When mechanical irrigation is not available or is malfunctioning, Contractor shall use alternative hand watering methods such as gator bags, or equivalents to ensure, promote, and maintain healthy growth.

C.45.8.13.17. Adjust, Clean, and Set Automatic Controllers RESERVED

C.45.8.13.18. Integrated Pest Management Plan

The Contractor shall utilize the Integrated Pest Management Plan for controlling pests and disease to ensure that landscape, trees, and shrubs are free of disease and infestation.

C.45.8.13.19. Plant Replacements

The Contractor shall be responsible for all costs associated with the replacement of all planted materials that have been damaged as a direct result of the Contractor's lack of oversight, neglect, or lack of proper care and maintenance. The Contractor shall use replacement plants that are native to the area to help further reduce the use of irrigation water.

C.45.9. Above Standard Services

The Contractor shall provide interior and exterior above standard services to fulfill the Government's intermittent need for work. These services are in addition to the services specified as a standard service.

The Contractor shall not divert workforce to accomplish above standard services.

Services with Quality Standards

C.45.9.1. Carpet Extraction

Extraction: Build-up spills and crusted materials shall be removed along with spots and smears. There shall be no areas of deterioration or fuzzing to the carpets and rugs as a result of harsh brushing or scrubbing. Cleaned areas of carpets and rugs shall be reasonably blended with surrounding carpets. The Contractor shall coordinate with the CO or their designee the times when carpet shall be cleaned. The carpet shall be dry

before customers occupy the building on the next business day. The Contractor shall take measures to prevent the growth of mold. Moving of duplicating equipment, computer equipment, and similar types of electric and electronic equipment is to be coordinated with the CO or their designee and customer, as required, prior to cleaning of the carpet. Any furnishings moved are to be returned to their original positions.

C.45.9.2. Window Washing (RESERVED)

C.45.9.3. Blinds and Coverings (Not Including Drapes, Curtains, and Unique Coverings) (RESERVED)

C.45.9.4. Pressure Washing and Steam Cleaning (RESERVED)

C.45.9.5. Tree Thinning (RESERVED)

C.45.9.6. Government Furnished Trees and Plants (Planted in Ground or Planters) RESERVED

C.45.9.7. Snow and Ice Removal for Areas Requiring Chemicals & Tools and Heavy Equipment (RESERVED)

C.45.9.8 Excrement Removal (Human, avian and rodent) (RESERVED)

C.45.9.9 Graffiti Removal (RESERVED)

C.45.9.10 Composting (RESERVED)

C.45.9.11 Trees and Shrubs (RESERVED)

C.45.10. Service Calls

Contractor shall provide adequate staff to respond to service calls during building(s) operating hours (see Building Information Data Sheet in Section J) AND during the Contractor's regular cleaning schedule. Contractor shall detail in its QCP how it will monitor and respond to service calls.

Service calls shall be monitored and satisfactorily responded to in a timely manner. Contractor shall include a method of recording customer calls, the time to complete the service call, and the corrective action taken. These records shall be made available for review by the CO or his/her designee.

The costs of all service calls shall be reimbursed to the Contractor if the request is outside the building(s) operating hours AND outside the Contractor's regular cleaning schedule.

The Contractor shall respond to ALL service call requests (custodial issues, moving, arranging, and rearranging furniture within a conference room, special event support, etc.) using building specific service call procedures.

Service calls that the CO or his/her designee determines to be urgent (spilled water in traffic areas, lack of toilet supplies, etc.) shall be handled immediately.

C.45.11. Communication Plan

The Contractor shall prepare and provide to the CO or his/her designee a communication plan detailing how the Contractor's plans on using technology (two-way digital communication) to communicate with GSA, to receive and respond to service calls, emergencies, status of projects, etc. The plan shall be submitted as part of the bid package for the Governments review and approval.

C.45.12. Protection and Damage

The Contractor shall make reasonable efforts to assist the Government to prevent hazardous conditions and property damage. To the extent that relevant conditions or activities are noted but are not associated with the Contractor's scope, the Contractor shall promptly report such conditions or activities to the CO or his/her designee or to security personnel.

The Contractor shall protect Government property, buildings, materials, equipment, supplies, records and data that are within the Contractor's control against unauthorized access, loss or damage.

The Contractor shall establish a system for on-site work force personnel to report potentially hazardous conditions in the building to the CO or his/her designee or other designated Government representative, regardless of whether the condition is within the Contractor's responsibility.

The Contractor and Contractor's employees and subcontractors shall comply with the "General Services Administration Rules and Regulations Governing Public Buildings and Grounds" (as posted in the building), and shall promptly report violations by employees, or as otherwise observed, to the CO or his/her designee or security personnel.

C.45.13. Waste Management Audit

At the beginning of a base year contract, the Contractor shall perform a solid waste audit of the building and submit the findings to the CO or his/her designee and Solid Waste Program Manager. Based on the findings, the Contractor shall partner with the Government to set up a recycling program that is cost effective and will maximize the amount of waste diverted from the landfill.

The Government may perform solid waste audits at their discretion and the Contractor shall partner with the Government to implement best practices solid waste audit recommendations.

C.45.14. Trash and Solid Waste Disposal and Removal

C.45.14.1. Extent of Work

A solid waste management program includes identifying and properly segregating all recyclable materials, composting materials, Universal Wastes, and trash.

The Contractor shall not collect hazardous materials unless specifically contracted to recycle them. Typical prohibited wastes include but are not limited to fluorescent light bulbs, thermostats, thermometers, most chemicals, and batteries (nickel-cadmium and small, sealed lead acid batteries in electronic equipment, mobile phones, portable computers, and emergency lighting). In addition, electronic equipment such as computers and printers shall not be discarded in the trash containers. The Contractor shall notify the CO or his/her designee of any prohibited or unauthorized items

observed in the trash receptacles. The Contractor is responsible for all costs of trash and recycling removal.

The Contractor shall be responsible for loading containers onto collection vehicles.

The custodial Contractor shall provide trash or solid waste removal and disposal services as described herein.

The Contractor shall collect and transport all solid waste, trash, and debris to designated locations on the loading dock or other areas (holding areas) for removal from the premises. Holding areas for solid waste accumulation shall be identified by the CO or his/her designee. If trash compactors are used at the building, the Contractor shall operate the compactor. The door is interlocked with the compactor and will not operate unless the door is closed. The **custodial Contractor** shall ensure that the appropriate Contractor personnel receive training in the safe and proper operation of the compactor.

All solid waste collected as a requirement of this contract shall be removed from the premises and transported to a solid waste disposal facility that has been certified by the appropriate state agency responsible for solid waste management, or by the Environmental Protection Agency.

The Contractor shall provide a sufficient number of waste removal containers to accommodate all trash generated between pick-up dates. The CO or his/her designee shall approve all container styles, types, and storage locations prior to placement. The Contractor shall be responsible for the delivery, maintenance, repair, cleanliness, labeling, and removal of storage containers and equipment, throughout the contract period. The containers must be kept free of holes, pests, grease, oil, and odors, etc. The Contractor will report any pest infestation in or around the containers to the CO or his/her designee. All Contractor-supplied equipment and materials shall remain the property of the Contractor during and subsequent to the contract period.

Location	Number of Containers	Container Size	Pick-up	Day of week
Key West FB-CT	1	8 cuyd	As needed	M-F

The overflow of materials from containers and dumpsters shall be picked up from the ground and floor area used to collect and consolidate the materials. The Contractor shall remove all hydraulic fluid and oil spillage caused either by the collection vehicles, or released from containers at the designated centralized collection site (loading dock, etc.). Spill residue and clean-up materials shall be disposed in accordance with the Environmental Protection Agency, and State and local regulatory agency requirements.

C.45.14.2. Solid Waste Records and Reports

The Contractor shall submit a monthly report showing the total weight or cubic yards of trash hauled and shall be provided to the CO or his/her designee, so that the report can be submitted as required by the Resource Conservation and Recovery Act.

If the Contractor can not provide total weight or cubic yards of trash hauled, the Contractor shall provide to the CO or his/her designee the container size, the number of containers, and the number of pickups and/or tips for each

Reports prepared by the Contractor shall be submitted to the Government electronically. When electronic submittals are not available, hard copy reports shall be used. Paper used by the Contractor

shall be printed on two-sided paper containing a minimum of 30 percent post consumer recycled content.

C.45.15. Recycling

The Contractor shall furnish all necessary labor, equipment, and supervision to provide recycling services as described herein. All recyclable materials shall be collected for removal from the premises. Overflow of materials from containers shall be picked up from the floor of the area used to collect and consolidate the materials.

C.45.15.1. Extent of Work

It is the intent of the Government to keep the maximum amount of material from the landfill through aggressive recycling.

The Contractor shall furnish all necessary labor, equipment, staff training, and supervision to provide recycling services as described herein. All recycled materials shall be collected for removal from the premises. Recyclable materials shall not be mixed with trash. Overflow of materials from containers shall be picked up from the floor of the area used to collect and consolidate the materials.

Materials to be recycled may include, but are not limited to: hard and soft bound books, telephone books, magazines and catalogs, legal briefs, publications, all types of office paper, computer paper, manila file folders, newspapers, junk mail, corrugated containers, manila envelopes, cardboard packaging, packing cartons, metals, used aluminum, plastic and glass beverage containers, unusable wood pallets, Universal Wastes, electronics, and old carpeting.

The Contractor shall remove all hydraulic fluid and/or oil spillage caused either by the collection vehicles, or released from containers at the designated centralized collection site (loading dock, etc.). Sorbent use for cleanup shall contain post consumer recycle content minimum as required. Minimums depend on type on sorbent used: see EPA/GPC website for details. Spill residue and clean-up materials shall be disposed in accordance with the Environmental Protection Agency (EPA), and State and local regulatory requirements.

Unless specifically contracted to recycle items or material identified by the EPA, and State and local regulatory agencies as hazardous waste, hazardous materials, or Universal Waste, the Contractor shall not collect these items. Typical prohibited wastes include but are not limited to fluorescent light bulbs, thermostats, thermometers, most chemicals, and batteries. Electronic equipment, such as computers shall not be discarded in the recycle bins. The Contractor shall notify the CO or his/her designee of any prohibited or unauthorized items observed in the trash or recycling receptacles.

The Contractor shall recycle to the maximum extent possible.

C.45.15.2. Recyclable Materials Disposition

The Contractor shall ensure that all recyclable materials are recycled and not placed in landfills. The CO or his/her designee may direct the Contractor to participate in joint efforts with State, city, and local governments regarding recycling.

C.45.15.3. Recycling Containers

Individual Desk-side and Central Collection Containers

The Government shall provide the collection containers.

Recycling Collection Containers: The **Government** shall provide the necessary collection containers/bins and other equipment for use throughout the building, for the collection of recyclable

materials. These are the containers the Contractor shall use to collect recyclables from deskside and/or central recycling containers. Containers shall be in sufficient quantities for the collection of recyclable material prior to removal to the designated holding area.

Storage Containers: The **Contractor** shall provide the necessary storage containers and other equipment for use in designated holding areas. Containers shall be in sufficient quantities for the collection and storage of the recyclable materials in the holding area prior to removal from the premises by the recycling Contractor.

Container and Equipment Responsibility: The Contractor shall be responsible for the removal of recyclables from collection containers and movement to the holding areas, throughout the contract period. The containers, excluding those used to collect paper, shall be labeled, lined and free of residue and any plastic liners shall not be torn, worn or contain residue. Containers shall be kept free from holes, vermin, or foreign matter that might cause injury or stain clothing or furniture, and the containers must not emit unpleasant odors. If any container emits unpleasant odors, as identified by the CO or his/her designee, it shall be immediately corrected by the Contractor at their expense. Recyclable materials shall not be handled, stored, or transported in any manner that causes a safety or health hazard.

All Government supplied equipment and materials shall remain the property of the Government. The Contractor shall be accountable for all recycling equipment and containers belonging to the Recycling Contractor and shall use it only for the intended purpose.

C.45.15.4. Recyclables

Collection and Pickup: Contractor shall ensure that recyclables are collected and placed in the designated holding areas on a schedule that will maximize the quantity of materials removed from the premises as scheduled. Additional collections of recyclable materials may be required on an irregular basis, and will be coordinated with the CO or his/her designee.

Container(s) provided by the Contractor shall be placed in the area designated by the CO or his/her designee where trash is collected. Container(s) will be placed on each floor to receive the collection of recyclable materials. Full containers with recyclables are to be transported by the Contractor to the dock for pickup by the vendor.

Pick-ups On call RESERVED

C.45.15.4.1. The Contractor Shall

A. Arrange for the removal of recyclables from premises. Be responsible for all fees, if any, associated with recycling.
B. Remove all recyclable materials to a storage area designated by the CO or his/her designee. Recyclable materials may be found in

- ☐ Central Recycling bins and containers (located in common areas such as hallways, break rooms, conference rooms, snack bars, cafeteria and/or restrooms, etc.)
- ☐ Desk side recycling bins and containers.
- ☒ Both.

C. Place recyclable materials in containers, dumpster, or compactor provided by recycler. The Contractor shall monitor containers to prevent littering of holding area. No trash shall accumulate in holding area.

D. Bale corrugated materials if a baler is available.

E Ensure that all custodial staff involved in the recycling program fully understand the recycling procedures and requirements.

F. Coordinate additional pickups within 24 hours of notification by the CO or his/her designee.

G. Retain any proceeds that result from the sale of recyclable materials covered by this contract. Verification of the amount of proceeds received from the sale of recycled materials shall be furnished to the CO or his/her designee.

C.45.15.4.2. Restriction on Use

Recyclable paper purchased under this contract shall be used or sold as recyclable paper only; i.e., for processing at a pulp mill to be made into new paper products. The Contractor shall not use, allow access to, or offer for resale any papers, documents, or file record material for the information contained therein.

C.45.15.4.3. Recycling Proceeds RESERVED

C.45.15.4.4. Recycling Records and Reports

The Government is required to report the percentage of the building's total waste stream diverted to recycling. Records showing the cost and amount of material hauled will be provided to the CO or his/her designee so that this report can be submitted as required by the Resource Conservation and Recovery Act (RCRA) and EO 13514.

Report as it relates to products and services used/provided by this contract. Reports prepared by the Contractor shall be submitted to the Government electronically. Reports from the Contractor should provide all required data for the OFEE and OMB Reporting Requirements as it relates to products and services used and/or provided by this contract. When electronic submittals are not available, hard copy reports shall be used. Paper used by the Contractor shall be printed on two-sided paper containing a minimum of 30 percent post consumer recycled content.

Reports. The Contractor shall submit two reports to the CO or his/her designee:

1. Monthly Recycling Reports. The Contractor shall submit a monthly Recycling Report by the 10th of each month listing the total recovered types and weights, including commingled items, of each material recycled using the spreadsheet in Exhibit J. Reports shall be provided to the CO or his/her designee for review.

2. Annual Recycling Report: The Contractor shall submit a listing of the types and weights, including commingled items, of materials recycled for a 12-month period covering October through September. If full year data is not available, the CO or his/her designee may request partial year data.

3. Waste Hauling Report: The Contractor shall submit a **Waste Hauling Report** to the CO or his/her designee, showing the amount of trash hauled, by volume or weight and tipping fees. The report shall be submitted monthly. Records and receipts obtained shall be made available to the CO or his/her designee upon request.

C.45.16. Integrated Pest Management

The Integrated Pest Management (IPM) Plan is a preventive maintenance process that coordinates many different programs to reduce sources of pest on a long-term basis for both the interior and

exterior areas of a building as defined in 7 U.S.C. 136r-1 http://uscode.house.gov. The Contractor shall employ practices and techniques, as they relate to cleaning, trash, and materials handling, that reduce the sources of food and water, harborage, and access routes used by pests in and around the building.

C.45.16.1. Preventive Pest Maintenance

The Contractor shall implement a preventive maintenance program that identifies and corrects conditions that contribute to pest infestation. Some of the most effective **EXAMPLES** include but are not limited to:

- Self-contained compactors rather than dumpsters or stationary dumpsters for storing solid waste awaiting pickup, wherever possible.
- Pressure washing of trash rooms, loading docks, and food preparation facilities.
- Food preparation and storage areas remain clean.
- Dedicated, tightly covered receptacles for food waste in indoor areas with chronic pest problems.
- Replacement of dense ground cover in landscapes with chronic rodent problems.
- Employ techniques that may include, but not limited to, keeping containers closed, removal of debris, etc.

C.45.16.2. Initial Pest Assessment

A certified pesticide applicator or licensed IPM Contractor shall conduct a thorough, initial assessment of the

☐ interior space and ☐ exterior grounds and paved areas. Access to building space shall be coordinated with the CO or his/her designee. The CO or his/her designee must inform the Contractor of any restrictions or areas requiring special scheduling. The purpose of the initial assessment is for the custodial Contractor to identify areas or practices that may contribute to pest infestation.

A written report detailing the findings of the initial assessment shall be submitted to the CO or his/her designee within fifteen (15) calendar days of the start of the contract. Throughout the life of this contract, the Contractor shall be responsible for notifying the CO or his/her designee, in writing, about any sanitary or procedural modifications deemed necessary to eliminate pest infestation.

C.45.16.3 RESERVED

C.45.16.4. General

The certified pesticide applicator or licensed IPM Contractor shall accomplish the monitoring trapping, and pesticide application and pest removal components of the IPM.

C.45.16.5. Pest Included and Excluded

The Contractor shall adequately suppress indoor populations of rats, mice, cockroaches, ants, flies, and any other arthropod pests not specifically excluded in this exhibit. This includes populations of these pests that are located outside of the specified facilities, but within the property boundaries of the facilities.

The following pests are excluded from this contract and should be ordered by the region under a specialized contract:

- Birds, mosquitoes
- Snakes
- Vertebrates that are not commensal rodents

- Bats
- Termites
- Other wood-destroying organisms
- Bed bugs

C.45.16.5. Pest Control Plan

Prior to initiation of services, the Contractor shall submit to the CO or his/her designee for approval a Pest Control Plan within 30 calendar days following the initial assessment. The plan should include integrated methods, routine site inspections and maintenance, routine pest inspections, pest population monitoring, evaluation of the need for pest control and one or more pest control methods. The plan shall also include a specification of the circumstances under which an emergency application of pesticides can be applied and a communications strategy directed to building occupants.

The Pest Control Plan shall consist of five parts:

A. Proposed Materials and Equipment for Service including labels and Material Safety Data Sheets for all pesticides to be used. A list of brand names of trapping devices, pesticide application equipment, rodent bait boxes, insect and rodent trapping devices, pest monitoring devices, pest detection equipment, and any other pest control devices or equipment that may be used to provide service. The use of green and sustainable methods and applications is preferred whenever possible

B. Proposed Methods for Monitoring and Detection including describing those methods and procedures to be used for identifying sites of pest harborage and access, and for making objective assessments of pest population levels throughout the term of the contract.

C. An inspection schedule for each building or site. Frequency of contract visits shall depend on the specific pest control needs of each premise. Large office facilities, or specified office areas within such facilities, with a history of pest infestations, will be visited more frequently.

D. A description of any structural or operational changes that would facilitate the pest control effort.

E. A copy of the Commercial Pesticide Applicator Certificate or License for every Contractor representative who will be performing on-site service in accordance with this exhibit.

C.45.16.6. Pesticide Application

The Contractor shall not apply any chemical or non-chemical pesticide product that have not been included in the Pest Control Plan or approved in writing by the CO or his/her designee. If the CO or his/her designee has concerns or questions regarding chemicals being used, the CO or his/her designee should contact the Integrated Pest Management Coordinator in GSA's National Capital Region. The Contractor shall employ the least hazardous materials, most precise application technique, and minimum quantity of pesticide necessary to achieve control. Pesticides used by the Contractor must be registered with the U.S. Environmental Protection Agency (EPA), state and/or local jurisdiction. Transport, handling, and use of all pesticides shall be in strict accordance with the manufacturer's label instructions and all applicable Federal, State, and local laws and regulations. All chemicals shall be in the original manufacturer's containers and properly labeled.

Chemical pesticides shall not be applied in any Child Care center without prior coordination and consent of the Child Care Director. Posting and notifying the Child Care Director must be initiated at least 24-48 hours in advance of using any chemical pesticides. Only qualified, trained, and certified personnel or licensed Contractors shall apply any chemicals. Uncertified individuals

working under the supervision of a certified pest applicator or licensed Contractor shall not be permitted to provide service under the terms of this contract. Chemicals shall be applied with extreme care to avoid hazard to any person or animal in the immediate or adjacent areas, or property damage.

Pesticide application shall be according to need and not by schedule. As a general rule, application of pesticides in any area shall not occur unless visual inspections or monitoring devices indicate the presence of pests in that specific area. In no case shall extremely toxic materials be permitted. The Contractor shall not store any pesticide product on Government property. **Any emergency applications of chemical pesticides must be approved by the CO or his/her designee prior to application**.

C.45.16.7.Structural and Procedural Recommendations

Structural modifications for pest control will be the responsibility of the Government. However, throughout the life of this contract, the Contractor shall be responsible for notifying the CO or his/her designee in writing about concerns with any structural, sanitary, or procedural modifications deemed necessary to eliminate food and water sources, harborage, or access routes that would allow building infestation by pests in and around the building.

C.45.16.8.Record Keeping

The Contractor shall be responsible for maintaining a pest control logbook or file for each building or site specified in this contract. The log shall include pesticide information on whether chemical and non-chemical methods were used to control pests. These records shall be kept on Government property and maintained by the Contractor.

Each log book or file shall contain at least the following items:

A. A copy of the Pesticide Control Plan, (including labels and MSDS for all pesticides used), brand names of all pest control devices and equipment, and the Contractor's service schedule for the inspection and/or treatment of the building.

B. Completed copies of GSA Form 3638, Pest Control Work and Inspection Report, or an equivalent such as other Contractor service report forms that is approved by the CO or his/her designee. The report form shall be used to advise the Contractor of routine service requests and to document the performance of all work. The Contractor shall also document on the GSA Form 3638, or equivalent all information on pesticide application that is required by statute in the jurisdiction where service is actually performed. Upon completion of a service visit to a building, the Contractor's representative performing the service shall complete, sign, and date the GSA Form 3638 or equivalent form.

C.45.16.9.Manner and Time to Conduct Service

Routine pest control services that do not adversely affect tenant health or productivity, shall be performed during the tenants' normal working hours. The Contractor shall notify the CO or his/her designee shall provide notice to occupants at least 72 hours before application of any pesticide during normal conditions and within 24 hours in emergency situations. When it is necessary to perform work outside of the tenants normal working hours, the Contractor shall notify the COR at least one day in advance.

C.45.16.10. Insect Control

The Contractor shall provide the CO or his/her designee with signs, placards, literature or other information so that the CO or his/her designee can inform building occupants of the nature of the

pest application. The information will include at a minimum a brief explanation regarding the reason for the pest application, the safety of the products being used and contact information should the building occupants have questions.

A. Non-pesticide Products and Use: The Contractor shall use non-pesticide methods of control wherever possible. For example:

- Portable vacuums with HEPA or MICRO filtration
- Trapping devices

B. Chemical Pesticide Products and Use: When it is determined that a chemical pesticides must be used in order to obtain adequate control, the Contractor shall employ the least hazardous material, most precise application technique, and minimum quantity of pesticide necessary to achieve control. The Contractor shall minimize the use of liquid pesticide applications wherever possible, for example:

- Bait stations and other types of bait formulations rather than sprays
- As a general rule, liquid, aerosol, or dust formulations shall be applied only as crack and crevice treatments.
- Application of pesticide liquid, aerosol, or dust to exposed surfaces, and pesticide space sprays (including fogs, mists, and ultra-low volume applications), shall be restricted to unique situations where no alternative measures are practical.

The Contractor shall obtain the approval of the CO or his/her designee prior to any application of pesticide liquid, aerosol, or dust to exposed surfaces, or any space spray treatment. Other than crack and crevice treatments, no liquid, aerosol, or dust applications shall be made while tenant personnel are present.

C.45.16.11 Rodent Control

A. Indoor Trapping: Generally, rodent control inside buildings shall be accomplished with trapping devices only. All such devices shall be concealed out of the general view and in protected areas so as not to be affected by routine cleaning and other operations. Traps shall be checked on a schedule approved by the CO or his/her designee. The Contractor shall be responsible for disposing of all trapped rodents and all rodent carcasses in an appropriate manner.

B. Use of Rodenticides: In extreme cases, when rodenticides are deemed essential for adequate rodent control inside buildings, the Contractor shall obtain approval from the CO or his/her designee prior to making any interior rodenticide treatment. All rodenticides, regardless of packaging, shall be placed either in locations not accessible to children, pets, wildlife, and domestic animals, or in EPA-approved tamper-resistant bait boxes. As a general rule, rodenticide application outside buildings shall emphasize the direct treatment of rodent burrows wherever feasible.

C. Use of Bait Boxes: All bait boxes shall be maintained in accordance with EPA regulations, with an emphasis on the safety of non-target organisms. The Contractor shall adhere to the following five points:

1. All bait boxes shall be placed out of the general view, in locations where they will not be disturbed by routine operations.
2. The lids of all bait boxes shall be securely locked or fastened shut.
3. All bait boxes shall be securely attached or anchored to floor, ground, wall, or other immovable surface, so that the box cannot be picked up or moved.

4. Bait shall always be secured in the feeding chamber of the box and never placed in the runway or entryways of the box.
5. All bait boxes shall be labeled on the inside with the Contractor's business name and address, and dated by the Contractor's technician at the time of installation and each servicing.

C.45.16.12. Safety and Health

All work shall comply with the applicable requirements of 29 CFR 1910, (http://www.access.gpo.gov/nara/cfr/waisidx_06/29cfr1910a_06.html), state and municipal safety and health requirements. Where there is a conflict between applicable regulations, the most stringent shall apply.

C.45.17 Child care Center RESERVED

C.45.18 Cleaning Schedules

The cleaning schedule is considered the Contractor's efficient approach to the work, and shall not limit the Contractor to specific levels of staffing, means or methods. Changes necessary for achieving the contract performance work statement requirements shall be the responsibility of the Contractor. Cleaning schedules and any revisions are to be submitted to the COR.

The Contractor's cleaning schedule shall, as a minimum, include the following frequency:

A. Daily cleaning
B. Periodic
   - Weekly cleaning
   - Monthly cleaning
   - Bi-Annual cleaning
   - Annual cleaning
   - Other frequencies

D. PACKAGING & MARKING

D.1. Payment Of Postage And Fees

All postage and fees related to submitting information including, forms, reports, etc., to the Contracting Officer or the Contracting Officer's Representative shall be paid by the Contractor.

D.2. Marking

All information submitted to the Contracting Officer or the Contracting Officer's Representative shall clearly indicate the contract number of the contract for which the information is being submitted.

E.INSPECTION & ACCEPTANCE

E.1. The Role Of Government Personnel And Responsibility For Contract Administration

E.1.1 Contractor Responsibility

The Contractor is responsible for the day-to-day examination and monitoring of all work performed to ensure compliance with the contract requirements, according to the Quality Control Plan submitted by the Contractor. The examinations conducted shall be documented. The Contractor shall follow through to assure that all defects or omissions are corrected. ** (Refer to Quality Control, Section C.

E.1.2 Contracting Officer

The Contracting Officer has the overall responsibility for the administration of this contract. He/She alone, without delegation, is authorized, but not limited to take the following actions on behalf of the Government to: amend, modify or deviate from the contract terms, conditions, requirements, specifications, details and/or delivery schedules; make final decisions on disputed deductions from contract payments for nonperformance or unsatisfactory performance; terminate the contract for convenience or default; issue final decisions regarding contract questions or matters under dispute. However, he/she may delegate certain other responsibilities to his/her authorized representatives.

E.1.3 Contracting Officer's Representatives

TBD at award

Contracting Officer's Representative (COR) "means an individual, including a contracting Officer's technical representative (COTR), designated in writing by the Contracting Officer to perform specific technical or administrative functions."

E.1.4 Government Quality Assurance

Quality Assurance Evaluators (QAE) are responsible for periodic inspection and monitoring of the Contractor's work.

All aspects of the services rendered under this contract is subject to Government inspection, during the Contractor's operations and after completion of the tasks. The Government's Quality Assurance Surveillance Program is not a substitute for Quality Control by the Contractor. All costs associated with rework are the responsibility of the Contractor. The Government reserves the right to choose the inspection methods to be used in implementing its Quality Assurance Program and to vary the inspection methods utilized during the work, without notice to the Contractor.

E.1.5 Occupant Complaint Program

Tenant satisfaction is one of the key controls to ensure that the building is maintained in a clean and sanitary manner.

A. A complaint log will be maintained by the Contractor to gauge tenant satisfaction as well as document cases of non-performance. This occupant complaint program will be considered in evaluating the Contractor's performance and in renewing the contract.

B. In addition to the occupant complaint log, the Government will periodically survey the tenants to ascertain the satisfaction level of the Contractors cleaning. The Contractor will be given results of all tenant surveys to assist in maintaining levels of acceptable service.

C. In the event tenant requests work not covered by the contract, the Contractor shall refer tenant to the CO or his/her designee.

D. In addition to the above, a Government representative will make a periodic walk through of the building and other areas covered by this contract with the Contractors representative, when possible, to ascertain the level of services being performed. The Contractor will be notified in writing of any deficiencies noted.

E.1.6 FAR 52.246-4 Inspection of Services-Fixed-Price (Aug 1996).

(a) *Definition.* "Services," as used in this clause, includes services performed, workmanship, and material furnished or utilized in the performance of services.
(b) The Contractor shall provide and maintain an inspection system acceptable to the Government covering the services under this contract. Complete records of all inspection work performed by the Contractor shall be maintained and made available to the Government during contract performance and for as long afterwards as the contract requires.
(c) The Government has the right to inspect and test all services called for by the contract, to the extent practicable at all times and places during the term of the contract. The Government shall perform inspections and tests in a manner that will not unduly delay the work.
(d) If the Government performs inspections or tests on the premises of the Contractor or a subcontractor, the Contractor shall furnish, and shall require subcontractors to furnish, at no increase in contract price, all reasonable facilities and assistance for the safe and convenient performance of these duties.
(e) If any of the services do not conform with contract requirements, the Government may require the Contractor to perform the services again in conformity with contract requirements, at no increase in contract amount. When the defects in services cannot be corrected by re-performance, the Government may-
(1) Require the Contractor to take necessary action to ensure that future performance conforms to contract requirements; and
(2) Reduce the contract price to reflect the reduced value of the services performed.
(f) If the Contractor fails to promptly perform the services again or to take the necessary action to ensure future performance in conformity with contract requirements, the Government may-
(1) By contract or otherwise, perform the services and charge to the Contractor any cost incurred by the Government that is directly related to the performance of such service; or
(2) Terminate the contract for default.

(End of clause)

E.1.7 FAR 52.246-16 Responsibility for Supplies (APR 1984).

(a) Title to supplies furnished under this contract shall pass to the Government upon formal acceptance, regardless of when or where the Government takes physical possession, unless the contract specifically provides for earlier passage of title.

(b) Unless the contract specifically provides otherwise, risk of loss of or damage to supplies shall remain with the Contractor until, and shall pass to the Government upon—

(1) Delivery of the supplies to a carrier, if transportation is f.o.b. origin; or

(2) Acceptance by the Government or delivery of the supplies to the Government at the destination specified in the contract, whichever is later, if transportation is f.o.b. destination.

(c)) Paragraph (b) of this clause shall not apply to supplies that so fail to conform to contract requirements as to give a right of rejection. The risk of loss of or damage to such nonconforming supplies remains with the Contractor until cure or acceptance. After cure or acceptance, paragraph (b) of this clause shall apply.

(d) Under paragraph (b) of this clause, the Contractor shall not be liable for loss of or damage to supplies caused by the negligence of officers, agents, or employees of the Government acting within the scope of their employment.

E.1.8 Failure to Perform

In the event work is performed unsatisfactorily, the Contractor will be requested in writing to correct the deficiencies within 10 calendar days. If the work remains deficient, the CO or his/her designee may have the work accomplished by other means and deduct the cost thereof from the monthly payment due the Contractor

F.DELIVERIES OR PERFORMANCE

F.1 PLACE OF PERFORMANCE

The services to be provided under this contract shall be accomplished at the following building(s):

1. Alto Lee Adams Sr. US Courthouse, Ft. Pierce, FL (FL0030ZZ)
2. Claude Pepper Federal Building, Miami, FL (FL0061ZZ)
3. Brickell Plaza Federal Building, Miami, FL (FL0079ZZ)
4. US Courthouse, Ft. Lauderdale, FL (FL0089ZZ)
5. James L King Federal Justice Building, Miami, FL (FL1021ZZ)
6. Sydney M. Arnovitz U.S. Courthouse, Key West, FL (FL0019ZZ)

F.2. TERM OF CONTRACT

F.2.1 Term of the Contract

After award, the successful Contractor will be given a written notice to proceed, and shall provide contractual services for a **twelve-month period**. This service requirement is subject to the availability of appropriations, in accordance with GSAR, Availability of Funds, commencing on the date specified in the notice to proceed. Work under this contract is expected to commence **on or about October 1, 2015**. If possible, the notice to proceed will provide for at least 30 working days preparation time before commencement of work.

F.2.2 Option to Extend the Term of the Contract

The Government shall have the unilateral option of extending the term of this contract in accordance with the following Federal Acquisition Regulation:

A. FAR 52.217-9, OPTION TO EXTEND THE TERM OF THE CONTRACT – SERVICES (MAR 2000).

B. FAR 52.217-8, OPTION TO EXTEND SERVICES (NOV 1999).

F.3. REPORTING REQUIREMENTS

Refer to Section J.3. Contract Deliverable References for submittal requirements.

F.3.1 Plans, Schedules and Report Format Submission Requirements

All reports submitted shall be transmitted electronically. The contractor shall scan in all related data that is annotated in paper form and present the data electronically The electronic reporting format shall be developed between the Contractor, the CO or his/her designee. Sample formats include but not limited to PDF, Microsoft Word or Microsoft Excel. If hard copy is required by the CO or his/her designee electronic copy is to be provided as well.

F.3.2 Other Reports

The Contractor shall provide any other reports required by the Government during the term of the contract. (Please refer to Section J.2.Deliverables for additional report requirements)

Report	When Due
• Security & Alarm Outages	Immediately to Control Center
•	Equipment opening or dismantling Minimum of 2 weeks prior
• Planned Utility & Security System	72 Hours in Advance of Outages
• Any Planned Work Disruptive to Building Occupants or Operations	72 Hours in Advance (two weeks notice for fire alarm testing)
• "As Built" Alteration Drawings	Upon Completion of Work
• Major Equipment/Systems Not Operational	As Required-Daily before 8 AM
• Copies of contracts & subcontracts	Prior to placement
• Switchgear Load Test Result	Two weeks after completion
• Phase Out Transition Period	One month prior to the expiration of the contract or any option periods

G. CONTRACT ADMINISTRATION DATA

G.1. PAYMENTS

G.1.1 General

Payment will be made on a calendar month basis in arrears upon submission of an invoice. Payment will be due on the 30th calendar day after receipt of a proper invoice, or date of receipt of services, whichever is later. In the event the contract begins or ends during the month, payments will be prorated based on the number of calendar days in that month. **It is the objective of the Government to obtain complete and satisfactory performance in accordance with the terms of the specifications and quality requirements of this contract.** Payment for any service rendered will be due in accordance with the Prompt Payment clause in Section I. Invoices shall be submitted to GSA's Office of Finance electronically via the following:

Web site address: www.finance.gsa.gov

General Services Administration
Greater Southwest Finance Center
Director, PBS Payments Branch (BCFA)
P.O. Box 17181
Ft. Worth, TX 76102-0181
Telephone: (817) 978-2408

(For any other information regarding this contract, contact the CO or his/her designee.)

Payment for any service rendered will be due in accordance with the Prompt Payment clause in Section I. In the event the contract begins or ends during the month, payments will be prorated based on the number of workdays in the respective month.

G.1.2 Payments for Additional Services

Payment for Additional Services as described in Part I, Section B, shall be made on the basis of an invoice submitted to GSA's Office of Finance electronically via the following:

Web site address: www.finance.gsa.gov

G.2. UNEXPECTED BUILDING CLOSURE

Deductions will not be assessed for requirements on those days in which services are not required by the Government because the building(s) is closed due to unanticipated holidays, declared by the President, **PROVIDED**, that payment to employees for such holidays is required in accordance with the wage determination applicable to this contract.

In the event services are not provided or required by the Government because the building(s) is closed due to inclement weather, deductions will not be assessed.

G.3. WITHHOLDING MONIES FOR NON-SUBMISSION OF WORK SCHEDULES

The Contractor is required to submit an acceptable quality control program and other deliverables as required by the contract not later than the contract performance date. The CO or the designated representative may grant an extension.

In the event the Contractor fails to submit the acceptable deliverables for operation plans and procedures, operator assignment sheets, work assignment sheets, proposed maintenance guides, and an annual schedule for periodic preventive maintenance by the contract performance date and any extensions granted by the Contracting Officer or his designated representative, all payments **shall be** withheld until the items are received and approved by the Government. The CO will notify the Contractor in writing in the event that payments are withheld.

G.4. WITHHOLDING MONIES FOR NON-SUBMISSION OF REPORTS

If the Contractor fails to prepare and/or submit acceptable reports as called for in Section J.3.Contract Deliverables within the required time frame, this may be construed to mean that the contract work has not been performed and the Government **may** withhold all payments until the required reports are satisfactorily completed and/or submitted to the Contracting Officer's Representative.

G.5. APPLICATION OF CRITERIA FOR DEDUCTIONS (NON-PERFORMANCE

A. Daily Services. If the Contractor fails to perform satisfactorily or omits work required for performance every 10 working day or more frequently, the Contractor's attention shall be called to this failure or omission. Costs to be deducted under this paragraph will be determined by using the formula in Section G, Paragraph 5C below.

B. Periodic Services. If the Contractor fails to perform satisfactorily, omits, or fails to reschedule tasks required to be performed less frequently than every 10 working days as outlined in the Contractor's approved periodic schedule, the Contracting Officer or his designated representative shall give the Contractor written notice of the failure or omission. Once notified, if the Contractor does not complete the work within the time allotted by the Contracting Officer or his designated representative the work may be performed by other means and the cost thereof shall be deducted from monies due or to become due the Contractor. Failure of the Contractor to perform, or if the omitted or unsatisfactory work cannot be rescheduled, a cost determined by using the formula in Section G, Paragraph 5C below shall be deducted from monies due or to become due the Contractor.

C. Quality Control Inspections. In the event the scheduled inspections as identified in the approved quality control program are not accomplished, a deduction shall be made from any monies due or to become due to the Contractor. The Government will determine the time (man-hours) necessary to make the inspection, including any travel time required and multiply the total by the following hourly rate to arrive at the total deductible dollar amount. The Contractor will be charged a minimum of 2 hours in the event the Government has to perform these inspections.

Quality Assurance Inspection / Re-inspection Hourly Rate

Quality Assurance Inspection	Base Year	Option I	Option II	Option III	Option IV
Hourly rate	Current GS-12 Step 1	Current GS-12 Step 1	Current GS-12 Step 1	Current GS-12 Step 1	Current GS-12 Step 1

G.6. REDUCTION AND ADDITION OF SPACE

A. When blocks of cleanable space per building are expected to change for 30 calendar days or longer, modifications will be made to the monthly payments due the Contractor. The CO or his/her designee will notify the Contractor, or his representative, in writing, of the effective date the areas are to be dropped from or returned to the normal cleaning schedule at least three (3) full working days in advance of these dates.

B. The period for adjusting changes in space will begin on the effective date as stipulated in writing by the CO or his/her designee, and will continue until the effective date in which the cleaning is resumed. The square footage may be made up of individual blocks of space totaling the square footage as indicated in the table below. Subsequent blocks of space totaling any square footage may be added or deleted after the initial threshold measurement is met.

SPACE REDUCTION SCALE

Total Cleanable Area	Threshold SF
100,000 SF and above	5,000 SF
99,999 SF – 50,000 SF	2,500 SF
49,999 SF – 25,000 SF	1,000 SF
24,999 – and below	500 SF

C. Calculating Additions/Reductions of Space. Pay adjustments due to reductions/additions of space will be computed by using the Contractor's negotiated per square foot cost minus subcontract cost (i.e., trash removal, window washing, pest control and grounds maintenance). Then, divide the total adjusted annual bid price by the cleanable area for the building(s) to arrive at an annual per square foot cost.

Further divide the adjusted annual per square foot cost by 12 to arrive at the adjusted monthly per square foot cost. The adjusted monthly per square foot cost is then divided by an average number of calendar days (30) to arrive at a daily per square foot rate. The deduction rate per square foot is to be carried out to four decimal places. The total cleanable area for the building involved is given in Exhibit 1, Building Information Sheet as provided in the statement of work. In the event the contract contains multiple buildings, each one will be calculated separately. Below is an example calculation of space deductions:

Example: Cleanable area as indicated on Exhibit 1, Bldg Info Sheet = 45,450 sq. ft. Annual contract price = $50,550 (-) Trash removal/$2,700, (-) Grounds maintenance/$1,700, (-) Window washing/$3,000, and (-) Pest control/$895 = Total adjusted annual cost of $42,255. The $42,255 is then divided by the total cleanable area of 45,450 to arrive at the adjusted annual per square foot cost of $.93 per square foot.

$.93 ÷ 12 = $.0775 per square foot per month
$.0775 ÷ 21 days = $.0026 per square foot per day

The deduction rate in dollars per day, multiplied by the number of square feet of unoccupied space and further multiplied by the number of days the space was not occupied will equal the total dollar deduction to be made.

The formula stated above will also be used to determine deductions for unsatisfactory or non-performance of services and addition of space not covered in the original contract.

G.7. Additions and Deletions of Buildings

The Government may add or delete buildings during the term of this contract upon approval of the CO. Facilities may be added provided it is within those counties either covered by the presently incorporated Wage Determination (Reference Section I) and/or within the cognizance of the territories assigned to the Service Center. The cost/price for any addition will be subject to negotiations after this office is in receipt of a detailed cost proposal based upon the current Wage Determination available at the time of the addition. The deletion of a building will be at the bid/offer price current for that building at the time of deletion.

H. SPECIAL CONTRACT REQUIREMENTS

H.1. SECURITY

H.1.1 GSAM 552.237-71 QUALIFICATIONS OF EMPLOYEES (MAY 1989)

(a) The contracting officer or a designated representative may require the Contractor to remove any employee(s) from GSA controlled buildings or other real property shall it be determined that the individual(s) is either unsuitable for security reasons or otherwise unfit to work on GSA controlled property.

(b) The Contractor shall fill out and cause each of its employees performing work on the contract work to fill out, for submission to the Government, such forms as may be necessary for security or other reasons. These forms shall be completed electronically unless that would create a hardship for the individual. Upon request of the Contracting Officer, the Contractor and its employees shall be fingerprinted.

(c) Each employee of the Contractor shall be a citizen of the United States of America, or an alien who has been lawfully admitted for permanent residence as evidenced by Alien

Registration Receipt Card Form I-151, or, who presents other evidence from the Immigration and Naturalization Service that employment will not affect his immigration status.

H-1.2. SUITABILITY DETERMINATIONS

(a) All contract employees requiring routine unescorted access to Federally-controlled facilities and/or information systems for more than 6 months (Regular Employees) will be required to undergo a suitability determination before a facility identification card is issued. Prior to the time that an identification card is issued, such Regular Employees will be required to comply with normal facility access control procedures, including sign-in, temporary badging, and escorted entry, as applicable.

(b) Failure of a Regular Employee to receive a favorable suitability determination shall be cause for removal of the employee from the work site and from other work in connection with the Contract.

(c) Contract employees working less than 6 months (Temporary Employees) may, at the Government's option, be required to undergo a lesser form of suitability determination. Prior to the time that an identification card is issued, if at all, such Temporary Employees will be required to comply with normal facility access control procedures, including sign-in, temporary badging, and escorted entry, as applicable.

(d) Temporary Employees who have not received a favorable suitability determination shall be escorted at all times while in non-public space, as directed by the Government.

(e) The Government, at its sole discretion, may grant temporary suitability determinations to Regular or Temporary Employees. However, the granting of a temporary suitability determination to any such employee shall not be considered as assurance that a favorable suitability determination will follow.

(f)The Contracting Officer or his/her designated representative shall provide the Contractor with required forms for obtaining necessary clearances. The Contractor shall be required to cause such forms to be returned to the Government for processing not later than 14 days following being provided by the Government.

(g) The Contractor shall be responsible for planning and scheduling its work in such a manner as to account for facility access issues. Difficulties encountered by the Contractor in gaining access to facilities by its employees and subcontractors shall not be an excuse to any Contractor performance under the Contract.

H-1.3. COMPLIANCE WITH SECURITY REQUIREMENTS

(a) The Contractor shall comply with all GSA and tenant agency security requirements in the building(s) where work is being performed.

(b) When a controlled personnel identification access system is used by a tenant agency at a site where work is performed, the tenant agency will be responsible for providing any required access credentials. Credentials shall be displayed at all times or as otherwise required by the tenant agency.

H.1.4. Suitability Determinations

a. All Contract employees requiring routine unescorted access to Federally-controlled facilities and/or information systems for more than 6 months (Regular Employees) will be required to undergo a suitability determination before a facility identification card is issued. Prior to the time that an identification card is issued, such Regular Employees will be required to comply with normal facility access control procedures, including sign-in, temporary badging, and escorted entry, as applicable.

b. Failure of a Regular Employee to receive a favorable suitability determination shall be cause for removal of the employee from the work site and from other work in connection with the Contract.

c. Contract employees working less than 6 months (Temporary Employees) may, at the Government's option, be required to undergo a lesser form of suitability determination. Prior to the time that an identification card is issued, if at all, such Temporary Employees will be required to comply with normal facility access control procedures, including sign-in, temporary badge, and escorted entry, as applicable.

d. Temporary Employees who have not received a favorable suitability determination shall be escorted government at all times while in non-public space, as directed by the CO . The CO shall provide the Contractor with required forms for obtaining necessary clearances. The Contractor shall be required to cause such forms to be returned to the Government for processing not later than 14 days following being provided by the Government.

e. The Government, at its sole discretion, may grant temporary suitability determinations to Regular or Temporary Employees. However, the granting of a temporary suitability determination to any such employee shall not be considered as assurance that a favorable suitability determination will follow.

f. The Contracting Officer or his/her designated representative shall provide the Contractor with required forms for obtaining necessary clearances. The Contractor shall be required to cause such forms to be returned to the Government for processing not later than 14 days following being provided by the Government.

g. The Contractor shall be responsible for planning and scheduling its work in such a manner as to account for facility access issues. Difficulties encountered by the Contractor in gaining access to facilities by its employees and subcontractors shall not be an excuse to any Contractor performance under the Contract.

H.1.5. Compliance with Security Requirements

a. The Contractor shall comply with all GSA and tenant Agency security requirements in the building(s) where work is being performed.

b. Contractor personnel requiring access to GSA's Network shall comply with all Federal Information Technology (IT) regulations regarding Trusted Internet Connection (TIC) in conjunction with PBS and GSA Chief Information Officer (CIO) IT policies, i.e., all PBS IT systems needing network connectivity must reside on the GSA network.

When a controlled personnel identification access system is used by a tenant Agency at a site where work is performed, the tenant Agency will be responsible for providing any required access credentials. Credentials shall be displayed at all times or as otherwise required by the tenant Agency.

H.1.6.Standards of Conduct

The Contractor shall be responsible for maintaining satisfactory standards of employee competency, conduct, appearance, and integrity and shall be responsible for taking such disciplinary action with respect to its employees as may be necessary.

H.2. IDENTIFICATION CREDENTIAL

a. Upon receipt of favorable suitability determination as indicated in this document, each employee of the Contractor will be issued an identification credential. At all times while working on the Contract, a Contract employee, including subcontractor employees, shall have in his or her possession the specific Government identification credential issued to him or her by the Government. The identification credential shall be displayed and be visible at all times while on Government property. The CO , Government law enforcement, or security person shall periodically verify passes of Contractor employees with their personnel identification. Contractor employees shall comply with security verification procedures at all times.

b. The Contractor shall ensure that every Contract employee has a Government issued identification credential before the employee enters on duty. As required by the Government, the Contractor shall make his employees available for photo identification badges, on a schedule to be worked out with the CO . The Government will make the identification credentials after a favorable security determination has been received for the Contractor's employees. Each identification credential shall have an expiration date and Contractor employees shall sign each badge at the time of photographing.

c. The Contractor shall be responsible for ensuring that all identification credentials are returned to the CO whenever his employees leave the Contract (when the Contract has been completed, employees leave the company, or employees are dismissed or terminated). The Contractor shall notify the CO whenever employee badges are lost.

d. The Contractor will be responsible for paying the Government for replacement credentials at the current cost per badge.

H.3. Escort Requirements

It may be necessary to escort temporary Contract employees who do not have favorable preliminary or final suitability determinations and shall work in federally controlled space. In those cases, all uncleared Contract employees shall be escorted in nonpublic space by a Government employee or another responsible cleared Contract employee who is approved by the CO . Other Government agencies may have specific Agency security requirements for their own space that may only allow escort by Government employees or those designated by their Agency. Government employees or approved cleared Contract employees who provide escorts for uncleared Contract employees shall always be in close proximity and within eyesight of the uncleared Contract employee. The Contract escort shall watch uncleared employees and remain with uncleared Contract employees for the entire time they are in the building and or federally controlled space. Uncleared employees cannot be left alone or out of eyesight at anytime they are in nonpublic space. A cleared and approved escort may not allow several uncleared Contract employees to be in Federally controlled space, that is not within close proximity and within eyesight at all times. A cleared and approved escort may not allow multiple uncleared employees in non-public space on different parts of one floor or different floors at the same time. Any security violation of escort requirements by a cleared and approved Contract employee will result in the immediate removal from the Contract of all Contract employees involved, i.e., escorts and uncleared escorted Contract employees. Also, violations of escort requirements by Contract employees in accordance with security requirements may be grounds for termination of the Contract.

H.4. Standards Of Conduct

The Contractor shall be responsible for maintaining satisfactory standards of employee competency, conduct, appearance, and integrity and shall be responsible for taking disciplinary action with respect to his employees as necessary. The Contractor is responsible for ensuring that his employees do not disturb papers on desks, open desk drawers or cabinets, or use Government telephones, except as authorized. Each employee is expected to adhere to standards of behavior that reflect favorably on his or her employer and the Federal Government. No smoking is allowed in the building. No smoking or tobacco products are allowed to be utilized in the building to include electronic cigarettes.

H.5. Removal From Contract Work

a. As provided in the clause entitled "Qualifications of Employees," the Contracting officer or a designated representative may require the Contractor to remove any employee(s) from GSA controlled buildings or other real property should it be determined that the individual(s) is either unsuitable for security reasons or otherwise unfit to work on GSA controlled property. This shall include, but not be limited to, instances where an employee

is determined, in the Government's sole discretion, to be incompetent, careless, insubordinate, unsuitable, or otherwise objectionable.

b. When the Government deems the employee's continued employment to be contrary to the public interest, inconsistent with the best interests of security, or when the employee is identified as a potential threat to the health, safety, security, general well-being, or operational mission of the facility and its population.

c. The CO may also request the Contractor to immediately remove any employee from the work site if it is determined that individuals are being assigned to duty who have been disqualified for either suitability or security reasons or who are found to be unfit for performing duties during their tour of duty.

d. Contractor employees who are removed from Contract work shall be required to leave the work site immediately.

e. The Contractor shall comply with any removal request. For clarification, a determination to remove an employee will be made for, but is not limited to, incidents involving the most immediately identifiable types of misconduct or delinquency as set forth below:

1. Failure to receive a suitability determination, temporary clearance, or clearance from GSA or a tenant Agency.
2. Violation of Federal, State, or Local law.
3. Violation of the Rules and Regulations Governing Public Buildings and Grounds, 41 CFR 101-20.3. This includes the carrying or possession of explosives or items intended to be used to fabricate an explosive or incendiary device.
4. Neglect of duty, including sleeping while on duty, unreasonable delays, or failure to carry out assigned tasks, conducting personal affairs during official time or refusing to render assistance, or to cooperate in upholding the integrity of the security program at the work site.
5. Falsification or unlawful concealment, removal, mutilation, or destruction of any official documents or records, or concealment of material facts by willful omissions from official documents or records.
6. Disorderly conduct, use of abusive or offensive language, quarreling, intimidation by words or actions, fighting, or participation in disruptive activities that interfere with the normal efficient operations of the Government.
7. Theft, vandalism, immoral conduct, or any other criminal actions.
8. Selling, consuming, or being under the influence of intoxicants, drugs, or substances that produce similar effects while in or on federally controlled property.
9. Improper use of Government identification.
10. Unauthorized use of communication equipment on Government property.
11. Violation of security procedures or regulations.

12. Violation of Title 18,U.S.C.,Section 930, which prohibits the knowing possession or the causing to be present of firearms or other dangerous weapons in Federal facilities and Court facilities.

f. The CO will make all determinations regarding the removal of any employee from work site, except under certain conditions. When a CO , either during the day or after hours, or in situations where a delay would not be in the best interest of the Government or is identified as a potential threat to the health, safety, security, general well being, or operational mission of the facility and its population, the CO will have the authority to immediately remove the Contract employee from the work site.

g. Law enforcement officers of the Department of Homeland Security/Immigration and Customs Enforcement/Federal Protective Service (DHS/ICE/FPS) will have the authority to immediately remove any Contract employee from the work site who is found to be in violation of any of the items mentioned above and where a delay in removal would not be in the best interest of the Government or security or is identified as a potential threat to the health, safety, security, general well being, or operational mission of the facility and its population. The CO will be notified by Law Enforcement Officers as soon after the incident as practical or at the beginning of the next business day if an action happened after hours. The CO will make all official notifications to the Contractor. In the event of a dispute, the CO will make a final determination. Specific reasons for removal of an employee will be provided to the Contractor in writing by the CO .

h. The Contractor is responsible for providing replacement employees in cases where Contract employees are removed from working at the work site or on the Contract.

H.6. Sensitive But Unclassified (SBU) Building Information

This clause applies to all recipients of SBU building information, including offerors, bidders, awardees, contractors, subcontractors, lessors, suppliers and manufacturers.
1. Marking SBU. Contractor-generated documents that contain building information must be reviewed by GSA to identify any SBU content, before the original or any copies are disseminated to any other parties. If SBU content is identified, the Contracting Officer (CO) may direct the contractor, as specified elsewhere in this contract, to imprint or affix SBU document markings to the original documents and all copies, before any dissemination.
2. Authorized recipients.
a. Building information designated SBU must be protected with access strictly controlled and limited to those individuals having a legitimate business need to know such information. Those with a need to know may include Federal, State and local government entities, and nongovernment entities engaged in the conduct of business on behalf of or with GSA. Nongovernment entities may include architects, engineers, consultants, contractors, subcontractors, suppliers, utilities, and others submitting an offer or bid to GSA, or performing work under a GSA contract or subcontract. Recipient contractors must be registered as “active” in the System for Award Management (SAM) database at www.sam.gov and have a legitimate business need to know such information. If a subcontractor is not registered in the SAM and has a need to possess SBU building information, the subcontractor shall provide to the contractor its DUNS number or its tax

ID number and a copy of its business license. The contractor shall keep this information related to the subcontractor for the duration of the contract and subcontract.

b. All GSA personnel and Contractors must be provided SBU building information when needed for the performance of official Federal, State, and local government functions, such as for code compliance reviews and for the issuance of building permits. Public safety entities such as fire and utility departments may require access to SBU building information on a need to know basis. This clause must not prevent or encumber the dissemination of SBU building information to public safety entities.

3. Dissemination of SBU building information:

a. By electronic transmission. Electronic transmission of SBU information outside of the GSA network must use session encryption (or alternatively, file encryption). Encryption must be via an approved NIST algorithm with a valid certification, such as Advanced Encryption Standard (AES) or Triple Data Encryption Standard (3DES), in accordance with Federal Information Processing Standards Publication (FIPS PUB) 140-2, Security Requirements for Cryptographic Modules per GSA policy.

b. By nonelectronic form or on portable electronic data storage devices. Portable electronic data storage devices include, but are not limited to CDs, DVDs, and USB drives. Nonelectronic forms of SBU building information include paper documents, among other formats.

i. By mail. Contractors must utilize only methods of shipping that provide services for monitoring receipt such as track and confirm, proof of delivery, signature confirmation, or return receipt.

ii. In person. Contractors must provide SBU building information only to authorized recipients with a need to know such information. Further information on authorized recipients is found in Section 2 of this clause.

4. Record keeping. Contractors must maintain a list of all entities to which SBU is disseminated, in accordance with sections 2 and 3 of this clause. This list must include at a minimum: (1) the name of the State, Federal, or local government entity, utility, or firm to which SBU has been disseminated; (2) the name of the individual at the entity or firm who is responsible for protecting the SBU building information, with access strictly controlled and limited to those individuals having a legitimate business need to know such information; (3) contact information for the named individual; and (4) a description of the SBU building information provided. Once “as built” drawings are submitted, the contractor must collect all lists maintained in accordance with this clause, including those maintained by any subcontractors and/or suppliers, and submit them to the CO. For Federal buildings, final payment may be withheld until the lists are received.

5. Safeguarding SBU documents. SBU building information (both electronic and paper formats) must be protected, with access strictly controlled and limited to those individuals having a legitimate business need to know such information. GSA contractors and subcontractors must not take SBU building information outside of GSA or their own facilities or network, except as necessary for the performance of that contract. Access to the information must be limited to those with a legitimate business need to know.

6. Destroying SBU building information. When no longer needed, SBU building information must be destroyed so that marked information is rendered unreadable and incapable of being restored, in accordance with guidelines provided for media sanitization within GSA CIO IT Security 06-32, Media Sanitization Guide and Appendix A of NIST Special Publication 800-88, Guidelines for Media Sanitization. Alternatively, SBU building information may be returned to the CO.

7. Notice of disposal. The contractor must notify the CO that all SBU building information has been returned or destroyed by the contractor and its subcontractors or suppliers in accordance with paragraphs 4 and 6 of this clause, with the exception of the contractor's record copy. This notice must be submitted to the CO at the completion of the contract to receive final payment. For leases, this notice must be submitted to the CO at the completion of the lease term. The contractor may return the SBU documents to the CO rather than destroying them.
8. Incidents. All improper disclosures of SBU building information must be immediately reported to the CO at tiffanie.oglesby@gsa.gov . If the contract provides for progress payments, the CO may withhold approval of progress payments until the contractor provides a corrective action plan explaining how the contractor will prevent future improper disclosures of SBU building information. Progress payments may also be withheld for failure to comply with any provision in this clause until the contractor provides a corrective action plan explaining how the contractor will rectify any noncompliance and comply with the clause in the future.
9. Subcontracts. The contractor and subcontractors must insert the substance of this clause in all subcontracts.

H.7. Recording Presence

Each Contract employee shall sign in when reporting for duty and sign out when leaving at the end of the workday and follow card access requirements as directed by the CO . The Contractor shall accumulate GSA Form 139 (Record of Time of Arrival and Departure from Building) or other designated form for use in recording presence each calendar week, certify in writing on each form that the information shown is true and correct and, and within 30 calendar days of week's end, turn them over to the CO .

H.8. Government Forms

The various Government forms mentioned in this document such as personal history forms, sign-out forms, inspection forms, etc., may be obtained from the CO .

H.9. Other Contractors

The Government may undertake or award other Contracts for additional work, and the Contractor shall fully cooperate with such other Contractors. The Contractor shall carefully schedule his own work, in conjunction with the additional work, as may be directed by the CO . In addition, the Contractor shall not commit or permit any act that will interfere with the performance of work by another Contractor or by Government employees.

H.10. Ordinances, Taxes, Permits, and Licenses

Without additional expense to the Government, the Contractor shall fully comply with all local, city, State, and Federal laws, regulations, and ordinances. The Contractor will also be liable for all applicable Federal, State, and local taxes and shall obtain and pay for all permits and licenses governing performance under the contract.

H.11. Discrepancy In The Specifications

In any case of discrepancy in the specifications, the matter shall be immediately submitted to the CO. The decision of the CO as to the proper interpretation of the specifications shall be final in accordance with the Disputes clause of this contract.

H.12. Affirmative Procurement Program (APP)

H.12.1 Standards

As a Federal procuring agency, the GSA is required by the Resource Conservation and Recovery Act (RCRA), Section 6002 and Executive Order (EO) 13423 Strengthening Federal Environmental, Energy, and Transportation Management to procure and use products containing post-consumer content (recycled material); environmentally preferable; and bio-based products. RCRA Section 6002 and Letter 92-4 requires Federal agencies to develop and implement their own Affirmative Procurement Program to facilitate the procurement of these products.

The Contractor shall use safe and environmentally friendly products as referenced throughout this specification. Green products and processes include, but are not limited to bio-based products, products containing recycled content, environmentally preferable products and services, and otherwise environmentally friendly products and services that minimize the use of energy, water, and other resources. Chemical concentrates that require dilutions are preferable compared to ready-to-use products and should be used whenever possible. Dilution control equipment should be employed to ensure correct dilutions of concentrates and to protect workers from exposure to concentrated chemicals. Products designated under federal sustainable product programs – USDA BioPreferred, EPA CPG, EPA Design for the Environment, and Department of Energy's EnergyStar and FEMP - can be found on www.sftool.gov. Sustainable products designated under third-party programs include but are not limited to EcoLogo, Green Seal™, and Environmental Choice. For those categories of product not recognized by one of the aforementioned standard's, preference shall be given to products meeting the California Code of Regulations maximum allowable Volatile Organic Compounds (VOC) levels for the appropriate cleaning product category(California Air Resource Board/California Code of Regulations (CCR), Tile 17 CCR Section 94509 – (Topic cited; Standards for consumer products at www.calregs.com).

Products including, but not limited to, cleaners, adhesives, sealants, solvents, and replacement fixtures and equipment - if applicable, must meet the sustainability standards for products listed in the Green Products Compilation (sftool.gov) see Exhibit 4. With the exceptions listed below. The Green Products Compilation lists all of the products that Federal agencies are required by statute to purchase green:

a. Green Seal standard GS-34 shall apply to degreasers
b. Green Products Compilation (sftool.gov) shall apply to industrial and institutional cleaning products [this covers concentrate issue]. The California Code of Regulations maximum allowable VOC levels for the appropriate product category (California Air Resource Board/California Code of Regulations (CCR), Tile 17 CCR Section 94509 – (Topic cited; Standards for consumer products at www.calregs.com).

In addition to the regulatory requirements specified in Section C of the specification, the contractor shall comply with the appropriate clauses and subparts of FAR 7,11,12,13, and 23. Cleaning

chemicals, tools, equipment, supplies, or materials shall be selected with consideration to minimizing the impact on both human health and safety as well as reducing other potential environmental impacts. Cleaning processes, work practices, and procedures used shall minimize exposures to workers and building occupants and contribute to the promotion of environmental stewardship.

H.12.2 Reporting

The Contractor shall provide an interim annual report, estimating the percentage of total recovered material used in contract performance, including, if applicable, the percentage of post-consumer material content. The Contractor shall provide the report to the CO in compliance with the Contractor schedule.

In addition, the Contractor shall track their green purchasing elements and report purchases specified in the environmental reporting section and Exhibit 2 of this specification.

H.12.3 Recycle Content Certification

In accordance with the FAR 52.223-9, Certification and Estimate of Percentage of Recovered Material Content for EPA-Designated Items purchased for the performance of work with this Contract, the Contractor shall provide to the CO the required certification and estimate at Contract completion.

H.12.4 Green Cleaning Training

The Contractor shall provide training to their employees that stress proper *stewardship* in green cleaning practices. The Contractor shall submit written certification to the CO within five (5) days of the completion of training. Information on stewardship, training, and other issues can be found in ASTM E1971-05, Standard Guide for Stewardship for the Cleaning of Commercial and Institutional Buildings www.astm.org/. The focus of this training is to address appropriate cleaning activities and processes to maximize eco-efficiency and to minimize adverse impacts on the building occupants, cleaning personnel, the building structure itself, and the environment. Adherence to the principles set forth in this guide can lead to greater tenant and occupant satisfaction, reduced operational costs, and greater productivity (for occupants and cleaning personnel).

H.13. Asbestos Awareness Training

The Contractor shall ensure that all employees, including replacement workers, receive asbestos training and refresher training in accordance with CFR 40-763 and 29 CFR 1910. The Contractor shall follow all instructions for each asbestos class job as outlined in 29 CFR 1910. The training shall be conducted, at no additional expense to the Government, at least 60 calendar days after the start date of the Contract. The Contractor shall submit written certification to the CO within 5 days of the completion of training.

H.14. Uniforms

All Contractor employees, including supervisors, shall present a neat appearance and wear appropriate uniforms. All other contract employees shall wear such clothing as coveralls, smocks, uniform shirt and trousers, or uniform blouse and skirt or slacks. Denim jeans and T-shirt, sleeveless shirt, or shirts without collars are not acceptable. Clothing shall have the Contractor's

name affixed in a permanent or semi-permanent manner, such as a badge or monogram, which is easily read. Any color or color combination is acceptable, except green.

H.15. Personnel Qualifications For Mechanical Personnel

H.15.1 Personnel Training

The Contractor shall establish training program to assure employees working in a Federal building have the knowledge, skills and abilities to perform the work required by this Contract. The Contractor shall provide training and/or document training that conforms to the core competencies of the Federal Buildings Personnel Training Act of 2010 and provide documentation to the CO .

H.15.1.1 ***Re-Tuning Training***

The Contractor must ensure that all Mechanical Engineers, Mechanical Supervisors, Operating Engineers, HVAC Mechanics, and Control Technician employees, including replacement workers, receive Building Re-Tuning Training, (http://retuningtraining.labworks.org/training/lms/), a 5-6 hour FREE (NO COST) on line course and refresher training every two years in accordance with the Federal Buildings Personnel Training Act of 2010. The training must be conducted, at no additional expense to the Government, at least 60 calendar days after the start date of the Contract. The Contractor must submit written certification to the CO within 5 days of the completion of training for each employee identified above.

H.15.2 Qualifications of Project Manager and Onsite Supervisory Personnel

Note Project Manager and Onsite Supervisor can be the same person.

H.15.2.1 ***Qualifications of Project Manager***

The Project Manager shall possess at a minimum at least 5 years of recent (within the past 7 years) experience in the management and supervision of building mechanical maintenance operations for buildings of the approximate size and characteristics of the buildings to be covered by this Contract. A detailed resume containing the information specified in this document shall be submitted to the CO for approval prior to the assignment of the project manager to the Contract. Both new and replacement project manager's shall meet these qualification standards. Minimally, the resume shall contain:

a. The full name of the proposed project manager.
b. A detailed description of the previous 7 years' employment history of the proposed project manager.
c. The names and addresses of the companies for whom the proposed project manager worked for the past 7 years, along with the names and telephone numbers of the immediate supervisors.

H.15.2.2 ***Qualifications of Onsite Supervisor***

The Onsite Supervisor shall also possess at least 5 years of recent (within the past 7 years) experience in directing operation and maintenance of equipment in a supervisory capacity for equipment of the approximate size, complexity, and other characteristics of the equipment to be operated and maintained under this Contract. A detailed resume containing the information specified in this document shall be submitted to the CO for approval prior to the assignment of

any supervisor to the Contract. Both new and replacement onsite supervisors shall meet these qualification standards. Minimally the resume shall contain:

a. The full name of the proposed supervisor.
b. A detailed description of the previous 7 years' employment history of the proposed supervisor.
c. The names and addresses of the companies for whom the proposed supervisor worked for the past 7 years, along with the names and telephone numbers of the immediate supervisors.

H.15.3 Qualifications of Technicians

General Requirements

Technicians engaged in the work to be accomplished under this contract, except for general maintenance workers and laborers, must possess at least 5 years of recent (within the past 7 years) experience in the operation and maintenance of equipment and systems comparable in complexity to systems covered by this contract. All personnel or sub-contractor personnel must possess all required registrations, certifications and licenses required by State and local jurisdictions, and any specific requirements noted below. The Contractor shall provide to the CO documentation of the certificates of training, licenses, and permits for all new employees not later than 7 days prior to that person beginning work under the terms of this contract. The Contractor shall ensure that all certificates of training, licenses, permits, and bonds are current and valid. All offers must include documentation and proof of any required certifications (e.g., including certification number and expiration date) and qualifications for each employee.

H.15.3.1 ***Qualifications of Fire Alarm System Technicians***

a. Technicians performing contract work involving the inspection, testing, and preventive maintenance or repair of fire alarm systems shall be certified by the National Institute for Certification in Engineering Technologies (NICET) and possess at least a NICET Level 2 (Associate Engineering Technician) in Fire Protection Engineering Technology, Fire Alarm Systems. The Contractor shall submit to the CO the NICET level certification number and expiration date for each field technician and inspector responsible for performing fire alarm system preventative maintenance and repair services required under the terms of this contract.
b. Technicians modifying the programming software of the fire alarm system shall also be factory trained and certified by the system manufacturer for the specific type and brand of fire alarm system being serviced. The Contractor shall submit to the CO the factory trained certification number and expiration date for each specific manufacturer's equipment for each technician responsible for performing programming of the fire alarm system.

H.15.3.2 ***Qualifications of Sprinkler System Technicians***

Technicians performing contract work involving the inspection, testing, and preventive maintenance or repair of water-based fire suppression systems shall be certified by the National Institute for Certification in Engineering Technologies (NICET) and possess at least a NICET Level 2 (Associate Engineering Technician) in Fire Protection Engineering Technology, Inspection, and Testing of Water-Based Systems. The Contractor shall submit to the CO the NICET level certification number and expiration date for each field technician and inspector

responsible for performing water-based fire suppression system preventative maintenance and repair services required under the terms of this contract.

H.15.3.3 ***Qualifications of Water-Based Fire Suppression System Technicians***

Technicians performing contract work involving the inspection, testing, and preventive maintenance or repair of water-based fire suppression systems shall be certified by the National Institute for Certification in Engineering Technologies (NICET) and possess at least a NICET Level 2 (Associate Engineering Technician) in Fire Protection Engineering Technology, Inspection, and Testing of Water-Based Systems. The Contractor shall submit to the CO the NICET level certification number and expiration date for each field technician and inspector responsible for performing water-based fire suppression system preventative maintenance and repair services required under the terms of this contract.

H.15.3.4 ***Qualifications of Dry Chemical and Wet Chemical Extinguishing System Technicians***

Technicians performing contract work involving the inspection, testing, and preventive maintenance of dry chemical and wet chemical extinguishing systems shall be trained in the manufacturer requirements and have passed a test confirming the individual's knowledge and competence on these systems. The Contractor shall submit to the CO the certification document and expiration date, issued by the manufacture or testing organization confirming the technician has been trained and passed a test, for each field technician and inspector responsible for performing dry chemical and wet chemical extinguishing system preventative maintenance and repair services required under the terms of this contract.

H.15.3.5 ***Qualifications of Clean Agent Fire Extinguisher System Technicians***

Technicians performing contract work involving the inspection, testing, and maintenance of clean agent fire extinguisher systems shall be trained in all aspects of safety related to the systems and possess a current training certificate for inspecting, testing, and maintaining these components from a manufacturer or a certificate by an organization acceptable to the CO. The Contractor shall submit to the CO the certification document and expiration date, issued by the manufacture or testing organization confirming the technician has been trained, for each field technician and inspector responsible for performing the inspection, testing, and maintenance of clean agent fire extinguisher systems required under the terms of this contract.

H.15.3.6 ***Qualifications of Halogenated Extinguishing System Technicians***

Technicians performing contract work involving the inspection, testing, maintenance, decommissioning and removal of halogenated extinguishing systems shall be trained in all aspects of safety related to halon systems and possess a current training certificate for inspecting, testing, and maintaining these components from a manufacturer or a certificate by an organization acceptable to the CO. The Contractor shall submit to the CO the certification document and expiration date, issued by the manufacture or testing organization confirming the technician has been trained, for each field technician and inspector responsible for performing the inspection, testing, maintenance, decommissioning and removal of halogenated extinguishing systems required under the terms of this contract.

H.15.3.7***Qualifications of Carbon Dioxide Extinguishing System Technicians***

Technicians performing contract work involving the inspection, testing, maintenance of carbon dioxide extinguishing systems shall be trained all aspects of safety related to carbon dioxide extinguishing systems, the operation and functions performed, and possess a current training certificate for inspecting, testing, and maintaining these components from an equipment manufacturer, installation company, or a certificate by an organization acceptable to the CO. The Contractor shall submit to the CO the certification document and expiration date, issued by the equipment manufacture or testing organization confirming the technician has been trained, for each field technician and inspector responsible for performing the inspection, testing, and maintenance of carbon dioxide extinguishing systems required under the terms of this contract.

H.15.3.8***Qualifications of Ventilation System Fire Extinguishing System Technicians***

Technicians performing contract work involving the inspection, testing, maintenance of fire extinguishing systems shall be trained and possess a current training certificate for inspecting, testing, and maintaining ventilation systems from an equipment manufacturer. The Contractor shall submit to the CO the certification document and expiration date, issued by the equipment manufacture confirming the technician has been trained, for each field technician and inspector responsible for performing the inspection, testing, and maintenance of fire extinguishing systems required under the terms of this contract.

H.15.3.9***Qualifications of Smoke Control Technicians***

Technicians performing contract work involving the inspection, testing, and maintenance of smoke control systems shall be trained and possess a current training certificate for inspecting, testing, and maintaining these components from a manufacturer or a certificate by an organization acceptable to the CO. The Contractor shall submit to the CO the certification document and expiration date, issued by the manufacture or testing organization confirming the technician has been trained, for each field technician and inspector responsible for performing the inspection, testing, and maintenance of smoke control systems required under the terms of this contract.

H.15.3.10***Qualification of Fire Damper, Smoke Damper, and Combination Fire/Smoke Damper Technicians***

Technicians performing contract work involving the inspection, testing, and maintenance of fire dampers, smoke dampers, radiation dampers, and combination fire/smoke dampers shall be trained and possess a current training certificate for inspecting, testing, and maintaining these components from an equipment manufacturer or a certificate by an organization acceptable to the CO. The Contractor shall submit to the CO the certification document and expiration date, issued by the equipment manufacture or testing organization confirming the technician has been trained, for each field technician and inspector responsible for performing the inspection, testing, and maintenance of fire dampers, smoke dampers, radiation dampers, and combination fire/smoke dampers required under the terms of this contract.

H.15.3.11***Qualifications of Fire-rated and Smoke Door Assemblies Technicians***

Technicians performing contract work involving the inspection, testing, and maintenance of fire-rated door assemblies and smoke door assemblies shall be trained and possess a current

training certificate for inspecting, testing, and maintaining these components from an equipment manufacturer or a certificate by an organization acceptable to the CO. The Contractor shall submit to the CO he certification document and expiration date, issued by the equipment manufacture or testing organization confirming the technician has been trained, for each field technician and inspector responsible for performing the inspection, testing, and maintenance of fire-rated door assemblies and smoke door assemblies required under the terms of this contract.

H.15.3.12***Qualifications of Portable Fire Extinguisher Technicians***

Technicians performing contract work involving the preventive maintenance and recharging of portable fire extinguishers shall be trained and possess a current training certificate for the specific type and brand of portable fire extinguisher being services or possess a current training test certificate by an organization acceptable to the CO. The Contractor shall submit to the CO the certification document and expiration date, issued by the manufacture or testing organization confirming the technician has been trained and passed a test, for each field technician and inspector responsible for performing dry chemical and wet chemical extinguishing system preventative maintenance and repair services required under the terms of this contract. Please note that these requirements do not apply to persons performing 30-day (i.e., monthly) inspections to determine if the unit is in place, charged, and ready for use.

H.15.3.13***Qualification of Emergency and Standby Power System Technicians***

Reserved

H.15.3.14***Qualifications of Emergency Lighting Equipment and Exit Signage Technicians***

Technicians performing contract work involving the inspection, testing, and maintenance of emergency lighting equipment and exit signage shall be trained and possess a current training certificate for inspecting, testing, and maintaining these components from an equipment manufacturer or a certificate by an organization acceptable to the CO. The Contractor shall submit to the CO the certification document and expiration date, issued by the equipment manufacture or testing organization confirming the technician has been trained, for each field technician and inspector responsible for performing the inspection, testing, and maintenance of emergency lighting equipment and exit signage required under the terms of this contract.

H.15.3.15***Qualifications of HVAC Technicians***

All personnel designated to work on, operate, maintain, and repair HVAC equipment (including boilers and heating systems) must possess one or more of the following certifications, and ~~maintain a minimum of sixteen (16) hours continuing education on HVAC and related equipment annually to maintain and improve upon competencies.~~ The Contractor is responsible for all costs associated with obtaining this training. All training must be tracked and reported to the COR annually.

1) **North American Technician Excellence (N.A.T.E.) Core Service plus Air Distribution Services Specialist or any service Knowledge Areas of Technician Expertise (K.A.T.E.) Specialty listed under the service category.**

2) **HVAC Excellence Professional - the following three certifications: Light Commercial Air Conditioning, Gas Heat, and Green Awareness Certification**

3) **UA Star HVACR Mastery Certification**

NOTE: (Incumbent and new hired Employees) All Incumbent personnel previously designated HVAC and new hire employees who operate, work on, maintain and repair HVAC equipment (including boilers and heating systems) will be required to become certified. The contractor shall develop a training plan for each employee and submit to the COR within the first 30 days and must be certified or completed within the first 6-months of the contract start date or employment date. Progress to complete this requirement shall be reported to the COR in the monthly progress reports.

Progress to maintain certification and report of continuing education received shall be reported to the COR annually.

H.15.3.16***Qualifications of AMS, BAS Technicians***

All personnel involved in the operation, adjustment and maintenance of all AMS, BAS, and EMS systems must be trained and qualified. The Contractor must provide to the CO documentation of the level of experience, including any certificates of training, for all employees who will be involved in this function. Technicians modifying AMS, BAS, and EMS systems must be factory trained and currently certified for the operating system, including software version, of the particular BAS and AMS systems and must provide documentation of this certification to the CO .

H.15.3.16.1***Qualifications of AMS, BAS, Smart Buildings Technicians***

All Contract personnel involved in the operation, adjustment, and maintenance of all BAS systems including energy management systems, modern converged technologies (Smart and Sustainable Building Technologies) must be trained and qualified. The Contractor shall provide to the CO documentation of the level of experience, including any certificates of training, for all employees who will be involved in this function. This includes, but is not limited to, skill sets involving Internet Protocol (IP) based Building Automation Systems (BAS), Information Technology (IT) Ethernet networks, and Building Management expertise to effectively understand and recommend troubleshooting procedures in the new converged technologies environment.

Contractors shall hire well-rounded resources capable of understanding converged technologies to better facilitate troubleshooting and building systems problem resolution.

The Contractor shall be proficient in applicable controls systems (e.g. JCI, Honeywell, Siemens, Delta, Automated Logic, Alerton, and Tridium). The Contractor shall be aware of building systems running on GSA IP Enterprise Network and capable of initiating trouble shooting if network communications is suspect. This means being familiar with procedure for logging GSA IT Help Desk ticket and following up to ensure ticket is being worked by assigned party. Some familiarization with the use of Integrated Control systems, GSA IP Addresses, function of network routers, function of network switches, networks communications, and BAS software will be necessary.

H.15.3.16.2***Smart and Sustainable Building (SSB) Training***

Mandatory Training (at least one staff member):

- One-hour "GSA Smart and Sustainable Buildings (SSB) Overview"
- Module 1 - Includes GSA FMSP Smart and Sustainable Buildings Overview
- Module 2 - Includes PBS CIO Support Procedures

Optional Training (Recommended for more in depth proficiency):

- Penn State GSA Smart Buildings Course (http://smartenergyacademy.org/gridstar/)

H.15.3.17 Qualifications of Electrical Technicians

Technicians performing Contract work involving the inspection, testing, and maintenance of the electrical switch gear must meet the qualification requirements of the American National Standards Institute/International Electrical Testing Association ETT-2000, Standard for Certification of Electrical Testing Technicians and hold at least a Level 3 or 4 (See Exhibit 13). The Contractor shall provide documentation to the CO on qualifications identified in this standard. Certification can be obtained through; the ANSI/NETA Certification program (http://www.netaworld.org/press-release/251) or Electrical Testing Technician Certification Institute (http://www.ettci.org/).

H.15.4 Submission of Resumes for New Employees

The Contractor shall submit to the CO the resumes of all personnel before they begin work during the performance periods of the Contract. The CO may deny permission to employ personnel if qualifications indicate a material degradation from the skill levels indicated in the Contractor's proposal for the Contract, or if skills or reliability concerns are such that the CO believes the protection of building equipment may be jeopardized.

H.15.5 State Licensing

All personnel shall be licensed and certified, or become licensed and certified within 90 calendar days of beginning employment, to perform work within their normal duties, where such licensing is required by the State for non-Federal locations. Contractor personnel shall also conform to all other licensing and certification requirements as described elsewhere in this document or in the Public Buildings Service Operations and Maintenance Standards.

H.15.6 Compliance with Federal, State, and Local Codes

The Contractor shall comply with all applicable Federal, State and Local laws, regulations and codes. The Contractor is responsible for determining which requirements are applicable, and complying appropriately; the Contractor may ask advice of the CO in this regard. GSA also has a policy of voluntary conformity to certain State and Local code requirements even when permission or approvals from Local regulators are not required; the Contractor shall ask the advice of the CO when such issues arise.

H.16. Personnel Qualifications For Custodial Personnel

H.16.1 Training

The Contractor shall provide employees with training to broaden their technical skills, improve customer service, and to promote personal development. Training provided shall embrace the concepts of providing and maintaining quality cleaning that is safe, healthy, and sustainable.

www.issa.com as well as other cleaning groups offers their members educational materials on these items.

H.16.1.1 Blood Borne Pathogens

The Contractor shall provide appropriate training to their employees and all necessary equipment and services required to perform clean-up of blood borne pathogens and fully comply with the requirements of the Blood Borne Pathogen Standard listed in 29 CFR §1910.1030.

H.16.2 Qualifications of Supervisory Employees

Supervisory contract employees shall have a minimum of 3 years of experience with managing and related services in building(s) of similar size and complexity. The Contractor shall provide employee resumes covering these positions to the CO for approval. At the discretion of the CO formal training may be substituted for experience. The on-site supervisor is required to be fully conversant in English.

H.16.3 Qualifications of Contractor Personnel

The Contractor shall provide appropriate training to their employees. The personnel employed by the Contractor shall be capable employees, who are trained and qualified in one or more related type service requirements.

The building(s) shall be fully staffed, beginning the first day of work under the contract, unless authorized by the CO . The Contractor's employees shall be familiar with the operation of the building(s) fire alarm system. In the event of a fire, the Contractor shall leave the building and not enter until authorized by Fire officials. The Contractor's staff shall also be familiar with the building's Occupancy Emergency Plan, which includes the shelter in place program. Further information on the program shall be provided by the CO .

H.17. FURNISHED MATERIALS

H.17.1 Government-Furnished Materials

The following items are furnished by the Government:

a. Electrical power at existing outlets for the Contractor to operate equipment that is necessary in the conduct of its work.
b. Hot and cold water as necessary, limited to the normal supply provided in the building. No special heating or cooling of the water will be provided.
c. Space in the building, including locker rooms, if available. Any existing equipment within GSA space, such as lockers, tables, benches, chairs, etc., placed within the building by the Government may be used by the Contractor during the term of the Contract, provided authorization is received from the CO . This space and equipment shall be kept neat and clean and returned to the Government at the expiration of the Contract in reasonably the same condition as at the time of entering into the Contract.
d. Space in the building for the storage of an inventory of supplies and equipment that will be used in the performance of work under the Contract. The Contractor shall maintain this space in a clean, neat, and orderly condition. Under no circumstances may the Contractor store flammable or explosive liquids (naphtha, gasoline, etc.) in the building. The Government will not be responsible in any way for damage or loss to the Contractor's stored supplies, materials, replacement parts, or equipment.

e. Custodial closets, where available, at various points throughout the building, for storing equipment, including mops, brooms, dust cloths, and other items. These closets and the stored equipment shall be kept clean and organized by the Contractor. Sinks and buckets shall be kept clean and free of standing water and hoses shall not be left connected to faucets when not in use.
f. Space in the building, when available, and furniture and furnishings (to include telephones for restricted use) for a supervisor's office to be used for official business only in the performance of this Contract. If the Government supplies telephones, they shall only be used for communication related to the Contract. The Contractor or the Contractor's employees shall not use Government property in any manner for any personal advantage, business gain, or other personal endeavor.
g. Heating and air conditioning of the space to be cleaned will be provided only during normal building operating hours.
h. The following is a list of GSA furnished equipment: Portable power lift at the Caude Pepper and the King buildings.

H.17.1.1 Use of Government Information Technology

Contractor personnel requiring access to GSA's Network shall comply with all Federal Information Technology (IT) regulations regarding Trusted Internet Connection (TIC) in conjunction with PBS and GSA Chief Information Officer (CIO) IT policies, i.e., all PBS IT systems needing network connectivity must reside on the GSA network.

Contractors that requirement Network Connection for PBS IT systems shall use only Government-furnished network equipment and computer hardware.

-Network equipment includes all equipment that has IP routing and switching functionality.

-Computer hardware includes, but is not limited to servers, PCs, laptops and their peripherals (monitors, mice and keyboards).

-Proprietary system hardware/software can be vendor provided, but is subject to network and system testing, review and approval for connection to GSA's network and acceptance of the PBS CIO.

If the Contractor requires access to GSA's Network they shall submit their request in writing to the CO for approval. Approved requests shall be forwarded to the PBS CIO for approval. The PBS CIO shall provide the Contractor with at least one desktop and/or one laptop to access the newly integrated Building Automation Systems (to the GSA network) sites for the purposes of giving the Contractor access to the building monitoring and control systems. Please note that the availability of computer hardware is dependent on budgeted funds dedicated for this purpose, which may or may not be renewed on an annual basis. Refreshes required for existing GSA workstation shall be coordinated through regional local OCIO's office. No hardware (workstations, servers, switches) shall be provided unless an approved network diagram is submitted.

Contractor's that require access to building monitoring and control systems (BMC) shall refer to the Technology Policy for PBS-Owned Buildings Monitoring and Control Systems and Building Technologies Technical Reference Guide for guidance related to the technical integration of BMC to the GSA network and within its GSA's information technology (IT) environment.

If a Contractor comes into contact with information or data where there is not a 'need to know' or they are do not have authorization to have, they shall turn in the information and/or data immediately to the CO .

Government Furnished Equipment -PBS CIO will make every effort to provide one desktop and/or one laptop to newly integrated Building Automation Systems (to the GSA network) sites for the purposes of giving new GSA users access to the building monitoring and control systems. Please note: availability of hardware is depending on the availability of budgeted funds dedicated for this purpose, which may or may not be renewed on an annual basis. Existing GSA workstation refreshes will still be coordinated through regional local OCIO's office. No hardware (workstations, servers, switches) will be provided unless an approved network diagram is submitted.

Reference documentation related to building monitoring and control systems (BMC) -Please reference the Technology Policy for PBS-Owned Buildings Monitoring and Control Systems and Building Technologies Technical Reference Guide for guidance related to the technical integration of building monitoring and control systems (BMC) to the GSA network and within its GSA's information technology (IT) environment.

H.17.2 Contractor-Furnished Materials

a. The Contractor shall provide all labor, services, supplies, material, and equipment necessary to efficiently and effectively perform the requirements of this Contract, except as explicitly stated within this document.

b. The Contractor shall provide at his or her expense an onsite computer with broadband Internet service and electronic Mail shall be established and monitored on a 24 hour basis in order to receive or communicate with the CO or his/her designee customer agency and tenant needs. In addition this computer shall be capable of operating with the format of N-CMMS and accessing Citrix for remote access to the BAS/EMS systems.

c. Text messaging device. The Contractor is responsible for all costs associated with the text messaging device. Examples are two-way pager, cell phone with text messaging, Smart phones, etc. **Devices shall be capable of receiving and sending e-mail documents with attachments.**

d. Fax. Receiving and sending faxes is acceptable as a secondary communication method for locations that have problems with wireless device signal strength. However, delaying faxes because of combined usage of voice and fax on the same line is not acceptable.

e. 4. Computerized Maintenance Management System (CMMS)

H.18. Additional Services [Indefinite Quantity Provisions]

H.18.1 General

The CO may order additional services at his or her discretion. Additional services may include any services related to O&M and repairs, systems upgrades, system operation, or tenant services within covered facilities but not covered within basic services (i.e., not already a requirement of the Contract).

H.18.2 Price Proposal for Additional Services Work

At the request of the CO , the Contractor shall provide a price proposal to accomplish an additional services job within 48 hours of the request. The price proposal shall follow the pricing guidelines described in this document. Price proposals for additional services become firm fixed price on acceptance and order by the Government. Although price negotiation and determination of price reasonableness is made on the basis of labor, materials, and subcontract costs following the pricing guidelines described in this document, the price accepted is not adjusted after completion of work to actual man-hours or actual materials cost.

H.18.3 Pricing

The Contractor's price proposal for an Additional Services job shall follow the guidelines described below.

H.18.4 Parts and Materials

If parts or materials are required for a project, the Government may provide the parts or materials, or the Contractor may be asked to provide the parts and materials. Parts and materials shall be priced at estimated actual cost marked up by the standard coefficient in the price schedule if stated. The CO may accept a different markup rate for parts and materials if the Contractor can demonstrate unusual costs or difficulties in obtaining the parts or materials.

H.18.5. Labor

Price proposals shall use the labor rates established in the price schedule, unless work is subcontracted. The labor categories in the price schedule correlate with the categories in the Service Contract Act Directory of Occupations. The rate will be determined by the nature of the work, not the usual job classification of the individuals performing the work.

H.18.6 Subcontracts

If work is to be subcontracted, the subcontracted part of the work is to be priced at actual cost to the Contractor, marked up by the standard coefficient in the price schedule.

H.18.6.1 Mark-up Agreement for Architectural/Structure and Maintenance Repair

Mark-Up Agreement for Architectural/Structural, Mechanical Maintenance repair, and Diagnostic Services when the cost of repair is above the threshold as listed in the contract

(1) WORK BY PRIME CONTRACTOR ONLY: Estimated Cost of Repair over $2500.00 the Prime Contractor is entitled to Overhead and Profit only.

(2) WORK BY PRIME AND SUB-CONTRACTORS: Prime Contractor is entitled to Overhead or fee, and Profit on work performed by his/her workforce and Subcontractor is entitled to Overhead and Profit on his/her work only.

(3) ALL WORK BY SUB-CONTRACT: Estimated Cost of Repair over $2,500.00 the Prime Contractor is entitled overhead or fee for overseeing the work and Subcontractor is entitled to overhead and profit.

The above Mark-Ups are agreeable and will be applied to all Architectural/Structural Mechanical Maintenance repair when the cost of repair is above the threshold as listed in the contract. In addition, the listed overhead shall also be used for subcontracted diagnostic services.

This agreement becomes effective upon award of the Contract and shall remain in effect for Base Period and for any exercised Option Period.

H.18.7 Cost Documentation

If the Contractor provides the parts and materials, or if work is subcontracted, the Contractor shall furnish on request copies of invoices, vendor quotes, or receipts, either with the Contractor's proposal or as substantiating documentation with the Contractor's invoice after completion of work.

H.18.8 Competitive Bids

If a single part or component, or a single type (line item) of parts, components, or materials for a project is anticipated to equal or exceed ***$2,500***, the CO may require that the Contractor obtain three bids from suppliers and include documentation of these bids with his proposal. If subcontract work is anticipated to cost more than ***$2,500***, the CO may require that the Contractor obtain three bids from potential subcontractors and include documentation of these bids with his proposal.

H.18.9 Method of Ordering

The CO may order work priced at less than ***$2,500*** orally and follow up with a written task order. The CO shall issue a Task Order (GSA Form 300) for work costing ***$2,500*** or more.

H.19. Award Fee Reserved

"Reserved"

H.20. Strike Contingency Plan (SCP)

The Contractor shall prepare a Strike Contingency Plan (SCP) to be used in the event of a strike by his employees. The SCP shall be submitted to the CO 5 calendar days prior to Contract start date and updated annually. At a minimum, the SCP shall include the following information:

a. Support Personnel: The SCP shall describe in detail how the Contractor shall staff the building to provide the services defined in this document in the event of strikes by his employees. This includes HSPD-12.
b. License and Certifications: The SCP shall describe in detail how the Contractor will provide personnel that meet experience requirements, assuring the Government that all temporary or replacement employees (including subcontractor employees) shall meet the experience and license requirements defined in this document.

H.21. Occupancy Emergency Plan (OEP)

The Government's Occupant Emergency Plan (OEP) is used by the CO during building emergencies. Designated Contractor personnel, including, the onsite supervisors, shall be thoroughly familiar with the Government's OEP and shall be trained by the Contractor to fully understand their responsibilities relative to each emergency plan. The Contractor shall participate in fire and other emergency drills. The Contractor shall be required to perform the services required by the Contract and as identified by the CO o the extent allowed during all emergency situations, including, but not limited to fires, accident and rescue operations, Contractor personnel strikes, civil disturbances, natural disasters, and utility service outages.

H.22. CONTRACTOR PANDEMIC PLAN

The Government is required by the National Strategy for Pandemic Influenza Preparedness and to have a plan that safeguards its employees and provides for continued operations in the event of an influenza pandemic. The Contractor shall also prepare a plan that outlines the steps that they must take to prevent and reduce the spread and mitigate the potential effect of an influenza pandemic on facilities operations. Given the unpredictable length and severity of a pandemic, the Contractor's plan shall link their planned actions to the periods and phases established the World Health Organization for a pandemic cycle. For information on the phases of a pandemic cycle see http://www.who.int/csr/disease/avian_influenza/phase/en/. The plan shall be submitted to the CO or his/her designee within thirty (30) calendar days of the start of the Contract. See components of Pandemic Planning at:
http://www.ed.gov/admins/lead/safety/emergencyplan/pandemic/planning-guide/basic.pdf

H.23. SUBCONTRACTING

The Government reserves the right to approve or disapprove the subcontractors selected. Therefore, the Contractor shall obtain the Contracting Officer's approval of all subcontractors and provide copies of subcontracts for any work required by this contract. The contractor shall execute with his own organization work equivalent to at least 50 percent of the total amount of the contract price.

H.24. CONSERVATION

Conservation is a planned and organized approach designed to conserve non-renewable sources. The Contractor shall ensure that work under this contract is performed in a manner that conserves energy, water, and other Government resources. Contractor shall take the necessary steps through training, communication, and implementing appropriate procedures in their use of natural resource consuming equipment and processes. This will preserve resources and support GSA's sustainability goals.

The Contractor shall ensure that their employees support the Government's efforts to comply with Section 102 of the Energy Policy Act of 2005 (EPAct), the Energy Independence and Security Act of 2007, Executive Order (EO) 13154, and EO 13423 which requires the Government to reduce Agency energy use.

The Contractor shall employ practices that reduce dependency on non-renewable sources of energy. The Contractor's personnel shall turn off lights in unoccupied areas where possible, once the area is cleaned. The Contractor shall close window blinds when practical, especially in the summer time, over long weekends, and during extended closures of the building.

The Contractor shall use their equipment in an efficient manner by turning it off during times it is not in use. When replacing existing equipment, the Contractor shall strive to acquire replacement equipment in the top 25% of efficiency as per the Energy Star guidelines. The Contractor shall never turn off or unplug Government equipment in the space they are cleaning without prior written approval by the CO .

The Contractor shall employ products, equipment and practices that eliminate wasteful use of water.

H.25. LEED-EB

This building shall seek Leadership in Energy and Environmental Design (LEED) certification, which requires more stringent guidelines and record keeping. Criteria for specific LEED existing buildings (EB) credits will be provided by the LEED-EB Project Manager . More information on LEED-EB is found at www.usgbc.org.

I. Contract Clauses

52.202-1 DEFINITIONS (NOV 2013)

52.203-3 GRATUITIES (APR 1984)

52.203-5 COVENANT AGAINST CONTINGENT FEES (MAY 2014)

52.203-6 RESTRICTIONS ON SUBCONTRACTOR SALES TO THE GOVERNMENT (SEP 2006)

52.203-7 ANTI-KICKBACK PROCEDURES (MAY 2014)

52.203-8 CANCELLATION, RESCISSION, AND RECOVERY OF FUNDS FOR ILLEGAL OR IMPROPER ACTIVITY (MAY 2014)

52.203-10 PRICE OR FEE ADJUSTMENT FOR ILLEGAL OR IMPROPER ACTIVITY (MAY 2014)

52.203-12 LIMITATION ON PAYMENTS TO INFLUENCE CERTAIN FEDERAL TRANSACTIONS (OCT 2010)

52.203-13 CONTRACTOR CODE OF BUSINESS ETHICS AND CONDUCT (APR 2010)

52.203-17 CONTRACTOR EMPLOYEE WHISTLEBLOWER RIGHTS AND REQUIREMENT TO INFORM EMPLOYEES OF WHISTLEBLOWER RIGHTS (APR 2014)

52.204-4 PRINTED OR COPIED DOUBLE-SIDED ON POSTCONSUMER FIBER CONTENT PAPER (MAY 2011)

52.204-9 PERSONAL IDENTITY VERIFICATION OF CONTRACTOR PERSONNEL (JAN 2011)

52.204-15 SERVICE CONTRACT REPORTING REQUIREMENTS FOR INDEFINITE-DELIVERY CONTRACTS (JAN 2014)

52.204-10 REPORTING EXECUTIVE COMPENSATION AND FIRST-TIER SUBCONTRACT AWARDS (JULY 2013)

52.209-6 PROTECTING THE GOVERNMENT` INTEREST WHEN SUBCONTRACTING WITH CONTRACTORS DEBARRED, SUSPENDED, OR PROPOSED FOR DEBARMENT (AUG 2013)

52.210-1 MARKET RESEARCH (APR 2011)

52.215-2 AUDIT AND RECORDS--NEGOTIATION (OCT 2010)

52.215-8 ORDER OF PRECEDENCE--UNIFORM CONTRACT FORMAT (OCT 1997)

52.219-8 UTILIZATION OF SMALL BUSINESS CONCERNS (MAY 2014)

52.219-14 LIMITATIONS ON SUBCONTRACTING (NOV 2011)

52.219-28 POST-AWARD SMALL BUSINESS PROGRAM REPRESENTATION (JUL 2013)

52.222-3 CONVICT LABOR (JUN 2003)

52.222-4 CONTRACT WORK HOURS AND SAFETY STANDARDS --OVERTIME COMPENSATION (MAY 2014)

52.222-17 {52.222-17} NONDISPLACEMENT OF QUALIFIED WORKERS (MAY 2014)

52.222-21 PROHIBITION OF SEGREGATED FACILITIES (FEB 1999)

52.222-26 EQUAL OPPORTUNITY (MAR 2007)

52.222-35 EQUAL OPPORTUNITY FOR VETERANS (SEP 2010)

52.222-36 AFFIRMATIVE ACTION FOR WORKERS WITH DISABILITIES (OCT 2010)

52.222-37 EMPLOYMENT REPORTS VETERANS (SEP 2010)

52.222-41 SERVICE CONTRACT LABOR STANDARDS (MAY 2014)

52.222-43 FAIR LABOR STANDARDS ACT AND SERVICE CONTRACT LABOR STANDARDS--PRICE ADJUSTMENT (MULTIPLE YEAR AND OPTION CONTRACTS) (MAY 2014)

52.222-50 COMBATING TRAFFICKING IN PERSONS (MAR 2015)

52.222-54 EMPLOYMENT ELIGIBILITY VERIFICATION (AUG 2012)

52.222-55 MINIMUM WAGES UNDER EXECUTIVE ORDER 13658 (DEC 2014)

52.223-2 AFFIRMATIVE PROCUREMENT OF BIOBASED PRODUCTS UNDER SERVICE AND CONSTRUCTION CONTRACTS (SEP 2013)

52.223-3 I HAZARDOUS MATERIAL IDENTIFICATION AND MATERIAL SAFETY DATA (JAN 1997)—ALTERNATE I (JUL 1995)

52.223-5 POLLUTION PREVENTION AND RIGHT-TO-KNOW INFORMATION (MAY 2011)

52.223-6 DRUG-FREE WORKPLACE (MAY 2001)

52.223-10 WASTE REDUCTION PROGRAM (MAY 2011)

52.223-12 REFRIGERATION EQUIPMENT AND AIR CONDITIONERS (MAY 1995)

52.223-15 ENERGY EFFICIENCY IN ENERGY-CONSUMING PRODUCTS (DEC 2007)

52.223-16 ACQUISITION OF EPEAT-REGISTERED PERSONAL COMPUTER PRODUCTS (JUN 2014)

52.223-18 ENCOURAGING CONTRACTOR POLICIES TO BAN TEXT MESSAGING WHILE DRIVING (AUG 2011)

52.223-19 COMPLIANCE WITH ENVIRONMENTAL MANAGEMENT SYSTEMS (MAY 2011)

52.225-13 RESTRICTIONS ON CERTAIN FOREIGN PURCHASES (JUN 2008)

52.228-5 INSURANCE--WORK ON A GOVERNMENT INSTALLATION (JAN 1997)

52.229-3 FEDERAL, STATE, AND LOCAL TAXES (FEB 2013)

52.232-1 PAYMENTS (APR 1984)

52.232-8 DISCOUNTS FOR PROMPT PAYMENT (FEB 2002)

52.232-11 EXTRAS (APR 1984)

52.232-17 INTEREST (MAY 2014)

52.232-18 AVAILABILITY OF FUNDS (APR 1984)

52.232-23 ASSIGNMENT OF CLAIMS (MAY 2014)

52.232-25 PROMPT PAYMENT (JUL 2013)

52.232-33 PAYMENT BY ELECTRONIC FUNDS TRANSFER--SYSTEM FOR AWARD MANAGEMENT (JUL 2013)

52.232-36 PAYMENT BY THIRD PARTY (MAY 2014)

52.232-39 UNENFORCEABILITY OF UNAUTHORIZED OBLIGATIONS (JUN 2013)

52.233-1 I DISPUTES (MAY 2014)--ALTERNATE I (DEC 1991)

52.233-3 PROTEST AFTER AWARD (AUG 1996)

52.233-4 APPLICABLE LAW FOR BREACH OF CONTRACT CLAIM (OCT 2004)

52.236-13 I ACCIDENT PREVENTION (NOV 1991)--ALTERNATE I (NOV 1991)

52.237-2 PROTECTION OF GOVERNMENT BUILDINGS, EQUIPMENT, AND VEGETATION (APR 1984)

52.242-13 BANKRUPTCY (JUL 1995)

52.243-1 CHANGES--FIXED-PRICE (AUG 1987)

52.244-6 SUBCONTRACTS FOR COMMERCIAL ITEMS (MAR 2015)

52.246-25 LIMITATION OF LIABILITY--SERVICES (FEB 1997)

52.248-1 VALUE ENGINEERING (OCT 2010)

52.249-4 TERMINATION FOR CONVENIENCE OF THE GOVERNMENT (SERVICES) (SHORT FORM) (APR 1984)

52.249-8 DEFAULT (FIXED-PRICE SUPPLY AND SERVICE) (APR 1984)

52.253-1 COMPUTER GENERATED FORMS (JAN 1991)

552.203-71 RESTRICTION ON ADVERTISING (SEP 1999)

552.215-70 EXAMINATION OF RECORDS BY GSA (FEB 1996)

552.252-6 AUTHORIZED DEVIATIONS IN CLAUSES (DEVIATION FAR 52.252-6) (SEP 1999)

52.204-16 commercial and government entity code reporting (nov 2014)

52.204-18 commercial and government entity code maintenance (nov 2014)

52.219-6 Notice of Total Small Business Set-Aside (Nov 2011)

52.227-14 Rights in Data -- General (May 2014)

52.228-11 Pledges of Assets (Jan 2012)

52.228-14 Irrevocable Letter of Credit (Nov 2014)

GSAM 552-204-9 Personal Identity Verification Requirements (Oct 2012)

GSAM 552.228-5 Government as Additional Insured (May 2009)

GSAM 552.232-72 Final Payment Under Building Services Contracts (Mar 2012)

GSAM 552.237-71 Qualifications of Employees (May 1989)

52.215-20 -- Requirements for Certified Cost or Pricing Data and Data Other Than Certified Cost or Pricing Data (Oct 2010)

a) *Exceptions from certified cost or pricing data.*

(1) In lieu of submitting certified cost or pricing data, offerors may submit a written request for exception by submitting the information described in the following subparagraphs. The Contracting Officer may require additional supporting information, but only to the extent necessary to determine whether an exception should be granted, and whether the price is fair and reasonable.

(i) *Identification of the law or regulation establishing the price offered.* If the price is controlled under law by periodic rulings, reviews, or similar actions of a governmental body, attach a copy of the controlling document, unless it was previously submitted to the contracting office.

(ii) *Commercial item exception*. For a commercial item exception, the offeror shall submit, at a minimum, information on prices at which the same item or similar items have previously been sold in the commercial market that is adequate for evaluating the reasonableness of the price for this acquisition. Such information may include --

(A) For catalog items, a copy of or identification of the catalog and its date, or the appropriate pages for the offered items, or a statement that the catalog is on file in the buying office to which the proposal is being submitted. Provide a copy or describe current discount policies and price lists (published or unpublished), *e.g.*, wholesale, original equipment manufacturer, or reseller. Also explain the basis of each offered price and its relationship to the established catalog price, including how the proposed price relates to the price of recent sales in quantities similar to the proposed quantities;

(B)) For market-priced items, the source and date or period of the market quotation or other basis for market price, the base amount, and applicable discounts. In addition, describe the nature of the market;

(C)) For items included on an active Federal Supply Service Multiple Award Schedule contract, proof that an exception has been granted for the schedule item.

(2) The offeror grants the Contracting Officer or an authorized representative the right to examine, at any time before award, books, records, documents, or other directly pertinent records to verify any request for an exception under this provision, and the reasonableness of price. For items priced

using catalog or market prices, or law or regulation, access does not extend to cost or profit information or other data relevant solely to the offeror's determination of the prices to be offered in the catalog or marketplace.
(b) *Requirements for certified cost or pricing data.* If the offeror is not granted an exception from the requirement to submit certified cost or pricing data, the following applies:
(1) The offeror shall prepare and submit certified cost or pricing data, and data other than certified cost or pricing data, and supporting attachments in accordance with the instructions contained in Table 15-2 of FAR 15.408, which is incorporated by reference with the same force and effect as though it were inserted here in full text. The instructions in Table 15-2 are incorporated as a mandatory format to be used in this contract, unless the Contracting Officer and the Contractor agree to a different format and change this clause to use Alternate I.

Alternate I (Oct 2010). As prescribed in 15.408(l), (and see 15.403-5(b)(1)), substitute the following paragraph (b)(1) for paragraph (b)(1) of the basic provision:
(b)(1) The offeror shall submit certified cost or pricing data, data other than certified cost or pricing data, and supporting attachments in the following format: Offerors shall submit their proposals in an editable Excel Spreadsheet organized by Contract Line Item Number for each year of this effort and shall include the applicable information as outlined in Section L.12.2 of this solicitation.

52.209-9 UPDATES OF PUBLICLY AVAILABLE INFORMATION REGARDING RESPONSIBILITY MATTERS (JULY 2013)
(a) The Contractor shall update the information in the Federal Awardee Performance and Integrity Information System (FAPIIS) on a semi-annual basis, throughout the life of the contract, by posting the required information in the System for Award Management database at https://www.acquisitions.gov.
(b) As required by section 3010 of the Supplemental Appropriations Act, 2010 (Pub. L. 111-212), all information posted in FAPIIS on or after April 15, 2011, except past performance reviews, will be publicly available. FAPIIS consists of two segments--
(1) The non-public segment, into which Government officials and the Contractor post information, which can only be viewed by--
(i)) Government personnel and authorized users performing business on behalf of the Government; or
(ii) The Contractor, when viewing data on itself; and
(2) The publicly-available segment, to which all data in the non-public segment of FAPIIS is automatically transferred after a waiting period of 14 calendar days, except for--
(i)) Past performance reviews required by subpart 42.15;
(ii)) Information that was entered prior to April 15, 2011; or
(iii)) Information that is withdrawn during the 14-calendar-day waiting period by the Government official who posted it in accordance with paragraph (c)(1) of this clause.
(c) The Contractor will receive notification when the Government posts new information to the Contractor` record.

(1) If the Contractor asserts in writing within 7 calendar days, to the Government official who posted the information, that some of the information posted to the non-public segment of FAPIIS is covered by a disclosure exemption under the Freedom of Information Act, the Government official who posted the information must within 7 calendar days remove the posting from FAPIIS and resolve the issue in accordance with agency Freedom of Information procedures, prior to reposting the releasable information. The contractor must cite 52.209-9 and request removal within 7 calendar days of the
posting to FAPIIS.
(2) The Contractor will also have an opportunity to post comments regarding information that has been posted by the Government. The comments will be retained as long as the associated information is retained, i.e., for a total period of 6 years. Contractor comments will remain a part of the record unless the Contractor revises them.
(3) As required by section 3010 of Pub. L. 111-212, all information posted in FAPIIS on or after April 15, 2011, except past performance reviews, will be publicly available.
(d) Public requests for system information posted prior to April 15, 2011, will be handled under Freedom of Information Act procedures, including, where appropriate, procedures promulgated under E.O. 12600.
(End of clause)

52.216-18 ORDERING (OCT 1995)
(a)) Any supplies and services to be furnished under this contract shall be ordered by issuance of delivery orders or task orders by the individuals or activities designated in the Schedule. Such orders may be issued from time of award through end of contract.
(b) All delivery orders or task orders are subject to the terms and conditions of this contract. In the event of conflict between a delivery order or task order and this contract, the contract shall control.
(c)) If mailed, a delivery order or task order is considered "issued" when the Government deposits the order in the mail. Orders may be issued orally, by facsimile, or by electronic commerce methods only if authorized in the Schedule.
(End of clause)

52.216-19 ORDER LIMITATIONS (OCT 1995)
(a)) "Minimum order." When the Government requires supplies or services covered by this contract in an amount of less than $200.00 the Government is not obligated to purchase, nor is the Contractor obligated to furnish, those supplies or services under the contract.
(b) "Maximum order." The Contractor is not obligated to honor--
(1) Any order for a single item in excess of $150,000
(2) Any order for a combination of items in excess of $150,000 or
(3) A series of orders from the same ordering office within ONE (1) days that together call for quantities exceeding the limitation in paragraph (b)(1) or (2) of this section.
(c)) If this is a requirements contract (i.e., includes the Requirements clause at subsection 52.216-21 of the Federal Acquisition Regulation (FAR)), the Government is not required to order a part of any one requirement from the Contractor if that requirement exceeds the maximum-order limitations in paragraph (b) of this section.

(d) Notwithstanding paragraphs (b) and (c) of this section, the Contractor shall honor any order exceeding the maximum order limitations in paragraph (b), unless that order (or orders) is returned to the ordering office within TWO (2) days after issuance, with written notice stating the Contractor`s intent not to ship the item (or items) called for and the reasons. Upon receiving this notice, the Government may acquire the supplies or services from another source.
(End of Clause)

52.216-22 INDEFINITE QUANTITY (OCT 1995)
(a) This is an indefinite-quantity contract for the supplies or services specified, and effective for the period stated, in the Schedule. The quantities of supplies and services specified in the Schedule are estimates only and are not purchased by this contract.
(b) Delivery or performance shall be made only as authorized by orders issued in accordance with the Ordering clause. The Contractor shall furnish to the Government, when and if ordered, the supplies or services specified in the Schedule up to and including the quantity designated in the Schedule as the "maximum." The Government shall order at least the quantity of supplies or services designated in the Schedule as the "minimum."
(c) Except for any limitations on quantities in the Order Limitations clause or in the Schedule, there is no limit on the number of orders that may be issued. The Government may issue orders requiring delivery to multiple destinations or performance at multiple locations.
(d) Any order issued during the effective period of this contract and not completed within that period shall be completed by the Contractor within the time specified in the order. The contract shall govern the Contractor`s and Government`s rights and obligations with respect to that order to the same extent as if the order were completed during the contract`s effective period; provided, that the Contractor shall not be required to make any deliveries under this contract after the completion date of the order.
(End of Clause)

52.217-8 OPTION TO EXTEND SERVICES (NOV 1999)
The Government may require continued performance of any services within the limits and at the rates specified in the contract. These rates may be adjusted only as a result of revisions to prevailing labor rates provided by the Secretary of Labor. The option provision may be exercised more than once, but the total extension of performance hereunder shall not exceed 6 months. The Contracting Officer may exercise the option by written notice to the Contractor within 30 DAYS
(End of Clause)

52.217-9 OPTION TO EXTEND THE TERM OF THE CONTRACT (MAR 2000)
(a) The Government may extend the term of this contract by written notice to the Contractor within 30 days provided that the Government gives the Contractor a preliminary written notice of its intent to extend at least 60 days days before the contract expires. The preliminary notice does not commit the Government to an extension.
(b) If the Government exercises this option, the extended contract shall be considered to include this option clause.
(c) The total duration of this contract, including the exercise of any options under this clause, shall not exceed 5 years and 6 months.
(End of Clause)

52.219-17 SECTION 8(a) AWARD (DEC 1996)

(a) By execution of a contract, the Small Business Administration (SBA) agrees to the following:
(1) To furnish the supplies or services set forth in the contract according to the specifications and the terms and conditions by subcontracting with the Offeror who has been determined an eligible concern pursuant to the provisions of section 8(a) of the Small Business Act, as amended (15 U.S.C. 637(a)).
(2) Except for novation agreements and advance payments, delegates to the GSA/PBS Region 4 Acquisition Division responsibility for administering the contract with complete authority to take any action on behalf of the Government under the terms and conditions of the contract; provided, however that the contracting agency shall give advance notice to the SBA before it issues a final notice terminating the right of the subcontractor to proceed with further performance, either in whole or in part, under the contract.
(3) That payments to be made under the contract will be made directly to the subcontractor by the contracting activity.
(4) To notify the GSA/PBS Region 4 Acquisition Division Contracting Officer immediately upon notification by the subcontractor that the
owner or owners upon whom 8(a) eligibility was based plan to relinquish ownership or control of the concern.
(5) That the subcontractor awarded a subcontract hereunder shall have the right of appeal from decisions of the cognizant Contracting Officer under the "Disputes" clause of the subcontract.
(b) The offeror/subcontractor agrees and acknowledges that it will, for and on behalf of the SBA, fulfill and perform all of the requirements of the contract.
(c) The offeror/subcontractor agrees that it will not subcontract the performance of any of the requirements of this subcontract to any lower tier subcontractor without the prior written approval of the SBA and the cognizant Contracting Officer of the GSA/PBS Region 4 Acquisition Division.
(End of Clause)

52.219-18 NOTIFICATION OF COMPETITION LIMITED TO ELIGIBLE 8(A) CONCERNS (JUN 2003)

(a)) Offers are solicited only from small business concerns expressly certified by the Small Business Administration (SBA) for participation in the SBA`s 8(a) Program and which meet the following criteria at the time of submission of offer--
(1) The Offeror is in conformance with the 8(a) support limitation set forth in its approved business plan; and
(2) The Offeror is in conformance with the Business Activity Targets set forth in its approved business plan or any remedial action directed by the SBA.
(b) By submission of its offer, the Offeror represents that it meets all of the criteria set forth in paragraph (a) of this clause.
(c)) Any award resulting from this solicitation will be made to the Small Business Administration, which will subcontract performance to the successful 8(a) offeror selected through the evaluation criteria set forth in this solicitation.
(d)
(1) "Agreement." A small business concern submitting an offer in its own name shall furnish, in

performing the contract, only end items manufactured or produced by small business concerns in the United States or its outlying areas. If this procurement is processed under simplified acquisition procedures and the total amount of this contract does not exceed $25,000, a small business concern may furnish the product of any domestic firm. This paragraph does not apply to construction or service contracts.

(2) The Contractor will notify the General Services Administration Contracting Officer in writing immediately upon entering an agreement (either oral or written) to transfer all or part of its stock or other ownership interest to any other party.

52.222-40 NOTIFICATION OF EMPLOYEE RIGHTS UNDER THE NATIONAL LABOR RELATIONS ACT (DEC 2010)

(a)) During the term of this contract, the Contractor shall post an employee notice, of such size and in such form, and containing such content as prescribed by the Secretary of Labor, in conspicuous places in and about its plants and offices where employees covered by the national Labor Relations Act engage in activities relating to the performance of the contract, including all places where notices to employees are customarily posted both physically and electronically, in the languages employees speak, in accordance with 29 CFR 471.2(d) and (f).

(1) Physical posting of the employee notice shall be in conspicuous places in and about the Contractor`s plants and offices so that the notice is prominent and readily seen by employees who are covered by the National Labor Relations Act and engage in activities related to the performance of the contact.

(2) If the Contractor customarily posts notices to employees electronically, then the Contractor shall also post the required notice electronically by displaying prominently, on any Web site that is maintained by the Contractor and is customarily used for notices to employees about terms and conditions of employment, a link to the Department of Labor`s Web site that contains the full text of the poster. The link to the Department`s Web site, as referenced in (b)(3) of this section, must read, "Important Notice about Employee Rights to Organize and Bargain Collectively with Their Employers."

(b) This required employee notice, printed by the Department of Labor, may be--

(1) Obtained from the Division of Interpretations and Standards, Office of Labor-Management Standards, U.S. Department of Labor, 200 Constitution Avenue, NW., Room N-5609, Washington, DC 20210,

(202) 693-0123, or from any field office of the Office of Labor-Management Standards or Office of Federal Contract Compliance Programs;

(2) Provided by the Federal contracting agency if requested;

(3) Downloaded from the Office of Labor-management Standards Web site at www.dol.gov/olms/regs/compliance/EO13496.htm; or

(4) Reproduced and used as exact duplicate copies of the Department of Labor`s official poster.

(c) The required text of the employee notice referred to in this clause is located at Appendix A, Subpart A, 29 CFR Part 471.

(d) The Contractor shall comply with all provisions of the employee notice and related rules, regulations, and orders of the Secretary of Labor.

(e)) In the event that the Contractor does not comply with the requirements set forth in paragraphs (a) through (d) of this clause, this contract may be terminated or suspended in whole or in part,

and the Contractor may be suspended or debarred in accordance with 29 CFR 471.14 and subpart 9.4
Such other sanctions or remedies may be imposed as are provided by 29 CFR part 471, which implements Executive Order 13496 or as otherwise provided by law.
(f) Subcontracts.
(1) The Contractor shall include the substance of this clause, including this paragraph (f), in every subcontract that exceeds $10,000 and will be performed wholly or partially in the Unites States, unless exempted by the rules, regulations, or orders of the Secretary of Labor issued pursuant to section 3 of Executive Order 13496 of January 30, 2009, so that such provisions will be binding upon each subcontractor.
(2) The Contractor shall not procure supplies or services in a way designed to avoid the applicability of Executive Order 13496 or this clause.
(3) The Contractor shall take such action with respect to any such subcontract as may be directed by the Secretary of Labor as a means of enforcing such provisions, including the imposition of sanctions for noncompliance.
(4) However, if the Contractor becomes involved in litigation with a subcontractor, or is threatened with such involvement, as a result of such direction, the Contractor ma request the United States, through the Secretary of Labor, to enter into such litigation to protect the interests of the United States.
(End of clause)

52.222-42 STATEMENT OF EQUIVALENT RATES FOR FEDERAL HIRES (MAY 2014)
In compliance with the Service Contract Labor Standards statute and the regulations of the Secretary of Labor (29 CFR part 4), this clause identifies the classes of service employees expected to be employed under the contract and states the wages and fringe benefits payable to each if they were employed by the contracting agency subject to the provisions of 5 U.S.C. 5341 or 5332. This Statement is for Information Only:
It is not a Wage Determination

HVAC (Research Facility) 53411	$20.23
JANITOR 11150	$10.39

(End of Clause)

52.223-9 ESTIMATE OF PERCENTAGE OF RECOVERED MATERIAL CONTENT FOR EPA-DESIGNATED ITEMS (MAY 2008)
(a)) "Definitions." As used in this clause--
"Postconsumer material" means a material or finished product that has served its intended use and has been discarded for disposal or recovery, having completed its life as a consumer item. Postconsumer material is a part of the broader category of "recovered material."
"Recovered material" means waste materials and by-products recovered or diverted from solid waste, but the term does not include those materials and by-products generated from, and commonly reused within, an original manufacturing process.
(b) The Contractor, on completion of this contract, shall--

(1) Estimate the percentage of the total recovered material content for EPA-designated item(s) delivered and/or used in contract performance, including, if applicable, the percentage of postconsumer material content; and
(2) Submit this estimate to the designated COR
(End of Clause)

52.223-11 OZONE-DEPLETING SUBSTANCES (MAY 2001)

(a)) "Definition." "Ozone-depleting substance," as used in this clause, means any substance the Environmental Protection Agency designates in 40 CFR part 82 as--
(1) Class I, including, but not limited to, chlorofluorocarbons, halons, carbon tetrachloride, and methyl chloroform; or
(2) Class II, including, but not limited to, hydrochlorofluorocarbons.
(b) The Contractor shall label products which contain or are manufactured with ozone-depleting substances in the manner and to the extent required by 42 U.S.C. 7671j (b), (c), and (d) and 40 CFR part 82, Subpart E, as follows:
Warning Contains (or manufactured with, if applicable) +_____, a substance(s) which harm(s) public health and environment by destroying ozone in the upper atmosphere.
+ The Contractor shall insert the name of the substance(s).
(End of Clause)

52.223-17 AFFIRMATIVE PROCUREMENT OF EPA-DESIGNATED ITEMS IN SERVICE AND CONSTRUCTION CONTRACTS (MAY 2008)

(a)) In the performance of this contract, the Contractor shall make maximum use of products containing recovered materials that are EPA-designated items unless the product cannot be acquired--
(1) Competitively within a timeframe providing for compliance with the contract performance schedule;
(2) Meeting contract performance requirements; or
(3) At a reasonable price.
(b) Information about this requirement is available at EPA`s Comprehensive Procurement Guidelines web site, http://www.epa.gov/cpg/. The list of EPA-designated items is available at http://www.epa.gov/cpg/products.htm.
(End of clause)

52.228-16 I PERFORMANCE AND PAYMENT BONDS--OTHER THAN CONSTRUCTION (JUL 2000)--ALTERNATE I (JUL 2000)

(a)) "Definitions." As used in this clause--
"Original contract price" means the award price of the contract or, for requirements contracts, the price payable for the estimated quantity; or, for indefinite-quantity contracts, the price payable for the specified minimum quantity. Original contract price does not include the price of any options, except those options exercised at the time of contract award.
(b) The Contractor shall furnish a performance bond (Standard Form 1418) for the protection of the Government in an amount equal to 10 percent of the original contract price.
(c) The Contractor shall furnish all executed bonds, including any necessary reinsurance agreements, to the Contracting Officer, within 30 days, but in any event, before starting work.

(d) The Government may require additional performance bond protection if the contract price is increased. The Government may secure the additional protection by directing the Contractor to increase the penal amount of the existing bond or to obtain an additional bond.
(e) The bonds shall be in the form of firm commitment, supported by corporate sureties whose names appear on the list contained in Treasury Department Circular 570, individual sureties, or by other acceptable security such as postal money order, certified check, cashier`s check, irrevocable letter of credit, or, in accordance with Treasury Department regulations, certain bonds or notes of the United States. Treasury Circular 570 is published in the Federal Register, or may be obtained from the:
U.S. Department of Treasury
Financial Management Service
Surety Bond Branch
401 14th Street, NW, 2nd Floor, West Wing
Washington, DC 20227
(End of Clause)

52.252-2 CLAUSES INCORPORATED BY REFERENCE (FEB 1998)
This contract incorporates one or more clauses by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. Also, the full text of a clause may be accessed electronically at this/these address(es):
www.acquisition.gov
(End of Clause)

552.216-74 TASK-ORDER AND DELIVERY-ORDER OMBUDSMAN (AUG 2010)
GSA has designated a Task-Order and Delivery-Order Ombudsman who will review complaints from contractors and ensure that they are afforded a fair opportunity for consideration in the award of task or delivery orders under Indefinite Delivery/Indefinite Quantity (ID/IQ) contracts, consistent with the procedures in the contract. Written complaints shall be submitted to the Ombudsman, with a copy to the Contracting Officer.
In the case that the contractor is not satisfied with the resolution of the complaint by the GSA Task-Order and Delivery-Order Ombudsman, the contractor may follow the procedures outlined in subpart 33.1.
The GSA Ombudsman is the Director, Office of Acquisition Integrity located at: General Services Administration (GSA), Office of Governmentwide Policy (OGP), Office of Acquisition Policy (MV), Acquisition Integrity Division (MVA), 1800 F Street, NW., Room 4014, Washington, D.C. 20405, Telephone: (202) 219-3454, Fax: (202) 219-3615, E-mail: joseph.neurauter@gsa.gov.
(End of Clause)

552.217-71 Notice Regarding Option(s) (Nov 1992)

The General Services Administration (GSA) has included an option to “extend the term of this contract” in order to demonstrate the value it places on quality performance by providing a mechanism for continuing a contractual relationship with a successful Offeror that performs at a level which meets or exceeds GSA’s quality performance expectations as communicated to the Contractor, in writing, by the Contracting Officer or designated representative. When deciding

whether to exercise the option, the Contracting Officer will consider the quality of the Contractor's past performance under this contract in accordance with 48 CFR 517.207.
(End of provision)

552.219-74 SECTION 8(A) DIRECT AWARD (SEP 1999)

(a) This contract is issued as a direct award between the contracting activity and the 8(a) contractor pursuant to the Memorandum of Understanding between the Small Business Administration (SBA) and the General Services Administration. SBA retains the responsibility for 8(a) certifications, 8(a) eligibility determinations, and related issues, and will provide counseling and assistance to the 8(a) contractor under the 8(a) program. The cognizant SBA district office is: (N/A at this time)
(b) The contracting activity is responsible for administering the contract and taking any action on behalf of the Government under the terms and conditions of the contract. However, the contracting activity shall give advance notice to SBA before it issues a final notice terminating performance, either in whole or in part, under the contract. The contracting activity shall also coordinate with SBA prior to processing any advance payments or novation agreements. The contracting activity may assign contract administration functions to a contract administration office.
(c) The Contractor agrees:
(1) To notifying the Contracting Officer, simultaneous with its notification to SBA (as required by SBA`s 8(a) regulations), when the owner or owners upon whom 8(a) eligibility is based plan to relinquish ownership or control of the concern. Consistent with 15 U.S.C. 637(a)(21), transfer of ownership or control shall result in termination of the contract for convenience, unless SBA waives the requirement for termination prior to the actual relinquishing of ownership and control.
(2) To the requirements of 52.219-14, Limitations on Subcontracting.
(End of Clause)

552.232-77 PAYMENT BY GOVERNMENT CHARGE CARD (NOV 2009)

(a)) Definitions.
"Governmentwide commercial purchase card" means a uniquely numbered charge card issued by a contractor under the GSA SmartPay program contract for Fleet, Travel, and Purchase Card Services to named individual Government employees or entities to pay for official Government purchases.
"Oral order" means an order placed orally either in person or by telephone.
(b) At the option of the Government and if agreeable to the Contractor, payments of $2,499 or less for oral or written orders may be made using the Governmentwide commercial purchase card.
(c) The Contractor shall not process a transaction for payment using the charge card until the purchased supplies have been shipped or services performed. Unless the cardholder requests correction or replacement of a defective or faulty item under other contract requirements, the Contractor must immediately credit a cardholder`s account for items returned as defective or faulty.
(d) Payments made using the Governmentwide commercial purchase card are not eligible for any negotiated prompt payment discount. Payment made using a Government debit card will receive the applicable prompt payment discount.
(End of Clause)

LIMITATION OF GOVERNMENTS OBLIGATION

(a) Contract line item(s)_____and_____are incrementally funded. For these item(s), the sum of $_____of the total price is presently available for payment and allotted to this contract. An allotment schedule is set forth in Paragraph (J) of this clause.

(b) For item(s) identified in paragraph (a) of this clause, the Contractor agrees to perform up to the point at which the total amount payable by the Government, including reimbursement in the event of termination of those item(s) for the Government's convenience, approximates the total amount currently allotted to the contract. The Contractor is not authorized to continue work on those item(s) beyond that point. The Government will not be obligated in any event to reimburse the Contractor in excess of the amount allotted to the contract for those item(s) regardless of anything to the contrary in the clause entitled "Termination for Convenience of the Government." As used in this clause, the total amount payable by the Government in the event of termination of applicable contract line items) for convenience includes costs, profit, and estimated termination settlement costs for those item(s).

(c) Notwithstanding the dates specified in the allotment schedule in paragraph (j)) of this clause, the Contractor shall be notified that funding is available by email (as annotated on the award document) to the contractor 15 days prior to the incremental funding dates as outlined in Paragraph J. Notice of funding will also be provided via a website (https:11finance3.qsa.qov). If after such notification additional funds are not allotted prior to the expiration date, the Contracting Officer will terminate any item(s) for which additional funds have not been allotted, pursuant to the clause of this contract entitled "Termination for Convenience of the Government."

(d) When additional funds are allotted for continued performance of the contract line item(s) identified in paragraph (a) of this clause, the Contractor agrees to continue performance in accordance with the contract. The provisions of paragraphs (b) and (d) of this clause will apply in like manner to the additional allotted funds and agreed substitute date.

(e) If, solely by reason of failure of the Government to allot additional funds, by the dates indicated below in Paragraph J, in amounts sufficient for timely performance of the contract line item(s) identified in paragraph (a) of this clause, the Contractor incurs additional costs or is delayed in the performance of the work under this contract and if additional funds are allotted, an equitable adjustment will be made in the price or prices (including appropriate target, billing, and ceiling prices where applicable) of the item(s), or in the time of delivery, or both. Failure to agree to any such equitable adjustment hereunder will be a dispute concerning a question of fact within the meaning of the clause entitled "Disputes."

(f) The Government may at any time prior to termination allot additional funds for the performance of the contract line item(s) identified in paragraph (a) of this clause.

(g) The termination provisions of this clause do not limit the rights of the Government under the clause entitled "Default." The provisions of this clause are limited to the work and allotment of funds for the contract line item(s) set forth in paragraph (a) of this clause. This clause no longer applies once the contract is fully funded except with regard to the rights or obligations of the parties concerning equitable adjustments negotiated under paragraphs (d) and (e) of this clause.

(h) Nothing in this clause affects the right of the Government to terminate this contract pursuant to the clause of this contract entitled "Termination for Convenience of the Government."

(i) Nothing in this clause shall be construed as authorization of voluntary services whose acceptance is otherwise prohibited under 31 U.S.C. § 1342.

(j) The parties contemplate that the Government will allot funds to this contract in increments from the date of award in accordance with the below schedule:

"Upon Execution of Award"	

J. List of Attachments

(List of documents, exhibits and Other Attachments)

J.1 Quality Assurance Surveillance Plan (QASP)

J.1.1.Contract Deliverables Reference

J.2 Green Purchasing Report

J.3. Solid Waste Audit Report

J.4 Summary of Environmentally Sustainable Product Attributes and Offerings

J.5 Building Information Sheets

J.6 Monthly Report Template

J.7 Building Operating Plan Template

J.8 Smart Buildings

J.9 Water Treatment Standards

J.10 Energy & Water Operational Performance Targets

J.11 Energy and Water Efficiency Use Plan - RESERVED

J.12 Energy and Water Efficiency Monthly Report - RESERVED

J.13 Annual Energy And Water Efficiency Report - RESERVED

J.14 Qualifications of Electrical Testing Technicians (ETT)

J. 15 Miscellaneous Best Practices - RESERVED

J.16 Equipment Inventory/CMMS

J.17 Preventive Maintenance Schedule

J.18 Solid Waste and Recycling Report

J.19. Elevator Tour Log - RESERVED

J.20. Underground Storage Tank (UST/AST)

J.21. On-boarding and Off-Boarding Contract employees Requiring Access to GSA IT Systems Procedures - Contractor Information Worksheet (CIW)

J.22. Custodial Surveillance Form

J.23. Building Exterior and Hardscape Plan

J.24. Erosion Sediment Control

J.25. Wage Determinations

J.1. QUALITY ASSURANCE SURVEILLANCE PLAN (QASP)

INTRODUCTION

This Quality Assurance Surveillance Plan (QASP) is designed to provide the General Services Administration (GSA) with an effective surveillance method of monitoring and evaluating the Contractor's performance under a Performance-Based Statement of Work (PBSOW) for both operation and maintenance services and custodial (and custodial related) services.

In accordance with Federal Acquisition Regulation (FAR) Part 37.601, performance-based contracting methods are intended to ensure that the required performance quality levels are achieved and that the total payment is related to the degree that services performed or outcomes achieved meet contract standards. GSA's role in quality assurance is to ensure that the Contractors are achieving the quality levels established in the operation and maintenance services contracts and focuses on the Contractors' QCP. GSA periodically validates the execution of the Contractors' quality control programs by reviewing such areas as the Contractors' inspection forms, service request logs, tenant reports, tenant satisfaction surveys, and the timeliness of corrective actions.

A. PURPOSE OF THE QASP

The QASP is intended to accomplish the following:

- Define the roles and responsibilities of participating Government officials.
- Identify the performance objectives based upon the PBSOW in accordance with FAR Part 46.401(a) (1).
- Identify the performance quality level standards in accordance with FAR Part 37.601(a) (2).
- Describe the methods of surveillance for GSA to identify quality levels in accordance with FAR Part 46.401(a) (2).
- Establish a method to provide feedback to the Contractor regarding quality and timeliness of the service performance, i.e., copies of inspection forms, copies of tenant reports, data on tenant satisfaction scores; and any other drivers or measures of performance that are required by the CO .
- Establish timeframes for communication and performance improvement if needed.
- Establish specified procedures for changes to the contract price when services are not performed or do not meet contract requirements in accordance to FAR Part 37.601(a) (3).
- Ensure the Contractor has developed and implemented a QCP establishing procedures and responsibilities for controlling the quality of work performed.

B. ROLES AND RESPONSIBILITIES OF GOVERNMENT OFFICIALS

The following Government officials will participate in assessing the quality of the Contractor's performance. Their roles and responsibilities are described as follows:

1. The person designated by the CO will serve as the COR. The COR is responsible for monitoring, assessing, recording, and reporting on the performance of the Contractor. The COR shall have the primary responsibility for completing forms that will be used to evaluate the Contractor's performance. In addition, the CO shall use the Contractor Performance System (CPS) to document the Contractor's performance

2. The person designated as the COR will have overall responsibility for overseeing the Contractor's performance. The CO shall be responsible for monitoring the Contractor's performance in the areas of contract compliance and contract administration. The CO will review the COR's written inspections and assessments of the Contractor's performance and resolve any discrepancies that may arise between the Contractor and COR. In addition, the CO shall use the Contractor Performance System (CPS) to document the Contractor's performance.

C. TYPES OF WORK TO BE PERFORMED

1. The Contractor's performance in providing the following operation and maintenance custodial and related services shall be evaluated by the Government:

a. Existing deficiency list
~~b. Building operating plan~~
c. Equipment inventory
d. Monthly progress reports
e. Reference library
f. Building management support services
g. Operational requirements
h. Service requests
i. Tours
j. Maintenance program
k. Water treatment
l. Oil analysis
m. Lamp and ballast replacements
n. Repairs
o. Safety and environmental
p. Fire Protection and Life Safety equipment and systems
q. Other services as described in section C and J

D. METHODS OF SURVEILLANCE

The method of surveillance is based on the performance criteria of the contract terms and specifications. Each requirement will describe the tasks to be performed and the standard for successful performance. GSA intends to monitor and evaluate the Contractor's performance based on any or all of the following surveillance methods:

1. **Periodic Surveillance Inspections:** This method consists of selected surveillance tasks by the Government that do not require 100 percent inspection, or are performed on a random basis. The CO will evaluate the Contractor's reports, surveys, etc. on a weekly, biweekly, monthly, or quarterly basis.

2. **Tenant Interviews:** All tenant concerns received through the CO will be documented and evaluated on a planned schedule developed by the CO . This method may help the CO focus on areas that may require further action from the CO.

3. **Service Request Documentation:** This method of surveillance will provide information to the CO , such as identification of the types of service requests received, the frequencies of service requests, corrective action taken, timeliness of completion, and any other pertinent data. At a minimum, this method shall be performed on a monthly basis.

4. **Tenant Satisfaction Surveys:** The Gallup Organization conducts surveys for one-third of GSA's tenants in Government-owned and leased buildings. These surveys gather important data in many areas, including specific categories pertaining to the operation and maintenance of GSA's buildings. The surveys provide the CO with satisfaction scores that can be further evaluated to determine if there are any weaknesses within the various programs. There are various measures that can be taken, such as reviewing the survey's comments, obtaining further feedback from the tenants, or sharing the scores with the Contractor to establish a plan of action.

E. QUALITY ASSURANCE FORMS AND REPORTS

Inspection Form: The GSA-3423 or equivalent forms will be used to document and evaluate the Contractor's performance. The COR will evaluate each event in accordance with the performance standards and performance requirements stated in the PBSOW. All tasks that are considered to have unacceptable performance shall be substantiated and documented on the GSA-3423 form or equivalent. The form will be completed and submitted to the Contractor within 24 hours. The Contractor shall return the GSA-3423 form or equivalent identifying the corrective action taken within time allotted by the COR.

Inspection of Services Clause: The CO shall fill in applicable commercial or non-commercial clause as appropriate, i.e., FAR Part 52.246.4 paragraphs (e) and (f).

F. ANALYSIS OF SURVEILLANCE RESULTS

Monthly CO Report: At the end of each month the COR will summarize the overall results of the Contractor's performance for the previous month and send to the CO. If appropriate, the CO may investigate the event(s) further to determine if all the facts and circumstances surrounding the event(s) are accurate. The CO may discuss with the Contractor an event or trend that indicates unacceptable performance.

G. QUALIY ASSURANCE SURVEILLANCE PLAN (QASP)

QASP Standards for Mechanical

Performance-Based Task	Services to Be Inspected	Standard for Successful Performance	Quality Assurance Surveillance Method
SECTION C Existing Deficiency Inspection/List and equipment inventory.	A thorough and systematic initial inspection and	A complete and accurate Deficiency list and inventory must be completed and	The Government will Evaluate performance based

	inventory of all equipment and systems and the performance of an annual inventory to verify and update the inventory.	submitted within the initial timeframe and an annual inventory must be scheduled and conducted to verify and update inventory.	on tenant satisfaction, surveys, tenant interviews, periodic inspections, and service request documentation.
Startup Phase.	The Contractor must provide all start up services necessary to provide seamless operation of all building systems. Adjustment to controls, BAS	Submission and review of all required building documentation without failures in providing service to our customers.	
Staffing and ability to communicate with CO.	Contractor must staff and provide communication methods to ensure services are adequately provided to the tenant.	Quality and quantity of staffing and methods of communication ensure adequate response to all Contract requirements.	
Onsite records.	All records required by the Contract must be accurate and available for inspection.	Records must be organized, up to date, and reflect actual conditions.	
CMMS (if applicable).	Service request record keeping using the computerized maintenance management system (CMMS).	Maintenance records are accurate and current and are properly populated within the CMMS to document historical maintenance efforts during the life cycle of the facility.	
~~Building Operating Plan (BOP).~~	~~BOP must detail all aspects of the Contractor's performance of the Contract and building equipment and system~~	~~BOP must be submitted and address all items.~~	

	~~information. Energy consumption must be monitored by the Contractor for indicators of inefficient operation.~~		
Monthly Progress Reports.	Reports of Contractor progress and activities must be provided monthly.	All reports must be thorough, accurate and submitted on time as required by the Contract.	
Reference library.	Information in the form of a reference library must be provided by the Contractor.	All required documents are to be included in the reference library and must be complete and up to date.	
Service Requests.	Service requests must be received, tracked, and responded to in accordance with Contract requirements.	All routine, emergency, and urgent service requests are responded to as required by the Contract and repairs are completed within specified timeframes.	
~~Energy and Water Efficiency Plan~~	~~Reports must contain monthly energy usage compared to last year and recommendations on improvement~~	~~Control systems must be operated to provide maximum efficiency as measured by energy consumption per gross sq. ft. while providing tenant comfort~~	
~~Tours.~~	~~Tours must be conducted and documented in accordance with Contract requirements.~~	~~All tours must be conducted and documented as required and will reflect actual conditions. Adjustments will be made as needed. Logs and check sheets must be adequate to track operating hours and equipment performance history.~~	
Leak testing.	Refrigerants and natural gas leaks must be avoided	Leak testing for refrigerants and natural gas must be	

	and detected as early as possible.	performed and documented in accordance with the BOP.	
Condensate pans	Condensate pans must be clear and algae free at all times.	~~On at least a monthly basis, tours must include inspection and~~ treatment of condensate pans with appropriate biocide to ensure proper drainage.	
Disruptive or hazardous tool use, disruption to utilities, lighting and space conditioning.	Tenants must not be unnecessarily disrupted during repairs or procedures.	All disruptive tool use during normal working hours must be approved by the CO and welding and burning must be approved via GSA Form 1755. The CO must approve in advance any work that will disrupt lighting, utilities, and space conditioning.	
Plumbing and restroom maintenance.	Plumbing and drain systems must be maintained and in good working order.	All drain systems must be clear and kept functional at all times.	
Maintenance program.	Equipment must be maintained to the minimum standard established in the Contract and developed by the Contractor.	Minimally, the Contractor must perform preventive maintenance in accordance with the manufacturer's recommended standards for all equipment requiring a preventive maintenance procedure. The Contractor must be required to use the specified NFPA Codes and Standards in this document to perform inspections, testing, and preventive maintenance of fire protection and life safety systems and equipment. In addition, the Contractor shall be required to follow the specific testing and inspection frequencies and methods specified in such NFPA Codes and Standards. The Contractor must record such inspection, testing, and services on the	

		appropriate NFPA inspection form.	
Water treatment.	The Contractor must provide for an effective water treatment program including equipment, monitoring, reporting, etc.	The Contractor must perform water treatment, monitoring, and testing in accordance with the Contract requirements.	
Oil analysis and oil changes.	Oil analysis and oil changes must be documented.	The Contractor must perform initial and periodic oil analysis and oil changes in accordance with the Contract provisions.	
Lamp and ballast replacements.	~~Quality,~~ energy-efficient replacement lamps and ballasts must be used by the Contractor.	The Contractor must perform lamp and ballast replacements in accordance with the Contract provisions	
Architectural and structural systems maintenance.	Interior and exterior building architectural and structural systems must be maintained in good repair.	The Contractor must conduct inspections, repairs, replacements, and touch up painting and patching to match existing finishes as required by Contract provisions.	
~~Interior signage and directories.~~	~~Signage must be up to date and in good repair.~~	~~Signage must be updated and repaired as required.~~	
Finishes maintenance.	All finishes must appear neat and have an esthetically appealing appearance.	The Contractor must maintain and touch up building finishes in a professional manner.	
Repairs.	All repairs must be performed in a timely professional manner, using quality parts and materials.	The Contractor must perform repairs in accordance with the provisions of the Contract including timeliness of response, invoicing, thresholds, replacement part quality standards, and warranty provisions.	

Safety and environmental management.	Scheduling and record keeping.	All required safety and environmental tests, certifications, permits and other procedures required in this document must be scheduled in the CMMS work order system, and documented in the CMMS. In addition, the Contractor must maintain copies of all such tests, certifications, permits and other required records.	
Refrigerant Control	Refrigerant control and certification.	The Contractor must control refrigerants and maintain records in accordance with EPA, GSA**,** and appropriate Air Quality Management District standards. The Contractor must take immediate action to contain refrigerant leaks and must report any leaks to the CO .	
AQMD	AQMD operating permits.	The Contractor must be familiar with the requirements of the Local Air Quality Management District (AQMD), and shall be responsible for obtaining operating permits for boilers, generators, and other emissions-producing equipment regulated by the district.	
Underground Storage Tanks.	Underground storage tanks.	The Contractor is responsible for complying with all Federal, State, and Local requirements for the periodic inspection, monitoring, permitting, certification and maintenance of underground storage tanks.	

~~Polychlorinated Biphenyls (PCBs)~~	~~Polychlorinated biphenyls (PCBs) control.~~	~~The Contractor must inspect all transformers containing (PCBs) and maintain records of such inspections in accordance with State, Local, and Environmental Protection Agency (EPA) regulations.~~	
Hazardous Waste.	Hazardous waste.	The Contractor must be cognizant of, and comply with, all Federal, State, and Local laws and regulations related to the disposal (landfill, sewer discharge, etc.) of hazardous waste and materials used or removed in the performance of the Contract or discharged by the building, and must comply with all such requirements, to include record keeping requirements.	
Electrical Safety.	Electrical safety.	The Contractor must comply with NFPA 70E when working on or around electrical equipment or systems. The Contractor must ensure that areas restricted to qualified personnel are secured and properly labeled.	
Lock out/tag out.	Lock out/tag out.	The Contractor must develop a lockout/tag out program in accordance with 29 CFR 1910. The program must include all anticipated energy sources, including but not limited to electricity, steam, pressurized fluids, and mechanical energy.	
Confined Space Permits	Confined spaces.	The Contractor must identify and label all confined spaces in accordance with OSHA requirements. The Contractor must develop a confined space entry permit system for all permit- required confined	

		spaces within 60 calendar days of commencement of the Contract.	
Asbestos Management Program	Asbestos management.	The Contractor shall be expected to occasionally perform Class III and Class IV asbestos work as defined in 29 CFR 1910.26.1101. The Contractor must be prepared to deal with asbestos on a small scale, short duration basis to effect emergency repairs and to clean up small spills. The Contractor must protect building tenants, visitors, and employees from asbestos exposure. The Contractor must comply with applicable National Institute of Building Sciences (NIBS) and OSHA standards.	
Material Safety Data Sheets	Hazardous materials.	The Contractor must make material safety data sheets (MSDSs) available to their employees in accordance with 29 CFR 1910.1200.	
Boiler and Pressure Vessel	Boiler/pressure vessel operation and inspection standards.	All tests must be done in accordance with ASME Boiler and Pressure vessel Code, National Board Inspection Code (NBIC), EPA Local AQMD requirements, ASME CSD-1, and NFPA 85.	
Backflow Prevention Devices.	Backflow prevention devices.	Backflow prevention devices used on water- based fire suppression systems must be inspected, tested and maintained according to NFPA 25.	
Potable Water Systems.	Potable water systems.	The Contractor must comply with the Safe Drinking Water Act, PL 99-339, as amended, and the EPA Safe Drinking Water regulations (40 CFR	

		141.43, Sections A and D), that address the quantity of lead allowable in new installations or repairs to existing drinking water systems and/or plumbing. Potable water systems which are repaired, modified, serviced, or breeched in any way must be disinfected and flushed prior to returning the system to service.	
Labeling.	Labeling.	The Contractor must label equipment, storage areas and workspaces in accordance with OSHA standards immediately after commencement of the Contract if such labels are not already in place.	
	Water-based fire suppression system	The Contractor is responsible for meeting the inspection, maintenance, testing frequencies and testing methods outlined in NFPA 25. Water-based fire suppression system testing, maintenance and repair shall be performed during normal business hours when it does not interfere with building operations. When such testing, maintenance or repair will interfere with building operations; it shall be performed after normal business hours without additional costs to the government, unless approved otherwise by the CO . The Contractor must provide a fire watch in areas left unprotected until the water-based fire suppression	

		system is completely restored to service. In no case must any water based fire suppression system be left in a disabled condition without notifying the CO . The Contractor must ensure that the sprinkler system is maintained and operable at all times except while being tested or repaired. It is essential that the Contractor carefully schedule with the building manager and CO all non emergency shutdowns of the sprinkler system and that back up protection be provided by the Contractor any time the sprinkler system is out of service for more than 4 hours. In addition, regardless of the duration of the shutdown, the affected portion of the system must be tested to ensure that the protection has been restored.	
	Fire Rated doors and assembles.	The Contractor must utilize qualified personnel meeting the applicable requirements in Section H15.3, Qualification of Technicians. in performing any task associated with this contract The Contractor must perform inspections, tests and maintenance or repairs in accordance with the current edition of NFPA 80 and NFPA 101. The Contractor is responsible for meeting the inspection, maintenance, testing	

		frequencies, testing methods, and documentation requirements outlined in NFPA 80 NFPA 101.	
	Fire Damper and combination fire/smoke dampers.	The Contractor must utilize qualified personnel meeting the applicable requirements in Section H15.3, Qualification of Technicians. in performing any task associated with this contract The Contractor must perform inspections, tests, and maintenance or repairs in accordance with the current edition of NFPA 80. Maintenance of combination fire/smoke dampers must also meet the requirements contained in NFPA 105. The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in NFPA 80. The Contractor must utilize qualified personnel meeting the applicable requirements in Section H15.3, Qualification of Technicians. in performing any task associated with this contract	
	Smoke doors and assemblies.	The Contractor must perform inspections, tests, and maintenance or repairs in accordance with the current edition of NFPA 105.	

		The Contractor must utilize qualified personnel meeting the applicable requirements in Section H15.3, Qualification of Technicians. in performing any task associated with this contract The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in NFPA 105.	
	Smoke dampers. Portable fire extinguishers.	The Contractor must perform inspections, tests and maintenance or repairs in accordance with the current edition of NFPA 105. The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in NFPA 105. The Contractor must utilize qualified personnel meeting the applicable requirements in Section H15.3, Qualification of Technicians. in performing any task associated with this contract The Contractor must perform inspections, tests, and maintenance or repairs in accordance with the current edition of NFPA 10.	

		The Contractor must utilize qualified personnel meeting the applicable requirements in Section H15.3, Qualification of Technicians. in performing any task associated with this contract The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in NFPA 10.	
	Non-water based fire extinguishing systems.	The Contractor must perform inspections, tests and maintenance in accordance with the current edition of the applicable NFPA standards (e.g., NFPA 12, 12A, 17, 17A, 96, 2001, etc.). The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in the applicable NFPA standards (e.g., NFPA 12, 12A, 17, 17A, 96, 2001, etc.). The Contractor must utilize qualified personnel meeting the applicable requirements in Section H15.3, Qualification of Technicians. in performing any task associated with this contract.	

	Emergency lighting systems and exit signage.	The Contractor must perform inspections, tests, and maintenance or repairs in accordance with the current edition of NFPA 101. The Contractor must utilize qualified personnel meeting the applicable requirements in Section H15.3, Qualification of Technicians. in performing any task associated with this contract The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in NFPA 101.	
~~Vertical transportation system maintenance.~~	***~~[[[Complete only if included in this scope.]]]~~***	***~~[[[Complete only if included in this scope.]]]~~***	
Miscellaneous work.	The Contractor must provide labor hours and parts and supplies as requested by the CO .	The Contractor must provide labor hours as requested by the CO to perform tasks in a timely manner.	
Section H	Green Purchasing Tracking	Shall track and report and amounts of green cleaning products and materials purchased. Furnish records upon request.	
	Recycle Content Product Purchase Annual Reporting	Annual report on recycle products if applicable.	

QASP Standards for Janitorial

Performance-based Task	Services to be inspected	Standard for successful performance	Quality Assurance Surveillance Method
SECTION C Standard Services Interior	GREEN CLEANING GREEN PURCHASING PLAN	-Shall use green cleaning products, processes and equipment -Shall track and report costs and amounts of green cleaning products and materials purchased	100% Inspection
	FLOOR CARE BARE FLOORS (lobbies, corridors, restrooms, etc.) Wet Mopping	Floors, base moldings and grout shall be clean and free of debris, including but not limited to, dirt, water streaks, mop marks, strings, gum, tar and other foreign matter. The floors shall maintain their natural luster and not have a dull appearance. Shall comply with the methods prescribed in the National Institute of Building Sciences (NIBS) Guidance Manual, "Asbestos Operations and Maintenance Work Practices".	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
	Asbestos Containing Building Material (ACBM) Floors	Damp mopping shall be the only method of wet cleaning for floors in Automated Data Processing (ADP)/Data Center space. Damp mopping shall be the only method of wet cleaning for floors containing asphalt material. All applicable floor areas shall be maintained in accordance with industry standards.	

SECTION C Standard Services Interior	ADP/Data Center Floors	Spill residue and clean-up materials shall be disposed of in accordance with the Environmental Protection Agency (EPA), and State and local regulatory agency requirements.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
	Asphalt Floors	Refer to the Standard Services – Interior Section on Postal Space	
	Granite and Marble Floors (Crystallization)	The old finish or wax shall be removed and new sealant applied in accordance with standard commercial practices. Spots shall be eliminated. There shall be no evidence of gum, rust, burns, or scuffmarks, or wax build-up in corners or crevices. UNDER NO CIRCUMSTANCES SHALL BURNISHING, HIGH SPEED BUFFING OR DRY STRIPPING METHODS BE USED ON ACBM FLOORS.	
	Loading Dock Floors	Sealant must adhere to the floor. Floor areas must be evenly coated with a slip resistant seal.	
	Postal Floors	There shall be no water solutions used on wood flooring. There shall be no dry stripping methods used on wood flooring.	
	Strip and Finish		The Government may evaluate

SECTION C Standard Services Interior	Sealing Wood Floors		performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C Standard Services Interior SECTION C Standard and Above Standard Services Interior	CARPETS AND RUGS EXTRACTION	Free of visible dirt, dust, and other debris. No spots, smears, crusted material, or spills. No fuzzing caused by harsh rubbing or brushing of carpet. Build-ups, spills, or crusted materials are to be removed along with spots and smears. Cleaned areas of carpets and rugs shall be reasonably blended with surrounding carpets.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.

SECTION C Standard Services Interior	SPOT CLEANING VACUUMING	Shall be free of removable spots, soiled traffic patterns, dirt, dust, debris, gum, and crusted materials. Shall be free of dirt, dust, and other debris.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C Standard Services Interior	FLOOR MATS AND RUNNERS	Mats and runners shall be free of removable spots, soiled traffic patterns, dirt, debris, gum and crusted materials. There shall be no areas of deterioration or fuzzing as a result of harsh brushing or scrubbing.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.

SECTION C Standard Services Interior	RESTROOMS, SHOWER ROOMS, LOCKER ROOMS, AND HOLDING CELLS	Areas shall be cleaned with a disinfectant cleaner. Fixtures shall maintain a high level of luster and be free of dust, mold, mildew, streaks, and encrustations. Partitions, doors, vents, sills, and walls shall be free of dust, dirt, bodily fluids, and waste and graffiti. Restrooms shall be free of discarded materials and trash shall be emptied to prevent the containers from overflowing.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C Standard Services Interior	FIXTURES	Fixtures and surfaces (washbasins, urinals, modesty panels, toilets, shower stalls etc.) shall be clean with no dust, spots, soiled substances, discolorations, rust, mold, build-ups, or excess moisture.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C Standard Services Interior	SURFACES Horizontal Surfaces Metal, Brass, and Woodwork	Surfaces shall be free of dust, dirt, oil spots, or smudges. Surfaces (including corners, crevices, moldings, ledges, hand rails, grills, doors, door knobs, door frames, kick plates, etc.) shall be free of dust, streaks, spots, hand marks, oils, smudges, dirt,	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and

	Glass Cleaning	soiled substances, rust, encrustation, and streaks. All glass, clear partitions, mirror surfaces, bookcases, and other glass (within approximately 70 inches of the floor) shall be clean and free of dirt, dust, streaks, smudges, watermarks, spots and grime, and shall not be cloudy. There shall be no water spots on the glass or adjacent fixtures and furniture.	service call documentation.
SECTION C Standard Services Interior	WALLS	Free of smudges, marks, dirt, and spots with no discolorations.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C Standard Services Interior	HIGH CLEANING	Surfaces above 70 inches and _____inches **(Region, Specify)** shall be cleaned free of dirt, dust, and cobwebs. Where glass is present, both sides shall be clean and free of streaks. This does not include removal of vents, tiles, or fixtures. Surfaces shall be free of dust.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.

	DUSTING		
SECTION C Standard Services Interior/Exterior	TRASH (Exterior also), WASTEBASKETS, AND ASH RECEPTACLES (Exterior also)	Trash containers shall be emptied and kept clean, odor-free and free of dirt, dust, debris, residues, and spilled materials. Plastic liners for all trash and debris containers shall not be torn, worn, or contain residue. All ash receptacles shall be free of dust, ashes, odors, tar, streaks, and tobacco residues.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C Standard Services Interior	RECYCABLES ELEVATOR, ESCALATORS, AND STAIRWAYS	Shall provide all labor, equipment, and means to collect and transport recyclable materials from recycling bins and containers located throughout the building. - Door tracks shall be clean and free of dirt, debris, built up grime, dust, smudges, and other extraneous matter. - Surfaces shall be clean and free of finger marks, smudges, and spills. - Carpets and floors shall be free of removable spots, dirt, and debris. Floors requiring a finish shall be maintained at a high luster. - Stairways, escalators, entrances, landings, railings, risers, ledges, grills, doors, radiators, and surrounding areas shall be free of dirt, dust, litter, and debris.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.

SECTION C Standard Services Interior/Exterior	PLATE GLASS (all glass - glass over and in exterior and vestibule doors, all plate glass around entrances, lobbies vestibules, and spandrel)	Shall be clean and free of dirt, grime, streaks, moisture, and shall not be cloudy.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C Standard and Above Standard Services Interior/Exterior	WINDOW WASHING	- Windows shall be clean (minimum is annually) and free of dirt, grime, streaks, moisture, and shall not be cloudy. - - Window sashes, sills, woodworks, and other surroundings of interior glass shall be wiped free of drippings and other watermarks.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C Standard Interior	BLINDS AND COVERINGS	All blinds, coverings, cord tapes, and valances shall be clean and free of dust and spots.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C Standard Services Interior	FINE ARTS COLLECTION	Shall identify artworks; provide floor polishing, dusting, and window washing; identify and help mitigate	The Government may evaluate performance based on any or all of the

SECTION C Standard Services Interior/Exterior	POLICING INSIDE AREAS	site-specific hazards such as pests. All trash, and other discarded materials shall be removed.	following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C Standard Services Interior	INTERIOR AND ATRIUM PLANTS (government plants)	Plants shall be free of dust and dead leaves and be properly hydrated.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C Standard Services Interior	CONCESSIONS	- All public areas (cafeteria furniture, seating areas, snack bars, and vending machine areas) shall be clean, sanitized, free of spillages, food crumbs, spots, smudges, marks, and soil. - Floors in serving and kitchen areas shall be cleaned only if open during the normal scheduled cleaning hours, except in Federally-equipped cafeteria facilities. - In Federally-equipped cafeteria facilities, the cleaning of kitchens and areas behind serving tables and salad and soup bars is the responsibility of the Concessions Contractor.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.

SECTION C Standard Services Interior	POSTAL SPACE	All postal floors shall be free of dirt, dust, debris, and other foreign matter. If stripping and refinishing is required, finish and wax shall be removed and reapplied in accordance with standard commercial practices. UNDER NO CIRCUMSTANCES SHALL BURNISHING, HIGH SPEED BUFFING OR DRY STRIPPING METHODS BE USED ON ACBM FLOORS.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C Standard Services Interior	FITNESS CENTERS, HEALTH UNITS, AND LABORATORIES	Areas such as the fitness centers, health units, and laboratories, shall be cleaned with disinfectant. All vinyl surfaces of exercise equipment and exercise mats shall be free of dust, dirt, spots, streaks, and smudges. Shower curtains surfaces shall be cleaned and free of mold and dirt. Lockers exterior surfaces shall be free of dust and streaks. All metal (door frames handles, fixtures, and equipment) and glazed surfaces (including partitions), shall be free of smears, finger marks, streaks and shall maintain a uniform luster.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C Standard Services Exterior	CANOPIES	Shall be clean and free of dirt, dust, cobwebs, nests, bird excrement, trash, and debris.	The Government may evaluate performance based on any or all of the following: tenant satisfaction,

			surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C Standard Services Exterior	HARD SURFACE AREAS (sidewalks, brick areas, hard surfaces, parking lots, surface parking, garages, docks, etc.)	Shall be clean and free of dirt, debris, gum, litter, gravel, weeds, oils, and grease. No residual dirt shall remain after the removal of the debris.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C Standard Services Exterior	SURFACES (signs, vending machines, tables, etc.) GRAFFITI REMOVAL EXCREMENT REMOVAL	Shall be clean, with no dirt, dust, residues, streaks, spots, soiled substances, discolorations, or rust. Remove graffiti using normal cleaning methods. Steps, stairs, entrances, sidewalks, arcades, landings, balconies, and ledges shall be cleaned of all excrement. All areas, including unimproved areas and fence lines shall be clean of gum, litter, debris, papers, trash, and other discarded materials.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.

	POLICING OUTSIDE AREAS		
SECTION C Standard Services Exterior	LANDSCAPE EROSION MANAGEMENT	Shall employ environmentally low-impact strategies: temporary/permanent seeding, mulching, earth dikes, silt fencing, sediment traps and sediment basins to correct existing erosion areas. Maintain all plants, trees, shrubs, ground covers, and lawns in a manner that prolongs life and sustains a healthy appearance free from pests. Shall seek to prevent pollution by, among other things, reducing fertilizer and pesticide use to protect the environment. Protect native plans and wild habitat. Shall compost yard waste. Tree supports shall be kept in good condition and functioning at all times and be removed when no longer needed. Shall trim trees and shrubs to clear all roads, drives, and walking areas. Shall prune trees and shrubs to remove dead or diseased foliage or branches.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
	GROUNDS MAINTENANCE		
	COMPOSTING		
	TREES AND SHRUBS		

SECTION C Standard and Above Standard Services Exterior SECTION C Standard Services Exterior	Trimming Pruning Survey MULCHING MOWING AND EDGING LEAF REMOVAL	Shall provide for a professional survey of the trees to evaluate their condition. Shall maintain and replace mulch. Shall mow and edge all turf areas. Shall clear grass clip pings from walkways and roadways and blow them onto the grass. Shall remove leaves and debris from premises and drain openings. Shall over-seed, dethatch, and plug as necessary to prevent bare areas and promote even growth of turf areas. Shall fertilizer lawns, trees and ground cover consistent with common local landscaping practices. - Flowerbeds are to be free from weeds and debris. - Preference shall be given to the use of native perennials instead of annuals. Shall be aerated and cultivated and ground cover provided.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.

SECTION C Standard Services Exterior	OVER SEEDING, DETHATCHING, AND PLUGGING FERTILIZATION FLOWERBEDS AND PLANTS SOIL AND GROUND COVER UNIMPROVED GROUNDS FENCE LINES	Shall mow unimproved grounds to present a neat, well-maintained appearance. Shall control the height of grass, native grasses, weeds, and other growth at the fence lines at border stations, not exceed_____inches in height **(Region Shall Specify).** Sidewalks, parking lots and roadways (excluding unimproved grounds) shall be free of weeds and unwanted growths. Shall conduct walk-through and inspect all irrigation systems (sprinklers, rain and freeze sensors, and drip systems) and submit a list of damages. Shall minimize inconvenience to the building occupants and visitors, and maximize percolation. Shall minimize run-off into drains and sewers. Shall operate watering systems using automatic timers with rain/freeze sensors. If mechanical irrigation is not available or malfunctioning, the Contractor shall use alternative hand watering methods such as gator bags, or equivalents.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.

SECTION C Standard Services Exterior	WEEDS IRRIGATION WATERING	Shall be adjusted, cleaned, and set for most energy efficient watering periods. Sprinklers and drip heads are clean and adjusted. Entrances and exits shall not be wet from watering, during the arrival and departure of occupants and visitors. Shall pay to repair and test irrigation systems damaged by the Contractor due to neglect. Shall notify Government of operational malfunctions, breakages, or failures to the irrigation system. Shall utilize IPM to control pests and disease to protect landscape, trees, and shrubs. Shall bear costs to replace planted materials that have been damaged as a direct result of the Contractor's lack of oversight, neglect, or lack of proper care and maintenance. Glass view plates and other surfaces shall be free of dirt, dust, streaks, and spots. Blinds and coverings shall be washed on both sides and coordinated with the CO. Remove all dirt, debris, residue, gum, grease, and tar.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.

SECTION C Standard Services Exterior SECTION C Above Standard Exterior	ADJUST, CLEAN AND SET AUTOMATIC CONTROLLERS INTEGRATED PEST MANAGEMNT PLAN (Landscape) PLANT REPLACEMENTS	Shall plant Government furnished trees and plants in ground or planter as approved by the CO. Shall provide appropriate staffing and response to service calls. Shall prepare and abide by the Communication Plan Shall make reasonable efforts to assist the Government to prevent hazardous conditions and property damage. - Conduct waste/trash stream audit **upon request**. - Shall perform collection, removal, recycling and related activities agreed upon by the Government and Contractor based on the solid waste/trash audit final report. - Shall remove solid waste/trash from building premises. - Pick-ups of solid waste/trash may be required. Pick-ups of solid waste/trash shall be accomplished within 24 hours of CO notification. - Paper shall be transported from recycling bins to storage containers in designated areas. - Recyclable materials are recycled and not placed in landfills.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation. The Government may evaluate performance based on any or all of the following: tenant satisfaction,

		- Shall maintain and submit solid waste/trash hauling and recycling reports. Shall submit information on green purchasing practices specific to the performance of this contract including USDA-designated bio-based products purchased, non-bio-based environmentally sustainable CPG products, and non-green products. - List of chemicals and purchased price for IPM. - Shall maintain documentation to support all the above reported activities.	surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C	POSTAL LOCK BOXES/MAIL CASES		100% Inspection
	WASHING BLINDS AND COVERINGS		100% Inspection
	PRESSURE WASHING/STEAM CLEANING		100% Inspection
	GOVERNMENT FURNISHED TREES AND PLANTS		100% Inspection
	SERVICE CALLS		100% Inspection
	COMMUNICATION PLAN		100% Inspection

SECTION C	PROTECTION AND DAMAGE		100% Inspection
	SOLID WASTE/TRASH MANAGEMENT		
	RECYCLING		

	ENVIRONMENTAL REPORTING		
SECTION C Contractor shall provide surveillance, trapping, extermination and pesticide application components of the integrated pest management (IPM) program.	IPM INITIAL INSPECTION	Shall provide a thorough initial inspection of interior spaces, exterior grounds, and paved areas. Shall identify all areas including equipment, structural features or practices that contribute to pest infestation.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
	IPM PERIODIC INSPECTION	Shall conduct quarterly inspections to determine if treatment is required.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C	IPM PLANS	Shall obtain approval from the COR BEFORE treatment is rendered.	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
	NON-PESTICIDE PRODUCTS AND USE	Shall use non-pesticide methods of control whenever and wherever possible.	The Government may evaluate performance based

			on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.
SECTION C	CHILD CARE CENTERS	See Section C 'Child Care'	The Government may evaluate performance based on any or all of the following: tenant satisfaction, surveys, tenant interviews, periodic inspections, and service call documentation.

J.1.1. Contract Deliverables Reference

DELIVERABLE	REF	DELIVERABLE DUE	POINT OF CONTACT
Existing deficiency inspection/initial deficiency list	C.4.2	Report due not later than 60 calendar days after start date of the contract.	CO .
Contract Startup/Transition phase including staffing plan	C.5.1	One month of transition startup services.	CO .
Phase-out transition.	C.6	One month of phase-out transition services. On the last performance day of the contract, Contractor shall turn over keys and identification badges or cards.	CO .
List of key personnel and emergency contact information, which may include subcontractor contacts as applicable.	C.8.1	The Contractor shall develop and submit to the COR within 15 calendar days after contract award.	CO .
CMMS Complete CMMS Audit	C.8.5	The Contractor shall use the Government-furnished CMMS, to include validating and updating the	CO

		equipment inventory database, including all data fields specified by the CO . Complete yearly. CMMS audit Option B The Contractor shall provide all hardware and software to support and maintain an automated database of building maintenance and repair activities using a CMMS.	
Quality control program.	C.8.6	Develop and submit for approval 90 calendar days after contract award date.	CO
~~Building operating plan.~~	~~C.9.1, C.9.2~~	~~Develop and submit for approval, not later than the three (3) months after start date.~~	CO .
Radon mitigation program.	C.9.2	Program must be described in the building operating plan.	CO
Equipment inventory update.	C.10	The Contractor shall update and verify the equipment inventory annually after contract start date.	CO .
Monthly progress reports.	C.11	On a monthly basis, not later than the fifth working day of the subsequent month.	CO .
Performance review meetings	C.12	Monthly for three months the quarterly thereafter	CO
~~Equipment condition assessment.~~	~~C.13~~	~~On an ongoing basis during the performance of the contract as requested.~~	CO .
Review of design documents.	C.16	Review as requested.	CO .
Building management support services.	C.17	Assist as requested.	CO .
Inspection assistance for space build outs	C.18	Assist as requested.	CO
Emergency Operating Plan	C.21.4	Develop and submit for approval 15 calendar days after start of the contract.	CO .
~~Utility Meter Readings~~	~~C.21.6~~	~~Electric, gas, diesel fuel levels, water, cooling tower water make up and lawn sprinkler meters and submit in the monthly progress report~~	CO .
~~Energy and Water Efficiency Report~~	~~C.21.6~~	~~Monthly / Annually~~	CO

Emergency service request and callback repair plan report.	C.23.2, C23.3	Written accounting of any emergency callback the morning of the next working day.	CO .
Urgent Service Request	C.23.4	Respond to urgent service request within 1 hour.	CO
Routine service request - response extension request.	C.23.5	Contractor shall immediately notify with a written extension request.	CO .
Preventive maintenance system.	C.35.1	Within 15 calendar days after contract award date.	CO .
Initial report and development of water treatment program.	C.36.3	Within the first 15 calendar days after contract award date.	CO
~~Corrosion Monitoring of water treatment program coupon.~~	~~C.36.5~~	~~Within the 30 calendar days after contract start.~~	CO
Monthly water treatment testing or makeup water chemical tracking.	C.36.6	Monthly within the monthly progress report.	CO .
Periodic diesel fuel and periodic oil analysis.	C.37.4	At least annually, with results submitted within the next monthly progress report.	CO .
~~Lamps and ballasts containing mercury record.~~	~~C.38~~	~~Document monthly all purchases of mercury-containing lamps within the monthly progress report.~~	CO .
~~Painting: If the Contractor shall disturb materials he suspects may contain lead-based paint.~~	~~C.39.4~~	~~The Contractor shall immediately report the condition to the CO .~~	CO .
~~Elevator communications and alarm test~~	~~C.39.8.1~~	~~Document weekly elevator phone and alarm test and submit in monthly progress report~~	CO
Repairs using subcontractors.	C.40	Shall provide justification for subcontract need in advance.	CO .
~~Reimbursable repairs completion date.~~	~~C.40.3~~	~~Mutually agreed upon by the COR and the Contractor.~~	CO .
~~Miscellaneous work log~~	~~C.40.4~~	~~Submit in the monthly progress reports.~~	CO .
Warranties not honored by manufacturer.	C.40.10	Contractor shall immediately notify COR if an installer or manufacturer fails to comply with the terms of a warranty.	CO .
Scheduling and recordkeeping of permits, personnel safety, control of hazardous substances, certifications, and records	C.41.2	Furnish copies in monthly progress reports.	CO .
Refrigerant control and certification log.	C.41.3.1	Furnish copies in monthly progress reports.	CO .

AQMD operating permits.	C.41.4	Copies made available immediately upon request.	CO .
Polychlorinated biphenyl (PCB) control transformer leaks.	C.41.6	Immediate notification.	CO .
Workplace safety plan.	C.41.8	A safety and health plan shall be submitted for review and approval within 30 days after contract award date.	CO .
Electrical safety.	C.41.9	Deficiencies shall be reported within 12 months after contract award date. Infrared Survey to be submitted electronically every three years	CO .
Confined space entry permit system.	C.41.13	The contractor shall develop a confined space entry permit system for all permit-required confined spaces within 60 calendar days of the contract start.	CO .
Fire alarm system: If the contractor shall disturb materials they suspects may contain ACM.	C.41.14	The Contractor shall immediately report the condition to the COR.	CO .
Hazardous materials: material safety data sheets – hazardous materials inventory.	C.41.15.1	MSDSs shall be developed during the contract within 30 days after award and made available for review. The Contractor shall prepare and submit hazardous materials inventory as an appendix to the building operating plan. This shall be updated and resubmitted annually by September 30 of each year. No chemicals shall be brought on premise without first submitting the MSDS sheets to the COR for approval.	CO .
Boiler and unfired pressure vessel certification	C.41.16.1	Annually.	CO .
Backflow prevention devices – annual inspection certificate.	C.41.16.3	Annually.	CO .
Labeling and signage.	C.41.17	Labeling per OSHA standards during the performance of after contract.	CO .
Fire protection systems on line at all times unless approval is given during maintenance periods.	C.42.1	Advance notification and approval per occurrence.	CO .

Fire alarm system: If the contractor encounters equipment that is in a condition that may endanger life or property.	C.42.2	The Contractor shall immediately notify the COR of the condition requiring immediate action. Within 24 hours the Contractor shall provide a written report to the COR of the hazardous condition and recommended corrective action.	CO .
Fire alarm system: The contractor is responsible for meeting the inspection, maintenance, testing frequencies and testing methods outlined in NFPA 72.	C.42.2	Throughout the year. Annual Certification. Documentation of the subject inspection, maintenance and testing results shall be recorded on the applicable Inspection and Testing Form from NFPA 72.	CO .
Water-based fire suppression systems: If the Contractor encounters equipment that is in a condition that may endanger life or property.	C.42.6	The Contractor shall immediately notify the COR of the condition requiring immediate action. Within 24 hours that Contractor shall provide a written report to the COR of the hazardous condition and recommended corrective action.	CO .
Water-based fire suppression systems: The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, and testing methods outlined in NFPA 25.	C.42.6	Throughout the year. Documentation of the subject inspection, maintenance, and testing results shall be recorded on the applicable "suggested form," as found in the current edition of NFPA 25.	CO .
Water-based fire suppression systems: If the contractor shall disturb materials he suspects may contain ACM.	C.42.6	The Contractor shall immediately report the condition to the COR.	CO .
Fire doors and other opening protectives: The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in NFPA 80.	C.42.7	Throughout the year. Documentation of the subject inspection, maintenance, and testing results shall be recorded in accordance with the requirements of NFPA 80.	CO .
Fire and combination fire/smoke dampers: The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in NFPA 80.	C.42.8	Throughout the year. Documentation of the subject inspection, maintenance, and testing results shall be recorded in accordance with the requirements of NFPA 80.	CO .

Smoke doors and other opening protectives: The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in NFPA 105.	C. 42.9	Throughout the year. Documentation of the subject inspection, maintenance, and testing results shall be recorded in accordance with the requirements of NFPA 105.	CO or COR.
Smoke dampers: The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in NFPA 105.	C.42.10	Throughout the year. Documentation of the subject inspection, maintenance and testing results shall be recorded in accordance with the requirements of NFPA 105.	CO .
Portable fire extinguishers: The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in NFPA 10.	C.42.11	Throughout the year. Documentation of the subject inspection, maintenance, and testing results shall be recorded in accordance with the requirements of NFPA 10.	CO .
Non-water-based extinguishing systems: The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in the applicable NFPA standard.	C.42.12	Throughout the year. Documentation of the subject inspection, maintenance, and testing results shall be recorded in accordance with the requirements of the applicable NFPA standard.	CO .
Smoke control systems: The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in NFPA 92A.	C.42.13	Throughout the year. Documentation of the subject inspection, maintenance, and testing results shall be recorded in accordance with the requirements of NFPA 92A.	CO .
Smoke management systems: The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in NFPA 92B.	C.42.13	Throughout the year. Documentation of the subject inspection, maintenance, and testing results shall be recorded in accordance with the requirements of NFPA 92B.	CO .
Emergency and standby power systems: The Contractor is	C.42.14	Throughout the year. Documentation of the subject inspection, maintenance,	CO .

responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in NFPA 110 and NFPA 111.		and testing results shall be recorded in accordance with the requirements of NFPA 110 and NFPA 111.	
Emergency lighting and exit signage: The Contractor is responsible for meeting the inspection, maintenance, testing frequencies, testing methods, and documentation requirements outlined in NFPA 101.	C.42.15	Throughout the year. Documentation of the subject inspection, maintenance, and testing results shall be recorded in accordance with the requirements of NFPA 101.	CO .
Security Clearances	H.1.1	Shall be submitted prior to contract start date	CO .
Qualification of employees (May 1989) paperwork	H.1.3	As requested	CO .
The collection and submission of GSA Form 139, Recording Presence.	H.7	Available when requested	CO .
Asbestos awareness training certification.	H.13	Training within 60 calendar days after start date. Certify completion within 5 days of training.	CO .
Submission of resumes for new employees.	H.15.4	The Contractor shall submit resumes for all personnel prior to personnel beginning work.	CO .
State licensing – if required.	H.15.5	Within 90 calendar days of beginning employment.	CO .
Price proposal for additional services work.	H.18.2	Within 48 hours of the request.	CO or COR.
Strike contingency plan (SCP) submission.	H.20	SCP must be submitted 5 calendar days prior to Contract start date and updated annually.	CO .

J.2. GREEN PURCHASE REPORT

[[[Note: This list is not all inclusive, the Contractor shall expand the list as appropriate to reflect non bio-based items purchased and used under this Contract]]]

Non Bio-based Purchase Reports					
Report Period Covered:	Date Report Prepared:				
Building:					
Contract Number:					
Contractor:					
	Attributes and Cost				
	CPG	**Design for the Environment (DfE)**	**Green Seal**	**Env Choice**	**Not Green**
Hand cleaners and sanitizers					
Mulch and Compost					
Odor Control / Neutralizer					
Mobile equipment hydraulic oil			$400.00 (sample entry)		
Stationary equipment hydraulic oil					
Diesel fuel additives				$200.00 (sample entry)	
2-cycle engine oil					
Penetrating lubricants					
Greases					$100.00 (sample entry)
Sorbents					
Adhesives and mastics					
Towels					
General purpose de-icer					
Wood and concrete sealers	$3,500 (Sample Entry				

Resources Guide: Green Seal http://www.greenseal.org/FindGreenSealProductsAndServices.aspx
Design for the Environment (Design for the Environment (DfE)) http://www.epa.gov/Design_for_the_Environment_(DfE)/
EPA-CPG http://www.epa.gov/epawaste/conserve/tools/cpg/index.htm
SFtool Green Procurement - Cleaning Products - GSA Sustainable Facilities Tool sftool.gov

Green Purchase Report

Annual Contractor Reporting of Designated Biobased Purchases

Section 9002 of the Farm Security and Rural Investment Act of 2002, as amended by the Food, Conservation, and Energy Act of 2008, Pub. L. 110-246 (the Farm Bill) requires Federal agencies to give a procurement preference to USDA-designated biobased products and to require agency contractors to report such purchases under service and construction contracts. The FAR Council subsequently published a Biobased final rule at 77 FR 23365, implementing reporting requirement in the FAR at FAR 52.223-2, Affirmative Procurement of Biobased Products Under Service and Construction Contracts with an effective date of May 18, 2012. To facilitate collection of report data, the USDA, in consultation with the Chief Acquisition Officers Council, was tasked to develop a reporting template.

To comply with the reporting provisions of the Act, Contractor must file an annual report on purchases of designated biobased products used under the performance of this contract.

Where to Submit:

CY2012 – By December 31, 2012. For contracts that were awarded between May 18, 2012 and September 30, 2012 and which were reported to the Federal Procurement Data System – Next Generation (FPDS-NG), contractors shall submit via the following USDA site: http://www.biopreferred.gov/FARReporting/FARReporting.xhtml

Note: This is an interim reporting template and should be used only for contracts meeting the above criteria. Other contracts will not pass the system validation test.

Future Reports – No later than October 31st in accordance with USDA reporting procedures. Contractor is responsible for monitoring USDA progress on the development of a long-term reporting tool.

Note: Contractor is responsible for monitoring USDA progress on the development of a long-term reporting tool.

All Reports–Contractor shall provide a copy of each report to the CO and Environmental Manager at PBSbiobasedreporting@gsa.gov.

Note: US Department of Agriculture (USDA) Bio- based products
http://www.biopreferred.gov/ProductCategories.aspx

J.3. SOLID WASTE AUDITS

BUILDING NUMBER/NAME/CITY:					
POINT OF CONTACT:					
CONTAINER ID:					
MATERIAL COLLECTED:					
DUMPSTER SIZE (VOLUME (cy):					
REPORTING MONTH:					
CIRCLE DAY OF MONTH EMPTIED:	CIRCLE OBSERVED % FULL				
1	0%	25%	50%	75%	100%
2	0%	25%	50%	75%	100%
3	0%	25%	50%	75%	100%
4	0%	25%	50%	75%	100%
5	0%	25%	50%	75%	100%
6	0%	25%	50%	75%	100%
7	0%	25%	50%	75%	100%
8	0%	25%	50%	75%	100%
9	0%	25%	50%	75%	100%
10	0%	25%	50%	75%	100%
11	0%	25%	50%	75%	100%
12	0%	25%	50%	75%	100%
13	0%	25%	50%	75%	100%
14	0%	25%	50%	75%	100%
15	0%	25%	50%	75%	100%
16	0%	25%	50%	75%	100%
17	0%	25%	50%	75%	100%
18	0%	25%	50%	75%	100%
19	0%	25%	50%	75%	100%
20	0%	25%	50%	75%	100%
21	0%	25%	50%	75%	100%
22	0%	25%	50%	75%	100%
23	0%	25%	50%	75%	100%
24	0%	25%	50%	75%	100%
25	0%	25%	50%	75%	100%
26	0%	25%	50%	75%	100%
27	0%	25%	50%	75%	100%
28	0%	25%	50%	75%	100%
29	0%	25%	50%	75%	100%
30	0%	25%	50%	75%	100%
31	0%	25%	50%	75%	100%

BUILDING NUMBER/NAME/CITY:					
NUMBER OF TIMES AT % FULL (Circled)					
Multiplied by % FULL/100					
Multiplied by Entered DUMPSTER SIZE VOLUME (cy)					
Equals VOLUME COLLECTED (cy)					
Add VOLUMES COLLECTED (line above) = DUMPSTER MONTHLY TOTAL (cy) COLLECTED. NOTE: ENTER this TOTAL VOLUME in Building Worksheet as CONTAINER SIZE (VOLUME), ENTER 100% Full For AMOUNT, and ENTER LAST DAY of MONTH for DATE.					

J.4. SUMMARY OF ENVIRONMENTALLY PREFERABLE PRODUCT ATTRIBUTES

Product Use	Preferable Contents	Contents to Avoid	Non-toxic Optional	Biobased Optional
Adhesive - Aerosol	Rubber-based; low-VOC	SARA 313 chemicals (cyclohexane, hexane, methylene chloride); petroleum distillates; CFCs	ü	X
Adhesive - Epoxy	Non-toxic; low-VOC	Isopropyl alcohol; SARA 313 chemicals (toluene)	ü	X
Adhesive Remover	Soy-based mixture; citrus extract; low-VOC	Aerosol; petroleum distillates	ü	ü
Coil Cleaner	Non-acid cleaners with non-toxic, biobased contents; low-VOC; if acid must be used acetic or phosphoric acid are preferable	Sulfuric acid, hydrofluoric acid, or similar caustic chemicals. SARA 313 chemicals (trichloroethylene)	ü	ü
Concrete/Wood Sealer	Water-based, latex-based, or biobased sealers; low-VOC	Acrylonitrile; SARA 313 chemicals (n-methyl-2-pyrrolidone)	ü	ü
Degreaser	Water or biobased (soy) degreasers; non-toxic; non-aerosol; low-VOC	Aerosol; petroleum distillates	ü	ü
Deicer (Road and Windshield)	Biodegradable windshield deicer; salt-free ice melt; magnesium chloride or calcium chloride; calcium magnesium or magnesium acetate	SARA 313 chemicals (methanol, isopropyl alcohol, ethylene glycol); aerosol; sodium chloride	ü	ü
Descaler	Enzyme-based descaler; urea; trisodium phosphate; low-VOC	Hydrochloric (muriatic) acid or similar caustic compounds (oxatic or hydrofluoric acid); sodium hypochlorite	ü	ü
Fuel Additive	Biobased; non-toxic	Petroleum distillates	ü	ü
Graffiti Remover	Biobased content (soy/corn); low-VOC	SARA 313 chemicals (toluene, xylene); acetone; isopropyl alcohol	ü*	ü
Grease / Lubricant	Biodegradable/biobased content (soy or vegetable oil); non-toxic; re-refined lubricating oils; low-VOC	Petroleum or mineral-based oils; metallic soaps or polyurea derivatives; sulfur, chlorine, zinc; amine phosphate or other irritants	ü	ü
Light Bulbs	Energy Star or FEMP fluorescent bulbs or tubes; reduced mercury content	Mercury	n/a	n/a
Mastic	Water or acrylic-based; non-toxic; low-VOC	Petroleum-distillates (mineral spirits)	ü	X
Paint	Remanufactured or recycled paint; water-based or latex-based; low-VOC	Aerosol; oil-based (alkyd) paints (mineral spirits, aliphatic hydrocarbons); SARA 313 chemicals (toluene, xylene, ethyl benzene); acetone	ü	X
Paint Remover	Biobased; non-toxic; low-VOC	SARA 313 chemicals (n-methyl-2-pyrrolidone, methanol, methylene chloride); isopropyl alcohol	ü*	ü
Spray Foam	CFC-free; biobased (soy); low-VOC	HCFCs; SARA 313 chemicals (formaldehyde)	X	ü*

ü Product available and offered through GSA Advantage
ü* Product available, but not currently offered through GSA Advantage
X Product currently not available

Notes:
a - On the GSA Advantage website some environmental product indicators, such as 'Non-Toxic' and 'Biobased', are specified by the product vendor and have not been independently verified. Prior to procurement, it is important to examine the Material Safety

J.5. BUILDING INFORMATION SHEETS

Building information is included in the Equipment Inventory Spreadsheet

J.6. Monthly Report Template

[[[This template is provided for optional use and contains the minimum required reporting elements from the SOW. Regions may add requirements if applicable]]]



MONTHLY REPORT FOR :	
TASK ORDER/CONTRACTOR #:	
DATE OF REPORT:	
FOR PERIOD:	

PREPARED BY

NAME:	
TITLE:	
CONTRACTOR:	
PHONE NUMBER:	

1. STATUS OF ALL open WORKORDERS – ~~Attach copy of CMMS printout if available~~

2. EQUIPMENT out of service and repair status

3. ~~OPERATING SCHEDULE CHANGES~~

4. DESCRIPTION OF LOST TIME FOR ACCIDENTS OR OTHER SAFETY PROBLEMS

5. QUALITY CONTROL INSPECTIONS

6. ~~BUILDING SERVICES, UTILITY MISCELLANEOUS HOURS~~

7. ~~COPIES OF ARRIVAL AND DEPARTURE REPORTS~~

8. MONTHLY WATER TREATMENT AND OTHER TEST RESULTS

~~9. RECALIBRATION DOCUMENTATION OF ADVANCED METERS (2 X/yr)~~

10. REFRIGERATION CONTROL LOGS

11. FUEL LEVELS

J.7. BUILDING OPERATING PLAN TEMPLATE

RESERVED

J.8. SMART BUILDING

Reserved

Water Treatment Standards

INSTRUCTIONS, CONDITIONS, AND NOTICES TO

Table of Contents

1.0 INTRODUCTION

2.1 **TYPES OF RECIRCULATING WATER LOOPS**

2.2 OPEN LOOP COOLING WATER SYSTEM
2.3 CLOSED LOOP COOLING WATER SYSTEMS
2.4 STEAM AND CONDENSATE RECIRCULATION SYSTEMS
2.5 CLOSED LOOP HOT WATER SYSTEMS
2.6 DOMESTIC HOT AND COLD WATER SYSTEM

3.1 **WATER CHEMICALS TREATMENT ADDITIVES**

3.2 MINERAL SCALE INHIBITOR
3.3 CORROSION INHIBITOR
3.4 BACTERIA CONTAMINATION CONTROL
3.5 GENERAL FOULING INHIBITOR
3.6 OXYGEN CORROSION CONTROL
3.7 GENERAL CORROSION CONTROL
3.8 CONDENSATE CORROSION CONTROL

4.1 **SETTING UP A WATER TREATMENT PROGRAM**

4.2 OPEN LOOP COOLING WATER SYSTEMS
4.3 CLOSED LOOP COOLING AND HOT WATER SYSTEMS
4.4 STEAM AND CONDENSATE RECIRCULATION SYSTEMS

5.1 **WATER SYSTEM TESTING**

5.2 WATER SAMPLING
5.3 COMMON WATER CHEMISTRY TESTS
5.4 MAINTENANCE PARAMETERS

6.1 **ALTERNATIVES TO CHEMICAL WATER TREATMENT**

6.2 PULSED ELECTROMAGNETIC FIELDS
6.3 OZONE GENERATORS

1.0 Introduction

This appendix establishes mandatory standards for water in HVAC and domestic water systems in GSA facilities, along with information related to the intent of the standards and guidelinies that in most circumstances can be used to construct a water treatment program that will be approved by GSA. Treatment standards are mandatory; procedural instructions in these guidelines are advisory unless required by law or regulation. Subject to GSA approval, maintenance contractors generally may propose alternative programs where accompanied with sufficient technical data and implementation detail for GSA to determine the likelihood of success of such an alternative program. Any program approved by GSA may be subsequently disapproved if results are unsatisfactory.

Regardless of the complexity or size of a loop, a qualified water treatment contractor or personnel should be consulted or employed to help the building maintenance personnel develop a water treatment program specific to the needs of each system. The treatment chemicals themselves should be purchased through a licensed supplier that specializes in commercial and/or industrial water systems. Many water treatment chemicals require licenses for specific uses and are regulated by federal, state and local governments. Maintenance contractors are responsible for selecting and submitting for approval an appropriate program, and for compliance with laws regarding chemical discharge and usage.

Maintenance contractors are responsible for providing all instrumentation and test equipment necessary to monitor compliance with these standards (e.g., installation of coupon racks or other corrosion monitoring equipment where not already installed).

2.1 Types of Recirculating Water Loops

There are five basic open and closed loop water systems used for the daily operation of commercial buildings. Each system is vital to the everyday operation of the buildings mechanical systems. The following open and closed loop water systems are described as follows;

2.2 Open Loop Cooling Water System

An open loop cooling water system generally uses cooling towers to cool condenser water that serves chilled water central plants, water source heat pumps and computer room air conditioning units. There are cases where a waterside economizer “free cooling” system is used in place of a chiller to cool condenser water during periods of low ambient conditions. During “free cooling” mode the chilled condenser water is passed through a heat exchanger to cool the closed loop cooling or chilled water loop.

An open loop is exposed to outside contaminants and requires frequent maintenance, chemical tests, and chemical treatment that should be determined by a water treatment contractor. In general, large systems require chemical tests be preformed weekly and a water treatment contractor to inspect the chemical systems monthly. The four main goals of maintaining an open loop cooling system are; inhibition of mineral scale, corrosion, minimizing bacteria contamination, and general fouling inhibition. See Section 3.0 for a detailed description of cause and effect when using chemical inhibitors.

2.3 Closed Loop Cooling Water Systems

A closed loop cooling water system can either be used for chilled water or condenser water. In a closed loop chilled or condenser water system the cooling water is circulated through the chiller or

heat exchanger where it is cooled then pumped through air handlers' cooling coils, fan coil units, computer rooms units, water source heat pumps…etc.

In view of the fact that a closed loop cooling water system will not be exposed to as much outside containments and no evaporation as in an open loop system, the dissolved mineral concentration in the system will remain relatively constant and there will be virtually no need for blowdown. Once the system is filled, every effort should be made to limit the amount of water leakage from seals, water sampling, valve testing and other routine system maintenance. When water leaks out of the system, it will be replaced with untreated makeup water. This water introduces additional minerals and dissolved oxygen into the system. Consistent chemical treatment is sustained with the use of chemical tablet "slug" feed water treatment products.

The treatment program for closed loop cooling water systems requires less frequent testing. The goal of the closed loop program is to inhibit corrosion, inhibit mineral scale formation, and inhibit bacteria growth. See Section 3.0 for a detailed description of cause and effect when using chemical inhibitors.

2.4 Steam and Condensate Recirculation Systems

Steam systems are closed loop systems that produce either saturated low pressure or superheated high-pressure steam via a steam boiler. The condensate water, with the addition of make up water, is recirculated through the steam boiler. A steam system should have an automated water makeup, a mechanical deaerator, condensate pumps, feed water pumps, steam traps, low feed water flame cut off controls and chemical pot feeders for condensate and makeup water treatment. The steam system will be a collection of steam regulators, steam turbines, heat exchanges for heating purposes, or through an absorption chiller to indirectly produce chilled water for space cooling.

The evaporation of water and elevated temperatures cause most of the minerals present in tap water to bond with each other, causing an increase in system mineral concentration. The four main goals to maintaining a steam system is prevention of mineral scale formation, oxygen corrosion, general corrosion, and condensate corrosion. Biocides are not needed in a steam system because bacteria do not grow in high temperature environments. Alternatively, if steam is supplied by a local utility, then the steam has already been chemically treated and further chemical treatment may not be necessary. See Section 3.0 for a detailed description of cause and effect when using chemical inhibitors.

2.5 Closed Loop Hot Water Systems

A closed loop hot water heating system is not exposed to a great deal of outside containments. Therefore the dissolved mineral concentration in the system will remain relatively constant and there will be virtually no need for blowdown. Once the system is filled, every effort should be made to limit the amount of water leakage from seals, water sampling, valve testing and other routine system maintenance. When water leaks out of the system, it will be replaced with untreated makeup water. This water introduces additional minerals and dissolved oxygen into the system. Consistent chemical treatment is sustained with the use of slug feed water treatment products.

The treatment program for this system is very similar to the closed loop cooling system. The key difference is that hot water systems require more corrosion inhibitor as a result of higher water temperatures. In fact most hot water systems require two to three times the corrosion inhibitor of closed loop cooling water systems. The goal of a closed loop hot water treatment program is to

inhibit corrosion, mineral scale formation, and bacteria growth. See Section 3.0 for a detailed description of cause and effect on using chemical inhibitors.

2.6 DOMESTIC HOT AND COLD WATER SYSTEM

A domestic hot and cold water system provides potable water for washing and general domestic use. The water within these systems will contact food, people or will be consumed, so there is no chemical treatment used for this system to prevent mineral scale or corrosion due to water supplied by the local utility. The only water treatments used for these systems is the addition of water softeners and filtration systems. The reduction of the corrosive and scaling tendencies of oxygenated hard or softened water is done by repairing leaky fittings and fixtures, limiting the velocity of the circulating water, and/or limiting the operating temperature of the hot water system.

3.1 WATER CHEMICALS TREATMENT ADDITIVES

Environmental regulations, handling guidelines and the chemical additives for water systems should be provided by a certified local water treatment consultant. It is the building operator's responsibility to ensure compliance with municipal by-laws, and environmental regulations when disposing of chemicals and handling accidental spills. Disposing of chemically treated water into the sewer system shall be monitored in blowdown logs and not allowed to exceed levels specified by municipal sewage utility by-laws.

The chemical additives suggested herein are organized by class to encompass a variety of chemical additives that are used in open and closed water loops and steam boiler systems.

3.2 Mineral Scale Inhibitor

Mineral scale is the precipitation of dissolved minerals such as calcium carbonate onto the surfaces of the cooling tower, boiler, heat exchangers tubes, and piping. This mineral scale forms an insulating layer on the surfaces that inhibits heat transfer and restricts flow through the system. Mineral scale also promotes corrosion and fouling in open loop and steam systems. All recirculating water and steam boiler systems should have a mineral scale inhibitor as part of their water treatment program.

Mineral scale inhibitors are separated into two main categories, sludge conditioners and dispersants. Sludge conditioners are typically used when there is a relatively high concentration of calcium and magnesium in the makeup water. Sludge conditioners are crystal modifiers that allow the minerals to precipitate but interfere with the structure of the crystal to help form a soft sludge that can be easily removed from the steam boiler or cooling tower through blowdown. Dispersants are usually polymer-based molecules that help to keep the trace minerals in solution so that they do not precipitate into scale deposits. The mineral scale inhibitors are especially needed when there is little or no pretreatment of the makeup water or when filtration equipment is not reliable. Even with excellent control of the scale inhibitor chemicals scale formation still occurs.

Water treatment consultants use computer models to determine the type of scale inhibitor needed as well as the limits for system pH and total dissolved solids (TDS). These computer models take into account the specific operating parameters of the system and help the water treatment consultant to choose a specific water treatment program that will work.

Open Loop Cooling Water System:

An open recirculating cooling water treatment program commonly uses a chemical additive that is a combination of a mineral scale inhibitor and a corrosion inhibitor. The type and dosage of mineral scale inhibitor needed is dependant upon the concentration and composition of the minerals in the makeup water, the pH of the cooling water, and the temperature of the cooling water.

The overall scale inhibitor program for a cooling water system may consist of a mineral scale inhibitor additive (such as a polymer dispersant), acid for pH control, and limits for the total dissolved solids and/or conductivity of the cooling water. Acid feed and pH control will not be needed in every system.

Steam Systems with Recirculating Water:

In steam boilers the build up of an insulating layer can lead to tube failure and efficiency losses. Calcium and magnesium are the most abundant forms of mineral scale found in a steam boiler system because the solubility of these two minerals decreases as the temperature increases. To minimize the potential for mineral scale formation, most steam boilers have some type of makeup water pretreatment to remove certain minerals from the water before it enters the boiler. The goal of most pretreatment equipment is to minimize the concentration of these two minerals in the makeup water so that there is a less significant chance that they will precipitate and form a crystal scale deposits. Even with good pretreatment, mineral scale inhibitors are needed in all steam boiler systems.

Dispersant mineral scale inhibitor programs are used in steam boilers that have good pretreatment and very low levels of calcium and magnesium in the makeup water. Dispersants are usually only used when the total hardness in the makeup water is greater than 5 ppm consistently. The dispersants are usually a polymer based molecule that helps keep the trace minerals in solution so that they do not precipitate into scale deposits.

Closed Loop Cooling Water and Hot Water (Heating) Systems

In a closed loop system the mineral concentration is relatively stable because very little makeup water is needed. This helps to minimize the need for mineral scale inhibitors. In systems that have poor quality makeup water, with a total hardness above 300 ppm, it is best to pre-treat the water with softeners to remove calcium and magnesium from the makeup water. In most cases pretreatment of the makeup water is not necessary. Closed loop cooling and hot water systems should be treated with a polymer dispersant mineral scale inhibitor. This scale inhibitor is usually combined with a corrosion inhibitor in a one-drum formulation.

3.3 Corrosion Inhibitor

Open Loop Cooling Water Systems:

The corrosion inhibitor chemical treatment protects the metal piping from degradation over time. The type of corrosion inhibitor that is used depends upon the specific metallurgy present in the system as well as the chemistry of the makeup water and pH level in the water. Corrosion inhibitor additives are intended to provide a protective layer on the interior walls of piping which stops the occurrence of corrosion in the system. A certified chemical water treatment consultant should be contacted to determine the specific type and amount of corrosion inhibitor necessary for each building's distinct system.

In most cases, there is more than one type of metallurgy in a system, such as galvanized steel, copper, stainless steal …etc. Different metals require distinct chemicals to prevent corrosion, so it is important that the corrosion inhibitor portion of the program have additives that are specific to each type of metal. In most cases, blends of different corrosion inhibitors are used to ensure that all of the metal is protected.

Closed Loop Cooling and Hot Water Systems

Corrosion is the principal concern in a closed loop cooling and hot water systems. There are many different types of corrosion inhibitors available on the market, but the most common products are nitrite based. As with any corrosion inhibitor program, the type of program used is determined by the type of metals used throughout the system. Mild steel systems should be treated with nitrite, molybdate, or phosphonate type inhibitors. Systems containing copper should have some type of azole product.

If bacteria contamination is a problem, Nitrite programs should be avoided. The nitrite corrosion inhibitor can act as a food source for bacteria. The bacteria will convert the Nitrite into Nitrate and Ammonia. This will destroy the corrosion inhibitor function of the product. A certified chemical water treatment consultant will be able to find the best product for this type of system.

There is one difference between a closed loop cooling and heating systems which is the dosage of the corrosion inhibitor. The corrosion inhibitor of closed loop hot water system will have dosage 2 – 3 times greater than the dosage for a closed loop cooling water system.

3.4 Bacteria Contamination Control

The control of the bacteria growth is the most important part of an open loop cooling and closed loop cooling and hot water treatment program because bacteria contamination can lead to fouling, mineral scale, and corrosion. Bacteria contamination is controlled through the use of biocides. Below is a description on bacteria contamination control that is used for open loop cooling, closed loop cooling and closed loop hot water systems.

Open Loop Cooling Water Systems

Open loop cooling water systems are inherently prone to bacteria contamination without a proper water treatment. High bacteria levels in a cooling water system can lead to bio-deposits (algae for example) and increased fouling that can reduce heat transfer in the heat exchangers and cooling tower. The bio-deposits and increased fouling can reduce water flow through the system if there is improper water treatment.

In view of the fact that open cooling water systems are highly susceptible to bacteria growth, the water treatment program should have some type of biocide chemical additive. Biocides kill living organisms and/or bacteria and can be categorized as either oxidizing or non-oxidizing. An oxidizing biocide, when applied at the correct dosage, will kill all types of bacteria. A non-oxidizing biocide targets certain bacteria and will not kill some types of bacteria.

A non-oxidizing biocide can be compared to an Anti-biotic that is used to treat bacterial infections in people. Over dosing a system or improper usage of a non-oxidizing biocide can create strains of bacteria in the cooling water system that are resistant to the biocide. Limit the program to the use of non-oxidizing biocides alone is never recommended. It is good practice to utilize both an

oxidizing biocide and a non-oxidizing biocide to strictly control bacteria contamination. This method is more costly so some building managers chose to only utilize only oxidizing biocides.

The types of oxidizing biocide needed are dependant upon the physical limitations of the facility, safety concerns, costs, and maintained pH of the recirculation water. For example, bromine based oxidizing biocides should be used any time the pH of the water in the system is above 7.5. A water treatment supplier or consultant can provide specific information regarding the different types of oxidizing and non-oxidizing biocides that will suit the needs of your system.

It is important to note that there are both federal and state laws that regulate the usage and application of biocides for commercial and industrial usage. When choosing a water treatment supplier or consultant, make sure that they are properly licensed and registered in your area to provide guidance on the usage of biocides or pesticides. Also, it is important that you only use biocide products that are specifically approved for use in an open loop cooling water system.

Closed Loop Cooling and Hot Water Systems

It is not uncommon for closed loop systems to experience bacteria contamination, especially if these systems are treated with nitrite. In general, the more makeup water a system needs, the more likely that system is predisposed to bacteria problems.

If a closed loop system has a bacteria problem or will not maintain a nitrite residual, there are basically two options to correct the problem. The first solution is to switch the corrosion Inhibitor program to a program that does not contain a food source for bacteria. The second best solution is to utilize non-oxidizing biocides to treat the bacteria problem. A non-oxidizing biocide should be used in a closed loop system because they do not react with the corrosion inhibitors and they do not promote corrosion themselves. An oxidizing biocide will degrade most corrosion inhibitors and they can increase corrosion rates in a closed loop system. It is always best to contact a licensed water treatment consultant that can help you to determine the dosages of biocide needed and which biocide will work for your system.

3.5 General Fouling Inhibitor

A fouling inhibitor is added to an open loop cooling water system when the makeup water contains high levels of suspended particles or turbidity. This includes high levels of dirt, silt, Iron, or other colloidal particles present in the makeup water, which occurs in rare applications. If this is the case, it may be necessary to add a fouling inhibitor additive to the system. These inhibitors are similar to mineral dispersants but are designed to target suspended particles instead of dissolved minerals. Generally, the mineral dispersant treatment program will be sufficient to provide general system fouling inhibition. If the mineral dispersants are not sufficient, contact a licensed water treatment consultant to see if a fouling inhibitor is needed for the system.

3.6 Oxygen Corrosion Control

Steam Systems with Condensate Recirculation

Due to the high temperatures produced by a steam boiler plant, the corrosive reaction between oxygen and carbon steel is greatly increased. The oxygen corrosion in a steam system usually causes internal pipe pitting and can lead to pipe failures and leaks very rapidly. In order to protect the steam system metal from oxygen pitting, it is very important to remove the oxygen from the makeup water using both mechanical deaeration and chemical processes.

At room temperature, water normally contains about 9 ppm of dissolved oxygen. As the temperature of the water is increased the solubility of oxygen in the water decreases. A mechanical deaerator is designed to raise the temperature of the feed water to just below boiling so that the oxygen concentration in the water drops from 9 ppm to less than 0.05 ppm. After the makeup water is mechanically depleted of its oxygen content, it is still necessary to reduce it further. The further reduction in oxygen content is done with an oxygen scavenger chemical, which will reduce the concentration of oxygen to levels below 0.005 ppm.

There are many different types of chemicals used as Oxygen Scavengers. The most common Oxygen Scavenger is Sodium Bi-Sulfite. Contact a licensed water treatment consultant that will decide what product meets all the needs of a given steam system.

3.7 General Corrosion Control

Steam Systems with Condensate Recirculation

A steam system should include an Oxygen corrosion control treatment program along with a general system corrosion control treatment program. A general corrosion control chemical treatment program includes the addition of buffering agents to the boiler feed water to minimize the potential for corrosion throughout the system. This buffering agent is frequently in the form of alkali solution. The alkali species neutralize acids in the water and raise the pH to create a slightly Basic environment that is less corrosive to the metal piping.

Some makeup water has enough natural alkalinity and is able to provide the feed water system with sufficient buffering, to keep the pH of the steam boiler feed water at or above 10.2. When there is not enough natural Alkalinity in the steam boiler feed water, a Caustic chemical should be added to raise the pH above 10.2. A water treatment consultant will be able to test the feed water in the steam system to determine if Caustic feed is needed and what dosage is necessary to raise the pH above 10.2.

3.8 Condensate Corrosion Control

Steam Systems with Condensate Recirculation

The feed water is heated to produce high or low-pressure steam by the boiler, when this occurs some of the alkali solution species will breakdown into Carbon Dioxide (CO_2) gas. The CO_2 vapor produced will leave the steam boiler, along with the steam and is dissolved into the condensed condensate water after the energy from the steam is utilized. As the CO_2 dissolves into the condensate water it produces a carbonic acid and will dramatically increase the corrosiveness of the condensate return water. In order to protect the condensate return piping from corrosion, the condensate shall be feed with corrosion control chemicals.

The two most common types of condensate water treatment are neutralizing and filming chemical additives. A neutralizing chemical additive will neutralize the Carbonic Acid in the condensate water and raise the pH above acidic levels. A filming chemical additive will provide a protective layer on the interior of the piping to keep the condensate return water from actually touching the metal. In most cases a neutralizing chemical additive will tend to be slightly more expensive, but these chemicals are usually more effective.

There are limitations to the type of condensate treatment implemented for steam systems. For example there are certain treatment programs are restricted if the steam is used for food

preparation or direct contact humidification, a treatment product that is approved for use with food preparation or direct contact humidification should be used. Contact a licensed water treatment consultant or supplier for more information regarding which products can be used and for which systems these chemicals are allowed.

4.1 Setting Up a Water Treatment Program

The most important step to setting up a water treatment program is to know what systems are present in the building and what are the requirements for water properties such as pH, conductivity, total dissolved solid (TDS), etc. The water property ranges, definitions and testing schedules are in section 5. Many of these water chemistry properties can be monitored using stand-alone controllers or global building automation system (BAS) controls. A licensed water treatment consultant should be employed to model the building's water systems and develop an appropriate treatment plan for each system. There are many treatment plans available; below is a summary of typical plans used for each system, which are used by water treatment consultants in the United States.

4.2 Open Loop Cooling Water Systems

Monitoring conductivity as a measurement of the concentration of Total Dissolve Solids (TDS) is a crucial part of controlling an open loop water system. Conductivity limits should be set by a water treatment consultant and routinely monitored to ensure that mineral scale does not form. Cycles of concentration of the system should not exceed limits set by water treatment consultant. Automated blown down controls with a conductivity meter is recommended for open loop systems. The pH of the water should be routinely monitored especially if an acidic additive is used to control the pH. Corrosion inhibitor residual tests should also be run to verify that the system is receiving the correct dosage. Routine tests should be conducted daily, weekly or monthly to monitor oxidizing biocide residuals and bacteria concentrations to ensure Micro-Bio levels are under control. In general, bacteria concentrations in the open loop cooling water system should be less than 100,000 cfu/ml (colony forming units per milliliter) at all times.

Corrosion Monitoring should be performed using a real time on-line monitoring device or corrosion coupons with a 90-day rotation schedule. Coupon test results should show mild steel corrosion rates less than 5.0 mils per year (MPY) and Copper Corrosion Rates less than 2.0 MPY at all times.

Recommended Corrosion and Scale Control Programs

Program 1:

Description:	Multifunctional Molybdate Based Corrosion Inhibitor and Dispersant
Function:	Corrosion Inhibition, Mineral Scale Inhibition
Components:	Molybdate for Mild Steel Corrosion Control
	Azole for Copper Corrosion Control
	Dispersant for Mineral Scale Inhibition

Form:	Liquid
Feed Location:	Tower Basin or Header
Control Tests:	Molybdate Residual or Test for Tracing Agent if present, Corrosion Monitoring

Program 2:

Description:	All Organic Based Multifunctional Corrosion Inhibitor and Dispersant
Function:	Corrosion Inhibition, Mineral Scale Inhibition
Components:	Phosphonate for Mild Steel Corrosion Control Azole for Copper Corrosion Control Dispersant for Mineral Scale Inhibition
Form:	Liquid
Feed Location:	Tower Basin or Header
Control Tests:	Organic Phosphate Test or Test for Tracing Agent if present, Corrosion Monitoring

Program 3:

Description:	Zinc Phosphate Multifunctional Corrosion Inhibitor and Dispersant
Function:	Corrosion Inhibition, Mineral Scale Inhibition
Components:	Zinc and Phosphate for Mild Steel Corrosion Control Azole for Copper Corrosion Control Dispersant for Mineral Scale Inhibition
Form:	Liquid
Feed Location:	Tower Basin or Header
Control Tests:	Ortho-Phosphate or Test for Tracing Agent if present

Program 4:

Description:	Stabilized Phosphate Corrosion Inhibitor and Dispersant
Function:	Corrosion Inhibition, Mineral Scale Inhibition
Components:	Phosphate for Mild Steel Corrosion Control Azole for Copper Corrosion Control Dispersant for Mineral Scale Inhibition

Form:	Liquid
Feed Location:	Tower Basin or Header
Control Tests:	Ortho-Phosphate or Test for Tracing Agent if present, Corrosion Monitoring

Bacteria Control Programs

Program 1:

Description:	Chlorine Bleach Oxidizing Biocide
Function:	Oxidizing Biocide
Components:	Sodium Hypochlorite
Form:	Liquid
Feed Location:	Tower Basin
Control Tests:	Free Chlorine Residual, Bacteria Monitoring

Program 2:

Description:	Stabilized Chlorine Oxidizing Biocide
Function:	Oxidizing Biocide
Components:	Stabilized Sodium Hypochlorite
Form:	Liquid
Feed Location:	Tower Basin
Control Tests:	Free Chlorine Residual, Bacteria Monitoring

Program 3:

Description:	Activated Bromine Oxidizing Biocide
Function:	Oxidizing Biocide
Components:	Separate Feed of Sodium Hypochlorite Separate Feed of Sodium Bromide
Form:	Both Liquid
Feed Location:	Mix together in feed line to activate Bromine then feed to Tower Basin
Control Tests:	Free Chlorine Residual, Bacteria Monitoring

Program 4:

Description:	Stabilized Bromine Based Oxidizing Biocide
Function:	Oxidizing Biocide

Components:	Stabilized Bromine
Form:	Liquid
Feed Location:	Tower Basin
Control Tests:	Free Chlorine Residual, Bacteria Monitoring

Program 5:

Description:	Solid Chlorine Bromine Tablets
Function:	Oxidizing Biocide
Components:	Chlorine and Bromine
Form:	Solid Tablet
Feed Location:	Fed from pot feeder to Tower basin
Control Tests:	Free Chlorine Residual, Bacteria Monitoring

Program 6:

Description:	Solid Chlorine Bromine Tablets
Function:	Oxidizing Biocide
Components:	Chlorine and Bromine
Form:	Solid Tablet
Feed Location:	Fed from pot feeder to Tower basin
Control Tests:	Free Chlorine Residual, Bacteria Monitoring

Program 7:

Description:	Isothiazoline
Function:	Non-Oxidizing Biocide
Components:	Isothiazoline
Form:	Liquid
Feed Location:	Slug fed to tower basin
Control Tests:	Bacteria Monitoring

Program 8:

Description:	Glutaraldehyde
Function:	Non-Oxidizing Biocide
Components:	Glutaraldehyde
Form:	Liquid
Feed Location:	Slug fed to tower basin

Control Tests:	Bacteria Monitoring

Program 9:

Description:	DBNPA
Function:	Non-Oxidizing Biocide
Components:	Dibromonitropropianamide
Form:	Liquid
Feed Location:	Slug fed to tower basin
Control Tests:	Bacteria Monitoring

Program 10:

Description:	Quaternary Amine
Function:	Non-Oxidizing Biocide
Components:	Quaternary Amine
Form:	Liquid
Feed Location:	Slug fed to tower basin
Control Tests:	Bacteria Monitoring

Program 11:

Description:	MBT
Function:	Non-Oxidizing Biocide
Components:	Methylene-bis-thiocyanate
Form:	Liquid
Feed Location:	Slug fed to tower basin
Control Tests:	Bacteria Monitoring

4.3 Closed Loop Cooling and Hot Water Systems

General guidelines for the control of a closed loop cooling or hot water system include the monitoring of the conductivity, pH, corrosion, and micro bio levels. Water chemistry limits should be set by a water treatment consultant and routinely monitored by maintenance personnel to ensure that mineral scale and corrosion does not occur. Automated make up water controls along with a makeup water meter should be added to the system to maintain a consistent amount of water. The pH of the water should be routinely monitored especially if an acidic additive is used to control the pH. Corrosion inhibitor residual tests should also be run to verify that the system is receiving the correct dosage. Monthly monitoring of bacteria concentrations to ensure biological organism levels are under control. If biological organism levels are above recommended levels, there could be a point where oxygen is entering the system, i.e. a leak in the system. Corrosion monitoring should be done with iron or copper corrosion coupons with a six month rotation schedule. Coupon

test results should show mild steel corrosion rates less than 0.5 mils per year (MPY) and Copper corrosion rates less than 0.2 MPY at all times.

Recommended Corrosion and Scale Inhibition Programs

Program 1:

Description:	Multifunctional Molybdate Based Corrosion Inhibitor and Dispersant
Function:	Corrosion Inhibition, Mineral Scale Inhibition
Components:	Molybdate for Mild Steel Corrosion Control Azole for Copper Corrosion Control Dispersant for Mineral Scale Inhibition
Form:	Liquid
Feed Location:	Slug feed with Pot Feeder
Control Tests:	Molybdate Residual or Test for Tracing Agent if present, Corrosion Monitoring

Program 2:

Description:	Multifunctional Nitrite Based Corrosion Inhibitor and Dispersant
Function:	Corrosion Inhibition, Mineral Scale Inhibition
Components:	Nitrite for Mild Steel Corrosion Control Azole for Copper Corrosion Control Dispersant for Mineral Scale Inhibition
Form:	Liquid
Feed Location:	Slug feed with Pot Feeder
Control Tests:	Nitrite Residual or Test for Tracing Agent if present, Corrosion Monitoring

4.4 Steam and Condensate Recirculation Systems

The water treatment program for a steam and condensate recirculation system should include monitoring for conductivity. Proper Conductivity limits will vary slightly depending upon the type, age, and size of the steam boiler system. The absolute maximum conductivity level for any steam system is 5,500 μmhos.

The alkalinity concentration in the steam boiler should routinely be monitored my maintenance personnel. There two main types of alkalinity measured in a steam system total (M)-Alkalinity and hydroxide (OH)-alkalinity. The P-alkalinity test is used to measure the portion of M-alkalinity contributed to by Hydroxide (OH)-alkalinity. Barium chloride is added to water samples

containing OH-alkalinity then sulphuric acid is added to neutralize the OH, alkalinity is then measured to show the change in alkalinity due to the elimination of OH molecules. P-Alkalinity is used to monitor the condensate return system, to avoid corrosion within the steam boiler OH-alkalinity is measured. Proper chemical dosage for the steam boiler is ensured by running routine chemical residual tests for the oxygen scavenger and internal scale inhibitor.

In addition it is very important to monitor the chemistry of the steam boiler's feed water. Maintenance personnel should test the conductivity of the feed water on a regular basis. If make up water pretreatment is exists, Maintenance personnel should also test the total hardness level of the teed water.

The remaining tests to be conducted on condensate return for filming Amine residual, or Iron concentration and the condensate pH should be tested to ensure that the system has received the proper chemical dosage. Further test can be conducted by a water treatment consultant to determine if dosages should be altered to maintain proper steam, makeup and feed water chemistry.

Recommended Oxygen Scavengers

Program 1:

Description:	Sulfite
Function:	Chemical Oxygen Scavenger
Components:	Catalyzed Sodium Sulfite
Form:	Liquid or Powder
Feed Location:	Deaerator Drop Leg or Storage Section
Control Tests:	Residual Sulfite

Program 2:

Description:	Volatile Oxygen Scavenger
Function:	Chemical Oxygen Scavenger
Components:	Various Types Available
Form:	Liquid
Feed Location:	Deaerator Drop Leg or Storage Section
Control Tests:	DEHA Residual

Recommended Scale Control Programs

Program 1:

Description:	Precipitating Phosphate
Function:	Sludge Conditioner
Components:	Phosphate

Form: Liquid

Feed Location: Boiler Steam Drum or Feedwater line

Control Tests: Conductivity, P Alkalinity, M Alkalinity, OH Alkalinity, Silica, Ortho-Phosphate,

Visual Color Test

Program 2:

Description: Polymer Dispersant

Function: Mineral Dispersant

Components: Polymer

Form: Liquid

Feed Location: Boiler Steam Drum or Feedwater line

Control Tests: Feedwater Hardness, Polymer Residual, Silica, OH-Alkalinity, Tracing Agent if available

Program 3:

Description: Chelant

Function: Sludge Conditioner

Components: EDTA Chelant

Form: Liquid

Feed Location: Boiler Steam Drum or Feedwater line

Control Tests: Feedwater Hardness, Chelate Residual, Silica, O-Alkalinity, Tracing Agent if available

Recommended Condensate Corrosion Control

Program 1:

Description: Neutralizing Amine

Function: Raise pH of Condensate

Components: Various Types

Form: Liquid

Feed Location: Steam Header or Boiler Steam Drum

Control Tests: Condensate pH, Condensate Iron

Program 2:

Description: Filming Amine

Function:	Provide Protective Barrier for Condensate Piping
Components:	Various Types
Form:	Liquid
Feed Location:	Steam Header or Boiler Steam Drum
Control Tests:	Filming Amine Residual, Condensate Iron

Recommended General Corrosion Control (Steam Drum)

Program 1:

Description:	Caustic
Function:	Increase Alkalinity
Components:	Sodium or Potassium Hydroxide
Form:	Liquid or Powder
Feed Location:	Deaerator storage or Boiler Steam Drum
Control Tests:	O-Alkalinity

5.1 Water System Testing

Routine water chemistry tests play an important role in maintaining building water systems; they can be used to anticipate and prevent water's capacity to accelerate fouling, scaling and corrosion within a mechanical system. Chemical test kits for each building water system are available through most water treatment chemical suppliers or consultants. Section 5.2 lists the most common water tests used and a water treatment consultant can determine if a system requires more rigorous tests.

5.2 Water Sampling

When water samples are taken they should be isolated from large amounts of mineral buildup, incoming feed water or makeup water and chemical feed points. Samples should be collected during normal operation before system blowdown and chemical dosing. When collecting water allow the samples container to overfill and to avoid sample contamination use sampled water to rinse cap or container. Label the container appropriately and test sample as soon as possible. A licensed water treatment consultant will be able to give advice on chemical testing. However, building maintenance staff should be familiar with specific test procedures that should be provided by the chemical test equipment supplier(s).

5.3 Common Water Chemistry Tests

Conductivity:

This test is used to estimate the Total Dissolved Solids (TDS) concentration in a water sample. Conductivity is the measures of electrical conductance in the water. In general 1.0 umhos of conductance is equal to 0.67 ppm of total dissolved solids or minerals. High levels of conductivity increase the scaling potential of the system which depends on water temperature, composition of dissolved solids and interaction with other chemical additives, and the system's metallurgy.

Cycles of concentration for a water system is measured as the ratio of mineral content (TDS) of system water divided by the mineral content (TDS) of make-up water. High cycles of concentration are an indicator of increased scaling potential. Maintaining high cycles can be done with proper chemical water treatment. Cycles of concentration are mainly monitored in open loop cooling systems and general range from 2 to 14 times the mineral content of the makeup water. The cycles of concentration of a system are completely dependent upon the TDS of the makeup water and the optimum point where corrosion and scale build-up are minimized. A water treatment consultant should specify the optimal cycles for the water system.

pH:

In general, low pH water is corrosive and has a high acidity, a meter reading lower than 7.0. High pH water is prone to scaling and is considered to be alkaline and is specified by a meter reading greater than 7.0 and less than 14. Tests for pH, acidity or alkalinity, are used to monitor chemical treatment product dosages and are used for general troubleshooting of a water system.

Corrosion Coupons:

Corrosion coupons are small slender circular or rectangular pieces of metal (Iron or copper) used to monitor the actual corrosion level in a water system. Typically corrosion coupons are monitored on a 90-day rotation schedule. The original dimensions, thickness, of the coupon are known. When the coupon is removed from the water loop the change in dimensions are noted as the corrosion rate. If the corrosion inhibitor program is effective the coupon's corrosion rate are below the recommended levels, as specified in section 5.3.

Bacteria Dip Slide:

This test measures the concentration of bacteria in an open or closed loop cooling water system water sample. A media called "Agar" is wetted with the cooling water then is placed into a tube were Bacteria, yeasts and fungi are grown. This test is used to confirm that biocide program in an open or closed cooling water system is effective.

Dissolved Iron:

Iron testing is used to monitor corrosion products in a water system. Iron testing is used to either verify that the treatment program is working or to troubleshoot a problem. Dissolved Iron levels should be less than 30 ppm. Increased corrosion problems, leaks, poor heat transfer efficiency, as well as bacteria problems can occur when the dissolved Iron level is high.

Molybdate:

A Molybdate test measures the concentration of Sodium Molybdate in both closed and open loop cooling water systems. A water treatment consultant will state the minimum levels of Molybdate that is needed to maintain the systems' corrosion inhibitor program.

Organic Phosphate:

This test measures the concentration of organic Phosphate in an open loop cooling water system. This test is needed only if an organic phosphate is used as a corrosion inhibitor. A water treatment consultant will set the minimum levels of organic phosphate that need to be maintained to prevent corrosion.

Ortho-Phosphate:

This test measures the concentration of inorganic Phosphate in a water sample. Ortho-Phosphate is a commonly used in closed loop cooling water and hot water systems as an Iron (ferrous) and non-ferrous alloy corrosion inhibitor. If phosphate is used a minimum concentration of 200 – 300 mg/L (ppm)

Free Chlorine:

A free chlorine test measures the concentration of active oxidizing biocide in a open loop cooling water system. Free Chlorine tests are used to monitor both Chlorine and Bromine and are more accurately described as free halogen tests. These tests are commonly used to monitor the dosage of oxidizing biocide in an open recirculating cooling water system. Since excessive chlorine concentrations are corrosive a free chlorine residual of 0.2 to 0.8 ppm is maintained.

Nitrite:

The concentration of Nitrite in a closed loop cooling or hot water system's water sample is measured to monitor the corrosion inhibitor program. Nitrite is used to passivate metal surface and remove dissolved oxygen resulting in a non-corrosive water system. A water treatment consultant will set the minimum levels of nitrate that need to be maintained.

Sulfite:

This test is a residual oxygen scavenger test used to determine the concentration of sulfite available in a closed loop hot water system. If used as the oxygen scavenger, Sulphite shall be maintained at levels between 30-50 mg/L (ppm). When Sulphite levels are not maintained corrosion will occur. Over charging a system with Sulphite will increase the conductivity of the water, corrosivity and may cause the growth of sulphate reducing bacteria.

Silica:

Silica testing measures the concentration of Dissolved Silica in a water sample, typically for steam boiler systems. If silica levels are too high and pH is low scaling will occur. Silica can form extremely hard and dense scale on heat transfer surfaces increasing the risk of mechanical failure. Common water test sample points for silica include the boiler drum and the saturated steam.

5.4 Maintenance Parameters

The following charts list the minimum monitoring requirements for each open loop or closed loop water system. The frequency of the water testing can be increased to better maintain the performance in open loop cooling water, steam boiler, or closed loop system. The chemical test ranges and frequencies given are general and should be clearly defined by a certified water treatment consultant. A water treatment program can be controlled to an optimum level if the system is checked on a daily basis and automated monitoring equipment such as conductivity and pH meters are installed.

The operating ranges are **mandatory performance standards**. The maintenance contractor shall maintain water within these tolerances, unless GSA gives a written waiver for specific reasons. GSA may require more rigorous standards where circumstances dictate. The testing frequencies establish **minimum mandatory frequencies**. Contractors may test more frequently. Sporadic short-term deviations from operating ranges may not, depending on the terms and conditions of

specific contracts, result in a determination of unsatisfactory contract performance where the contractor takes prompt action to correct the condition.

Open Loop Cooling Water Systems

Chemistry Tests	Frequency of Test	Operating Ranges
Tower Water Conductivity	Auto Blowdown: Weekly, Monthly Manual Blowdown: Daily	160-2400 mmHOS (110-1600 ppm)
Makeup Water Conductivity (Hardness)	Auto Blowdown: Weekly, Monthly	40-600 mmHOS (30-400 ppm)
pH Test	Daily, Weekly	7.5 to 9.5
Corrosion Monitoring (Coupon Test)	Quarterly (3 months)	Iron: 2 to 5 mils/ year Copper: 0.2 to 0.5 mils/ yr
Bacteria Testing	Monthly	Max: 10^3 cfu/ml (colony forming units/ ml)
Chlorides	Weekly, Monthly	Max: 250 ppm as Cl Max: 410 ppm as NaCL
Sulfites	Weekly, Monthly	50-100 ppm SO_3 80-160 ppm Na_2SO_3
Corrosion Inhibitor Residual	Auto Chem. Feed: Weekly, Monthly	Defined by Consultant
Oxidizing Biocide Residual	Auto Chem. Feed: Weekly, Monthly	Defined by Consultant

Closed Loop Cooling Water Systems

Chemistry Tests	Frequency of Test	Optimum Operating Ranges
pH	Monthly	7.5-9.5
Total Dissolved Solids (TDS) or Coductivity	Quarterly (3 months)	Maximum: 2000 ppm or (2500µS/cm)
PolyPhosphates (PO_4)	Monthly	10- 20 ppm
Sulfites	Monthly	50-100 ppm SO_3 80-160 ppm Na_2SO_3
Bacteria Testing	Monthly	Max: 10^3 cfu/ml (colony forming units/ ml)
Corrosion Monitoring (Coupon Test)	Bi-Annually (6 months)	Iron: max. 0.5 mils/ year Copper: max. 0.2 mils/ yr
Corrosion Inhibitor Residual	Monthly	Defined By Consultant

Steam Systems with Recirculating Water

Chemistry Tests	Frequency of Test	Optimum Operating Ranges
Total Hardness Concentration	Daily or 3 times/week	Less Than 2 ppm $CaCO_3$
Feed water pH	Daily or 3 times/week	10.5-11.5
Feed Water Conductivity or TDS	Daily or 3 times/week	1500 - 3000 ppm (2000 – 4000 µS/cm)
Condensate Return pH	Daily or 3 times/week	8.5-9.5 pH
Condensate Return Conductivity or TDS	Daily or 3 times/week	40 ppm (50 µS/cm)
Makeup Water Conductivity	Weekly	40-600 mmHOS (30-400 ppm)
Hydroxide Alkalinity	Daily or 3 times/week	150-300 ppm $CaCO_3$
Total Alkalinity	Auto Chem Feed: Dailiy, Weekly	<700 ppm $CaCO_3$
Sulphite	Daily or 3 times/week	30-60 ppm SO_3 50 ppm Na_2SO_3
Steam Drum Scale Inhibitor Residual	Auto Chem Feed: Dailiy, Weekly	Defined By Consultant
Steam Drum Oxygen Scavenger Residual	Auto Chem Feed: Dailiy, Weekly	Defined By Consultant

Closed Loop Hot Water Systems

Chemistry Tests	Frequency of Test	Optimum Operating Ranges
pH	Monthly	7.5-9.5
Total Dissolved Solids (TDS) or Coductivity	Monthly	Maximum: 2000 ppm or (2500µS/cm)
Sulfites	Monthly	50-100 ppm SO_3 80-160 ppm Na_2SO_3

Corrosion Monitoring (Coupon Test)	Bi-Annually (6 months)	Iron: max. 0.5 mils/ year Copper: max. 0.2 mils/ yr
Corrosion Inhibitor Residual	Monthly	Defined By Consultant

6.1 Alternatives to Chemical Water Treatment

There are many alternative non-chemical methods to treating closed and open loop cooling and hot water systems. Not all alternatives on the market have been proven to be effective so carefully consider products that promise too much. The products listed below have been used in many systems and have been an effective means of non-chemical water treatment. There are numerous practical studies that can be referenced, when making a decision for or against either of these non-chemical water treatments.

6.2 Pulsed Electromagnetic Fields

This chemical free water treatment system uses a pulsed electromagnetic field to treat water. The common application of this technology is on open loop water processes subject to scale, corrosion, bio-fouling or bacterial contamination. Typical applications include open process water loops, cooling towers and fountains. The technology originated in the food and beverage industry as an FDA approved means for water sterilization.

The principal of operation is to generate a pulsating magnetic field around a section of pipe in the water process system. Each generated electromagnetic wave varies in amplitude and frequency and as the wave decays harmonics are created that can be measured in the megahertz range. It is this harmonic wave that is used to treat the water.

The harmonic wave alters the minerals; i.e. Calcium Carbonates, electrical charge causing the minerals to clump together into finally divide particles; colloidal nucleation. The minerals concentrate due to evaporation and attract each other thus clumping together into fine particles. The minerals then precipitate out of solution as a non-adhesive powder in the cooling tower basin rather than on the inside of the piping and heat transfer surfaces as scale. The powder is then carried off in the water discharged from the cooling tower during blow-down.

This pulsed electro magnetic field technology also has an effect on biological organisms, such as bacteria. The effect is described by two processes known as electroporation and encapsulation. Electroporation is the electromagnetic pulse causes damage to the cell membrane of biological organisms by repeatedly exposing it to an electromagnetic field. This inhibits the reproductive ability of the bacteria thus exhausting their ability to multiply. Encapsulation is the process of calcium carbonate precipitates surrounding and encapsulating the biological organisms in the condenser water. This prevents bio-fouling and bacteria from accumulating in open water loops. Eliminating the need for oxidizing biocides; which are corrosive substances such as bleach, chlorine and bromine, directly reduces the predominance for corrosion within cooling towers.

The cycles of concentration of the process loop are increased the environment become more alkaline which reduces the rate of corrosion. Increased cycles of concentration equal a reduction in system blow downs which saves water and water costs. Monitoring of pH and conductivity should still be conducted on a daily or weekly basis. The installation of this system requires the installation of a conductivity sensor to monitor water basin conductivity and automatic blowdown

controls. Cooling tower systems using this non-chemical water treatment system typically average less than 2 mils per year, which is an industry standard. Below 2 is considered very good with 2 to 5 being acceptable. Corrosion coupon test should be conducted on a quarterly basis.

6.3 Ozone Generators

Ozone generators have been used for portable drinking water sterilization for over two decades, to kill bacteria and other bio growth in water. This method of water sterilization is used to replace the use chlorination as a water purification method. The applications of Ozone generation for water treatment have expanded to open loop cooling water systems. They are usually installed at the cooling tower of the open loop water. Cooling tower manufactures and water treatment companies offer Ozone generators as a replacement for chemical treatment. Monitoring of pH, conductivity and bacteria testing should still be conducted on a daily or weekly basis and monthly. The installation of this system requires the installation of a conductivity sensor to monitor water basin conductivity and automatic blowdown controls.

The untreated water enters the Ozone generation system and treated water is introduced back into the open loop system at the cooling tower. Ozone generator units produce Ozone by one of three possible methods; sending dried oxygen enriched air through an electrode, ultraviolet irradiator or cold plasma. The most common method used for cooling water applications is the electrode method. The size of the generation unit is based on the size of the cooling water system and will be specified by the manufacturer. In addition, Ozone generation units require a system to clean and remove the humidity from the air. The air dryer and de-humidifier system require routine maintenance and should be conducted by the manufacturer or qualified maintenance personnel, while the unit is off.

Ozone is a strong oxidizer since it is an unstable three atom (tri-automic) oxygen molecule. Oxygen molecules are naturally diatomic (two atom) molecules at atmospheric pressure and are necessary for life. Ozone will naturally discard its additional oxygen molecule to form a stable diatomic oxygen molecule. Leaving a highly reactive oxygen atom, this atom will destroy bacteria, biological organisms and it eliminates phenols (odor causing organic compound) through oxidation. An Ozone generator should not be installed in any occupied space because it is considered a toxic gas, according to the U.S. Environmental Protection Agency (EPA) and Food & Drug Administration (FDA). It is regulated because the same chemical properties that allow ozone to react with organic compounds outside the body give it the same ability to react similarly with organic compounds that makeup the body.

J.10. ENERGY & WATER OPERATIONAL PERFORMANCE TARGETS

[The purpose of this document is to clearly identify the building-specific energy and water performance targets for the Contractor. These targets will be established in consultation with the Regional Energy Coordinator. This section also identifies how the energy and water performance will be monitored through the monthly progress reporting requirements of section C.11, Monthly Progress Reports, and the Building Energy and Water Efficiency Plan as required in section C.21.6, Energy and Water Efficiency.]

The Energy Independence and Security Act of 2007 (Public Law 110-140) requires Federal agencies to improve energy efficiency by 30% by end of FY 2015 as compared to the 2003 baseline (while targeting an annual reduction in energy use of roughly 3%). Executive Order 13514, Federal Leadership in Environmental, Energy, and Economic Performance mandates Federal agencies reduce potable water use intensity relative to their 2007 baseline by 26% total reduction by FY2020 (while targeting an annual reduction in water use of roughly 2% annually).

To comply with these mandates GSA has initiated internal Regional Targets on an annual basis so that the overall agency effort is successful. Each year a new internal Regional Target is established by the Energy Center of Expertise and each region is responsible for meeting that target. Within each region, it is up to the Regional Energy Coordinator, in collaboration with the Property Manager [and the O&M Contractor], to establish performance targets for each facility to ensure that the Regional Targets are met. To meet the regional objective, separate but reasonable and achievable reduction targets will be set for each building taking into account many parameters and circumstances such as historical energy and water usage, climate, age, performance, capital projects, and other mutually agreeable factors. ***[The solicitation development process does not explicitly involve the Regional Energy Coordinator. However, it is strongly recommended that the assigned Regional Energy Coordinator be consulted in developing building-specific energy and water performance targets. This approach will allow for establishing targets that are appropriate, reasonable and manageable for both the Contractor and GSA. When the O&M contract is being renewed/extended, it is recommended that the O&M Contractor also be consulted when establishing new/revised energy and water performance targets.]*** Further, the energy and water performance targets established are to be revisited and revised as appropriate for each contract extension period, or as other major events may warrant. *[Major equipment failures, building damage, tenant mission changes requiring significantly more overtime utilities, prolonged severe weather, and faulty energy or water use data are examples of events that can justify a revision to building-specific performance targets during the contract period. In these cases, the Regional Energy Coordinator should be consulted regarding possible target revision. Input from the Contractor should also be obtained, but the adjustments to the targets should be done with the concurrence of the Regional Energy Coordinator.]*

These energy and water performance targets are to be accomplished simultaneously to GSA's overall quality workplace/tenant satisfaction goals.

Energy Performance Targets

The energy performance target for this building, which is the sum of all building energy uses (electricity, natural gas, purchased steam/high temperature hot water, purchased chilled water, fuel oil, and any other purchased or site-generated energy) used in the 12-month contract period, has

been established to support regional objectives in meeting Federal mandates. The energy usage index (EUI) measured in Btu/GSF (British thermal units/gross square foot) is the standard unit of measurement for tracking energy consumption. The GSA Regional Energy Coordinator has been consulted to determine the most practical and achievable energy performance target for this building.

The annual energy performance target and historical data for the buildings covered in the contract shall be provided by the Government. Historical data is intended to provide a relative measure of the building's current energy usage and overall annual usage trends.

Contractor energy efficiency performance will be monitored through the monthly progress reports (see section C.11, Monthly Progress Reports), monthly tracking against the Contractor-developed Building Energy and Water Efficiency Use Plan (see section C.21.6, Energy and Water Efficiency), and evaluated over the full 12-month contract term to determine success in meeting the building energy performance target. GSA recognizes that there are factors/events that will impact the overall measured building energy performance, that many of these factors/events are outside the Contractor's control, and that there may be resulting impacts, both negative and positive. These factors/events will be considered by GSA in evaluating the Contractor's energy efficiency performance. It is the Contractor's responsibility to provide timely data analysis, and summaries of findings and recommendations to GSA for issues that impact the building's energy performance. *[This paragraph defines an ongoing process of energy management review by GSA and the Contractor, while also reinforcing the monthly progress reporting requirements and the value of the Building Energy and Water Efficiency Plan.]*

Water Performance Targets

The annual water performance target for this building has been established to support regional objectives in meeting Federal mandates for potable water use. The water usage index measured in gal/GSF (gallons/gross square foot) is the standard unit of measurement for tracking water consumption. (Note that the gross square footage used for both the energy and water usage indexes are the same.) The GSA Regional Energy Coordinator has evaluated the water usage data to determine the most practical and achievable target to meet the annual regional targets.

The annual water performance target and historical data for the buildings covered in the contract shall be provided by the Government. Historical data is intended to provide a relative measure of the building's current energy usage and overall annual usage trends.

Contractor water efficiency performance will be monitored through the monthly progress reports (see section C.11, Monthly Progress Reports), monthly tracking against the Contractor-developed Building Energy and Water Efficiency Plan (see section C.21.6, Energy and Water Efficiency), and evaluated over the full 12-month contract term to determine success in meeting the building water performance target. GSA recognizes that there are factors/events that will impact the overall measured building water performance, that many of these factors/events are outside the Contractor's control, and that there may be resulting impacts, both negative and positive. These factors/events will be considered by GSA in evaluating the Contractor's energy efficiency performance. It is the Contractor's responsibility to provide timely water usage data, data analysis, and summaries of findings and recommendations to GSA for issues that impact the building's water performance. [This paragraph defines an ongoing process of energy management review by

GSA and the Contractor, while also reinforcing the monthly progress reporting requirements and the value of the Building Energy and Water Efficiency Plan.]

J.11. ENERGY & WATER EFFICIENCY USE PLAN - RESERVED

J.12. Energy and Water Efficiency Monthly Report

"Reserved"

J.13. ANNUAL ENERGY AND WATER EFFICIENCY REPORT RESERVED

J.14. QUALIFICATIONS OF ELECTRICAL TESTING TECHNICIANS (FTT)

[[[This exhibit is provided to assist the CO in determining the Contractor's qualifications in H.15.3.8.]]]

(ANSI/NETA ETT-2010 Standard for Certification of Electrical Testing Technicians)

TITLE: **LEVEL:**	**Trainee Technician** **Level I**	**Assistant Technician** **Level II**	**Certified Technician** **Level III**	**Certified Senior Technician** **Level IV**
EDUCATION AND TRAINING:	High School / GED	Safety 40 hours Electrical 160 hours	Safety 24 hours add'l Electrical 240 hours add'l	Safety 40 hours add'l Electrical 200 hours add'l
RELATED EXPERIENCE:	None	Two Years*	Five Years*	Ten Years*
TYPICAL DUTIES:	None	Generally requires direct supervision. Responsible for safety of self. Understands hazardous electrical energy control procedures.	Capable of supervising Levels I and II. Routine and moderately complex projects. Record keeping. Safety of others. Switching. Evaluations.	Supervises large projects, multiple crews. Works independently. More complex investigations, tests, and evaluations.
TYPICAL ACTIVITIES:	Simple assistance. Simple measurements. Test equipment set up and removal. Cleaning.	Assists. Inspects. Tests. Data collection. Test for de-energized locked out/tagged out equipment.	Lockout/Tagout, safety grounding. Test for de-energized medium-voltage equipment. Performs moderately complex tasks. Interacts with other skills and operations.	Corrects system failures. Performs very complex tests. Interacts with engineers and managers. Writes reports.
EXAMINATION:	By employer	By certifying organization 70% minimum score	By certifying organization 70% minimum score	By certifying organization 70 % minimum score

NOTE: Candidates for Levels II, III, and IV must have met the qualifications for all previous levels.

***Completion of two or more years of technical education in an electrical field shall be equivalent to a maximum of one year of experience.**

J.15. MISCELLANEOUS BEST PRACTICES

"Reserved"

J.16. EQUIPMENT INVENTORY/CMMS

Note: The contractor, at the time the contractor is developing an offer in anticipation of the contract, is responsible for assessing the facility equipment inventory, condition of the equipment and systems, and effort needed to operate and maintain all of the equipment and systems. The contractor is solely responsible for assessing the cost and effort needed to meet contract requirements. Equipment inventory and any other maintenance records provided for review of offerors are provided in good faith for informational purposes only, but may contain some errors. The contract price will NOT be adjusted on the basis of errors in any government information reviewed by the contractor when preparing the offer.

Exhibit 15 N-CMMS
Equip Temp

Equipment Inventory Sheets Begin after page 357 and are labled "J.16 Equipment Inventory/CMMS"**

J.17. PREVENTIVE MAINTENANCE SCHEDULE

GSA PM Guide Final
Rev 3

Per Section C.35.2 Maintenance Standard refer to Public Buildings Service Operations and Maintenance Standards 2012 (PM Guide).

J.18. SOLID WASTE AND RECYCLING REPORT

Solid Waste and Recycling Report

Solid Waste and Recycling Report									
Building #		Building Name							
Building Address									
Contractor Name		Contractor Phone #							
Submission Date									
RECYCLING									
Description	Outside Container Volume/Size	Number of Containers	Pick-up Frequency	Total Volume	Conversion Factor	Total Weight (tons)	Per Ton Recycling Fee	Total Cost	Recycler Name
TOTAL									
WASTE									
	Outside Container Volume/Size	Number of Containers	Pick-up Frequency	Total Volume	Conversion Factor	Total Weight (tons)	Per Ton Tipping Fee	Total Cost	Hauler Name
TOTAL									

Conversion Source(s):

HOW TO FILL OUT THE FORM:

1. Report all recyclables. For source separated recycling, provide weight for each type of material recycled. For commingled recycling, provide total weight for the mixed recyclable materials. Specify when items are composted.

2. All fields must be filled out.

3. Provide actual weight whenever possible. ** When actual weight is not available use standard Volume-to-Weight Conversion Factors for calculation. Allowances shall be made and reported for volumes that are not filled to capacity (i.e. half full, 3/4 full, etc.)

4. Pick Up Frequency: Based on monthly activity (e.g. once a week= 4, twice a week = 8, etc.)

5. Indicate conversion factor source(s).

Solid Waste and Recycling Report

Building #	IXXLER	**Building Name**	The Citizens CH
Building Address	123 American Blvd, Fun Town, USA		
Contractor Name	The Best Company	**Contractor Phone #**	555-121-6583
Submission Date	Nov 15, 2010		

RECYCLING

Description	Outside Container Volume/Size	Number of Containers	Pick-up Frequency	Total Volume	Conversion Factor	Total Weight (tons)	Per Ton Recycling Fee	Total Cost	Recycler Name
Commingled (mixed paper, cardboard, plastic)	8 cubic yard	4	4	128	1000	64	$20.00	$1,280.00	Green Company
Aluminum Cans (Compacted)	6 cubic yard	2	8	96	430	20.64	$0.00	$0.00	Green Company 2
Glass	3 Cubic yard	1	2	6	600	1.8	$30.00	$54.00	Green Company 2
Food Waste Scrap	55 gal Drums	5	2	550	412	113.3	$18.00	$2,039.40	Green Company
Wood Waste	20 cubic yard	2	4	160	40	3.2	$10.00	$32.00	Green Company
Yard Waste Composted	4 cubic yard	2	4	32	1500	24	$50.00	$1,200.00	Green Company
TOTAL		16	24	972		226.94		$4,605.40	

WASTE

	Outside Container Volume/Size	Number of Containers	Pick-up Frequency	Total Volume	Conversion Factor	Total Weight (tons)	Per Ton Tipping Fee	Total Cost	Hauler Name
	30 cubic yard roll off	3	4	360	1000	180.00	$85.00	$15,300.00	Waste Hauler 1
	20 cubic yard roll off	1	4	80	600	24.00	$79.00	$1,896.00	Waste Hauler 1
TOTAL		4	8	440	1600	204.00	$164.00	$17,196.00	

Conversion Source: EPA's Standard Volume-to-Weight Conversion Factors (http://www.epa.gov/epawaste/conserve/tools/recmeas/docs/guide_b.pdf

HOW TO FILL OUT THE FORM:

1. Report all recyclables. For source separated recycling, provide weight for each type of material recycled. For commingled recycling, provide total weight for the mixed recyclable materials. Specify when items are composted.
2. All fields must be filled out.
3. Provide actual weight whenever possible. ** When actual weight is not available, use standard Volume-to-Weight Conversion Factors for calculation. Allowances shall be made and reported for volumes that are not filled to capacity (i.e. half full, 3/4 full, etc.).
4. Pick Up Frequency: Based on monthly activity (e.g. once a week= 4, twice a week = 8, etc.)
5. Indicate conversion factor source(s).

J.19. ELEVATOR TOUR LOG - RESERVED

J.20. UNDERGROUND STORAGE TANK (UST/AST)

GSA Region 4 – UST/AST Operator Training Requirements

http://www.dep.state.fl.us/waste/categories/tanks/default.htm

UNDERGROUND STORAGE TANK (UST)
(FLORIDA STATE REQUIREMENTS)

GSA Region 4 - UST Operator Training Requirements

Background: The Energy Policy of 2005 (EPAct) mandated that the Environmental Protection Agency (EPA), in coordination with the states, develop training guidelines for persons who operate and maintain Underground Storage Tanks (USTs) subject to the regulations at 40 CFR 280. The guidelines specify that tank operators – referred to as Class A, B, and C UST operators – be trained according to their level of responsibility prior to contract award. State UST operator training requirements must follow EPA guidelines at a minimum. In the absence of state-designated training curricula, UST operators are not responsible for complying with the EPAct training requirements.

The UST operator classes are:

Class A Operator This individual is generally responsible for ***managing resources*** and personnel, and performs activities such as establishing work assignments to achieve and maintain compliance with regulatory requirements. The Class A operator training objective is to ensure broad knowledge of regulatory requirements that provide a basis for informed decision-making regarding compliance, and to ensure appropriate individuals are in place to fulfill operation, maintenance, and recordkeeping requirements and standards.

Class B Operator This individual generally is responsible for field implementation of applicable UST regulatory requirements and carries out day-to-day aspects of operating, maintaining, and recordkeeping for USTs at one or more facilities. The Class B operator training objective is to ensure in-depth knowledge of how to ***implement regulatory requirements*** (e.g., operation, maintenance, and recordkeeping requirements).

Class C Operator This individual is generally the first line of ***response when emergencies occur***. The Class C operator training objective is to ensure knowledge of actions to take in the event of a leak or other emergency. Class C operators must be present when the facility is manned and available within a reasonable amount of time when the facility is unmanned.

Requirements: UST operator certification requirements vary by state; some states require that operators take a course, while other states require that applicants pass an exam. Some states provide free training, while others require operators to pay for training provided by an approved third party.

Furthermore, states may require either site-specific operator training, which is focused only on equipment used at the UST facility, or broader training regarding regulatory requirements. International Code Council (ICC) certification as a Class A or Class B UST system operator is accepted by many but not all states. For more information on the ICC exam, visit http://pearsonvue.com/icc/cert/.

The Class C operator is generally trained by the sites' Class A or B operator, but some states require third-party training.

The EPA requires that Class A and Class B operators be trained ***within 30 days of*** assuming operation and maintenance responsibilities; Class C operators must be trained ***before*** assuming responsibility for emergency response.

Proof: Many states require that the proof of certification or completed training is maintained onsite; some states require the information to be submitted to the state UST office. For GSA purposes, copies of exam results, course attendance, and related certificates (as applicable) should be maintained onsite and available electronically to facility and property managers.

Next Steps: Each GSA Region should designate individuals responsible for the tanks in each building and define their specific roles; those staff should then obtain the appropriate UST system operator certification. Going forward all operation and maintenance (O&M) contracts should include requirements for Class A, Class B, and Class C UST system operator designation and mandate certification at the appropriate level . In most instances, one person may serve the role of both the Class A operator and the Class B operator. However, the Class C Operator can NOT be responsible for multiple buildings. Persons designated in multiple operator classes must complete training specific to each assigned operator class.

Florida

General Information

Overview	As of March 1, 2012, Florida UST operator training requirements are under development. In the meantime, the Florida Department of Environmental Protection (FDEP) is accepting operator training from other state-approved training programs in EPA Region 4 (Alabama, Georgia, Kentucky, Mississippi, North Carolina, South Carolina, Tennessee) and third party training providers, provided that they cover UST requirements specific to Florida. Vouchers for online training provided by American Petroleum Institute - Antea may be available through the PBS Environment Division. For more information, contact Gina Noel in Central Office. UST operator training is not required until state UST operator training requirements are finalized or federal UST regulations are amended to include such requirements.
Website	Florida UST Program
Deadline	August 8, 2012 (same as federal deadline)

After this date, Class A and B operators must be trained within 30 days of assuming their job duties. Class C operators must be trained before assuming their duties.

Certification Requirements

Class A & B	The certification requirements for Class A and B operators have not yet been established. In the meantime, a list of state-approved training programs is available here.
Class C	The certification requirements for Class C operators have not yet been established. However, ahead of state regulations, Class C operators should be trained on general tank operations and emergency response procedures.
Renewal	Renewal certification requirements for Class A, B, and C operators have not yet been established.

Documentation

Class A, B, & C	Documentation requirements for UST operators have not yet been established. However, certificates indicating completion of training should be printed and maintained onsite.
GSA Requirements	For GSA purposes, copies of exam results, course participation, and certificates (as applicable) for all UST operators should be maintained onsite and available electronically to facility and property managers.

Recommended Steps to Compliance

- Formally designate (in writing) Class A, Class B, and Class C operators for each UST system.
- Complete state-authorized training courses. Where state rules have not been established, check with the state agency on a routine basis to determine if training requirements have been finalized.
- Work with the Contracting Officer's Technical Representative (COTR) to advise contractors of the UST operator training requirements. Property managers/COTRs should obtain written acknowledgement from contractors stating that they are aware of the requirements, concur with the designation of their personnel as operators, and have a plan to ensure that contract personnel will be trained to the appropriate operator level and that refresher training will take place as required.
- Check with the state agency periodically to determine if training requirements have changed. If they have, complete the updated state-authorized training course as applicable.
- Review facility records to ensure that Class A, B, and C operator designations are current for each building.
- Complete refresher training as required by the state.

Consult your Regional Environmental Office for assistance.

J.21. On-boarding and Off-Boarding Contract Employees Requiring Access to GSA IT Systems Procedures – Contractor Information Worksheet (CIW)

Contracting Officers (COs) and Contracting Officer Representatives (CORs) are responsible for overseeing the on-boarding and off-boarding contract employees who require access to GSA IT systems.

Contracting Officers (COs) and Contracting Officer Representatives (CORs) are responsible for overseeing the on-boarding and off-boarding contract employees who require access to GSA IT systems.

During the on-boarding process, the CO shall:

● Have the contract employee complete a Contractor Information Worksheet (CIW)

● Contracting Officers (COs) and Contracting Officer Representatives (CORs) are responsible for overseeing the on-boarding and off-boarding contract employees who require access to GSA IT systems.

During the on-boarding process, the CO shall:

● Have the contract employee complete a Contractor Information Worksheet (CIW)

● Sponsor the contract employee in GSA's Credential and Identity Management System (GCIMS) or provide the CIW to the contract employee's Regional Credentialing Officer (RCO) or Access Card Point of Contact (POC) to sponsor the contract employee in GCIMS.

● Submit a Service Catalog Request noting the contract employee's start date, contract name, IT system access and hardware requirements.

During the off-boarding process of the CO shall:

● Collect the contract employee's GSA Access Card and return it to the Regional Credentialing Officer (RCO) or Access Card POC or have the RCO or Access Card POC collect the GSA Access Card directly from the contract employee.

● Ask the RCO or Access Card POC to mark the contract employee's record as inactive in GCIMS.

● Submit a Service Catalog Request for the termination of all user accounts associated with the contract employee and include an effective date of departure.

● All government-furnished equipment will be picked up by Local Support.

If you still have questions, please check out the GSA Enterprise Service Desk section of the IT Insider to learn more about submitting Service Catalog Requests. GSA is reviewing its contract employee on-boarding and off-boarding policies and procedures and will issue updated guidance in the future. Sponsor the contract employee in GSA's Credential and Identity Management System (GCIMS) or provide the CIW to the contract employee's Regional Credentialing Officer (RCO) or Access Card Point of Contact (POC) to sponsor the contract employee in GCIMS.

● Submit a Service Catalog Request noting the contract employee's start date, contract name, IT system access and hardware requirements.

During the off-boarding process of the CO shall:

● Collect the contract employee's GSA Access Card and return it to the Regional Credentialing Officer (RCO) or Access Card POC or have the RCO or Access Card POC collect the GSA Access Card directly from the contract employee.

● Ask the RCO or Access Card POC to mark the contract employee's record as inactive in GCIMS

● Submit a Service Catalog Request for the termination of all user accounts associated with the contract employee and include an effective date of departure

● All government-furnished equipment will be picked up by Local Support.

If you still have questions, please check out the GSA Enterprise Service Desk section of the IT Insider to learn more about submitting Service Catalog Requests. GSA is reviewing its contract employee on-boarding and off-boarding policies and procedures and will issue updated guidance in the future.

J.22. CUSTODIAL SURVEILLANCE FORMS

GSA Form 1181A – Contract Cleaning Inspection Report

This form shall be filled out and submitted to the Contractor when deficiencies are found during the COR's inspections.

This form can be found at: GSA Insite/Financial Transactions/GSA Forms Library

CONTRACT CLEANING INSPECTION REPORT

INSTRUCTIONS: Form is used for inspection of contract cleaning by inspectors to record results. The condition of area(s) inspected will be rated SATISFACTORY or UNSATISFACTORY. Explain unsatisfactory rating in remarks column and complete quantity column.

BUILDING	Report NO.	CONTRACT NO.
U.S. Courthouse GS-04-13-EW_D-0000		

INSPECTOR (*Print Name*) INSPECTOR'S SIGNATURE
JOHN DOE

TIMED STARTED	TIME COMPLETED	DATE OF INSPECTION
9:00 A.M.	10:50 A.M.	10/31/13

INTERVIEWED BY	DATE	CONTRACTOR'S RECEIPT	TIME
MS. DEE	11/01/06	sup. signature	1:00 p.m.

DATE
11/01/06

WORK DESCRIPTION – LOCATION *(Room No., Corridor, lobby, or either)* *By Measure or count* .	QUANTITY CHECK ONE SAT.	UNSAT.	REMARKS
3rd Floor East			
M3-5171		X	Rust on toilet base under bolt of toilet
3-5178	X		
Women's Restroom			Public
X			
Men's Public			Restroom -M-7665
X			Slight build up in corners of

urinal

Drinking Fountains -1st near room 1-5566	X	Mineral Build up

GENERAL SERVICES ADMINISTRATION GSA FORM 1181A

Quality Deficiency Notice

This form shall be filled out and submitted to the contractor when deficiencies are found during the COR's inspections.

QUALITY DEFICIENCY NOTICE

NAME OF CONTRACTOR
CONTRACTOR ADDRESS
XXXX Cleaning Services
333 Smith St. Ste. 201
San Francisco, CA 94102
CONTRACT NO. GS-09P-06-KSD-0000

A deficiency exists in your quality control system. The nature of the deficiency is

Continuous findings on 3rd floor men's restroom (M) 3-5171-Rust on toilet base under bolt of toilet. Rust needs to be removed and base needs to be cleaned.

Immediate action is required to correct the deficiency and the condition that caused it. Failure to take acceptable corrective action on time may result in termination of your right to proceed with this contract.

Please provide a written response of corrective action taken to the CO within _____workdays after receiving this notice.

OAS NAME AND SIGNATURE
ADDRESS
DATE
CO . 450 Golden Gate Ave., Ste #7 11/5/12
San Francisco, CA 94102
RECEIPT ACKNOWLEDGED CERTIFIED RECEIPT NO.

EVALUATION OF CORRECTION ACTION

□ Corrective action verified and found acceptable
□ Corrective action not acceptable and /or not implemented (Explain below)

This matter is being referred to the Contracting Officer for action. Direct further correspondence on this matter to the CO.

QAS SIGNATURE	DATE
RECEIPT ACKNOWLEDGED	DATE

QASP Monthly Inspection Report

BUILDING NAME & LOCATION: Phillip Burton Federal Building & US Courthouse
CONTRACT NO.: GS-04P-13-EW-D-0000
CONTRACTOR NAME: XXX Cleaning Service

Please report all deficiencies found during the previous month inspection(s). Attach copies of all **GSA 3539 Forms** submitted to the contractor with this form. If there were no deficiencies, please submit this form indicating there were no deficiencies reported for the month. This form will become a part of the official QA documentation.

DEFIENCIES & CORRECTIVE ACTIONS	COMMENTS
Documented on the Contract Cleaning Inspection Reports	**All deficiencies minor, corrected by the Contractor**

COR

Signature: _____ Date: _____

COR's Checklist for Inspections

	CUSTODIAL AND RELATED SERVICES	COMMENTS
	Submittals: -a list of names and telephone numbers of on-site supervisors -security clearance documentation (current & new employees) - work schedules - floor maintenance schedules - MSDS documentation - initial IPM inspection report	
	Quality Control Plan (QCP) - description of training programs - description of disciplinary procedures - description of contingency plan for separation of employees	
	Inspection Reports	
	Service Call Logs	
	Tenant Reports	
	Integrated Pest Management (IPM) Quarterly Reports	
	Recycling and Solid Waste/Trash Hauling Reports	

NOTE: This checklist does NOT represent an all-inclusive list of items that may be reviewed during an inspection. It is provide ONLY as guidance for the CO .

J.23. BUILDING EXTERIOR AND HARDSCAPE PLAN

The Contractor shall submit to the CO a detailed Building Exterior and Hardscape Plan that addresses the listed work items. The plan helps ensure that grounds/site/building exterior management practices have the lowest environmental impact possible and that these practices preserve ecological integrity, enhance diversity and protect wildlife, while supporting building performance and integration into surrounding landscapes. At a minimum, the custodial and related services portion of the plan shall address the following items:

-Goals and Scope

-Responsible Party

-Guidance for Resources and Implementation

-Performance Measurement

-Training

-Maintenance Equipment

-Use of Chemical Concentrates and Dilution Systems

-Sustainable Building Exterior, Sidewalks, and Pavement Cleaning

-Paints and Sealants Used on the Building Exterior

-Cleaning of building exterior

-Cleaning equipment

-Cleaning of sidewalks, pavement, and other Hardscape

-Animal and vegetation pest control

-Landscape waste

-Fertilizer use

-Quality Assurance/Quality Control Processes

J.24. EROSION SEDIMENT CONTROL

IPM, Erosion Control, Landscape Management Plan[1]

Used only when Contractor is required to perform activities that disturbs the existing grounds conditions **THE REQUIREMENTS OF THIS PART CAN BE SATISFIED WITH A SINGLE PLAN OR WITH SEPARATE PLANS. WHEN AN 'IMP' IS PREPARED SEPARATELY, IT NEED ONLY BE REFERENCED IN THE PLAN.**

The Contractor shall employ strategies such as temporary and permanent seeding, mulching, earth dikes, silt fencing, sediment traps and sediment basins to correct existing erosion such as typically found as the result of foot traffic killing the vegetation, steep slopes where sheet flow from storm water exceeds existing vegetation holding power, or point storm water outflow that exceeds the holding power of the vegetation covering the soil. The Contractor shall submit to the CO an IPM Erosion Control, Landscape Management Plan outlining how this will be accomplished. At a minimum, the custodial and related services portion of the plan shall address the following items:

-Goals and Scope

-Responsible Parties

-Guidance for Resources and Implementation

-Performance Measurement

-Training

-Chemical Treatment Purchasing and Application

-Integrated Pest Management (IPM)

-Erosion and Sediment Control

-Storm-Water Management Plan

-Landscape Management

-Composting

-Quality Assurance/Quality Control Processes

[1] This is a sample and is not intended to be comprehensive. Excerpts are from United States Green Building Council (USGBC.

J.25. WAGE DETERMINATIONS

WD 05-2119 (Rev.-17) was first posted on www.wdol.gov on 07/14/2015

REGISTER OF WAGE DETERMINATIONS UNDER THE SERVICE CONTRACT ACT
By direction of the Secretary of Labor

U.S. DEPARTMENT OF LABOR
EMPLOYMENT STANDARDS ADMINISTRATION
WAGE AND HOUR DIVISION
WASHINGTON D.C. 20210

Wage Determination No.: 2005-2119
Revision No.: 17
Date Of Revision: 07/08/2015

Daniel W. Simms
Director

Division of
Wage Determinations

Note: Executive Order (EO) 13658 establishes an hourly minimum wage of $10.10 for 2015 that applies to all contracts subject to the Service Contract Act for which the solicitation is issued on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least $10.10 (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract. The EO minimum wage rate will be adjusted annually. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

State: Florida

Area: Florida Counties of Collier, Dade, Monroe

Fringe Benefits Required Follow the Occupational Listing

OCCUPATION CODE - TITLE	FOOTNOTE	RATE
01000 - Administrative Support And Clerical Occupations		
01011 - Accounting Clerk I		14.11
01012 - Accounting Clerk II		16.24
01013 - Accounting Clerk III		18.17
01020 - Administrative Assistant		22.64
01040 - Court Reporter		18.82
01051 - Data Entry Operator I		12.92
01052 - Data Entry Operator II		14.09
01060 - Dispatcher, Motor Vehicle		16.82
01070 - Document Preparation Clerk		12.67
01090 - Duplicating Machine Operator		12.67
01111 - General Clerk I		12.62
01112 - General Clerk II		13.88
01113 - General Clerk III		15.59
01120 - Housing Referral Assistant		20.88
01141 - Messenger Courier		12.39
01191 - Order Clerk I		12.71
01192 - Order Clerk II		13.86
01261 - Personnel Assistant (Employment) I		15.88
01262 - Personnel Assistant (Employment) II		18.07
01263 - Personnel Assistant (Employment) III		20.30
01270 - Production Control Clerk		20.00
01280 - Receptionist		13.44
01290 - Rental Clerk		14.93
01300 - Scheduler, Maintenance		16.74
01311 - Secretary I		16.74
01312 - Secretary II		18.73
01313 - Secretary III		20.88
01320 - Service Order Dispatcher		14.66
01410 - Supply Technician		23.21
01420 - Survey Worker		18.82

01531 - Travel Clerk I	12.57
01532 - Travel Clerk II	13.48
01533 - Travel Clerk III	14.33
01611 - Word Processor I	13.30
01612 - Word Processor II	14.93
01613 - Word Processor III	16.98
05000 - Automotive Service Occupations	
05005 - Automobile Body Repairer, Fiberglass	17.44
05010 - Automotive Electrician	16.61
05040 - Automotive Glass Installer	15.52
05070 - Automotive Worker	15.52
05110 - Mobile Equipment Servicer	13.34
05130 - Motor Equipment Metal Mechanic	17.56
05160 - Motor Equipment Metal Worker	15.52
05190 - Motor Vehicle Mechanic	17.34
05220 - Motor Vehicle Mechanic Helper	12.24
05250 - Motor Vehicle Upholstery Worker	14.42
05280 - Motor Vehicle Wrecker	15.52
05310 - Painter, Automotive	16.62
05340 - Radiator Repair Specialist	15.52
05370 - Tire Repairer	11.41
05400 - Transmission Repair Specialist	17.53
07000 - Food Preparation And Service Occupations	
07010 - Baker	12.65
07041 - Cook I	11.08
07042 - Cook II	12.90
07070 - Dishwasher	8.72
07130 - Food Service Worker	9.89
07210 - Meat Cutter	12.75
07260 - Waiter/Waitress	9.85
09000 - Furniture Maintenance And Repair Occupations	
09010 - Electrostatic Spray Painter	14.98
09040 - Furniture Handler	7.71
09080 - Furniture Refinisher	14.98
09090 - Furniture Refinisher Helper	11.03
09110 - Furniture Repairer, Minor	13.00
09130 - Upholsterer	16.48
11000 - General Services And Support Occupations	
11030 - Cleaner, Vehicles	9.80
11060 - Elevator Operator	10.39
11090 - Gardener	14.13
11122 - Housekeeping Aide	10.39
11150 - Janitor	10.39
11210 - Laborer, Grounds Maintenance	11.40
11240 - Maid or Houseman	9.59
11260 - Pruner	9.93
11270 - Tractor Operator	14.36
11330 - Trail Maintenance Worker	11.40
11360 - Window Cleaner	11.94
12000 - Health Occupations	
12010 - Ambulance Driver	15.34
12011 - Breath Alcohol Technician	17.33
12012 - Certified Occupational Therapist Assistant	26.46
12015 - Certified Physical Therapist Assistant	24.15
12020 - Dental Assistant	15.13
12025 - Dental Hygienist	31.91
12030 - EKG Technician	22.01
12035 - Electroneurodiagnostic Technologist	22.01
12040 - Emergency Medical Technician	15.34
12071 - Licensed Practical Nurse I	15.49
12072 - Licensed Practical Nurse II	17.33

12073 - Licensed Practical Nurse III		19.32
12100 - Medical Assistant		15.38
12130 - Medical Laboratory Technician		17.89
12160 - Medical Record Clerk		14.69
12190 - Medical Record Technician		15.38
12195 - Medical Transcriptionist		15.86
12210 - Nuclear Medicine Technologist		34.45
12221 - Nursing Assistant I		10.55
12222 - Nursing Assistant II		11.87
12223 - Nursing Assistant III		12.95
12224 - Nursing Assistant IV		14.53
12235 - Optical Dispenser		17.57
12236 - Optical Technician		15.24
12250 - Pharmacy Technician		15.84
12280 - Phlebotomist		14.53
12305 - Radiologic Technologist		25.46
12311 - Registered Nurse I		26.32
12312 - Registered Nurse II		29.80
12313 - Registered Nurse II, Specialist		29.80
12314 - Registered Nurse III		36.61
12315 - Registered Nurse III, Anesthetist		36.61
12316 - Registered Nurse IV		43.22
12317 - Scheduler (Drug and Alcohol Testing)		19.28
13000 - Information And Arts Occupations		
13011 - Exhibits Specialist I		19.01
13012 - Exhibits Specialist II		23.54
13013 - Exhibits Specialist III		28.80
13041 - Illustrator I		20.64
13042 - Illustrator II		25.57
13043 - Illustrator III		31.27
13047 - Librarian		31.86
13050 - Library Aide/Clerk		12.37
13054 - Library Information Technology Systems Administrator		26.99
13058 - Library Technician		16.53
13061 - Media Specialist I		16.17
13062 - Media Specialist II		18.41
13063 - Media Specialist III		20.54
13071 - Photographer I		15.54
13072 - Photographer II		17.83
13073 - Photographer III		21.43
13074 - Photographer IV		27.00
13075 - Photographer V		32.66
13110 - Video Teleconference Technician		16.88
14000 - Information Technology Occupations		
14041 - Computer Operator I		16.41
14042 - Computer Operator II		18.36
14043 - Computer Operator III		20.47
14044 - Computer Operator IV		22.75
14045 - Computer Operator V		25.19
14071 - Computer Programmer I	(see 1)	22.76
14072 - Computer Programmer II	(see 1)	
14073 - Computer Programmer III	(see 1)	
14074 - Computer Programmer IV	(see 1)	
14101 - Computer Systems Analyst I	(see 1)	
14102 - Computer Systems Analyst II	(see 1)	
14103 - Computer Systems Analyst III	(see 1)	
14150 - Peripheral Equipment Operator		16.41
14160 - Personal Computer Support Technician		22.75
15000 - Instructional Occupations		
15010 - Aircrew Training Devices Instructor (Non-Rated)		31.48

15020 - Aircrew Training Devices Instructor (Rated)	38.08
15030 - Air Crew Training Devices Instructor (Pilot)	42.90
15050 - Computer Based Training Specialist / Instructor	31.48
15060 - Educational Technologist	26.06
15070 - Flight Instructor (Pilot)	42.90
15080 - Graphic Artist	25.96
15090 - Technical Instructor	21.38
15095 - Technical Instructor/Course Developer	26.16
15110 - Test Proctor	17.26
15120 - Tutor	17.26
16000 - Laundry, Dry-Cleaning, Pressing And Related Occupations	
16010 - Assembler	9.62
16030 - Counter Attendant	9.62
16040 - Dry Cleaner	11.86
16070 - Finisher, Flatwork, Machine	9.62
16090 - Presser, Hand	9.62
16110 - Presser, Machine, Drycleaning	9.62
16130 - Presser, Machine, Shirts	9.62
16160 - Presser, Machine, Wearing Apparel, Laundry	9.62
16190 - Sewing Machine Operator	12.52
16220 - Tailor	13.18
16250 - Washer, Machine	10.41
19000 - Machine Tool Operation And Repair Occupations	
19010 - Machine-Tool Operator (Tool Room)	17.51
19040 - Tool And Die Maker	22.29
21000 - Materials Handling And Packing Occupations	
21020 - Forklift Operator	14.81
21030 - Material Coordinator	19.02
21040 - Material Expediter	19.02
21050 - Material Handling Laborer	12.17
21071 - Order Filler	11.60
21080 - Production Line Worker (Food Processing)	14.81
21110 - Shipping Packer	14.81
21130 - Shipping/Receiving Clerk	14.81
21140 - Store Worker I	9.45
21150 - Stock Clerk	14.43
21210 - Tools And Parts Attendant	14.81
21410 - Warehouse Specialist	14.81
23000 - Mechanics And Maintenance And Repair Occupations	
23010 - Aerospace Structural Welder	24.81
23021 - Aircraft Mechanic I	23.31
23022 - Aircraft Mechanic II	24.81
23023 - Aircraft Mechanic III	26.28
23040 - Aircraft Mechanic Helper	15.59
23050 - Aircraft, Painter	18.88
23060 - Aircraft Servicer	18.80
23080 - Aircraft Worker	20.33
23110 - Appliance Mechanic	18.53
23120 - Bicycle Repairer	11.41
23125 - Cable Splicer	24.61
23130 - Carpenter, Maintenance	17.55
23140 - Carpet Layer	17.33
23160 - Electrician, Maintenance	19.25
23181 - Electronics Technician Maintenance I	21.43
23182 - Electronics Technician Maintenance II	23.32
23183 - Electronics Technician Maintenance III	25.75
23260 - Fabric Worker	17.63
23290 - Fire Alarm System Mechanic	18.83
23310 - Fire Extinguisher Repairer	14.71
23311 - Fuel Distribution System Mechanic	20.59
23312 - Fuel Distribution System Operator	15.49

23370 - General Maintenance Worker	16.44
23380 - Ground Support Equipment Mechanic	23.31
23381 - Ground Support Equipment Servicer	18.80
23382 - Ground Support Equipment Worker	20.33
23391 - Gunsmith I	14.71
23392 - Gunsmith II	17.40
23393 - Gunsmith III	19.85
23410 - Heating, Ventilation And Air-Conditioning Mechanic	19.01
23411 - Heating, Ventilation And Air Contditioning Mechanic (Research Facility)	20.23
23430 - Heavy Equipment Mechanic	19.94
23440 - Heavy Equipment Operator	18.20
23460 - Instrument Mechanic	18.69
23465 - Laboratory/Shelter Mechanic	18.62
23470 - Laborer	11.51
23510 - Locksmith	16.19
23530 - Machinery Maintenance Mechanic	22.48
23550 - Machinist, Maintenance	18.00
23580 - Maintenance Trades Helper	13.11
23591 - Metrology Technician I	18.69
23592 - Metrology Technician II	19.89
23593 - Metrology Technician III	21.08
23640 - Millwright	21.19
23710 - Office Appliance Repairer	17.94
23760 - Painter, Maintenance	17.51
23790 - Pipefitter, Maintenance	20.20
23810 - Plumber, Maintenance	19.23
23820 - Pneudraulic Systems Mechanic	19.85
23850 - Rigger	19.85
23870 - Scale Mechanic	17.40
23890 - Sheet-Metal Worker, Maintenance	18.24
23910 - Small Engine Mechanic	15.16
23931 - Telecommunications Mechanic I	23.92
23932 - Telecommunications Mechanic II	25.46
23950 - Telephone Lineman	21.16
23960 - Welder, Combination, Maintenance	18.69
23965 - Well Driller	18.71
23970 - Woodcraft Worker	19.85
23980 - Woodworker	14.71
24000 - Personal Needs Occupations	
24570 - Child Care Attendant	8.81
24580 - Child Care Center Clerk	15.33
24610 - Chore Aide	9.40
24620 - Family Readiness And Support Services Coordinator	14.45
24630 - Homemaker	17.05
25000 - Plant And System Operations Occupations	
25010 - Boiler Tender	19.01
25040 - Sewage Plant Operator	20.16
25070 - Stationary Engineer	19.01
25190 - Ventilation Equipment Tender	12.90
25210 - Water Treatment Plant Operator	20.16
27000 - Protective Service Occupations	
27004 - Alarm Monitor	20.47
27007 - Baggage Inspector	10.61
27008 - Corrections Officer	25.15
27010 - Court Security Officer	28.50
27030 - Detection Dog Handler	18.11
27040 - Detention Officer	25.15
27070 - Firefighter	26.09

27101 - Guard I		10.61
27102 - Guard II		18.11
27131 - Police Officer I		30.90
27132 - Police Officer II		34.34
28000 - Recreation Occupations		
28041 - Carnival Equipment Operator		13.37
28042 - Carnival Equipment Repairer		14.74
28043 - Carnival Equpment Worker		9.40
28210 - Gate Attendant/Gate Tender		14.63
28310 - Lifeguard		13.49
28350 - Park Attendant (Aide)		16.39
28510 - Recreation Aide/Health Facility Attendant		11.96
28515 - Recreation Specialist		20.30
28630 - Sports Official		13.04
28690 - Swimming Pool Operator		19.77
29000 - Stevedoring/Longshoremen Occupational Services		
29010 - Blocker And Bracer		22.76
29020 - Hatch Tender		22.76
29030 - Line Handler		22.76
29041 - Stevedore I		20.86
29042 - Stevedore II		24.67
30000 - Technical Occupations		
30010 - Air Traffic Control Specialist, Center (HFO)	(see 2)	37.85
30011 - Air Traffic Control Specialist, Station (HFO)	(see 2)	26.10
30012 - Air Traffic Control Specialist, Terminal (HFO)	(see 2)	28.74
30021 - Archeological Technician I		15.98
30022 - Archeological Technician II		18.25
30023 - Archeological Technician III		24.98
30030 - Cartographic Technician		25.86
30040 - Civil Engineering Technician		24.73
30061 - Drafter/CAD Operator I		18.66
30062 - Drafter/CAD Operator II		20.89
30063 - Drafter/CAD Operator III		23.28
30064 - Drafter/CAD Operator IV		28.66
30081 - Engineering Technician I		17.93
30082 - Engineering Technician II		21.92
30083 - Engineering Technician III		24.53
30084 - Engineering Technician IV		27.90
30085 - Engineering Technician V		34.13
30086 - Engineering Technician VI		41.29
30090 - Environmental Technician		19.85
30210 - Laboratory Technician		18.62
30240 - Mathematical Technician		25.86
30361 - Paralegal/Legal Assistant I		17.91
30362 - Paralegal/Legal Assistant II		22.18
30363 - Paralegal/Legal Assistant III		27.14
30364 - Paralegal/Legal Assistant IV		32.83
30390 - Photo-Optics Technician		25.86
30461 - Technical Writer I		23.25
30462 - Technical Writer II		28.46
30463 - Technical Writer III		31.36
30491 - Unexploded Ordnance (UXO) Technician I		24.06
30492 - Unexploded Ordnance (UXO) Technician II		29.10
30493 - Unexploded Ordnance (UXO) Technician III		34.89
30494 - Unexploded (UXO) Safety Escort		24.06
30495 - Unexploded (UXO) Sweep Personnel		24.06
30620 - Weather Observer, Combined Upper Air Or Surface Programs	(see 2)	23.28
30621 - Weather Observer, Senior	(see 2)	25.86
31000 - Transportation/Mobile Equipment Operation Occupations		
31020 - Bus Aide		9.78

31030 - Bus Driver	15.04
31043 - Driver Courier	14.92
31260 - Parking and Lot Attendant	9.46
31290 - Shuttle Bus Driver	16.45
31310 - Taxi Driver	10.67
31361 - Truckdriver, Light	16.45
31362 - Truckdriver, Medium	17.99
31363 - Truckdriver, Heavy	19.54
31364 - Truckdriver, Tractor-Trailer	19.54
99000 - Miscellaneous Occupations	
99030 - Cashier	9.31
99050 - Desk Clerk	10.67
99095 - Embalmer	22.48
99251 - Laboratory Animal Caretaker I	10.75
99252 - Laboratory Animal Caretaker II	11.86
99310 - Mortician	24.52
99410 - Pest Controller	14.45
99510 - Photofinishing Worker	11.95
99710 - Recycling Laborer	15.31
99711 - Recycling Specialist	19.30
99730 - Refuse Collector	13.33
99810 - Sales Clerk	12.45
99820 - School Crossing Guard	11.80
99830 - Survey Party Chief	18.80
99831 - Surveying Aide	10.24
99832 - Surveying Technician	16.78
99840 - Vending Machine Attendant	12.85
99841 - Vending Machine Repairer	16.68
99842 - Vending Machine Repairer Helper	12.85

ALL OCCUPATIONS LISTED ABOVE RECEIVE THE FOLLOWING BENEFITS:

HEALTH & WELFARE: $4.27 per hour or $170.80 per week or $740.13 per month

VACATION: 2 weeks paid vacation after 1 year of service with a contractor or successor; 3 weeks after 5 years, 4 weeks after 15 years, and 5 weeks after 20 years. Length of service includes the whole span of continuous service with the present contractor or successor, wherever employed, and with the predecessor contractors in the performance of similar work at the same Federal facility. (Reg. 29 CFR 4.173)

HOLIDAYS: A minimum of ten paid holidays per year, New Year's Day, Martin Luther King Jr's Birthday, Washington's Birthday, Memorial Day, Independence Day, Labor Day, Columbus Day, Veterans' Day, Thanksgiving Day, and Christmas Day. (A contractor may substitute for any of the named holidays another day off with pay in accordance with a plan communicated to the employees involved.) (See 29 CFR 4174)

THE OCCUPATIONS WHICH HAVE NUMBERED FOOTNOTES IN PARENTHESES RECEIVE THE FOLLOWING:

1) COMPUTER EMPLOYEES: Under the SCA at section 8(b), this wage determination does not apply to any employee who individually qualifies as a bona fide executive, administrative, or professional employee as defined in 29 C.F.R. Part 541. Because most Computer System Analysts and Computer Programmers who are compensated at a rate not less than $27.63 (or on a salary or fee basis at a rate not less than $455 per week) an hour would likely qualify as exempt computer professionals, (29 C.F.R. 541.

400) wage rates may not be listed on this wage determination for all occupations within those job families. In addition, because this wage determination may not list a wage rate for some or all occupations within those job families if the survey data indicates that the prevailing wage rate for the occupation equals or exceeds $27.63 per hour conformances may be necessary for certain nonexempt employees. For example, if an individual employee is nonexempt but nevertheless performs duties within the scope of one of the Computer Systems Analyst or Computer Programmer occupations for which this wage determination does not specify an SCA wage rate, then the wage rate for that employee must be conformed in accordance with the conformance procedures described in the conformance note included on this wage determination.

Additionally, because job titles vary widely and change quickly in the computer industry, job titles are not determinative of the application of the computer professional exemption. Therefore, the exemption applies only to computer employees who satisfy the compensation requirements and whose primary duty consists of:
(1) The application of systems analysis techniques and procedures, including consulting with users, to determine hardware, software or system functional specifications;
(2) The design, development, documentation, analysis, creation, testing or modification of computer systems or programs, including prototypes, based on and related to user or system design specifications;
(3) The design, documentation, testing, creation or modification of computer programs related to machine operating systems; or
(4) A combination of the aforementioned duties, the performance of which requires the same level of skills. (29 C.F.R. 541.400).

2) AIR TRAFFIC CONTROLLERS AND WEATHER OBSERVERS - NIGHT PAY & SUNDAY PAY: If you work at night as part of a regular tour of duty, you will earn a night differential and receive an additional 10% of basic pay for any hours worked between 6pm and 6am. If you are a full-time employed (40 hours a week) and Sunday is part of your regularly scheduled workweek, you are paid at your rate of basic pay plus a Sunday premium of 25% of your basic rate for each hour of Sunday work which is not overtime (i.e. occasional work on Sunday outside the normal tour of duty is considered overtime work).

HAZARDOUS PAY DIFFERENTIAL: An 8 percent differential is applicable to employees employed in a position that represents a high degree of hazard when working with or in close proximity to ordinance, explosives, and incendiary materials. This includes work such as screening, blending, dying, mixing, and pressing of sensitive ordance, explosives, and pyrotechnic compositions such as lead azide, black powder and photoflash powder. All dry-house activities involving propellants or explosives. Demilitarization, modification, renovation, demolition, and maintenance operations on sensitive ordnance, explosives and incendiary materials. All operations involving regrading and cleaning of artillery ranges.

A 4 percent differential is applicable to employees employed in a position that represents a low degree of hazard when working with, or in close proximity to ordance, (or employees possibly adjacent to) explosives and incendiary materials which involves potential injury such as laceration of hands, face, or arms of the employee engaged in the operation, irritation of the skin, minor burns and the like; minimal damage to immediate or adjacent work area or equipment being used. All operations involving, unloading, storage, and hauling of ordance, explosive, and incendiary ordnance material other than small arms ammunition. These differentials are only applicable to work that has been specifically designated by the agency for ordance, explosives, and incendiary material differential pay.

** UNIFORM ALLOWANCE **

If employees are required to wear uniforms in the performance of this contract

(either by the terms of the Government contract, by the employer, by the state or local law, etc.), the cost of furnishing such uniforms and maintaining (by laundering or dry cleaning) such uniforms is an expense that may not be borne by an employee where such cost reduces the hourly rate below that required by the wage determination. The Department of Labor will accept payment in accordance with the following standards as compliance:

The contractor or subcontractor is required to furnish all employees with an adequate number of uniforms without cost or to reimburse employees for the actual cost of the uniforms. In addition, where uniform cleaning and maintenance is made the responsibility of the employee, all contractors and subcontractors subject to this wage determination shall (in the absence of a bona fide collective bargaining agreement providing for a different amount, or the furnishing of contrary affirmative proof as to the actual cost), reimburse all employees for such cleaning and maintenance at a rate of $3.35 per week (or $.67 cents per day). However, in those instances where the uniforms furnished are made of "wash and wear" materials, may be routinely washed and dried with other personal garments, and do not require any special treatment such as dry cleaning, daily washing, or commercial laundering in order to meet the cleanliness or appearance standards set by the terms of the Government contract, by the contractor, by law, or by the nature of the work, there is no requirement that employees be reimbursed for uniform maintenance costs.

The duties of employees under job titles listed are those described in the "Service Contract Act Directory of Occupations", Fifth Edition, April 2006, unless otherwise indicated. Copies of the Directory are available on the Internet. A links to the Directory may be found on the WHD home page at http://www.dol.gov/esa/whd/ or through the Wage Determinations On-Line (WDOL) Web site at http://wdol.gov/.

REQUEST FOR AUTHORIZATION OF ADDITIONAL CLASSIFICATION AND WAGE RATE {Standard Form 1444 (SF 1444)}

Conformance Process:

The contracting officer shall require that any class of service employee which is not listed herein and which is to be employed under the contract (i.e., the work to be performed is not performed by any classification listed in the wage determination), be classified by the contractor so as to provide a reasonable relationship (i.e., appropriate level of skill comparison) between such unlisted classifications and the classifications listed in the wage determination. Such conformed classes of employees shall be paid the monetary wages and furnished the fringe benefits as are determined. Such conforming process shall be initiated by the contractor prior to the performance of contract work by such unlisted class(es) of employees. The conformed classification, wage rate, and/or fringe benefits shall be retroactive to the commencement date of the contract. {See Section 4.6 (C)(vi)} When multiple wage determinations are included in a contract, a separate SF 1444 should be prepared for each wage determination to which a class(es) is to be conformed.

The process for preparing a conformance request is as follows:

1) When preparing the bid, the contractor identifies the need for a conformed occupation(s) and computes a proposed rate(s).

2) After contract award, the contractor prepares a written report listing in order proposed classification title(s), a Federal grade equivalency (FGE) for each proposed classification(s), job description(s), and rationale for proposed wage rate(s), including information regarding the agreement or disagreement of the authorized representative of the employees involved, or where there is no authorized representative, the employees themselves. This report should be submitted to the contracting officer no later than 30 days after such unlisted class(es) of employees

performs any contract work.

3) The contracting officer reviews the proposed action and promptly submits a report of the action, together with the agency's recommendations and pertinent information including the position of the contractor and the employees, to the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, for review. (See section 4.6(b)(2) of Regulations 29 CFR Part 4).

4) Within 30 days of receipt, the Wage and Hour Division approves, modifies, or disapproves the action via transmittal to the agency contracting officer, or notifies the contracting officer that additional time will be required to process the request.

5) The contracting officer transmits the Wage and Hour decision to the contractor.

6) The contractor informs the affected employees.

Information required by the Regulations must be submitted on SF 1444 or bond paper.

When preparing a conformance request, the "Service Contract Act Directory of Occupations" (the Directory) should be used to compare job definitions to insure that duties requested are not performed by a classification already listed in the wage determination. Remember, it is not the job title, but the required tasks that determine whether a class is included in an established wage determination. Conformances may not be used to artificially split, combine, or subdivide classifications listed in the wage determination.

WD 05-2111 (Rev.-17) was first posted on www.wdol.gov on 07/14/2015

****

REGISTER OF WAGE DETERMINATIONS UNDER THE SERVICE CONTRACT ACT By direction of the Secretary of Labor	U.S. DEPARTMENT OF LABOR EMPLOYMENT STANDARDS ADMINISTRATION WAGE AND HOUR DIVISION WASHINGTON D.C. 20210
Daniel W. Simms Director Division of Wage Determinations	Wage Determination No.: 2005-2111 Revision No.: 17 Date Of Revision: 07/08/2015

Note: Executive Order (EO) 13658 establishes an hourly minimum wage of $10.10 for 2015 that applies to all contracts subject to the Service Contract Act for which the solicitation is issued on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least $10.10 (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract. The EO minimum wage rate will be adjusted annually. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

State: Florida

Area: Florida Counties of Broward, Glades, Hendry, Martin, Okeechobee, Palm Beach, St Lucie

Fringe Benefits Required Follow the Occupational Listing

OCCUPATION CODE - TITLE	FOOTNOTE	RATE
01000 - Administrative Support And Clerical Occupations		
01011 - Accounting Clerk I		14.11
01012 - Accounting Clerk II		16.74
01013 - Accounting Clerk III		18.73
01020 - Administrative Assistant		22.64
01040 - Court Reporter		18.82
01051 - Data Entry Operator I		12.92
01052 - Data Entry Operator II		14.09
01060 - Dispatcher, Motor Vehicle		17.16
01070 - Document Preparation Clerk		12.67
01090 - Duplicating Machine Operator		12.67
01111 - General Clerk I		12.62
01112 - General Clerk II		13.88
01113 - General Clerk III		15.59
01120 - Housing Referral Assistant		20.88
01141 - Messenger Courier		12.39
01191 - Order Clerk I		12.71
01192 - Order Clerk II		13.86
01261 - Personnel Assistant (Employment) I		15.88
01262 - Personnel Assistant (Employment) II		17.90
01263 - Personnel Assistant (Employment) III		20.30
01270 - Production Control Clerk		20.00
01280 - Receptionist		13.44
01290 - Rental Clerk		14.93
01300 - Scheduler, Maintenance		16.74
01311 - Secretary I		16.74
01312 - Secretary II		18.73
01313 - Secretary III		20.88
01320 - Service Order Dispatcher		15.35
01410 - Supply Technician		23.21

01420 - Survey Worker	18.82
01531 - Travel Clerk I	12.57
01532 - Travel Clerk II	13.48
01533 - Travel Clerk III	14.33
01611 - Word Processor I	13.30
01612 - Word Processor II	14.93
01613 - Word Processor III	16.71
05000 - Automotive Service Occupations	
05005 - Automobile Body Repairer, Fiberglass	17.74
05010 - Automotive Electrician	16.61
05040 - Automotive Glass Installer	15.52
05070 - Automotive Worker	15.52
05110 - Mobile Equipment Servicer	13.34
05130 - Motor Equipment Metal Mechanic	17.56
05160 - Motor Equipment Metal Worker	15.52
05190 - Motor Vehicle Mechanic	17.68
05220 - Motor Vehicle Mechanic Helper	12.24
05250 - Motor Vehicle Upholstery Worker	14.42
05280 - Motor Vehicle Wrecker	15.52
05310 - Painter, Automotive	16.62
05340 - Radiator Repair Specialist	15.52
05370 - Tire Repairer	11.60
05400 - Transmission Repair Specialist	17.56
07000 - Food Preparation And Service Occupations	
07010 - Baker	12.65
07041 - Cook I	11.08
07042 - Cook II	12.90
07070 - Dishwasher	8.72
07130 - Food Service Worker	9.89
07210 - Meat Cutter	12.75
07260 - Waiter/Waitress	9.85
09000 - Furniture Maintenance And Repair Occupations	
09010 - Electrostatic Spray Painter	14.98
09040 - Furniture Handler	9.80
09080 - Furniture Refinisher	14.98
09090 - Furniture Refinisher Helper	11.03
09110 - Furniture Repairer, Minor	13.00
09130 - Upholsterer	16.48
11000 - General Services And Support Occupations	
11030 - Cleaner, Vehicles	9.80
11060 - Elevator Operator	10.39
11090 - Gardener	15.29
11122 - Housekeeping Aide	10.39
11150 - Janitor	10.39
11210 - Laborer, Grounds Maintenance	11.40
11240 - Maid or Houseman	9.59
11260 - Pruner	9.93
11270 - Tractor Operator	14.36
11330 - Trail Maintenance Worker	11.40
11360 - Window Cleaner	11.94
12000 - Health Occupations	
12010 - Ambulance Driver	15.34
12011 - Breath Alcohol Technician	17.33
12012 - Certified Occupational Therapist Assistant	26.46
12015 - Certified Physical Therapist Assistant	24.15
12020 - Dental Assistant	15.13
12025 - Dental Hygienist	31.91
12030 - EKG Technician	22.01
12035 - Electroneurodiagnostic Technologist	22.01
12040 - Emergency Medical Technician	15.34
12071 - Licensed Practical Nurse I	15.49

12072 - Licensed Practical Nurse II		17.33
12073 - Licensed Practical Nurse III		19.32
12100 - Medical Assistant		15.38
12130 - Medical Laboratory Technician		17.89
12160 - Medical Record Clerk		13.95
12190 - Medical Record Technician		15.38
12195 - Medical Transcriptionist		15.86
12210 - Nuclear Medicine Technologist		34.45
12221 - Nursing Assistant I		10.55
12222 - Nursing Assistant II		11.87
12223 - Nursing Assistant III		12.95
12224 - Nursing Assistant IV		14.87
12235 - Optical Dispenser		17.57
12236 - Optical Technician		15.24
12250 - Pharmacy Technician		15.81
12280 - Phlebotomist		14.87
12305 - Radiologic Technologist		25.46
12311 - Registered Nurse I		26.32
12312 - Registered Nurse II		29.80
12313 - Registered Nurse II, Specialist		29.80
12314 - Registered Nurse III		36.04
12315 - Registered Nurse III, Anesthetist		36.04
12316 - Registered Nurse IV		43.22
12317 - Scheduler (Drug and Alcohol Testing)		19.28
13000 - Information And Arts Occupations		
13011 - Exhibits Specialist I		19.30
13012 - Exhibits Specialist II		23.54
13013 - Exhibits Specialist III		28.80
13041 - Illustrator I		20.64
13042 - Illustrator II		25.57
13043 - Illustrator III		30.22
13047 - Librarian		30.39
13050 - Library Aide/Clerk		12.37
13054 - Library Information Technology Systems Administrator		26.99
13058 - Library Technician		16.53
13061 - Media Specialist I		16.17
13062 - Media Specialist II		18.41
13063 - Media Specialist III		20.54
13071 - Photographer I		15.46
13072 - Photographer II		17.30
13073 - Photographer III		21.43
13074 - Photographer IV		26.21
13075 - Photographer V		31.70
13110 - Video Teleconference Technician		16.88
14000 - Information Technology Occupations		
14041 - Computer Operator I		16.41
14042 - Computer Operator II		18.36
14043 - Computer Operator III		20.47
14044 - Computer Operator IV		22.75
14045 - Computer Operator V		25.19
14071 - Computer Programmer I	(see 1)	22.63
14072 - Computer Programmer II	(see 1)	
14073 - Computer Programmer III	(see 1)	
14074 - Computer Programmer IV	(see 1)	
14101 - Computer Systems Analyst I	(see 1)	
14102 - Computer Systems Analyst II	(see 1)	
14103 - Computer Systems Analyst III	(see 1)	
14150 - Peripheral Equipment Operator		16.41
14160 - Personal Computer Support Technician		22.75
15000 - Instructional Occupations		

15010 - Aircrew Training Devices Instructor (Non-Rated)	31.48
15020 - Aircrew Training Devices Instructor (Rated)	38.08
15030 - Air Crew Training Devices Instructor (Pilot)	41.70
15050 - Computer Based Training Specialist / Instructor	31.48
15060 - Educational Technologist	26.06
15070 - Flight Instructor (Pilot)	41.70
15080 - Graphic Artist	23.71
15090 - Technical Instructor	21.38
15095 - Technical Instructor/Course Developer	26.16
15110 - Test Proctor	17.26
15120 - Tutor	17.26
16000 - Laundry, Dry-Cleaning, Pressing And Related Occupations	
16010 - Assembler	9.62
16030 - Counter Attendant	9.62
16040 - Dry Cleaner	11.86
16070 - Finisher, Flatwork, Machine	9.62
16090 - Presser, Hand	9.62
16110 - Presser, Machine, Drycleaning	9.62
16130 - Presser, Machine, Shirts	9.62
16160 - Presser, Machine, Wearing Apparel, Laundry	9.62
16190 - Sewing Machine Operator	12.52
16220 - Tailor	13.18
16250 - Washer, Machine	10.41
19000 - Machine Tool Operation And Repair Occupations	
19010 - Machine-Tool Operator (Tool Room)	17.51
19040 - Tool And Die Maker	22.29
21000 - Materials Handling And Packing Occupations	
21020 - Forklift Operator	14.81
21030 - Material Coordinator	19.02
21040 - Material Expediter	19.02
21050 - Material Handling Laborer	12.17
21071 - Order Filler	11.60
21080 - Production Line Worker (Food Processing)	14.81
21110 - Shipping Packer	14.81
21130 - Shipping/Receiving Clerk	14.81
21140 - Store Worker I	9.45
21150 - Stock Clerk	14.43
21210 - Tools And Parts Attendant	14.81
21410 - Warehouse Specialist	14.81
23000 - Mechanics And Maintenance And Repair Occupations	
23010 - Aerospace Structural Welder	24.81
23021 - Aircraft Mechanic I	23.31
23022 - Aircraft Mechanic II	24.81
23023 - Aircraft Mechanic III	26.28
23040 - Aircraft Mechanic Helper	15.59
23050 - Aircraft, Painter	18.88
23060 - Aircraft Servicer	18.80
23080 - Aircraft Worker	20.33
23110 - Appliance Mechanic	18.53
23120 - Bicycle Repairer	11.60
23125 - Cable Splicer	24.61
23130 - Carpenter, Maintenance	17.55
23140 - Carpet Layer	17.51
23160 - Electrician, Maintenance	19.25
23181 - Electronics Technician Maintenance I	21.43
23182 - Electronics Technician Maintenance II	26.58
23183 - Electronics Technician Maintenance III	29.81
23260 - Fabric Worker	17.63
23290 - Fire Alarm System Mechanic	18.04
23310 - Fire Extinguisher Repairer	14.71
23311 - Fuel Distribution System Mechanic	18.65

23312 - Fuel Distribution System Operator	13.82
23370 - General Maintenance Worker	16.44
23380 - Ground Support Equipment Mechanic	23.31
23381 - Ground Support Equipment Servicer	18.80
23382 - Ground Support Equipment Worker	20.33
23391 - Gunsmith I	14.71
23392 - Gunsmith II	17.40
23393 - Gunsmith III	19.85
23410 - Heating, Ventilation And Air-Conditioning Mechanic	19.01
23411 - Heating, Ventilation And Air Contditioning Mechanic (Research Facility)	20.23
23430 - Heavy Equipment Mechanic	19.94
23440 - Heavy Equipment Operator	19.18
23460 - Instrument Mechanic	21.09
23465 - Laboratory/Shelter Mechanic	18.62
23470 - Laborer	11.51
23510 - Locksmith	17.22
23530 - Machinery Maintenance Mechanic	22.48
23550 - Machinist, Maintenance	18.00
23580 - Maintenance Trades Helper	13.90
23591 - Metrology Technician I	21.09
23592 - Metrology Technician II	22.74
23593 - Metrology Technician III	23.86
23640 - Millwright	21.19
23710 - Office Appliance Repairer	17.94
23760 - Painter, Maintenance	17.51
23790 - Pipefitter, Maintenance	20.20
23810 - Plumber, Maintenance	19.23
23820 - Pneudraulic Systems Mechanic	19.85
23850 - Rigger	19.85
23870 - Scale Mechanic	17.40
23890 - Sheet-Metal Worker, Maintenance	18.24
23910 - Small Engine Mechanic	15.52
23931 - Telecommunications Mechanic I	23.36
23932 - Telecommunications Mechanic II	25.46
23950 - Telephone Lineman	20.79
23960 - Welder, Combination, Maintenance	18.69
23965 - Well Driller	18.71
23970 - Woodcraft Worker	19.85
23980 - Woodworker	14.71
24000 - Personal Needs Occupations	
24570 - Child Care Attendant	9.49
24580 - Child Care Center Clerk	15.33
24610 - Chore Aide	9.40
24620 - Family Readiness And Support Services Coordinator	14.45
24630 - Homemaker	17.05
25000 - Plant And System Operations Occupations	
25010 - Boiler Tender	19.01
25040 - Sewage Plant Operator	20.16
25070 - Stationary Engineer	19.01
25190 - Ventilation Equipment Tender	12.86
25210 - Water Treatment Plant Operator	20.16
27000 - Protective Service Occupations	
27004 - Alarm Monitor	20.47
27007 - Baggage Inspector	10.61
27008 - Corrections Officer	25.15
27010 - Court Security Officer	28.50
27030 - Detection Dog Handler	18.11
27040 - Detention Officer	25.15

27070 - Firefighter		26.09
27101 - Guard I		10.61
27102 - Guard II		18.11
27131 - Police Officer I		30.90
27132 - Police Officer II		34.34
28000 - Recreation Occupations		
28041 - Carnival Equipment Operator		13.37
28042 - Carnival Equipment Repairer		14.74
28043 - Carnival Equpment Worker		9.40
28210 - Gate Attendant/Gate Tender		14.63
28310 - Lifeguard		13.49
28350 - Park Attendant (Aide)		16.39
28510 - Recreation Aide/Health Facility Attendant		11.96
28515 - Recreation Specialist		19.57
28630 - Sports Official		13.04
28690 - Swimming Pool Operator		17.92
29000 - Stevedoring/Longshoremen Occupational Services		
29010 - Blocker And Bracer		21.65
29020 - Hatch Tender		21.65
29030 - Line Handler		21.65
29041 - Stevedore I		20.86
29042 - Stevedore II		24.35
30000 - Technical Occupations		
30010 - Air Traffic Control Specialist, Center (HFO)	(see 2)	37.85
30011 - Air Traffic Control Specialist, Station (HFO)	(see 2)	26.10
30012 - Air Traffic Control Specialist, Terminal (HFO)	(see 2)	28.74
30021 - Archeological Technician I		15.98
30022 - Archeological Technician II		18.25
30023 - Archeological Technician III		24.98
30030 - Cartographic Technician		25.86
30040 - Civil Engineering Technician		23.88
30061 - Drafter/CAD Operator I		18.66
30062 - Drafter/CAD Operator II		20.89
30063 - Drafter/CAD Operator III		23.28
30064 - Drafter/CAD Operator IV		28.66
30081 - Engineering Technician I		18.79
30082 - Engineering Technician II		21.92
30083 - Engineering Technician III		24.53
30084 - Engineering Technician IV		29.22
30085 - Engineering Technician V		35.73
30086 - Engineering Technician VI		41.29
30090 - Environmental Technician		20.88
30210 - Laboratory Technician		18.62
30240 - Mathematical Technician		25.86
30361 - Paralegal/Legal Assistant I		17.91
30362 - Paralegal/Legal Assistant II		22.18
30363 - Paralegal/Legal Assistant III		27.14
30364 - Paralegal/Legal Assistant IV		32.83
30390 - Photo-Optics Technician		25.86
30461 - Technical Writer I		23.25
30462 - Technical Writer II		28.46
30463 - Technical Writer III		32.87
30491 - Unexploded Ordnance (UXO) Technician I		24.06
30492 - Unexploded Ordnance (UXO) Technician II		29.10
30493 - Unexploded Ordnance (UXO) Technician III		34.89
30494 - Unexploded (UXO) Safety Escort		24.06
30495 - Unexploded (UXO) Sweep Personnel		24.06
30620 - Weather Observer, Combined Upper Air Or Surface Programs	(see 2)	23.28
30621 - Weather Observer, Senior	(see 2)	25.86
31000 - Transportation/Mobile Equipment Operation Occupations		

31020 - Bus Aide	9.78
31030 - Bus Driver	14.86
31043 - Driver Courier	14.92
31260 - Parking and Lot Attendant	9.46
31290 - Shuttle Bus Driver	16.45
31310 - Taxi Driver	11.02
31361 - Truckdriver, Light	16.45
31362 - Truckdriver, Medium	17.99
31363 - Truckdriver, Heavy	19.54
31364 - Truckdriver, Tractor-Trailer	19.54
99000 - Miscellaneous Occupations	
99030 - Cashier	9.31
99050 - Desk Clerk	10.67
99095 - Embalmer	21.54
99251 - Laboratory Animal Caretaker I	10.75
99252 - Laboratory Animal Caretaker II	11.86
99310 - Mortician	24.52
99410 - Pest Controller	14.26
99510 - Photofinishing Worker	11.95
99710 - Recycling Laborer	15.31
99711 - Recycling Specialist	19.30
99730 - Refuse Collector	13.33
99810 - Sales Clerk	12.58
99820 - School Crossing Guard	11.80
99830 - Survey Party Chief	18.42
99831 - Surveying Aide	11.12
99832 - Surveying Technician	16.78
99840 - Vending Machine Attendant	11.67
99841 - Vending Machine Repairer	14.81
99842 - Vending Machine Repairer Helper	11.66

ALL OCCUPATIONS LISTED ABOVE RECEIVE THE FOLLOWING BENEFITS:

HEALTH & WELFARE: $4.27 per hour or $170.80 per week or $740.13 per month

VACATION: 2 weeks paid vacation after 1 year of service with a contractor or successor; 3 weeks after 5 years, and 4 weeks after 15 years. Length of service includes the whole span of continuous service with the present contractor or successor, wherever employed, and with the predecessor contractors in the performance of similar work at the same Federal facility. (Reg. 29 CFR 4.173)

HOLIDAYS: A minimum of ten paid holidays per year, New Year's Day, Martin Luther King Jr's Birthday, Washington's Birthday, Memorial Day, Independence Day, Labor Day, Columbus Day, Veterans' Day, Thanksgiving Day, and Christmas Day. (A contractor may substitute for any of the named holidays another day off with pay in accordance with a plan communicated to the employees involved.) (See 29 CFR 4174)

THE OCCUPATIONS WHICH HAVE NUMBERED FOOTNOTES IN PARENTHESES RECEIVE THE FOLLOWING:

1) COMPUTER EMPLOYEES: Under the SCA at section 8(b), this wage determination does not apply to any employee who individually qualifies as a bona fide executive, administrative, or professional employee as defined in 29 C.F.R. Part 541. Because most Computer System Analysts and Computer Programmers who are compensated at a rate not less than $27.63 (or on a salary or fee basis at a rate not less than $455 per

week) an hour would likely qualify as exempt computer professionals, (29 C.F.R. 541. 400) wage rates may not be listed on this wage determination for all occupations within those job families. In addition, because this wage determination may not list a wage rate for some or all occupations within those job families if the survey data indicates that the prevailing wage rate for the occupation equals or exceeds $27.63 per hour conformances may be necessary for certain nonexempt employees. For example, if an individual employee is nonexempt but nevertheless performs duties within the scope of one of the Computer Systems Analyst or Computer Programmer occupations for which this wage determination does not specify an SCA wage rate, then the wage rate for that employee must be conformed in accordance with the conformance procedures described in the conformance note included on this wage determination.

Additionally, because job titles vary widely and change quickly in the computer industry, job titles are not determinative of the application of the computer professional exemption. Therefore, the exemption applies only to computer employees who satisfy the compensation requirements and whose primary duty consists of:
(1) The application of systems analysis techniques and procedures, including consulting with users, to determine hardware, software or system functional specifications;
(2) The design, development, documentation, analysis, creation, testing or modification of computer systems or programs, including prototypes, based on and related to user or system design specifications;
(3) The design, documentation, testing, creation or modification of computer programs related to machine operating systems; or
(4) A combination of the aforementioned duties, the performance of which requires the same level of skills. (29 C.F.R. 541.400).

2) AIR TRAFFIC CONTROLLERS AND WEATHER OBSERVERS - NIGHT PAY & SUNDAY PAY: If you work at night as part of a regular tour of duty, you will earn a night differential and receive an additional 10% of basic pay for any hours worked between 6pm and 6am. If you are a full-time employed (40 hours a week) and Sunday is part of your regularly scheduled workweek, you are paid at your rate of basic pay plus a Sunday premium of 25% of your basic rate for each hour of Sunday work which is not overtime (i.e. occasional work on Sunday outside the normal tour of duty is considered overtime work).

HAZARDOUS PAY DIFFERENTIAL: An 8 percent differential is applicable to employees employed in a position that represents a high degree of hazard when working with or in close proximity to ordinance, explosives, and incendiary materials. This includes work such as screening, blending, dying, mixing, and pressing of sensitive ordance, explosives, and pyrotechnic compositions such as lead azide, black powder and photoflash powder. All dry-house activities involving propellants or explosives. Demilitarization, modification, renovation, demolition, and maintenance operations on sensitive ordnance, explosives and incendiary materials. All operations involving regrading and cleaning of artillery ranges.

A 4 percent differential is applicable to employees employed in a position that represents a low degree of hazard when working with, or in close proximity to ordance, (or employees possibly adjacent to) explosives and incendiary materials which involves potential injury such as laceration of hands, face, or arms of the employee engaged in the operation, irritation of the skin, minor burns and the like; minimal damage to immediate or adjacent work area or equipment being used. All operations involving, unloading, storage, and hauling of ordance, explosive, and incendiary ordnance material other than small arms ammunition. These differentials are only applicable to work that has been specifically designated by the agency for ordance, explosives, and incendiary material differential pay.

** UNIFORM ALLOWANCE **

If employees are required to wear uniforms in the performance of this contract (either by the terms of the Government contract, by the employer, by the state or local law, etc.), the cost of furnishing such uniforms and maintaining (by laundering or dry cleaning) such uniforms is an expense that may not be borne by an employee where such cost reduces the hourly rate below that required by the wage determination. The Department of Labor will accept payment in accordance with the following standards as compliance:

The contractor or subcontractor is required to furnish all employees with an adequate number of uniforms without cost or to reimburse employees for the actual cost of the uniforms. In addition, where uniform cleaning and maintenance is made the responsibility of the employee, all contractors and subcontractors subject to this wage determination shall (in the absence of a bona fide collective bargaining agreement providing for a different amount, or the furnishing of contrary affirmative proof as to the actual cost), reimburse all employees for such cleaning and maintenance at a rate of $3.35 per week (or $.67 cents per day). However, in those instances where the uniforms furnished are made of "wash and wear" materials, may be routinely washed and dried with other personal garments, and do not require any special treatment such as dry cleaning, daily washing, or commercial laundering in order to meet the cleanliness or appearance standards set by the terms of the Government contract, by the contractor, by law, or by the nature of the work, there is no requirement that employees be reimbursed for uniform maintenance costs.

The duties of employees under job titles listed are those described in the "Service Contract Act Directory of Occupations", Fifth Edition, April 2006, unless otherwise indicated. Copies of the Directory are available on the Internet. A links to the Directory may be found on the WHD home page at http://www.dol.gov/esa/whd/ or through the Wage Determinations On-Line (WDOL) Web site at http://wdol.gov/.

REQUEST FOR AUTHORIZATION OF ADDITIONAL CLASSIFICATION AND WAGE RATE {Standard Form 1444 (SF 1444)}

Conformance Process:

The contracting officer shall require that any class of service employee which is not listed herein and which is to be employed under the contract (i.e., the work to be performed is not performed by any classification listed in the wage determination), be classified by the contractor so as to provide a reasonable relationship (i.e., appropriate level of skill comparison) between such unlisted classifications and the classifications listed in the wage determination. Such conformed classes of employees shall be paid the monetary wages and furnished the fringe benefits as are determined. Such conforming process shall be initiated by the contractor prior to the performance of contract work by such unlisted class(es) of employees. The conformed classification, wage rate, and/or fringe benefits shall be retroactive to the commencement date of the contract. {See Section 4.6 (C)(vi)} When multiple wage determinations are included in a contract, a separate SF 1444 should be prepared for each wage determination to which a class(es) is to be conformed.

The process for preparing a conformance request is as follows:

1) When preparing the bid, the contractor identifies the need for a conformed occupation(s) and computes a proposed rate(s).

2) After contract award, the contractor prepares a written report listing in order proposed classification title(s), a Federal grade equivalency (FGE) for each proposed classification(s), job description(s), and rationale for proposed wage rate(s), including information regarding the agreement or disagreement of the authorized representative of the employees involved, or where there is no authorized representative, the employees themselves. This report should be submitted to the

contracting officer no later than 30 days after such unlisted class(es) of employees performs any contract work.

3) The contracting officer reviews the proposed action and promptly submits a report of the action, together with the agency's recommendations and pertinent information including the position of the contractor and the employees, to the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, for review. (See section 4.6(b)(2) of Regulations 29 CFR Part 4).

4) Within 30 days of receipt, the Wage and Hour Division approves, modifies, or disapproves the action via transmittal to the agency contracting officer, or notifies the contracting officer that additional time will be required to process the request.

5) The contracting officer transmits the Wage and Hour decision to the contractor.

6) The contractor informs the affected employees.

Information required by the Regulations must be submitted on SF 1444 or bond paper.

When preparing a conformance request, the "Service Contract Act Directory of Occupations" (the Directory) should be used to compare job definitions to insure that duties requested are not performed by a classification already listed in the wage determination. Remember, it is not the job title, but the required tasks that determine whether a class is included in an established wage determination. Conformances may not be used to artificially split, combine, or subdivide classifications listed in the wage determination.

K. REPRESENTATIONS, CERTIFICATIONS, AND OTHER STATEMENTS OF BIDDERS/OFFERERS

52.204-8 ANNUAL REPRESENTATIONS AND CERTIFICATIONS (DEC 2014)

(a)

(1) The North American Industry classification System (NAICS) code for this acquisition is 561210.

(2) The small business size standard is $38.5M.

(3) The small business size standard for a concern which submits an offer in its own name, other than on a construction or service contract, but which proposes to furnish a product which it did not itself manufacture, is 500 employees.

(b)

(1) If the provision at 52.204-7, System for Award Management, is included in this solicitation, paragraph (d) of this provision applies.

(2) If the provision at 52.204-7 is not included in this solicitation, and the offeror is currently registered in the System for Award Management (SAM), and has completed the Representations and Certifications section of SAM electronically, the offeror may choose to use paragraph (d) of this provision instead of completing the corresponding individual representations and certification in the solicitation. The offeror shall indicate which option applies by checking one of the following boxes:

[_] (i) Paragraph (d) applies.

[_] (ii) Paragraph (d) does not apply and the offeror has completed the individual representations and certifications in the solicitation.

(c)

(1) The following representations or certifications in SAM are applicable to this solicitation as indicated:

(i)) 52.203-2, Certificate of Independent Price Determination. This provision applies to solicitations when a firm-fixed-price contract or fixed-price contract with economic price adjustment is contemplated, unless—

(A) The acquisition is to be made under the simplified acquisition procedures in Part 13;

(B) The solicitation is a request for technical proposals under two-step sealed bidding procedures; or

(C) The solicitation is for utility services for which rates are set by law or regulation.

(ii)) 52.203-11, Certification and Disclosure Regarding Payments to Influence Certain Federal Transactions. This provision applies to solicitations expected to exceed $150,000.

(iii)) 52.204-3, Taxpayer Identification. This provision applies to solicitations that do not include the provision at 52.204-7, System for Award Management.

(iv)) 52.204-5, Women-Owned Business (Other Than Small Business). This provision applies to solicitations that—

(A) Are not set aside for small business concerns;

(B) Exceed the simplified acquisition threshold; and

(C)) Are for contracts that will be performed in the United States or its outlying areas.

(v) 52.209-2, Prohibition on Contracting with Inverted Domestic Corporations—Representation.

(vi) ; Certification Regarding Responsibility Matters. This provision applies to solicitations where the contract value is expected to exceed the simplified acquisition threshold.

(vii) lace of Performance--Sealed Bidding. This provision applies to invitations for bids except those in which the place of performance is specified by the Government.

(viii) lace of Performance. This provision applies to solicitations unless the place of performance is specified by the Government.

(ix)) 52.219-1, Small Business Program Representations (Basic & Alternate I). This provision applies to solicitations when the contract will be performed in the United States or its outlying areas.

(A) The basic provision applies when the solicitations are issued by other than DoD, NASA, and the Coast Guard.

(B) The provision with its Alternate I applies to solicitations issued by DoD, NASA, or the Coast Guard.

(x) 52.219-2, Equal Low Bids. This provision applies to solicitations when contracting by sealed bidding and the contract will be performed in the United States or its outlying areas.

(xi) evious Contracts and Compliance Reports. This provision applies to solicitations that include the clause at 52.222-26, Equal Opportunity.

(xii) irmative Action Compliance. This provision applies to solicitations, other than those for construction, when the solicitation includes the clause at 52.222-26, Equal Opportunity.

(xiii) Compliance with Veterans' Employment Reporting Requirements. This provision applies to solicitations when it is anticipated the contract award will exceed the simplified acquisition threshold and the contract is not for acquisition of commercial items.

(xiv) v) 52.223-1, Biobased Product Certification. This provision applies to solicitations that require the delivery or specify the use of USDA-designated items;

or include the clause at 52.223-2, Affirmative Procurement of Biobased Products Under Service and Construction Contracts.

(xv) 52.223-4, Recovered Material Certification. This provision applies to solicitations that are for, or specify the use of, EPA- designated items.

(xvi) Buy American Certificate. This provision applies to solicitations containing the clause at 52.225-1.

(xvii) Buy American--Free Trade Agreements--Israeli Trade Act Certificate. (Basic, Alternates I, II, and III.) This provision applies to solicitations containing the clause at 52.225- 3.

(A) If the acquisition value is less than $25,000, the basic provision applies.

(B)) If the acquisition value is $25,000 or more but is less than $50,000, the provision with its Alternate I applies.

(C)) If the acquisition value is $50,000 or more but is less than $79,507, the provision with its Alternate II applies.

(D) If the acquisition value is $79,507 or more but is less than $100,000, the provision with its Alternate III applies.

(xviii) Trade Agreements Certificate. This provision applies to solicitations containing the clause at 52.225-5.

(xix) x) 52.225-20, Prohibition on Conducting Restricted Business Operations in Sudan--Certification. This provision applies to all solicitations.

(xx) 52.225-25, Prohibition on Contracting with Entities Engaging in Certain Activities or Transactions Relating to Iran—Representation and Certification. This provision applies to all solicitations.

(xxi) istorically Black College or University and Minority Institution Representation. This provision applies to solicitations for research, studies, supplies, or services of the type normally acquired from higher educational institutions.

(2) The following certifications are applicable as indicated by the Contracting Officer:

[Contracting Officer check as appropriate.]

_x__(i) 52.204-17, Ownership or Control of Offeror.

____(ii) 52.222-18, Certification Regarding Knowledge of Child Labor for Listed End Products.

____(iii) 52.222-48, Exemption from Application of the Service Contract Labor Standards to Contracts for Maintenance, Calibration, or Repair of Certain Equipment--Certification.

____(iv) 52.222-52 Exemption from Application of the Service Contract Labor Standards to Contracts for Certain Services--Certification.

___(v) 52.223-9, with its Alternate I, Estimate of Percentage of Recovered Material Content for EPA-Designated Products (Alternate I only).

___(vi) 52.227-6, Royalty Information.

___(A) Basic.

___(B) Alternate I.

___(vii) 52.227-15, Representation of Limited Rights Data and Restricted Computer Software.

(d) The offeror has completed the annual representations and certifications electronically via the SAM Web site accessed through https://www.acquisition.gov . After reviewing the SAM database information, the offeror verifies by submission of the offer that the representations and certifications currently posted electronically that apply to this solicitation as indicated in paragraph (c) of this provision have been entered or updated within the last 12 months, are current, accurate, complete, and applicable to this solicitation (including the business size standard applicable to the NAICS code referenced for this solicitation), as of the date of this offer and are incorporated in this offer by reference (see FAR 4.1201); except for the changes identified below *[offeror to insert changes, identifying change by clause number, title, date]*. These amended representation(s) and/or certification(s) are also incorporated in this offer and are current, accurate, and complete as of the date of this offer.

FAR Clause	Title	Date	Change

Any changes provided by the offeror are applicable to this solicitation only, and do not result in an update to the representations and certifications posted on SAM.

(End of Provision)

52.209-7 INFORMATION REGARDING RESPONSIBILITY MATTERS (JULY 2013)

(a)) Definitions. As used in this provision--

"Administrative proceeding" means a non-judicial process that is adjudicatory in nature in order to make a determination of fault or liability (e.g., Securities and Exchange Commission Administrative Proceedings, Civilian Board of Contract Appeals Proceedings, and Armed Services Board of Contract Appeals Proceedings). This includes administrative proceedings at the Federal and State level but only in connection with performance of a Federal contract or grant. It does not include agency actions such as contract audits, site visits, corrective plans, or inspection of deliverables.

"Federal contracts and grants with total value greater than $10,000,000" means--

(1) The total value of all current, active contracts and grants, including all priced options; and

(2) The total value of all current, active orders including all priced options under indefinitedelivery, indefinite-quantity, 8(a), or requirements contracts (including task and delivery and multiple-award Schedules).

"Principal" means an officer, director, owner, partner, or a person having primary management or supervisory responsibilities within a business entity (e.g., general manager; plant manager; head of a division or business segment; and similar positions).
(b) The offeror [ ] has [ ] does not have current active Federal contracts and grants with total value greater than $10,000,000.
(c)) If the offeror checked "has" in paragraph (b) of this provision, the offeror represents, by submission of this offer, that the information it has entered in the Federal Awardee Performance and Integrity Information System (FAPIIS) is current, accurate, and complete as of the date of submission of this offer with regard to the following information:
(1) Whether the offeror, and/or any of its principals, has or has not, within the last five years, in connection with the award to or performance by the offeror of a Federal contract or grant, been the subject of a proceeding, at the Federal or State level that resulted in any of the following dispositions:
(i)) In a criminal proceeding, a conviction.
(ii)) In a civil proceeding, a finding of fault and liability that results in the payment of a monetary fine, penalty, reimbursement, restitution, or damages of $5,000 or more.
(iii)) In an administrative proceeding, a finding of fault and liability that results in--
(A) The payment of a monetary fine or penalty of $5,000 or more; or
(B) The payment of a reimbursement, restitution, or damages in excess of $100,000.
(iv)) In a criminal, civil, or administrative proceeding, a disposition of the matter by consent or compromise with an acknowledgment of fault by the Contractor if the proceeding could have led to any of the outcomes specified in paragraphs (c)(1)(i), (c)(1)(ii), or (c)(1)(iii) of this provision.
(2) If the offeror has been involved in the last five years in any of the occurrences listed in (c)(1) of this provision, whether the offeror has provided the requested information with regard to each occurrence.
(d) The offeror shall post the information in paragraphs (c)(1)(i) through (c)(1)(iv) of this provision in FAPIIS as required through maintaining an active registration in the System for Award Management database at https://www.acquisition.gov (see 52.204-7).
(End of provision)

52.204-19 Incorporation by Reference of Representations and Certifications (DEC 2014)

The Contractor’s representations and certifications, including those completed electronically via the System for Award Management (SAM), are incorporated by reference into the contract.

L.

INSTRUCTIONS FOR SUBMITTING PROPOSAL

L.1 52.204-7 SYSTEM FOR AWARD MANAGEMENT (JUL 2013)

(a) Definitions. As used in this provision—

"Data Universal Numbering System (DUNS) number" means the 9-digit number assigned by Dun and Bradstreet, Inc. (D&B) to identify unique business entities.

"Data Universal Numbering System+4 (DUNS+4) number" means the DUNS number means the number assigned by D&B plus a 4-character suffix that may be assigned by a business concern. (D&B has no affiliation with this 4-character suffix.) This 4-character suffix may be assigned at the discretion of the business concern to establish additional System for Award Management records for identifying alternative Electronic Funds Transfer (EFT) accounts (see the FAR at Subpart 32.11) for the same concern.

"Registered in the System for Award Management (SAM) database" means that—

(1) The Offeror has entered all mandatory information, including the DUNS number or the DUNS+4 number, the Contractor and Government Entity (CAGE) code, as well as data required by the Federal Funding Accountability and Transparency Act of 2006 (see Subpart 4.14), into the SAM database; and

(2) The offeror has completed the Core, Assertions, and Representations and Certification, and Points of contact sections of the registration in the SAM database;

(3) The Government has validated all mandatory data fields, to include validation of the Taxpayer Identification Number (TIN) with the Internal Revenue Service (IRS). The Offeror will be required to provide consent for TIN validation to the Government as a part of the SAM registration process.

(4) The Government has marked the record "Active".

(b)

(1) By submission of an offer, the offeror acknowledges the requirement that a prospective awardee shall be registered in the SAM database prior to award, during performance, and through final payment of any contract, basic agreement, basic ordering agreement, or blanket purchasing agreement resulting from this solicitation.

(2) The offeror shall enter, in the block with its name and address on the cover page of its offer, the annotation "DUNS" or "DUNS+4" followed by the DUNS or DUNS+4 number that identifies the offeror's name and address exactly as stated in the offer. The DUNS number will be used by the Contracting Officer to verify that the offeror is registered in the SAM database.

(c) If the offeror does not have a DUNS number, it should contact Dun and Bradstreet directly to obtain one.

(1) An offeror may obtain a DUNS number—

(i) Via the internet at http://fedgov.dnb.com/webform or if the offeror does not have internet access, it may call Dun and Bradstreet at 1-866-705-5711 if located within the United States; or

(ii) If located outside the United States, by contacting the local Dun and Bradstreet office. The offeror should indicate that it is an offeror for a U.S. Government contract when contacting the local Dun and Bradstreet office.

(2) The offeror should be prepared to provide the following information:

(i) Company legal business name.

(ii) Tradestyle, doing business, or other name by which your entity is commonly recognized.

(iii) Company physical street address, city, state and Zip Code.

(iv) Company mailing address, city, state and Zip Code (if separate from physical).

(v) Company telephone number.

(vi) Date the company was started.

(vii) Number of employees at your location.

(viii) Chief executive officer/key manager.

(ix) Line of business (industry).

(x) Company Headquarters name and address (reporting relationship within your entity).

(d) If the Offeror does not become registered in the SAM database in the time prescribed by the Contracting Officer, the Contracting Officer will proceed to award to the next otherwise successful registered Offeror.

(e) Processing time, which normally takes 48 hours, should be taken into consideration when registering. Offerors who are not registered should consider applying for registration immediately upon receipt of this solicitation.

(f) Offerors may obtain information on registration at https://www.acquisition.gov.

(End of Provision)

L.2 52.215-1 INSTRUCTIONS TO OFFERORS--COMPETITIVE ACQUISITION (JAN 2004)

L.3 52.222-24 PREAWARD ON-SITE EQUAL OPPORTUNITY COMPLIANCE EVALUATION (FEB 1999)

L.4 52.237-1 SITE VISIT (APR 1984)

L.5 52.216-1 TYPE OF CONTRACT (APR 1984) The Government contemplates award of a Firm-Fixed Price contract resulting from this solicitation.

(End of Provision)

L.6 52.233-2 SERVICE OF PROTEST (SEP 2006)

(a)) Protests, as defined in section 33.101 of the Federal Acquisition Regulation, that are filed directly with an agency, and copies of any protests that are filed with the General Accountability Office (GAO), or the General Services Administrtaion Board of Contract Appeals (GSBCA), shall be served on the Contracting Officer, (addressed as follows)by obtaining written and dated acknowledgment of receipt from:

General Services Administration
Attn: Tiffanie N. Oglesby
Acquisition Division, 4PQSA
77 Forsyth Street, Suite T8
Atlanta, GA 30303

(b) The copy of any protest shall be received in the office designated above within one day of filing a protest with the GAO.

(End of Provision)

L.7 52.252-1 SOLICITATION PROVISIONS INCORPORATED BY REFERENCE (FEB 1998)

This solicitation incorporates one or more solicitation provisions by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. The offeror is cautioned that the listed provisions may include blocks that must be completed by the offeror and submitted with its quotation or offer. In lieu of submitting the full

text of those provisions, the offeror may identify the provision by paragraph identifier and provide the appropriate information with its quotation or offer. Also, the full text of a solicitation provision may be accessed electronically at this/these address(es): www.acquisition.gov

(End of Provision)

L.8 552.252-5 AUTHORIZED DEVIATIONS IN PROVISIONS (DEVIATION FAR 52.252-5) (SEP 1999)

(a)) "Deviations to FAR provisions."
(1) This solicitation indicates any authorized deviation to a Federal Acquisition Regulation (48 CFR Chapter 1) provision by the addition of "(DEVIATION)" after the date of the provision, if the provision is not published in the General Services Administration Acquisition Regulation (48 CFR Chapter 5).
(2) This solicitation indicates any authorized deviation to a Federal Acquisition Regulation (FAR) provision that is published in the General Services Administration Acquisition Regulation by the addition of "(DEVIATION (FAR provision no.))" after the date of the provision.
(b) "Deviations to GSAR provisions." This solicitation indicates any authorized deviation to a General Services Administration Acquisition Regulation provision by the addition of "(DEVIATION)" after the date of the provision.
(c)) "Substantially the same as" provisions. Changes in wording of provisions prescribed for use on a "substantially the same as" basis are not considered deviations.

(End of Provision)

L.9 INSPECTION OF FACILITY RESERVED

~~**A.** Offerors are **encouraged** to attend the scheduled site visit to make an in-depth review of the facility, equipment, job requirements, etc. in order to determine the condition of the building(s) and equipment systems to be maintained.~~

~~**B. The pre-proposal conference will be held on Tuesday, June 23, 2015, via teleconference from 8:00 a.m. to 9:00 a.m. EST. The call in number for this conference is 1-866-928-2008; enter participant code 898746 to join call.**~~

~~C. The pre-proposal site visit will be held beginning on Tuesday, June 23, 2015 at 10:00 a.m. EST at the Alto Lee Adams Sr Courthouse in Fort Pierce, FL . All questions SHALL be submitted in writing via email to the Contract Specialist below. No more than three (3) representatives per potential offeror shall attend. No questions may be asked at the tour. The detailed tour schedule is below:~~

Miami 6 Pre-proposal Site Visit Schedule

Tues, June 23, 2015: Ft. Pierce & Fort Lauderdale
Meet at Alto Lee Adams CH, Ft. Pierce, 10:00am, outside of main entrance under overhead walkway, tour guide Keith Wright, Jonathan Cox , and Christopher Singian.
Meet at U.S. Courthouse, Ft. Lauderdale, 2:30pm, outside of main entrance (west side of building), tour guide Keith Wright, Jonathan Cox, and Cassandra Perez .

Wed, June 24, 2015: Claude Pepper & King Building
Meet at Claude Pepper, 8am, outside of main public entrance (notify guards), tour guide Keith Wright, Jonathan Cox , and Sheri Toyosi.
Meet at King Building, 10:30am, outside of main public entrance, tour guide Keith Wright, Jonathan Cox ,and Kevin Pryor

Thurs, June 25, 2015: Key West
Meet at Sydney M. Arnovitz CH, Key West, 8am, outside of main public entrance, tour guide Keith Wright, Jonathan Cox, and Christine Allen.

Fri, June 26, 2015: Brickell Plaza
Meet at Brickell Plaza, 9am, outside of main public entrance, tour guide Keith Wright, Jonathan Cox, and Giselle Mudarra

ALL questions are to be submitted in writing to the Contracting Specialist at the below email address no later than 1730 EST on Wednesday, July 1, 2015. Responses to questions will be posted via an amendment to the solicitation and posted to FedBiz Ops.

You are subject to a security check; please do not bring weapons, cameras, laptops, IPADS etc... of any kind. **NO ELECTRONIC DEVICES ALLOWED.**

Failure to attend the pre-proposal site visit meeting may not be used as an excuse for omissions of miscalculations in your proposal. No other tours will be scheduled

For further information pertaining to the site visit, please contact Amanda Hodge, Contract Specialist, at Amanda.Hodge@gsa.gov.

L.10. Instructions For Submitting Proposal

L.10.1 General

The instructions below provide guidance for the preparation and submission of the proposal. The purpose is to establish requirements for the format and content of the proposal so that the proposal is complete, contains all the essential information, and can be evaluated equitably. The price proposal should reflect the pricing data submitted under Section B.

L.10.2 Submission and Content of Proposal

A. Proposals shall be submitted in three (3) separate envelopes as follows:

(i) Part One --- Technical Proposal

(ii) Part Two --- Price Proposal

(iii) Part Three --- Electronic Copy

B. Offerors shall submit one (1) hard copy of both the technical and price proposal in addition to one (1) electronic copy of each submitted on an unencrypted USB Flash Drive/Jump drive containing no executable files (i.e. should contain Word, Adobe PDF, Excel files ONLY). The technical proposal shall not contain any pricing. The hard copy and electronic copy of both the technical and price proposals should mirror each other. Should there be any discrepancies or if the hard copy and electronic copy fail to mirror each other, the hard copy will be used during the evaluation. The electronic copy will not then be evaluated. The proposal package shall be comprised of three (3) sealed envelopes, one to contain the technical proposal and marked "TECHNICAL PROPOSAL RFP GS-04P-15-EW-D-0088". One envelope shall contain the price proposal and marked "PRICE PROPOSAL RFP GS-04P-15-EW-D-0088". The third envelope shall contain the electronic copy of both the technical and price proposal and marked "ELECTRONIC COPY RFP GS-04P-15-EW-D-0088". All three envelopes shall be sealed in a fourth envelope and/or container and should be identified with the solicitation number and offeror's name.

The proposal shall be submitted to Amanda Hodge, Contract Specialist, at the following address:

77 Forsyth Street
Terrace Level
Martin Luther King Federal Building
Atlanta, GA 30303

L.11. Contents Of Technical Proposal

The offeror's technical proposal shall be in the format described below.

L.11.1 Minimum Performance Standard

Complete and submit the "Minimum Performance Standards" worksheet provided at L.18. The references provided shall be for projects performed for a minimum of twenty- four (24) consecutive months within the past five years of the issuance date of this solicitation that are similar in size, scope and complexity to this requirement. The minimum square footage for similar size is 250,000 sq. ft.

Provide a summary of each recent and relevant experience demonstrating how each falls within the definition of recent and relevant as defined in Section M.4. Additionally, it is the contractor's responsibility to provide valid references and phone numbers.

If the contractor marks 'Yes' but does not provide the supporting information as requested, the offer will be considered technically unacceptable.

If the references provided cannot be reached or information cannot be validated, the Minimum Performance Standard factor will be considered technically unacceptable.

The contractor will be technically unacceptable if they cannot meet the minimum standards.

L.11. 2 MANAGEMENT APPROACH

The Management Approach should reflect the Offeror's clear understanding of the requirements, deliverables, and ability to successfully perform all requirements as outlined in the Performance Work Statement, Section "C" of the contract. The offerors' response will be evaluated to determine if the Offeror can successfully perform the requirements of the Performance Work Statement. An acceptable rating for each sub-factor must be received for the Management Approach to be considered technically Acceptable.

- **Organizational Chart**
  a. Staffing by numbers/location,
     i. To be found technically acceptable, the proposal shall completely and adequately address this sub-factor to demonstrate that the Offeror can successfully perform the requirements outlined in Performance Work Statement (PWS).
- **Preventative Maintenance Program**
  a. Maintenance standard for maintaining equipment/systems.
     i. To be found technically acceptable, the proposal shall completely and adequately address this sub-factor to demonstrate that the Offeror can successfully perform the requirements outlined in PWS.
- **Service Order Dispatch**
  a. Service Requests tracking/reporting
     i. To be found technically acceptable, the proposal shall completely and adequately address this sub-factor to demonstrate that the Offeror can successfully perform the requirements outlined in PWS.
- **Training Plan**
  a. Training
     i. To be found technically acceptable, the proposal shall completely and adequately address this sub-factor to demonstrate that the Offeror can successfully perform the requirements outlined in PWS .
- **Cleaning program**
  a. Green Cleaning Plan
     i. To be found technically acceptable, the proposal shall completely and adequately address this sub-factor to demonstrate that the Offeror can successfully perform the requirements outlined in PWS.
  b. Pest Control Program
     i. To be found technically acceptable, the proposal shall completely and adequately address this sub-factor to demonstrate that the Offeror can successfully perform the requirements outlined in PWS .
  c. Ground Maintenance.
     i. To be found technically acceptable, the proposal shall completely and adequately address this sub-factor to demonstrate that the Offeror can successfully perform the requirements outlined in PWS.

The narrative for L.11.2 Management Approach shall be no more than 50 type-written pages 8 ½ x 11 in 12 font. The page limit includes any charts and illustrations.

L.11. 3 PAST PERFORMANCE

Past Performance is relevant information regarding an Offeror's performance under previously awarded contracts. The Offeror shall provide three (3) Past Performance Questionnaires (Appendix I, page 348) for projects where the Contractor performed for a minimum of twenty-four (24) consecutive months within the past five years that are similar in size, scope and complexity of services and equipment to the ones described in this solicitation. Of these three (3) Past Performance Questionnaires, **the contractor shall submit one (1) project consisting of Janitorial and related services and two (2) projects consisting of Operations and Maintenance services of a facility size of at least 250,000 square feet and similar in scope and complexity of services and equipment as described in this solicitation.** The offeror SHALL clearly identify on their past performance questionnaires a 1, 2, or 3. This shall occur for both the O&M and Janitorial submission(s). Any past performance questionnaires submitted beyond the three projects requested SHALL NOT BE CONSIDERED. Offeror SHALL submit the aforementioned past performance questionnaires with their proposal submission. The minimum square footage for similar size is 250,000 sq. ft.

If submitting information for current/ongoing contracts, the Contractor must have a minimum of twenty-four (24) months experience performing the services at those locations by the issuance date of this solicitation in order for those contracts to be deemed relevant.

The Offeror cannot use the same reference (i.e., same project and same contact person) more than once.

The past performance questionnaires (Appendix I, page 348) SHALL be completed by the appropriate agency or commercial individual responsible for administration or oversight of the projects referenced.

If an offeror submits their proposal as an SBA approved joint venture or teaming arrangement, unless the prior experience submitted is specifically for the joint venture or teaming arrangement, each firm in the joint venture or teaming arrangement will be required to provide past performance references in accordance with the terms outlined above relevant to the services they are to perform.

In addition to those references provided directly by the Offeror, the Contracting Officer may identify and analyze the past performance of the Offeror on any other contract on which they have performed within the past five (5) years of which the Contracting Officer has knowledge or obtains knowledge. In addition, all offerors will be evaluated in accordance with FAR 15.305(a)(2)(iv). A "neutral" rating from this inquiry will be deemed "acceptable" for purposes of 15.305(a)(2)(iv).

APPENDIX I

Past Performance Questionnaire

Contract Number: _____

Total Contract Value: $_____

Contract Term: _____

Size of Area Contractor is Responsible For: _____

Service(s) Provided: _____

1. Does the contractor have an effective quality control program? ( ) Yes ( ) No
2. Is the contractor's service delivery performed in a timely manner? ( ) Yes ( ) No
3. Did the staff appear to be adequately trained in the performance of their duties?
   ( ) Yes ( ) No
4. Were the tenants/customers generally satisfied with the services performed by the contractor?
   ( ) Yes ( ) No
5. Has the contractor performed satisfactorily in accordance with the contractual terms and conditions?
   ( ) Yes ( ) No
8. Did the contract run its full term? ( ) Yes ( ) No

If no, please explain: _____

_____

_____

Please provide any other comments:_____

_____

_____

_____

_____

Thank you for taking the time to provide your evaluation. The U.S. General Services Administration appreciates the time and effort required in preparing a response.

Based on the above information and any other considerations you may have, please provide an overall adjectival rating of "***acceptable***," or "**unacceptable**"

I hereby assign a rating of_____to the contractor based on my knowledge and experience.

Client Information

Name: _____

Title: _____

Phone Number: _____

Email Address: _____

_____ _____

Signature Date

L.12. Information To Be Included In Price Proposal

L.12.1 General

The price proposal should reflect the pricing data submitted under the Bid Sheets.

L.12.2 Specific Instructions For Price Proposal

The following instructions are provided to assist offerors in developing the price proposal.

(a) Direct Costs:

(i) Labor: Submit manning tables showing the basis for the labor cost proposed.

(ii) Labor Burden: Submit a schedule showing the basis of the amount of payroll burden proposed. The labor burden should include such items as FICA, FUTA, SUTA, Workmen's Compensation, etc., and the cost of providing fringe benefits such as holiday, vacation, and sick pay.

(iii) Other Direct Costs: Prepare a supporting schedule to define all direct costs not included above in the cost summary, e.g., uniform allowances, equipment repair costs, etc.

(b) Indirect Costs: Enter a dollar amount allocable to this contract from your company General and Administrative (G&A) and/or Overhead pool. Indirect costs are costs incurred for common or joint objectives and not readily subject treatment as direct costs. Identify the company's policy and procedures for allocated G&A expenses. Include a schedule that shows the computation of the proposed G&A rate. This rate will also apply to maintenance repair performed on an hourly basis.

(c) Subcontracts: Prepare a subcontract schedule which identifies all functions to be subcontracted and amount of each subcontract.

(d) Supplies, Materials, and Replacement Parts: Prepare a supporting schedule of supplies, materials, and replacement parts. List the items proposed by description, unit costs, quantity, and extended total cost.

(e) Equipment: Prepare a supporting schedule of equipment. List equipment proposed by nomenclature, unit cost, quantity, and extended total cost. Prepare separate schedule of equipment which will be depreciated.

L.13. Notice to Joint Ventures

If an offeror will be submitting a proposal under a joint venture, the joint venture's legal name shall be registered in the System for Award Management (SAM) database, the On-line Representations and Certifications Application database, and possess a Data Universal Numbering System (DUNS) number by the time of proposal submission. If the Joint Venture's legal name is not registered in SAM by the time of proposal submission, the offeror will not be

considered for award. In addition, the joint venture's legal name shall be clearly printed in Block 17a of the SF1449 when submitting the proposal package.

The proposal must clearly state who the prime contractor will be for the joint venture. In addition, a copy of the executed joint venture agreement shall be on file with the contracting office prior to award. If the joint venture is submitted under the 8A Small Business Program, it shall be subject to approval by the U.S. Small Business Administration prior to award in accordance with 13 CFR 124.513.

L.14. Service Classification And Size Standard

The services covered by this solicitation are classified as Facility Support Services (NAIC) 561210. The small business size standard is $38.5 Million.

L.15. OFFERORS INTERESTED IN MORE THAN ONE PROPOSAL

If more than one proposal is offered by any one party by or in the name of his or their clerk, partner, or other person, all such proposal may be rejected. This shall not prevent an offerors from submitting alternative proposals when called for. A party who has quoted prices on materials to an offerors is not thereby disqualified from quoting prices to other offerors or from submitting a proposal directly for the contemplated work.

L.16. Preparation, Receipt And Opening Of PROPOSAL

Offer shall submit one original copy (one copy of **Standard Form 33** only) on the form furnished, and the original copy shall be signed in ink (original signatures). Only one copy of the remaining

required information shall be furnished with the bid/offer package. Offer signed by an agency shall be accompanied by evidence of his authority.

L.17. Small Business Assistance

NEED HELP? There are many places where it is available. In addition to the Federal Government, sources such as GSA's Office of Enterprise Development and the Small Business Administration, assistance is available from Small Business Development Centers and Procurement Technical Assistance Centers located at major state supported colleges and universities. These Centers are funded in part by the Federal Government and can assist you with quality control, pre-award surveys, marketing, contract administration and other contractual matters.

Trained counselors will help you understand a solicitation's requirements and terminology and guide you through the bidding process. Individual counseling on bid/proposal preparation is also available. Workshops and seminars on How to Bid, How to Market, How to Negotiate, Selling to the Government and other subjects related to the Federal procurement process are conducted at many Centers on an ongoing basis. Contact the college or university nearest you and ask about this free service, or contact the GSA's Office of Enterprise Development at (404) 331-3032.

L.18. Minimum Performance Standards

Review each minimum performance standard listed below, and respond to the questions located across the top of the form. Fill in appropriate reference information by name, number, and company. If the contractor marks 'Yes' but does not provide valid supporting information as outlined in L.11.1, the offer will be considered as technically unacceptable.

If the contractor cannot validate meeting the minimum standard select 'No".

The contractor will be technically unacceptable if they cannot meet the below minimum standards, and the offer will not be evaluated and will not be considered for award.

Minimum Performance Standard	Meet Minimum Standard	Does Not Meet Minimal Standards	Provide a reference contact by name & phone # and/or email for each standard	For Government Use Only
Identifying, implementing, controlling, tracking and scheduling preventive maintenance, service request, and equipment inventory in an automated database				
Performing Quality Control inspections utilizing qualified parties not actually performing the work being inspected				
Updating and maintaining building equipment inventory to include all mechanical & associated peripheral equipment				
Meeting operational performance goals such as energy and water usage (Implementing Energy Conservation Measures)				
Performing and/or Managing Janitorial & related Services (grounds maintenance) in commercial class A buildings				
Performing Integrated Pest Management for a building similar in size to the U.S. Courthouse, Key West, FL				
Performing Trash and Solid Waste Disposal and Removal for a building similar in size to the U.S. Courthouse Key West, FL.				
Operating, and maintaining facilities of similar size and complexity as those required under this contract. Complexity as further defined includes, but is not limited to, HVAC equipment, AHU, Pumps, Life Safety, and EMS (to include all design settings/control strategies).				

M.

EVALUATION FACTORS FOR AWARD

M.1. FAR 52.217-5 EVALUATION OF OPTIONS (JUL 1990)

Except when it is determined in accordance with FAR 17.206(b) not to be in the Government's best interests, the Government will evaluate offers for award purposes by adding the total price for all options to the total price for the basic requirement. Evaluation of options will not obligate the Government to exercise the option(s).

(END OF PROVISION)

M.2. FAR 52.232-15 PROGRESS PAYMENTS NOT INCLUDED (APR 1984)

A progress payments clause is not included in this solicitation, and will not be added to the resulting contract at the time of award. Bids conditioned upon inclusion of a progress payment clause in the resulting contract will be rejected as nonresponsive.

(END OF PROVISION)

M.3. UNBALANCED OFFERS

The Government may determine that a proposal is unacceptable if the prices proposed are materially unbalanced between line items or sub-line items. Unbalanced pricing exists when, despite an acceptable total evaluated price, the price of one or more contract line items is significantly overstated or understated as indicated by the application of cost or price analysis techniques. A proposal may be rejected if the Contracting Officer determines that the lack of balance poses an unacceptable risk to the Government. (FAR 52.215-1(f)(8).

M.4. FACTORS FOR AWARD

A. Basis of Award

This acquisition will utilize Lowest Price Technically Acceptable (LPTA) source selection procedures in accordance with FAR 15.101-2,

Accordingly, award will be made on the basis of the lowest evaluated price of the proposal meeting the technical factors. No tradeoffs are permitted. Additionally, proposals will be evaluated for acceptability but not ranked using the non-cost/price factors.

To be considered technically acceptable, no evaluation factor in the offer may be determined to be unacceptable. The failure of a proposal to meet all of the requirements under any factor will result in a technically unacceptable rating and preclude award.

The Government may reject any or all proposals if such action is in the Government's interest.

The Government may waive informalities and minor irregularities in proposals received.

The Government intends to evaluate proposals and award on initial proposal submission. Therefore, the offeror's initial proposal shall contain the offeror's most favorable terms from a technical and price standpoint. However, exchanges may occur.

Any costs incurred by offerors in preparing or submitting offers are the offerors' sole responsibility; the United States will not reimburse any offeror for any proposal preparation costs.

Proposals shall be valid for a minimum of 90 calendar days after submission or will be deemed technically unacceptable.

B. Lowest Price Technically Acceptable Evaluation Process

The technical factors will be evaluated on an "Acceptable" or "Unacceptable" basis. The "Acceptable" and "Unacceptable" criteria will define a standard of comparison for the solicitation requirements. Proposals shall completely and adequately address (sub) factor(s) to demonstrate that the Offeror can successfully perform the solicitation technical requirements to be considered as "Acceptable" and therefore technically acceptable. Proposals failing to demonstrate that the Offeror can successfully perform all the solicitation technical requirements will be considered as "Unacceptable" and therefore not technically acceptable.

The Government will first rank proposals by price. Then the government will evaluate the technical proposal of the lowest offeror.If the technical proposal of the lowest price offeror is found to be technically acceptable, price will then be evaluated for reasonableness and realism in accordance with Section M-6 Price Evaluation contained in the solicitation. The Government intends to evaluate the technical proposals of only the lowest priced offer. The remaining technical proposals, if any, shall not be evaluated as to technical acceptability unless the lowest price offers proves to be technically unacceptable. If the lowest priced proposals proves to be technically unacceptable, then the second-lowest priced proposal (and so on) will be evaluated for technical acceptability.

Owing to the volume of responses anticipated and the desire on the part of the Government for an equitable and accurate assessment of each proposal, offerors shall submit proposals conforming to the structure described in Section L. Proposals which do not conform to all requirements described in Section L may be rejected without further evaluation.

The Government intends to select ONE contractor for award of this effort.

Award may be made without negotiation or discussion. Therefore, offerors are requested to initially submit proposals to the Government on the most favorable terms from a technical and price standpoint.

C. Technical Factors

For the purpose of award, the government shall evaluate offers based on the evaluation factors described below:

Factor 1 – Minimum Performance Standards

To be considered technically acceptable, the Offeror has met the minimum performance standards in section L.18 and the references provided are for projects performed for a minimum of twenty-four (24) consecutive months within the past five years of the issuance date of this solicitation that are similar in size, scope and complexity to this requirement.

The minimum square footage for similar size is 250,000 sq. ft.

If the contractor marks 'Yes' but does not provide the supporting information as requested above, the offer will be considered technically unacceptable.

If the references provided cannot be reached or information cannot be validated, the Minimum Performance Standard factor will be considered technically unacceptable.

The contractor will be technically unacceptable if they cannot meet the minimum standards.

Minimum Performance Standards Acceptability Criteria	
Rating	**Description**
Acceptable	The Offeror meets the minimum performance standards which indicate that the Offeror has the capability to successfully perform this requirement.
Unacceptable	The Offeror does not meet the Minimum Performance Standards which does not provide the Government with any degree of comfort that the Offeror has the capability to successfully perform this requirement.

For the minimum performance to be considered it must be recent and relevant performance. The definition of recent and relevant is defined below. If the minimum performance was not performed within the parameters of the recent and relevant definitions, then that minimum performance will be considered as technically unacceptable.

Relevancy	
Rating	**Definition**
Acceptable	Services provided are for projects similar in size, scope and complexity to the one described in this solicitation.
Unacceptable	Services provided are not for projects similar in size, scope and complexity to the one described in this solicitation.

Recency	
Rating	**Definition**
Acceptable	Project has been performed for a minimum of twenty-four (24) consecutive months within the past five years . of the issuance date of this solicitation

Unacceptable	Project has not been performed for a minimum of twenty-four (24) consecutive months within the past five years of the issuance date of this solicitation.

Factor 2 - Management Approach

The Management Approach should reflect the Offeror's clear understanding of the requirements, deliverables, and ability to successfully perform all requirements as outlined in the Performance Work Statement, Section "C" of the contract. The offerors' response will be evaluated to determine if the Offeror can successfully perform the requirements of the Performance Work Statement. An acceptable rating for each subfactor must be received for the Management Approach to be considered technically Acceptable.

- **Organizational Chart**
  a. Staffing by numbers/location,
     i. To be found technically acceptable, the proposal shall completely and adequately address this sub-factor to demonstrate that the Offeror can successfully perform the requirements outlined in the Performance Work Statement (PWS).
- **Preventative Maintenance Program**
  a. Maintenance standard for maintaining equipment/systems.
     i. To be found technically acceptable, the proposal shall completely and adequately address this sub-factor to demonstrate that the Offeror can successfully perform the requirements outlined in the PWS.
- **Service Order Dispatch**
  a. Service Requests tracking/reporting
     i. To be found technically acceptable, the proposal shall completely and adequately address this sub-factor to demonstrate that the Offeror can successfully perform the requirements outlined in the PWS .
- **Training Plan**
  a. Training
     i. To be found technically acceptable, the proposal shall completely and adequately address this sub-factor to demonstrate that the Offeror can successfully perform the requirements outlined in the PWS.
- **Cleaning program**
  a. Green Cleaning Plan
     i. To be found technically acceptable, the proposal shall completely and adequately address this sub-factor to demonstrate that the Offeror can

successfully perform the requirements outlined in the PWS.

b. Pest Control Program

i. To be found technically acceptable, the proposal shall completely and adequately address this sub-factor to demonstrate that the Offeror can successfully perform the requirements outlined in the PWS.

c. Ground Maintenance.

i. To be found technically acceptable, the proposal shall completely and adequately address this sub-factor to demonstrate that the Offeror can successfully perform the requirements outlined in the PWS.

Technical Acceptability Criteria	
Rating	**Description**
Acceptable	The proposal demonstrates that the Offeror can successfully perform this requirement.
Unacceptable	The proposal does not demonstrate that the Offeror can successfully perform this requirement.

FACTOR 3 – PAST PERFORMANCE

Past Performance is relevant information regarding an Offeror's performance under previously awarded contracts. The Offeror shall provide three (3) Past Performance Questionnaires (Appendix I, page 348) for projects where the Contractor performed for a minimum of twenty-four (24) consecutive months within the past five years that are similar in size, scope and complexity of services and equipment to the ones described in this solicitation. Of these three (3) Past Performance Questionnaires, **the contractor shall submit one (1) project consisting of Janitorial and related services and two (2) projects consisting of Operations and Maintenance services of a facility size of at least 250,000 square feet and similar in scope and complexity of services and equipment as described in this solicitation.** The offeror SHALL clearly identify on their past performance questionnaires a 1, 2, or 3. This shall occur for both the O&M and Janitorial submission(s). Any past performance questionnaires submitted beyond the three projects requested SHALL NOT BE CONSIDERED. Offeror SHALL submit the aforementioned past performance questionnaires with their proposal submission. The minimum square footage for similar size is 250,000 sq. ft.

If submitting information for current/ongoing contracts, the Contractor must have a minimum of twenty-four (24) months experience performing the services at those locations by the issuance date of this solicitation in order for those contracts to be deemed relevant.

The Offeror cannot use the same reference (i.e., same project and same contact person) more than once.

The past performance questionnaires (Appendix I) SHALL be completed by the appropriate agency or commercial individual responsible for administration or oversight of the projects referenced.

If an offeror submits their proposal as an SBA approved joint venture or teaming arrangement, unless the prior experience submitted is specifically for the joint venture or teaming arrangement, each firm in the joint venture or teaming arrangement will be required to provide past performance references in accordance with the terms outlined above relevant to the services they are to perform.

In addition to those references provided directly by the Offeror, the Contracting Officer may identify and analyze the past performance of the Offeror on any other contract on which they have performed within the past five (5) years of which the Contracting Officer has knowledge or obtains knowledge. In addition, all offerors will be evaluated in accordance with FAR 15.305(a)(2)(iv). A "neutral" rating from this inquiry will be deemed "acceptable" for purposes of FAR 15.305(a)(2)(iv).

Past Performance Acceptability Criteria	
Rating	**Description**
Acceptable	Based on the Offeror's performance record, the Government has a reasonable expectation that the Offeror will successfully perform the required effort, or the Offeror's past performance record is unknown.
Unacceptable	Based on the Offeror's performance record, the Government has no reasonable expectation that the Offeror will be able to successfully perform the required effort.

For the Past performance record to be considered, it must meet the definition of recency and relevancy as defined below.

Relevancy	
Rating	**Definition**
Acceptable	Services provided are for projects similar in size, scope and complexity to the one described in this solicitation.
Unacceptable	Services provided are not for projects similar in size, scope and complexity to the one described in this solicitation.

Recency	
Rating	**Definition**

Acceptable	Project has been performed for a minimum of twenty-four(24) consecutive months within the past five years.
Unacceptable	Project has not been performed for a minimum of twenty-four (24) consecutive months within the past five years.

M.5. FORMULA FOR EVALUATING – PRICE PROPOSALS

The Total Evaluated Contract Price shall be the sum of the calculations computed by adding the following:

A. The total monthly prices on the Bid Sheets multiplied by the number of months for the initial year and each option year for operation and mechanical services, janitorial related services, pest control and landscape and ground maintenance as applicable to each building.
B. Plus, additional mechanical maintenance, overtime mechanical maintenance, emergency call back, architectural structure/Maintenance repair and miscellaneous labor for all buildings x 25 hours.
C. Plus, proposed overhead, profit and fee x $100,000.
D. Plus, additional janitorial services, and overtime janitorial services for all buildings x 50 hours, and proposed carpet cleaning x 10,000 square feet and blind cleaning x1.

The Total Evaluated Contract Price shall be the sum of the calculations in subparagraph M.5-A through M.5-D.

M.6. PRICE EVALUATION FACTORS

A price analysis will be conducted to determine if the proposed price is considered fair and reasonable.

The Government may determine that a proposal is unacceptable if the prices proposed are materially unbalanced between line items or sub-line items (52.215-1(f)(8)).

J.16. EQUIPMENT INVENTORY/CMMS

Alto Lee Adams SR, US Courthouse, FL0030ZZ O&M
101 South US Highway 1
Fort Pierce, FL 34950
111,306 rentable square feet (rsf)

United States Courthouse

Fort Pierce, FL

Equipment List

Plan Number	TAG No	Task #	R S Means Cross Reference	Description	Equipment Location	Egency Equip.	Equip Start-up	Model	Serial No.
	MCSYS	C-6,8	D3065 100 1950	BASS/EMS	Maintenance Office		X	#-PMC-2346-12 Serial#-110873	N/A
13851	FPCP	F-6 A,B		Fire Pump controler	Basement		X	ECKTZ-150-10046-FHJNOYX	110872
WEG	FIRP	F-6 A,B	D4015 210 1950	Fire Pump	Parkin Lot		X	100360P3E365TS1.0SF	29JUN09-1004843966
Simplex	N/A	F-1 - F-17		Fire Alarm Panell 1	!st Floor		X	4100-U	
Simplex	N/A	F-1 - F-17		Fire Alarm Panell 2	!st Floor		X	4100-U	
Simplex	N/A	F-1 - F-17		ID Net Pannel	!st Floor		X	4000-ID-NET	N/A
Simplex	N/A	F-1 - F-17		ID Net Pannel	!st Floor			4000-ID-NET	N/A
Simplex	N/A	F-1 - F-17		ID Net Pannel	!st Floor			4000-ID-NET	N/A
Fire Extingushers	FE	F 22, 24,25		Fire Extingushers total of 63 10 LBS	All Levels			3010	N/A
V.C. Packaged Pump System	DWP1-2	P-4		Domstic Water Pump	Basement		X	2VC-VFD	VC10-2832
15185-01	CHWP-1	P-4	G3015 126 1095	Chilled Water Pump	Basement		X	R352-Type-DE-FR-256T-	RPM-1775/H.P-20./230/460/3
15185-02	CHWP-2	P-4	G3015 126 1095	Chilled Water Pump	Basement		X	R352-Type-DE-FR-256T-	RPM-1775/H.P-20./230/460/3
15185-03	CWP-1	P-4	G3015 126 1095	Condenser Water Pump	Basement		X	R352-Type-DE-FR-256T-	RPM-1775/H.P-20./230/460/3
15185-04	CWP-2	P-4	G3015 126 1095	Condenser Water Pump	Basement		X	R352-Type-DE-FR-256T-	RPM-1775/H.P-20./230/460/3
15185-05	CHWP-3	P-4	G3015 126 1095	Chilled Water Pump	Basement		X	HVF145TTDR3543ABP	903586
15185-06	CHWP-4	P-4	G3015 126 1095	Chilled Water Pump	Basement		X	HVF145TTDR3543ABP	903586
N/A	Water tre	W-8	G3015 650 1950	Chemical Pump	Chiller room		X	AA151-392S1	3DT-5000-B-1036
N/A	Water tre	W-8	G3015 650 1950	Chemical Pump	Chiller room		X	AA151-392S1	3DT-5000-B-1036
N/A	Water tre	W-8	G3015 650 1950	Chemical Pump	Chiller room		X	AA151-392S1	3DT-5000-B-1036
N/A	Water tre	W-8	G3015 650 1950	Chemical Controller	Chiller room		X	3DT-5000-B-1036	30483
15185-07	RCP-2.1	P4	G3015 126 1095	Domestic Hot Water Recirculating Pump	2ND FLOOR		X	UP15-29SU	5989-6775PI

United States Courthouse

Fort Pierce, FL

Equipment List

Plan Number	TAG No	Task #	R S Means Cross Reference	Description	Equipment Location	Egency Equip.	Equip Start-up	Model	Serial No.
N/A	Abb-Drives	X-50A	N/A	VFD	Loading Dock		X	ACH550-VDR-03A3-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Roof		X	ACH550-VDR-03A3-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Roof		X	ACH550-VDR-03A3-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Roof		X	ACH550-VDR-03A3-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Roof		X	ACH550-VDR-03A3-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Roof		X	ACH550-VDR-03A3-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Roof		X	ACH550-VDR-03A3-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Chiller Room		X	ACH550-VDR-03A3-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	GSA Mail Room		X	ACH550-VDR-04A1-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Roof Fan		X	ACH550-VDR-031A-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Roof Fan		X	ACH550-VDR-031A-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Garage Exhaust Fan		X	ACH550-VDR-06A9-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Garage Exhaust Fan		X	ACH550-VDR-06A9-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Garage Exhaust Fan		X	ACH550-VDR-03A3-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Garage Exhaust Fan		X	ACH550-VDR-03A3-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	MU. Sup. Smoke		X	ACH550-VDR-045A-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Loading Dock		X	ACH550-VDR-03A3-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	CT. RM. MU. AIR		X	ACH550-VDR-03A3-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	CT. RM. MU. AIR		X	ACH550-VDR-03A3-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	1ST FLOOR		X	ACH550-VDR-059A-4+F267	21032000015
N/A	Abb-Drives	X-50A	N/A	VFD	1ST FLOOR		X	ACH550-VDR-059A-4+F267	21032000041

United States Courthouse

Fort Pierce, FL

Equipment List

Plan Number	TAG No	Task #	R S Means Cross Reference	Description	Equipment Location	Egency Equip.	Equip Start-up	Model	Serial No.
N/A	Abb-Drives	X-50A	N/A	VFD	3RD FLOOR		X	ACH550-VDR-038A-4+F267	21032000011
N/A	Abb-Drives	X-50A	N/A	VFD	5TH-FL-Roof		X	ACH550-VDR-O59A-4+F267	21032000007
N/A	Abb-Drives	X-50A	N/A	VFD	Basement		X	ACH550-VDR-031A-4+F267	21032000020
N/A	Abb-Drives	X-50A	N/A	VFD	5TH-FL-Roof		X	ACH550-VDR-045A-4+F267	21032000037
N/A	Abb-Drives	X-50A	N/A	VFD	Basement		X	ACH550-VDR-031A-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Basement		X	ACH55O-VDR-031A-4+F267	210320000
N/A	Abb-Drives	X-50A	N/A	VFD	Outside Grd. Level		X	ACH550-VDR-031A-4+F267	210320000
15444-01	DB-1, DB-2	X-50A	N/A	Packaged Duplex Domestic Water	Basement		X	2VC-VFD	VC10-2832
15444-01	DB-1, DB-2	X-50A	N/A	Domestic Water Pumps	Basement		X	2VC-VFD	VC10-2832
15485-01	EWH-0.1	H3	N/A	Electric Tankless Water Heater	Basement	X	X	016647-45	11BC77279
15485-02	EWH-0.2	H3	N/A	Electric Tankless Water Heater	Basement	X	X	016647-45	11BC77279
15485-03	EWH-1.1	H3	N/A	Electric Tankless Water Heater	1ST FLOOR	X	X	016647-45	11BC77279
15485-04	EWH-1.2	H3	N/A	Electric Water Heater	1ST FLOOR	X	X	016647-45	11BC77279
15485-05	EWH-1.3	H3	N/A	Electric Tankless Water Heater	1ST FLOOR	X	X	016647-45	11BC77279
15485-06	EWH-1.4	H3	N/A	Electric Tankless Water Heater	1ST FLOOR	X	X	016647-45	11BC77279
15485-07	EWH-2.1	H3	N/A	Electric Water Heater	2ND FLOOR	X	X	DRE-120-100	1101M000684
15485-08	EWH-2.2	H3	N/A	Electric Water Heater	2ND FLOOR	X	X	DRE-120-100	1101M000685
15485-08A	EWH-2.2A	H3	N/A	Electric Water Heater	2ND FLOOR	X	X	016647-45	11BC77279
15485-09	EWH-2.3	H3	N/A	Electric Water Heater	2ND FLOOR	X	X	016647-45	11BC77279
15485-10	EWH-2.4	H3	N/A	Electric Tankless Water Heater	2ND FLOOR	X	X	016647-45	11BC77279

15485-11	EWH-3.1	H3	N/A	Electric Tankless Water Heater	3RD FLOOR	X	X	016647-45	11BC77279
15485-12	EWH-3.2	H3	N/A	Electric Tankless Water Heater	3RD FLOOR	X	X	016647-45	11BC77279

United States Courthouse

Fort Pierce, FL

Equipment List

Plan Number	TAG No	Task #	R S Means Cross Reference	Description	Equipment Location	Egency Equip.	Equip Start-up	Model	Serial No.
15485-13	EWH-4.0	H3	N/A	Electric Water Heater	4TH FLOOR	X	X	016647-45	11BC77279
15485-14	EWH-4.1	H3	N/A	Electric Tankless Water Heater	4TH FLOOR	X	X	016647-45	11BC77279
15485-15	EWH-4.2	H3	N/A	Electric Tankless Water Heater	4TH FLOOR	X	X	016647-45	11BC77279
15485-16	EWH-4.3	H3	N/A	Electric Water Heater	4TH FLOOR		X	016647-45	11BC77279
15485-17	EWH-4.4	H3	N/A	Electric Water Heater	4TH FLOOR		X	016647-45	11BC77279
15485-18	EWH-4.5	H3	N/A	Electric Tankless Water Heater	4TH FLOOR	X	X	016647-45	11BC77279
15485-19	EWH-4.6	H3	N/A	Electric Tankless Water Heater	4TH FLOOR	X	X	016647-45	11BC77279
15485-20	EWH-4.7	H3	N/A	Electric Tankless Water Heater	4TH FLOOR	X	X	016647-45	11BC77279
15625-01	CH-1	R-5,8, 11,13 14	D3035 140 2950	Water Cooled Chiller	BASEMENT		X	CVHE400	LO9HO1177
15625-02	CH-2	R-5,8, 11,13 14	D3035 140 2950	Water Cooled Chiller	BASEMENT		X	CVHE400	LO9HO1316
15625-03	CH-3	R-6,8, 11,13 14	D3035 130 2950	Air Cooled Chiller	Ground		X	CGAM-052F-2C02-AXD2-A1B1	U1OCI5312
15641-01	CT-1	C9- C10	D3035 110 2950	Cooling Tower	Ground		X	NC8304E1	10014322-A2-NC8405PANGF-09
15641-02	CT-2	C9- C10	D3035 110 2950	Cooling Tower	Ground		X	NC8304E1	10014322-A2-NC8405PANGF-10
15720-01	AHU-1	A11	D3045 110 2950	Air Handling Unit	1ST FLOOR		X	MCCBO5OUAOCOUB	KO9J31681
15720-02	AHU-2	A11	D3045 110 2950	Air Handling Unit	1ST FLOOR		X	MCCBO5OUAOCOUB	KO9J31689
15720-03	AHU-3	A11	D3045 110 2950	Air Handling Unit	3RD FLOOR		X	MCCBO4OUAOCOUA	KO9J31695
15720-04	AHU-4	A11	D3045 110 2950	Air Handling Unit	5th-fl. Roof		X	MCCBO57UAOCOUA	KO9J31702
15720-05	AHU-5	A11	D3045 110 2950	Air Handling Unit	BASEMENT		X	MCCBO3OUAOCOUA	KO9J31709
15720-06	AHU-OA	A11	D3045 110 2950	Air Handling Unit - Outdoor Air	5th-fl. Roof		X	MCCBO5OUAOCOUB	KO9J32256
15734-01	ACU-1	A7	D3055 230 1950	Air Conditioning Unit	CPR. RM. 2034	X		MMD3C	100803212
15734-02	ACU-2	A7	D3055 230 1950	Air Conditioning Unit	CPR. RM. 2034	X		MMD3C	100803212
15734-03	ACU-3	A7	D3055 230 1950	Air Conditioning Unit	CPR. RM. 2026	X		MMD40C	100803212

United States Courthouse

Fort Pierce, FL

Equipment List

Plan Number	TAG No	Task #	R S Means Cross Reference	Description	Equipment Location	Egency Equip.	Equip Start-up	Model	Serial No.
15734-04	ACU-4	A7	D3055 230 1950	Air Conditioning Unit	CTR. RM. 1102	X		MMD23C	100803212
15763-01	FCU-1	I-2-4-5	D3040 120 1950	Fan Coil Unit	ELECT MECH. RM		X	FC-D-O6O	T10B09397
15763-02	FCU-2	I-2-4-5	D3040 120 1950	Fan Coil Unit	ROOM 1178		X	BCHC O72	T10B09397
15763-03	FCU-3	I-2-4-5	D3040 120 1950	Fan Coil Unit	ROOM 2030		X	BCHC O72	T10B09397
15763-04	FCU-4	I-2-4-5	D3040 120 1950	Fan Coil Unit	ROOM 4168		X	FC-D-120	T10B09397
15763-05	FCU-5	I-2-4-5	D3040 120 1950	Fan Coil Unit	ELECT MECH. RM		X	FC-D-030	T10B09397
15763-06	FCU-6	I-2-4-5	D3040 120 1950	Fan Coil Unit	ROOM 1174		X	BBCHC-036	T10B09397
15763-07	FCU-7	I-2-4-5	D3040 120 1950	Fan Coil Unit	ELECT MECH. RM		X	FC-D-030	T10B09397
15763-08	FCU-8	I-2-4-5	D3040 120 1950	Fan Coil Unit	ELECT MECH. RM		X	FC-D-030	T10B09397
15763-09	FCU-9	I-2-4-5	D3040 120 1950	Fan Coil Unit	ELECT MECH. RM		X	FC-D-060	T10B09397
15763-10	FCU-10	I-2-4-5	D3040 120 1950	Fan Coil Unit	ELECT MECH. RM		X	FC-D-060	T10B09397
15763-11	FCU-11	I-2-4-5	D3040 120 1950	Fan Coil Unit	ELECT MECH. RM		X	FC-D-060	T10B09397
15763-12	FCU-12	I-2-4-5	D3040 120 1950	Fan Coil Unit	ROOM 25		X	FG-D-040	T10B09397
15763-13	FCU-13	I-2-4-5	D3040 120 1950	Fan Coil Unit	GSA SHOP		X	BCHC-036	T10B09397
15763-14	FCU-14	I-2-4-5	D3040 120 1950	Fan Coil Unit	ELECT. RM. 33		X	FC-D-040	T10B09397
15763-15	FCU-15	I-2-4-5	D3040 120 1950	Fan Coil Unit	ELECT.RM. 31		X	FC-D- 120	T10B09397
15763-16	FCU-16	I-2-4-5	D3040 120 1950	Fan Coil Unit	GSA. MAIL RM.		X	BCVCO24EIEOC3NO2HIO5OA	TIO5361O
15763-17	FCU-17	I-2-4-5	D3040 120 1950	Fan Coil Unit	ROOM 25		X	FG-D-040	T10B09397
15763-18	FCU-18	I-2-4-5	D3040 120 1950	Fan Coil Unit	ELECT. MECH. RM.		X	FC-D-030	T10B09397
15763-19	FCU-19	I-2-4-5	D3040 120 1950	Fan Coil Unit	Inter. Tell. 3173		X	FC-D-024	T10B09397
15763-20	FCU-20	I-2-4-5	D3040 120 1950	Fan Coil Unit	Telecom 1004		X	FC-D-024	T10B09397
15763-21	FCU-21	I-2-4-5	D3040 120 1950	Fan Coil Unit	Telecom 4019		X	FC-D-030	T10B09397

United States Courthouse

Fort Pierce, FL

Equipment List

Plan Number	TAG No	Task #	R S Means Cross Reference	Description	Equipment Location	Egency Equip.	Equip Start-up	Model	Serial No.
15763-22	FCU-22	I-2-4-5	D3040 120 1950	Fan Coil Unit	Telecom 2111		X	FC-D-030	T10B09397
15763-23	FCU-23	I-2-4-5	D3040 120 1950	Fan Coil Unit	Elect. Rm.45		X	FC-D-030	T10B09397
15763-24	FCU-24	I-2-4-5	D3040 120 1950	Fan Coil Unit	SYS. RM. 47		X	FC-D-020	T10B09397
15763-25	FCU-25	I-2-4-5	D3040 120 1950	Fan Coil Unit	MECH. RM. 32		X	BCHC-036	T10B09397
15836-01	EF-1	F27	D3045 220 1950	Exhaust Fan	Loading Dock		X	OFI-18-1-7	1.1877E+11
15836-02	EF-2	F27	D3045 220 1950	Exhaust Fan	TOILET		X	SP-13IIO	1.19E+12
15836-03	EF-3	F27	D3045 220 1950	Exhaust Fan	TOILET		X	GB-081-4	1.88E+13
15836-04	EF-4	F27	D3045 220 1950	Exhaust Fan	TOILET		X	GB-180-10	1.88E+14
15836-05	EF-5	F27	D3045 220 1950	Exhaust Fan	TOILET		X	GB-081-4	1.88E+15
15836-06	EF-6	F27	D3045 220 1950	Exhaust Fan	TOILET		X	GB-180-10	1.88E+16
15836-07	EF-7	F27	D3045 220 1950	Exhaust Fan	TOILET		X	SP-B110	1.88E+17
15836-08	EF-8	F27	D3045 220 3950	Exhaust Fan	CHILLER RM.		X	BSQ-130-15	F96D38132
15836-09	MREF-1	F27	D3045 220 3950	Mailroom Exhaust Fan	GSA. MAIL RM.		X	TCB-2-10-20	691357820
15836-10	SEF-1	F27	D3045 220 3950	Smoke Exhaust Fan	Roof Fan		X	SWB-1-30-30	T1-908-10
15836-11	SEF-2	F27	D3045 220 3950	Smoke Exhaust Fan	Roof Fan		X	SWB-1-30-30	T1-908-11
15836-12	GEF-1A	F27	D3045 220 3950	Garage Exhaust Fan	GARAGE		X	VABS-24F14	C2D-109F-02
15836-13	GEF-1B	F27	D3045 220 3950	Garage Exhaust Fan	GARAGE		X	VABS-24F14	C2D-109F-03
15836-14	GEF-2	F27	D3045 220 3950	Garage Exhaust Fan	GARAGE		X	VABS-24F14	C2D-109F-04
15836-15	GEF-3	F27	D3045 220 3950	Garage Exhaust Fan	GARAGE		X	VABS-24F14	C2D-109F-05
15836-16	SF-1	F27	D3045 220 3950	Supply Fan	MU. SUP.SMOKE		X	QEP-15	L1-556-08
15836-17	SF-2	F27	D3045 220 3950	Supply Fan	Loading Dock		X	QEP-15	L1-556-09
15836-18	SF-3	F27	D3045 220 3950	Supply Fan	CT.RM. MU. AIR		X	LSF-15	1057-245-11

United States Courthouse

Fort Pierce, FL

Equipment List

Plan Number	TAG No	Task #	R S Means Cross Reference	Description	Equipment Location	Egency Equip.	Equip Start-up	Model	Serial No.
15836-19	SF-4	F27	D3045 220 3950	Supply Fan	CT.RM. MU. AIR		X	LSF-15	1057-245-11
15840-01	CTU-1-1	C5	D3045 160 1950	Terminal Units (1st Floor)	1ST FLOOR		X	DESV	589069
15840-01	CTU-1-2	C5	D3045 160 1950	Terminal Units (1st Floor)	1ST FLOOR		X	DESV	589069
15840-01	CTU-1-3	C5	D3045 160 1950	Terminal Units (1st Floor)	1ST FLOOR		X	DESV	589069
15840-01	CTU-1-4	C5	D3045 160 1950	Terminal Units (1st Floor)	1ST FLOOR		X	DESV	589069
15840-02	CTU-2-1	C5	D3045 160 1950	Terminal Units (2nd Floor)	2ND FLOOR		X	DESV	589069
15840-02	CTU-2-2	C5	D3045 160 1950	VolumeTerminal Units (2nd Floor)	2ND FLOOR		X	DESV	589069
15840-02	CTU-2-3	C5	D3045 160 1950	Terminal Units (2nd Floor)	2ND FLOOR		X	DESV	589069
15840-03	CTU-3-1	C5	D3045 160 1950	Terminal Units (3rd Floor)	3RD FLOOR		X	DESV	589069
15840-03	CTU-3-2	C5	D3045 160 1950	Terminal Units (3rd Floor)	3RD FLOOR		X	DESV	589069
15840-03	CTU-3-3	C5	D3045 160 1950	Terminal Units (3rd Floor)	3RD FLOOR		X	DESV	589069
15804-04	CTU-4-1	C5	D3045 160 1950	Terminal Units (4th Floor)	4TH FLOOR		X	DESV	589069
15840-04	CTU-4-2	C5	D3045 160 1950	Terminal Units (4th Floor)	4TH FLOOR		X	DESV	589069
15840-04	CTU-4-3	C5	D3045 160 1950	Terminal Units (4th Floor)	4TH FLOOR		X	DESV	589069
15840-04	CTU-4-4	C5	D3045 160 1950	Terminal Units (4th Floor)	4TH FLOOR		X	DESV	589069
15840-05	CTU-5-1	C5	D3045 160 1950	Terminal Units (5th Floor)	5TH FLOOR		X	DESV	589069
15804-05	CTU-5-2	C5	D3045 160 1950	Terminal Units (5th Floor)	5TH FLOOR		X	DESV	589069
15840-05	CTU-5-3	C5	D3045 160 1950	Terminal Units (5th Floor)	5TH FLOOR		X	DESV	589069
15840-01	VTU-1-1	C5	D3045 160 1950	Variable Air Volume Terminal Units	1ST FLOOR		X	DESV	600214
15840-01	VTU-1-2	C5	D3045 160 1950	Variable Air Volume Terminal Units	1ST FLOOR		X	DESV	600214
15840-01	VTU-1-3	C5	D3045 160 1950	Variable Air Volume Terminal Units	1ST FLOOR		X	DESV	600214
15840-01	VTU-1-4	C5	D3045 160 1950	Variable Air Volume Terminal Units	1ST FLOOR		X	DESV	600214

United States Courthouse

Fort Pierce, FL

Equipment List

	A	B	C	D	E	F	G	H	I	J
5	**Plan**	**TAG**						**Equip**		
6	**Number**	**No**	**Task #**	**R S Means Cross Reference**	**Description**	**Equipment Location**	**Egency Equip.**	**Start-up**	**Model**	**Serial No.**
161	15840-01	VTU-1-5	C5	D3045 160 1950	Variable Air Volume Terminal Units	1ST FLOOR		X	DESV	600214

Claude Pepper Federal Building FL0061ZZ O&M Only
51 SW 1St Ave
Miami, FL 33130
259427 rentable square feet (rsf)

Equipment List by Building and Equipment ID - Detail

Total Record Counts: 1262

Building: FL0061ZZ

Equipment ID	Equipment Description	Equipment Type	Floor	Room	Location	Manufacturer	Model No.	Serial No.
FL0061ZZ-000000001	Air Dryer	ADR	01	CH	Floor 01 CHILLER Mechanical Room By CHILLER #2	INGERSOL-RAND	D54IN	11M-033725
FL0061ZZ-000000002	Air Handling Unit, 3 ton thru 24 ton	AHU-01	01	CH	Floor 01 Chiller Mechanical Room By chiller #1 serving west wing	Magic air	120-BHW-4	not available
FL0061ZZ-000000003	Air Handling Unit, 3 ton thru 24 ton	AHU-01	01	OF	Floor 01 Office By mail room serving room 102 (ROOM 105)	CARRIER AIR	39LA1081AB1131-R	5189T07102
FL0061ZZ-000000004	Air Handling Unit, 3 ton thru 24 ton	AHU-01	01	OF	Floor 01 Office By mail room serving room 119	Magic air	not available	not available
FL0061ZZ-000000005	Air Handling Unit, 3 ton thru 24 ton	AHU-01	01	RRM	Floor 01 MEN'S Restroom Serving main lobby	McQUAY	LSL111CH	32F00729-06
FL0061ZZ-000000006	Air Handling Unit, 3 ton thru 24 ton	AHU-01	01	CF	Floor 01 Conference Room Serving room 100	TRANE	CSAA006UAC00	K12K10A10458
FL0061ZZ-000000008	Air Handling Unit, 3 ton thru 24 ton	AHU-01	01	EE	Floor 01 Electrical Equipment Room North Side of the Room	FHP	EMV 4-2-3	JD 2984
FL0061ZZ-000000009	Air Handling Unit, 3 ton thru 24 ton	AHU-01	01	EE	Floor 01 Electrical Equipment Room North Side of the Room	FHP	EMV 4-2-3	JD 2984
FL0061ZZ-000000010	Air Handling Unit, 3 ton thru 24 ton	AHU-01	01	SO	Floor 02 Storage Room - Middle	CARRIER	40RE008-610	3390V02706
FL0061ZZ-000000007	Air Handling Unit, 25 ton thru 50 ton	AHU-02	01	MC	Floor 01 Mechanical Equipment Room			
FL0061ZZ-000000011	Air Handling Unit, 25 ton thru 50 ton	AHU-02	01	MC	Floor 18 Mechanical Equipment Room			
FL0061ZZ-000000350	Fire Detection and Alarm System	ALM	01	CH	Floor 01 CHILLER Mechanical Room Center wall	Trane	RWE 100AA0	L99F01234
FL0061ZZ-000000351	Fire Detection and Alarm System	ALM	01	EE	Floor 01 Electrical Equipment Room East Side of the Room	NOTIFIER	DR-A4B	M 635
FL0061ZZ-000000352	Fire Detection and Alarm System	ALM	01	EE	Floor 01 Electrical Equipment Room East Side of the Room	NOTIFIER	FCPS-2458	S2424
FL0061ZZ-000000353	Fire Detection and Alarm System	ALM	01	EE	Floor 01 Electrical Equipment Room South Side of the Room	NOTIFIER	FCPS-2458	S2424

FL0061ZZ-000000354	Fire Detection and Alarm System	ALM	01	EE	Floor 01 Electrical Equipment Room annunciator on the South Side of the Room	CHI ALARM	LD-4	Not available
FL0061ZZ-000000355	Fire Detection and Alarm System	ALM	01	EE	Floor 01 Electrical Equipment Room F/A Sub-pnel on the South Side of the Room	NOTIFIER	DR-A4B	I-9800A
FL0061ZZ-000000356	Fire Detection and Alarm System	ALM	02	EE	Floor 02 Electrical Equipment Room power supply on the telePhone Room	NOTIFIER	FCPS-2458	S2424
FL0061ZZ-000000357	Fire Detection and Alarm System	ALM	03	EE	Floor 03 Electrical Equipment Room Phone Room	NOTIFIER	Not available	S2424
FL0061ZZ-000000358	Fire Detection and Alarm System	ALM	03	EE	Floor 03 Electrical Equipment Room Phone Room	NOTIFIER	FCPS-24SB	S2424
FL0061ZZ-000000359	Fire Detection and Alarm System	ALM	03	EE	Floor 03 Electrical Equipment Room Phone Room	NOTIFIER	NFS3030D	Not available
FL0061ZZ-000000360	Fire Detection and Alarm System	ALM	04	EE	Floor 04 Electrical Equipment Room Phone Room	NOTIFIER	FCPS-24S8	S2424
FL0061ZZ-000000361	Fire Detection and Alarm System	ALM	05	EE	Floor 05 Electrical Equipment Room Phone Room	NOTIFIER	FCPS-24S8	S2424
FL0061ZZ-000000362	Fire Detection and Alarm System	ALM	05	EE	Floor 05 Electrical Equipment Room Phone Room	NOTIFIER	MEA-317-01-E	S-1613-C
FL0061ZZ-000000363	Fire Detection and Alarm System	ALM	06	EE	Floor 06 Electrical Equipment Room Phone Room	NOTIFIER	FCPS-24S8	S2424
FL0061ZZ-000000364	Fire Detection and Alarm System	ALM	07	EE	Floor 07 Electrical Equipment Room Phone Room	NOTIFIER	DR-A4B	I-9800A
FL0061ZZ-000000365	Fire Detection and Alarm System	ALM	07	EE	Floor 07 Electrical Equipment Room Phone Room	NOTIFIER	FCPS-2458	S2424
FL0061ZZ-000000366	Fire Detection and Alarm System	ALM	08	EE	Floor 08 Electrical Equipment Room Phone Room	NOTIFIER	FCPS-24S8	S2424
FL0061ZZ-000000367	Fire Detection and Alarm System	ALM	09	EE	Floor 09 Electrical Equipment Room Phone Room	NOTIFIER	FLPS24S8	S2424
FL0061ZZ-000000368	Fire Detection and Alarm System	ALM	09	EE	Floor 09 Electrical Equipment Room Phone Room	NOTIFIER	NFS3030	Not available
FL0061ZZ-000000369	Fire Detection and Alarm System	ALM	10	EE	Floor 10 Electrical Equipment Room Phone Room	NOTIFIER	FCPS-24S8	S2424
FL0061ZZ-000000370	Fire Detection and Alarm System	ALM	11	EE	Floor 11 Electrical Equipment Room Phone Room	NOTIFIER	CT06472	Not available
FL0061ZZ-000000371	Fire Detection and Alarm System	ALM	11	EE	Floor 11 Electrical Equipment Room Phone Room	NOTIFIER	FCPS-24SB	Not available
FL0061ZZ-000000372	Fire Detection and Alarm System	ALM	12	EE	Floor 12 Electrical Equipment Room Phone Room	NOTIFIER	FCPS-24S8	S 2424
FL0061ZZ-000000373	Fire Detection and Alarm System	ALM	13	EE	Floor 13 Electrical Equipment Room Phone Room	NOTIFIER	FCPS-24S8	AU-9408
FL0061ZZ-000000374	Fire Detection and Alarm System	ALM	13	EE	Floor 13 Electrical Equipment Room Phone Room	NOTIFIER	CT-06472	ECN 04-202

FL0061ZZ-000000375	Fire Detection and Alarm System	ALM	14	EE	Floor 14 Electrical Equipment Room Phone Room	NOTIFIER	FCPS-24S8	AV-7996
FL0061ZZ-000000376	Fire Detection and Alarm System	ALM	15	EE	Floor 15 Electrical Equipment Room Phone Room	NOTIFIER	FCPS-24S8	30404
FL0061ZZ-000000377	Fire Detection and Alarm System	ALM	15	EE	Floor 15 Electrical Equipment Room Phone Room	NOTIFIER	MEA 317-01-E	51924-E
FL0061ZZ-000000378	Fire Detection and Alarm System	ALM	16	EE	Floor 16 Electrical Equipment Room power supply on the telePhone Room	NOTIFIER	FCPS-2458	S2424
FL0061ZZ-000000379	Fire Detection and Alarm System	ALM	17	EE	Floor 17 Electrical Equipment Room By Entrance Door	NOTIFIER	S639	BK 376
FL0061ZZ-000000380	Fire Detection and Alarm System	ALM	17	EE	Floor 17 Electrical Equipment Room By Roof Door	NOTIFIER	S635	XPIQNB
FL0061ZZ-000000650	Switch, Automatic Transfer	ATS	01	CH	Floor 01 CHILLER Mechanical Room ATS#1	ONAN	OTCU1000973G	
FL0061ZZ-000000651	Switch, Automatic Transfer	ATS	01	CH	Floor 01 CHILLER Mechanical Room FIRE ALARM POWER TRANSFER SWITCH	LINCGUARD	FT4900-BD150B	
FL0061ZZ-000000652	Switch, Automatic Transfer	ATS	01	CH	Floor 01 CHILLER Mechanical Room By X RAY MACHINE	KOHLER	K-166341-0600	K25019
FL0061ZZ-000000653	Switch, Automatic Transfer	ATS	01	EE	Floor 01 Electrical Equipment Room Main Electrical Room	WESTINGHOUSE	E 38116	340
FL0061ZZ-000000017	Building Automation System, DDC	BAS-01	17	MC	Floor 17 Mechanical Equipment Room By AHU #2	CSI	2716-2	125771796
FL0061ZZ-000000014	Building Automation System, Pnuematic	BAS-02	01	CH	Floor 01 CHILLER Mechanical Room Dampers and thermosthat control system	CSI	NO INFORMATIon	
FL0061ZZ-000000015	Building Automation System, Pnuematic	BAS-02	01	CH	Floor 01 CHILLER Mechanical Room Dampers and thermosthat control system	CSI	NO INFORMATIon	
FL0061ZZ-000000016	Building Automation System, Pnuematic	BAS-02	01	CH	Floor 01 CHILLER Mechanical Room Dampers and thermosthat control system	CSI	NO INFORMATIon	
FL0061ZZ-000000018	Building Automation System, Pnuematic	BAS-02	18	MC	Floor 18 Mechanical Equipment Room left Side of the Hallway	CSI	2716-2	125771796
FL0061ZZ-000000013	Boiler, Hot Water, Oil/Gas/Comb, 120 to 500 MBH	BLR-HW2	01	BL	Floor 01 Boiler Mechanical Room Mechanical Room South Side	ACE BUEHLER INC.	B3E	78478
FL0061ZZ-000000012	Boiler, Steam, Oil/Gas/Comb, 500 to 1000 MBH	BLR-ST3	01	BL	Floor 01 Boiler Mechanical Room Mechanical Room beSides the CHILLER #2	KEWANEE	M-265-KGO	97211
FL0061ZZ-000000019	CHILLER, Centrifugal, water cooled, over 100 tons	CHL-CW2	01	MC	Floor 01 Mechanical Equipment Room Mechanical Room between Electrical panels	TRANE	CVHE045FA2K03UK2157W7E8R1C0000000Q00F000001	L97A00347

FL0061ZZ-000000020	CHILLER, Centrifugal, water cooled, over 100 tons	CHL-CW2	01	BL	Floor 01 Boiler Mechanical Room Mechanical Room beSides the boiler	TRANE	CVHE045GA4XD PC321757AF5N BC0000000R000 000L000002C10	L10A00246
FL0061ZZ-000000654	Switch, Disconnect	DCT	01	CF	Floor 01 Conference Room on Closet on the back Side of the Room	TRANE	MCCB-06	Not available
FL0061ZZ-000000655	Switch, Disconnect	DCT	01	CH	Floor 01 CHILLER Mechanical Room By fire pump transfer switch	WESTINGHOUSE	CAU 361	431D253G09
FL0061ZZ-000000656	Switch, Disconnect	DCT	01	CH	Floor 01 CHILLER Mechanical Room By the Gym water heater	WESTINGHOUSE	CAU 361	451D253G09
FL0061ZZ-000000657	Switch, Disconnect	DCT	01	CH	Floor 01 CHILLER Mechanical Room South Side of the fire pump	WESTINGHOUSE	CAU 361	431D253G09
FL0061ZZ-000000658	Switch, Disconnect	DCT	01	CH	Floor 01 CHILLER Mechanical Room By Domestic water pump	SQUARE D	A 85341	Not available
FL0061ZZ-000000659	Switch, Disconnect	DCT	01	CH	Floor 01 CHILLER Mechanical Room PUMP #1 By TREATMENT WATER DEVICE	ITE	JU321	Not available
FL0061ZZ-000000660	Switch, Disconnect	DCT	01	CH	Floor 01 CHILLER Mechanical Room PUMP #2 By TREATMENT WATER DEVICE	ITE	JU321	Not available
FL0061ZZ-000000661	Switch, Disconnect	DCT	01	CH	Floor 01 CHILLER Mechanical Room By AIR COMPRESSOR #1	SQUARE D	Not available	Not available
FL0061ZZ-000000662	Switch, Disconnect	DCT	01	CH	Floor 01 CHILLER Mechanical Room By AIR COMPRESSOR #1	SQUARE D	Not available	Not available
FL0061ZZ-000000663	Switch, Disconnect	DCT	01	MT	Floor 01 Office Maintenance Office	SQUARE D	D-321-N	B-40274-208-15
FL0061ZZ-000000664	Switch, Disconnect	DCT	01	MT	Floor 01 Office Maintenance Office	SQUARE D	QO2-4L70S	40274-654-02
FL0061ZZ-000000665	Switch, Disconnect	DCT	01	CH	Floor 01 CHILLER Mechanical Room By COMPRESSOR #2	ITE	NF 301	Not available
FL0061ZZ-000000666	Switch, Disconnect	DCT	01	CH	Floor 01 CHILLER Mechanical Room By COMPRESSOR #2	ITE	NF 301	Not available
FL0061ZZ-000000667	Switch, Disconnect	DCT	01	CH	Floor 01 CHILLER Mechanical Room By Water Heather	GE	T63221-7	Not available
FL0061ZZ-000000668	Switch, Disconnect	DCT	01	CH	Floor 01 CHILLER Mechanical Room By Water Heather	GE	T63221-7	Not available
FL0061ZZ-000000669	Switch, Disconnect	DCT	01	CH	Floor 01 CHILLER Mechanical Room By Water Heather	ITE	JU 321	Not available
FL0061ZZ-000000670	Switch, Disconnect	DCT	01	CH	Floor 01 CHILLER Mechanical Room By CHILLER #1	ITE	F 356	B-40274-208-15
FL0061ZZ-000000671	Switch, Disconnect	DCT	01	CH	Floor 01 CHILLER Mechanical Room By COMPRESSOR #2	SQUARE D	QO-403	Not available
FL0061ZZ-000000672	Switch, Disconnect	DCT	01	MT	Floor 01 Office Maintenance Office	JUNIOR VACU BREAK	JN 321	Not available
FL0061ZZ-000000673	Switch, Disconnect	DCT	01	EE	Floor 01 Electrical Equipment Room East Side of the Electrical Room By PANELBOARD	GENERAL ELEC	NP 266212-D	Not available

FL0061ZZ-000000674	Switch, Disconnect	DCT	01	EE	Floor 01 Electrical Equipment Room East Side of the Electrical Room on toP OF the PANELBOARD	SQUARE D	QC483	Not available
FL0061ZZ-000000675	Switch, Disconnect	DCT	01	EE	Floor 01 Electrical Equipment Room East Side of the Electrical Room	SQUARE D	73770	S1
FL0061ZZ-000000676	Switch, Disconnect	DCT	01	EE	Floor 01 Electrical Equipment Room South Side of the Electrical Room	SQUARE D	75716	S1
FL0061ZZ-000000677	Switch, Disconnect	DCT	01	EE	Floor 01 Electrical Equipment Room North Side of the Room	SQUARE D	D-321-N	B-40274-208-15
FL0061ZZ-000000678	Switch, Disconnect	DCT	02	EE	Floor 02 Electrical Equipment Room South Side of the Room	WESTINGHOUSE	Not available	147P454H01
FL0061ZZ-000000679	Switch, Disconnect	DCT	02	EE	Floor 02 Electrical Equipment Room North Side of the Room	SQUARE D	B-40274-185-01	Not available
FL0061ZZ-000000680	Switch, Disconnect	DCT	02	ST	Floor 02 Office South Side of the Room	WESTINGHOUSE	GFN421N	Not available
FL0061ZZ-000000681	Switch, Disconnect	DCT	03	EE	Floor 03 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	3D-E-6186	1479454H01
FL0061ZZ-000000682	Switch, Disconnect	DCT	03	EE	Floor 03 Electrical Equipment Room East Side of the Room	CUTLER HAMME	Not available	Not available
FL0061ZZ-000000683	Switch, Disconnect	DCT	03	EE	Floor 03 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147P454H01
FL0061ZZ-000000684	Switch, Disconnect	DCT	03	EE	Floor 03 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6187	100P688H01
FL0061ZZ-000000685	Switch, Disconnect	DCT	03	EE	Floor 03 Electrical Equipment Room Phone Room	SQUARE D	NC44S	11491
FL0061ZZ-000000686	Switch, Disconnect	DCT	04	EE	Floor 04 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147-454H01
FL0061ZZ-000000687	Switch, Disconnect	DCT	04	EE	Floor 04 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147-454H01
FL0061ZZ-000000688	Switch, Disconnect	DCT	05	EE	Floor 05 Electrical Equipment Room South EAT Side of the Room	SQUARE D	C-40474-289-06	Not available
FL0061ZZ-000000689	Switch, Disconnect	DCT	05	EE	Floor 05 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147-454H01
FL0061ZZ-000000690	Switch, Disconnect	DCT	05	EE	Floor 05 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6187	147-454H01
FL0061ZZ-000000691	Switch, Disconnect	DCT	06	EE	Floor 06 Electrical Equipment Room South Side of the Room	SQUARE D	C40274-289-06	Not available
FL0061ZZ-000000692	Switch, Disconnect	DCT	06	EE	Floor 06 Electrical Equipment Room North East Side of the Room	SQUARE D	C-40274-289-06	Not available
FL0061ZZ-000000693	Switch, Disconnect	DCT	07	EE	Floor 07 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147P454H01
FL0061ZZ-000000694	Switch, Disconnect	DCT	07	EE	Floor 07 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6187	147P454H01

FL0061ZZ-000000695	Switch, Disconnect	DCT	07	EE	Floor 07 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	60-E-6187	Not available
FL0061ZZ-000000696	Switch, Disconnect	DCT	08	EE	Floor 08 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147P454H01
FL0061ZZ-000000697	Switch, Disconnect	DCT	08	EE	Floor 08 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147P454H01
FL0061ZZ-000000698	Switch, Disconnect	DCT	08	EE	Floor 08 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	60-E-6187	Not available
FL0061ZZ-000000699	Switch, Disconnect	DCT	08	EE	Floor 08 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	60-E-6187	Not available
FL0061ZZ-000000700	Switch, Disconnect	DCT	08	EE	Floor 08 Electrical Equipment Room East Side of the Room	SIEMENS	JN423	A
FL0061ZZ-000000701	Switch, Disconnect	DCT	09	EE	Floor 09 Electrical Equipment Room South East Side of the Room	SQUARE D	9LC	11432
FL0061ZZ-000000702	Switch, Disconnect	DCT	09	EE	Floor 09 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147P454-H01
FL0061ZZ-000000703	Switch, Disconnect	DCT	09	EE	Floor 09 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147P454-H01
FL0061ZZ-000000704	Switch, Disconnect	DCT	10	EE	Floor 10 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147P454H01
FL0061ZZ-000000705	Switch, Disconnect	DCT	10	EE	Floor 10 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6187	147P454H02
FL0061ZZ-000000706	Switch, Disconnect	DCT	11	EE	Floor 11 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147P454H01
FL0061ZZ-000000707	Switch, Disconnect	DCT	11	EE	Floor 11 Electrical Equipment Room East Side of the Room	SQUARE D	Not available	Not available
FL0061ZZ-000000708	Switch, Disconnect	DCT	11	EE	Floor 11 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	145P454H01
FL0061ZZ-000000709	Switch, Disconnect	DCT	11	EE	Floor 11 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147P454H01
FL0061ZZ-000000710	Switch, Disconnect	DCT	11	EE	Floor 12 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147P454H01
FL0061ZZ-000000711	Switch, Disconnect	DCT	12	EE	Floor 12 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6187	147P454H02
FL0061ZZ-000000712	Switch, Disconnect	DCT	13	EE	Floor 13 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	AG85776	1737858A
FL0061ZZ-000000713	Switch, Disconnect	DCT	13	EE	Floor 13 Electrical Equipment Room South Side of the Room	WESTINGHOUSE	AG85692	1737858A
FL0061ZZ-000000714	Switch, Disconnect	DCT	14	EE	Floor 14 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147P454H01
FL0061ZZ-000000715	Switch, Disconnect	DCT	14	EE	Floor 14 Electrical Equipment Room North East Side of the Room	SQUARE D	J353634	Not available
FL0061ZZ-000000716	Switch, Disconnect	DCT	14	EE	Floor 14 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147P450H01

FL0061ZZ-000000717	Switch, Disconnect	DCT	15	EE	Floor 15 Electrical Equipment Room South East Side of the Room	WESTINGHOUSE	30-E-6186	147P454H01
FL0061ZZ-000000718	Switch, Disconnect	DCT	15	EE	Floor 15 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147P454H01
FL0061ZZ-000000719	Switch, Disconnect	DCT	16	EE	Floor 16 Electrical Equipment Room South Side of the Room	SQUARE D	0480769-503	A80045-009-01
FL0061ZZ-000000720	Switch, Disconnect	DCT	16	EE	Floor 16 Electrical Equipment Room North Side of the Room	lonDIS & GYR	MPU/DVP	125-1754
FL0061ZZ-000000721	Switch, Disconnect	DCT	17	EE	Floor 17 Electrical Equipment Room Besides power control PANEL OLD Cooling tower #1	FURNAS	NO INFORMATIon	Not available
FL0061ZZ-000000722	Switch, Disconnect	DCT	17	EE	Floor 17 Electrical Equipment Room Besides power control PANEL OLD Cooling tower #2	FURNAS	NO INFORMATIon	Not available
FL0061ZZ-000000723	Switch, Disconnect	DCT	17	EE	Floor 17 Electrical Equipment Room Besides power control	WESTINGHOUSE	CAV-363	Not available
FL0061ZZ-000000724	Switch, Disconnect	DCT	17	EE	Floor 17 Electrical Equipment Room Besides power control	WESTINGHOUSE	CAV-363	Not available
FL0061ZZ-000000725	Switch, Disconnect	DCT	17	EE	Floor 17 Electrical Equipment Room Cooling tower fan #1	SQUARE D	4D274-225-02	Not available
FL0061ZZ-000000726	Switch, Disconnect	DCT	17	EE	Floor 17 Electrical Equipment Room Cooling tower #1	MARLEY	NO INFORMATIon	B 06555L
FL0061ZZ-000000727	Switch, Disconnect	DCT	17	EE	Floor 17 Electrical Equipment Room Cooling tower #2	MARLEY	NO INFORMATIon	B 06555L
FL0061ZZ-000000728	Switch, Disconnect	DCT	17	MC	Floor 17 Mechanical Equipment Room Right Side of the Hallway	Master Vac-Break	NF-354	Not available
FL0061ZZ-000000729	Switch, Disconnect	DCT	17	MC	Floor 17 Mechanical Equipment Room Right Side of the Hallway	Master Vac-Break	NF-355	Not available
FL0061ZZ-000000730	Switch, Disconnect	DCT	17	RF	Floor 17 Roof / Roof Installed Item South Side of the building	SQUARE D	2589 SBA 25	23755T
FL0061ZZ-000000731	Switch, Disconnect	DCT	18	MC	Floor 18 Mechanical Equipment Room By the AHU #2 return Door	WESTINGHOUSE	Form 30	1110
FL0061ZZ-000000732	Switch, Disconnect	DCT	18	EE	Floor 18 Electrical Equipment Room	WESTINGHOUSE	CAV361	451D253G09
FL0061ZZ-000000742	Transformer, Dry	DTT	01	EE	Floor 01 Electrical Equipment Room East Side of the Electrical Room	WESTINGHOUSE	V48J-28T458	62H6357
FL0061ZZ-000000743	Transformer, Dry	DTT	02	EE	Floor 02 Electrical Equipment Room West Side of the Room	WESTINGHOUSE	DJ-3 V48J28T75B	62M2898
FL0061ZZ-000000744	Transformer, Dry	DTT	03	EE	Floor 03 Electrical Equipment Room South Side of the Room	SQUARE D	5S1F	Not available
FL0061ZZ-000000745	Transformer, Dry	DTT	03	EE	Floor 03 Electrical Equipment Room Phone Room	SQUARE D	EE45T3HISNL	006500074829
FL0061ZZ-000000746	Transformer, Dry	DTT	04	EE	Floor 04 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	DT-3 V48J28T75B	62M2902

FL0061ZZ-000000747	Transformer, Dry	DTT	05	EE	Floor 05 Electrical Equipment Room 2ND Electrical Room South Side of the Main Electrical Room OF the FLOOR	SQUARE D	WS363 45T3H	79TS22C
FL0061ZZ-000000748	Transformer, Dry	DTT	05	EE	Floor 05 Electrical Equipment Room 5th Electrical Room South Side of the Main Electrical Room OF the FLOOR	SQUARE D	3T2F	43006-261-02
FL0061ZZ-000000749	Transformer, Dry	DTT	06	EE	Floor 06 Electrical Equipment Room WEast Side of the Room	WESTINGHOUSE	DT-3 V48J28T75B	6PM397
FL0061ZZ-000000750	Transformer, Dry	DTT	06	EE	Floor 06 Electrical Equipment Room Electrical Room for BANKRUPTCY computer Room	SQUARE D	30T3H	40336-382-04
FL0061ZZ-000000751	Transformer, Dry	DTT	06	EE	Floor 06 Electrical Equipment Room Electrical Room for BANKRUPTCY computer Room	SQUARE D	30T3H1S	43006-383-03
FL0061ZZ-000000752	Transformer, Dry	DTT	06	EE	Floor 06 Electrical Equipment Room Electrical Room for BANKRUPTCY computer Room	SQUARE D	3T2F	43006-261-02
FL0061ZZ-000000753	Transformer, Dry	DTT	08	EE	Floor 08 IRS Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30T3H V48J28T75B	40336-382-04
FL0061ZZ-000000754	Transformer, Dry	DTT	09	EE	Floor 09 Electrical Equipment Room North East Side of the Room	SQUARE D	5S1F	115LBS
FL0061ZZ-000000755	Transformer, Dry	DTT	09	EE	Floor 09 Electrical Equipment Room South Side of the Room	SQUARE D	EF45T3H1SNL	WS364 0005000074830
FL0061ZZ-000000756	Transformer, Dry	DTT	10	EE	Floor 10 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	DT-3 V48J28T75B	62M2895
FL0061ZZ-000000757	Transformer, Dry	DTT	10	EE	Floor 10 Electrical Equipment Room 3rd electrical room by the south side of the phone room	SQUARE D	3T2F	43006-261-02
FL0061ZZ-000000758	Transformer, Dry	DTT	12	EE	Floor 12 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	DT-3 V48J28T75B	62M2899
FL0061ZZ-000000759	Transformer, Dry	DTT	14	EE	Floor 14 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	DT-3 V48J28T75B	62M395
FL0061ZZ-000000760	Transformer, Dry	DTT	16	EE	Floor 16 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	DT-3 V48J28T75B	62D3527
FL0061ZZ-000000761	Transformer, Dry	DTT	16	EE	Floor 16 Electrical Equipment Room South Side of the Room	SQUARE D	31949-17445-003	Not available
FL0061ZZ-000000022	Emergency Lighting	ELT	01	EE	Floor 01 Electrical Equipment Room Main Electrical Room	LITHONIA	ELT36C	Not available
FL0061ZZ-000000023	Emergency Lighting	ELT	01	CH	Floor 01 CHILLER Mechanical Room By the Chemical equipments	Cooper	UMB1	no available

FL0061ZZ-000000024	Emergency Lighting	ELT	01	CH	Floor 01 CHILLER Mechanical Room By the fire pump	lIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000025	Emergency Lighting	ELT	01	SW	Floor 01 Stairwell #2 South Side	LIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000026	Emergency Lighting	ELT	01	SW	Floor 01 Stairwell #1 North Side	LIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000027	Emergency Lighting	ELT	02	SW	Floor 02 Stairwell #2 South Side	LITHONIA	ELT36C	Not available
FL0061ZZ-000000028	Emergency Lighting	ELT	02	SW	Floor 02 Stairwell #1 North Side	LIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000029	Emergency Lighting	ELT	03	SW	Floor 03 Stairwell #2 South Side	lIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000030	Emergency Lighting	ELT	03	SW	Floor 03 Stairwell #1 North Side	LIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000031	Emergency Lighting	ELT	04	SW	Floor 04 Stairwell #2 South Side	lIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000032	Emergency Lighting	ELT	04	SW	Floor 04 Stairwell #1 North Side	LIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000033	Emergency Lighting	ELT	05	SW	Floor 05 Stairwell #2 South Side	lIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000034	Emergency Lighting	ELT	05	SW	Floor 05 Stairwell #1 North Side	LIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000035	Emergency Lighting	ELT	06	SW	Floor 06 Stairwell #2 South Side	lIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000036	Emergency Lighting	ELT	06	SW	Floor 06 Stairwell #1 North Side	LITHONIA	ELT36C	Not available
FL0061ZZ-000000037	Emergency Lighting	ELT	07	SW	Floor 07 Stairwell #2 South Side	LIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000038	Emergency Lighting	ELT	07	SW	Floor 07 Stairwell #1 North Side	LITHONIA	ELT36C	Not available
FL0061ZZ-000000039	Emergency Lighting	ELT	08	SW	Floor 08 Stairwell #1 North Side	LIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000040	Emergency Lighting	ELT	08	SW	Floor 08 Stairwell #2 South Side	LIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000041	Emergency Lighting	ELT	09	SW	Floor 09 Stairwell #2 South Side	lIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000042	Emergency Lighting	ELT	09	SW	Floor 09 Stairwell #1 North Side	LITHONIA	ELT36C	Not available
FL0061ZZ-000000043	Emergency Lighting	ELT	10	SW	Floor 10 Stairwell #2 South Side	lIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000044	Emergency Lighting	ELT	10	SW	Floor 10 Stairwell #1 North Side	DUAL-LITE	ML-2E-NY	9704011487
FL0061ZZ-000000045	Emergency Lighting	ELT	16	SW	Floor 16 Stairwell #2 South Side	LIGHTALARMS	MOD 3237	3230-00-283-3237
FL0061ZZ-000000046	Emergency Lighting	ELT	11	SW	Floor 11 Stairwell #2 South Side	lIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000047	Emergency Lighting	ELT	11	SW	Floor 11 Stairwell #1 North Side	LITHONIA	ELT36C	Not available
FL0061ZZ-000000048	Emergency Lighting	ELT	12	SW	Floor 12 Stairwell #2 South Side	lIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000049	Emergency Lighting	ELT	12	SW	Floor 12 Stairwell #1 North Side	lIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000050	Emergency Lighting	ELT	13	SW	Floor 13 Stairwell #2 South Side	LITHONIA	ELT36C	Not available
FL0061ZZ-000000051	Emergency Lighting	ELT	13	SW	Floor 13 Stairwell #1 North Side	lIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000052	Emergency Lighting	ELT	14	SW	Floor 14 Stairwell #2 South Side	lIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000053	Emergency Lighting	ELT	14	SW	Floor 14 Stairwell #1 North Side	lIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000054	Emergency Lighting	ELT	15	SW	Floor 15 Stairwell #2 South Side	lIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000055	Emergency Lighting	ELT	15	SW	Floor 15 Stairwell #1 North Side	lIGHTALARMS	MOD 3238	3230-00-283-3237
FL0061ZZ-000000056	Emergency Lighting	ELT	16	SW	Floor 16 Stairwell #1 North Side	lIGHTALARMS	MOD 3238	3230-00-283-3237

FL0061ZZ-000000021	Emergency Diesel Generator	EMG-01	01	PL	Floor 01 Parking Lot East Side of the Parking Lot (OUTSIDE)	DETROIT DIESEL	650D8EC	GM47454-GA6S
FL0061ZZ-000000539	Panelboard, Power Distribution	EPB	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) Main Electrical Room	WESTINGHOUSE	Not available	Not available
FL0061ZZ-000000540	Panelboard, Power Distribution	EPB	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) Main Electrical Room	WESTINGHOUSE	Not available	Not available
FL0061ZZ-000000541	Panelboard, Power Distribution	EPB	01	EE	Floor 01 Electrical Equipment Room Main Electrical Room LOAD CENTER	WESTINGHOUSE	QM	80030-552-01
FL0061ZZ-000000542	Panelboard, Power Distribution	EPB	01	CH	Floor 01 CHILLER Mechanical Room Power control center	WESTINGHOUSE	ATHD80930-2CGX	30774-B
FL0061ZZ-000000543	Panelboard, Power Distribution	EPB	01	CH	Floor 01 CHILLER Mechanical Room Power control center	WESTINGHOUSE	MRHC16603	30774-B
FL0061ZZ-000000544	Panelboard, Power Distribution	EPB	01	CH	Floor 01 CHILLER Mechanical Room Old emergency Power control center	WESTINGHOUSE	NO INFORMATIon	
FL0061ZZ-000000545	Panelboard, Power Distribution	EPB	01	CH	Floor 01 CHILLER Mechanical Room By X RAY MACHINE	SQUARE D	QMB EB	42-0480769-509
FL0061ZZ-000000546	Panelboard, Power Distribution	EPB	01	CH	Floor 01 CHILLER Mechanical Room By X RAY MACHINE	SQUARE D	QMB GB	42-0480769-507
FL0061ZZ-000000306	Drinking Fountain, Packaged	EWC	01	LB	Floor 01 Lobby AT Room 100 Entrance	OASIS	P8AMSL-D300	020302-1856
FL0061ZZ-000000307	Drinking Fountain, Packaged	EWC	01	SW	Floor 01 Stairwell #2 By the South Stairwell	HALSLEY TAYL	BFC-7FS-2	016578850E89
FL0061ZZ-000000308	Drinking Fountain, Packaged	EWC	02	HW	Floor 02 General Building Hallway By the Elevator Lobby	HALSLEY TAYL	SW8 A-3	016576558-E89
FL0061ZZ-000000309	Drinking Fountain, Packaged	EWC	02	ST	Floor 02 General Building By the South Stairwell	HALSLEY TAYL	BFC-7FS-2	016576254-E89
FL0061ZZ-000000310	Drinking Fountain, Packaged	EWC	03	HW	Floor 03 General Building Hallway By the Elevator Lobby	ELKAY	EZFSTL8ID	111123772
FL0061ZZ-000000311	Drinking Fountain, Packaged	EWC	04	HW	Floor 04 General Building Hallway By the Elevator Lobby	HALSLEY TAYL	SW8 A-3	016576558-E89
FL0061ZZ-000000312	Drinking Fountain, Packaged	EWC	04	ST	Floor 04 General Building By the South Stairwell	HALSLEY TAYL	BFC-7FS-2	016576254-E89
FL0061ZZ-000000313	Drinking Fountain, Packaged	EWC	05	HW	Floor 05 General Building Hallway By the Elevator Lobby	HALSLEY TAYL	SW8 A-3	016576254-E89
FL0061ZZ-000000314	Drinking Fountain, Packaged	EWC	05	ST	Floor 05 General Building By the South Stairwell	HALSLEY TAYL	SW8 A-3	016576558-E89
FL0061ZZ-000000315	Drinking Fountain, Packaged	EWC	06	HW	Floor 06 General Building Hallway By the Elevator Lobby	HALSLEY TAYL	SW8 A-3	016576558-E89
FL0061ZZ-000000316	Drinking Fountain, Packaged	EWC	06	ST	Floor 06 General Building By the South Stairwell	HALSLEY TAYL	BFC-7FS-2	016576254-E89
FL0061ZZ-000000317	Drinking Fountain, Packaged	EWC	07	HW	Floor 07 General Building Hallway By the Elevator Lobby	HALSLEY TAYL	BFC-7FS-2	016576254-E89

FL0061ZZ-000000318	Drinking Fountain, Packaged	EWC	07	ST	Floor 07 General Building By the South Stairwell	HALSLEY TAYL	SW8 A-3	016576558-E89
FL0061ZZ-000000319	Drinking Fountain, Packaged	EWC	08	HW	Floor 08 General Building Hallway By the Elevator Lobby	HALSLEY TAYL	BFC-7FS-2	016576254-E89
FL0061ZZ-000000320	Drinking Fountain, Packaged	EWC	09	ST	Floor 09 General Building By the South Stairwell	HALSLEY TAYL	SW8 A-3	016576558-E89
FL0061ZZ-000000321	Drinking Fountain, Packaged	EWC	09	HW	Floor 09 General Building Hallway By the Elevator Lobby	HALSLEY TAYL	BFC-7FS-2	016576254-E89
FL0061ZZ-000000322	Drinking Fountain, Packaged	EWC	10	ST	Floor 10 General Building By the South Stairwell	HALSLEY TAYL	SW8 A-3	016576558-E89
FL0061ZZ-000000323	Drinking Fountain, Packaged	EWC	10	HW	Floor 10 General Building Hallway By the Elevator Lobby	HALSLEY TAYL	BFC-7FS-2	016576254-E89
FL0061ZZ-000000324	Drinking Fountain, Packaged	EWC	11	ST	Floor 11 General Building By the South Stairwell	HALSLEY TAYL	SW8 A-3	016576558-E89
FL0061ZZ-000000325	Drinking Fountain, Packaged	EWC	11	HW	Floor 11 General Building Hallway By the Elevator Lobby	HALSLEY TAYL	BFC-7FS-2	016576254-E89
FL0061ZZ-000000326	Drinking Fountain, Packaged	EWC	12	ST	Floor 12 General Building By the South Stairwell	HALSLEY TAYL	BFC-7FS-2	016576254-E89
FL0061ZZ-000000327	Drinking Fountain, Packaged	EWC	13	ST	Floor 13 General Building By the South Stairwell	HALSLEY TAYL	SW8 A-3	016576458-E89
FL0061ZZ-000000328	Drinking Fountain, Packaged	EWC	14	ST	Floor 14 General Building By the South Stairwell	HALSLEY TAYL	BFC-7FS-2	016576458-E89
FL0061ZZ-000000329	Drinking Fountain, Packaged	EWC	14	HW	Floor 14 General Building Hallway By the Elevator Lobby	HALSLEY TAYL	SW8 A-3	016576254-E89
FL0061ZZ-000000330	Drinking Fountain, Packaged	EWC	15	ST	Floor 15 General Building By the South Stairwell	HALSLEY TAYL	SW8 A-3	016576558-E89
FL0061ZZ-000000331	Drinking Fountain, Packaged	EWC	15	HW	Floor 15 General Building Hallway By the Elevator Lobby	HALSLEY TAYL	BFC-7FS-2	016576254-E89
FL0061ZZ-000000332	Drinking Fountain, Packaged	EWC	16	ST	Floor 16 General Building By the South Stairwell	HALSLEY TAYL	BFC-7FS-2	016576254-E89
FL0061ZZ-000000333	Drinking Fountain, Packaged	EWC	16	HW	Floor 16 General Building Hallway By the Elevator Lobby	HALSLEY TAYL	BFC-7FS-2	016576254-E90
FL0061ZZ-000000057	Exit Signs	EXS	01	LB	Floor 01 Lobby NE outSide Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000058	Exit Signs	EXS	01	LB	Floor 01 Lobby SE outSide Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000059	Exit Signs	EXS	01	SV-HW	Floor 01 General Building Service Hallway to Mechanical Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000060	Exit Signs	EXS	01	SV-HW	Floor 01 General Building Service Hallway to Main Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000061	Exit Signs	EXS	01	SV-HW	Floor 01 General Building Service Hallway to Parking Lot	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000062	Exit Signs	EXS	01	SV-HW	Floor 01 General Building Service Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8

FL0061ZZ-000000063	Exit Signs	EXS	01	LB	Floor 01 General Building Main Lobby to NE Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000064	Exit Signs	EXS	01	LB	Floor 01 General Building Main Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000065	Exit Signs	EXS	01	LB	Floor 01 General Building Main Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000066	Exit Signs	EXS	01	100	Floor 01 General Building Room 100	Manufacturers	6507	914-2-4191
FL0061ZZ-000000067	Exit Signs	EXS	01	100	Floor 01 General Building Room 100	Manufacturers	6507	914-2-4191
FL0061ZZ-000000068	Exit Signs	EXS	01	100	Floor 01 General Building Room 100	Manufacturers	6507	914-2-4191
FL0061ZZ-000000069	Exit Signs	EXS	01	100	Floor 01 General Building Room 100	Manufacturers	6507	914-2-4191
FL0061ZZ-000000070	Exit Signs	EXS	01	100	Floor 01 General Building Room 100	Manufacturers	6507	914-2-4191
FL0061ZZ-000000071	Exit Signs	EXS	01	100	Floor 01 Conference Room Room 100 Conference Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000072	Exit Signs	EXS	01	100	Floor 01 Conference Room Room 100 Conference Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000073	Exit Signs	EXS	01	100	Floor 01 Conference Room Room 100 Conference Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000074	Exit Signs	EXS	01	100	Floor 01 Conference Room Room 100 Conference Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000075	Exit Signs	EXS	01	100	Floor 01 Conference Room Room 100 Conference Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000076	Exit Signs	EXS	01	EN	Floor 01 Conference Room Room 102 entrnace Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000077	Exit Signs	EXS	02	ET	Floor 02 General Building East Side	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000078	Exit Signs	EXS	02	FC	Floor 02 Food Service, Break Room By the Entrance Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000079	Exit Signs	EXS	02	WT	Floor 02 General Building West Side	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000080	Exit Signs	EXS	02		Floor 02 General Building By the Main Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000081	Exit Signs	EXS	02		Floor 02 General Building By the Service Elevator	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000082	Exit Signs	EXS	02	EV	Floor 02 General Building By Elevator Room Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000083	Exit Signs	EXS	02		Floor 02 General Building By Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000084	Exit Signs	EXS	02	NT	Floor 02 General Building By North Side stairways	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000085	Exit Signs	EXS	03	ST	Floor 03 General Building By South stairways	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000086	Exit Signs	EXS	03	NT	Floor 03 General Building By North stairways	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000087	Exit Signs	EXS	03	HW	Floor 03 General Building In the Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000088	Exit Signs	EXS	03	HW	Floor 03 General Building In the Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8

FL0061ZZ-000000089	Exit Signs	EXS	03	HW	Floor 03 General Building In the Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000090	Exit Signs	EXS	03	HW	Floor 03 General Building In the Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000091	Exit Signs	EXS	03	OF	Floor 03 General Building East Offices	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000092	Exit Signs	EXS	03	OF	Floor 03 General Building East Offices	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000093	Exit Signs	EXS	03	OF	Floor 03 General Building East Offices	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000094	Exit Signs	EXS	03	OF	Floor 03 General Building East Offices	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000095	Exit Signs	EXS	03	OF-WT	Floor 03 General Building West Offices	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000096	Exit Signs	EXS	03	OF-WT	Floor 03 General Building West Offices	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000097	Exit Signs	EXS	03	OF-WT	Floor 03 General Building West Offices	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000098	Exit Signs	EXS	03	OF-WT	Floor 03 General Building West Offices	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000099	Exit Signs	EXS	03	OF-WT	Floor 03 General Building West Offices	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000100	Exit Signs	EXS	03	OF-WT	Floor 03 General Building West Offices	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000101	Exit Signs	EXS	03	OF-WT	Floor 03 General Building West Offices	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000102	Exit Signs	EXS	03	OF-WT	Floor 03 General Building West Offices	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000103	Exit Signs	EXS	03	OF-WT	Floor 03 General Building West Offices	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000104	Exit Signs	EXS	03	OF-WT	Floor 03 General Building West Offices	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000105	Exit Signs	EXS	04	HW	Floor 04 General Building Hallway By North stairwell Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000106	Exit Signs	EXS	04	HW	Floor 04 General Building Hallway North	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000107	Exit Signs	EXS	04	HW	Floor 04 General Building Hallway South	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000108	Exit Signs	EXS	04	HW	Floor 04 General Building Hallway By Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000109	Exit Signs	EXS	04	HW	Floor 04 General Building Hallway By Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000110	Exit Signs	EXS	04	EV	Floor 04 General Building Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000111	Exit Signs	EXS	04	SV-EE	Floor 04 General Building Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000112	Exit Signs	EXS	04	404	Floor 04 General Building Room 404 Exit doo	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000113	Exit Signs	EXS	04	417	Floor 04 General Building Room 417 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000114	Exit Signs	EXS	04	418	Floor 04 General Building Room 418 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000115	Exit Signs	EXS	04	419	Floor 04 General Building Room 419 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000116	Exit Signs	EXS	04	423	Floor 04 General Building Room 423 Entrance Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000117	Exit Signs	EXS	04	LB	Floor 04 General Building Room 423 Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8

FL0061ZZ-000000118	Exit Signs	EXS	04	HW	Floor 04 General Building Hallway By kitchen Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000119	Exit Signs	EXS	04	KT	Floor 04 General Building Kitchen Room Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000120	Exit Signs	EXS	04	HW	Floor 04 General Building Hallway North West Side	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000121	Exit Signs	EXS	04	HW	Floor 04 General Building Hallway North East Side	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000122	Exit Signs	EXS	04	421	Floor 04 General Building Room 421 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000123	Exit Signs	EXS	04	422	Floor 04 General Building Room 422 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000124	Exit Signs	EXS	05	HW	Floor 05 General Building Hallway By North stairwell Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000125	Exit Signs	EXS	05	HW	Floor 05 General Building Hallway North	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000126	Exit Signs	EXS	05	HW	Floor 05 General Building Hallway South	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000127	Exit Signs	EXS	05	HW	Floor 05 General Building Hallway By Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000128	Exit Signs	EXS	05	HW	Floor 05 General Building Hallway By Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000129	Exit Signs	EXS	05	EV	Floor 05 General Building Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000130	Exit Signs	EXS	05	SV-EE	Floor 05 General Building Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000131	Exit Signs	EXS	05	504	Floor 05 General Building Room 504 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000132	Exit Signs	EXS	05	504	Floor 05 General Building Room 504 interior	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000133	Exit Signs	EXS	05	NT	Floor 05 General Building North not occupied Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000134	Exit Signs	EXS	05	NT	Floor 05 General Building North not occupied Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000135	Exit Signs	EXS	05	NT	Floor 05 General Building North not occupied Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000136	Exit Signs	EXS	05	ST	Floor 05 General Building South not occupied Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000137	Exit Signs	EXS	05	ST	Floor 05 General Building South not occupied Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000138	Exit Signs	EXS	05	523	Floor 05 General Building Room 523 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000139	Exit Signs	EXS	05	523	Floor 05 General Building Room 523 interior	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000140	Exit Signs	EXS	05	531	Floor 05 General Building Room 531 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8

FL0061ZZ-000000141	Exit Signs	EXS	05	531	Floor 05 General Building Room 531 interior	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000142	Exit Signs	EXS	06	HW	Floor 06 General Building Hallway By North stairwell Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000143	Exit Signs	EXS	06	HW	Floor 06 General Building Hallway North	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000144	Exit Signs	EXS	06	HW	Floor 06 General Building Hallway South	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000145	Exit Signs	EXS	06	HW	Floor 06 General Building Hallway By Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000146	Exit Signs	EXS	06	HW	Floor 06 General Building Hallway By Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000147	Exit Signs	EXS	06	EV	Floor 06 General Building Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000148	Exit Signs	EXS	06	SV-EE	Floor 06 General Building Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000149	Exit Signs	EXS	06		Floor 06 General Building By Miami federal Credit union Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000150	Exit Signs	EXS	06		Floor 06 General Building By Miami federal Credit union break Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000151	Exit Signs	EXS	06	621	Floor 06 General Building Room 621 Exit Door	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000152	Exit Signs	EXS	06	621	Floor 06 General Building Romm 621 computer Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000153	Exit Signs	EXS	07	HW	Floor 07 General Building Hallway By North stairwell Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000154	Exit Signs	EXS	07	HW	Floor 07 General Building Hallway North	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000155	Exit Signs	EXS	07	HW	Floor 07 General Building Hallway South	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000156	Exit Signs	EXS	07	HW	Floor 07 General Building Hallway By Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000157	Exit Signs	EXS	07	HW	Floor 07 General Building Hallway By Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000158	Exit Signs	EXS	07	EV	Floor 07 General Building Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000159	Exit Signs	EXS	07	SV-EE	Floor 07 General Building Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000160	Exit Signs	EXS	08	HW	Floor 08 General Building Hallway By North stairwell Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000161	Exit Signs	EXS	08	HW	Floor 08 General Building Hallway North	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000162	Exit Signs	EXS	08	HW	Floor 08 General Building Hallway South	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000163	Exit Signs	EXS	08	HW	Floor 08 General Building Hallway By Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000164	Exit Signs	EXS	08	HW	Floor 08 General Building Hallway By Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000165	Exit Signs	EXS	08	EV	Floor 08 General Building Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8

FL0061ZZ-000000166	Exit Signs	EXS	08	SV-EE	Floor 08 General Building Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000167	Exit Signs	EXS	09	HW	Floor 09 General Building Hallway By North stairwell Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000168	Exit Signs	EXS	09	HW	Floor 09 General Building Hallway North	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000169	Exit Signs	EXS	09	HW	Floor 09 General Building Hallway South	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000170	Exit Signs	EXS	09	HW	Floor 09 General Building Hallway By Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000171	Exit Signs	EXS	09	HW	Floor 09 General Building Hallway By Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000172	Exit Signs	EXS	09	HW	Floor 09 General Building Hallway By North stairwell Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000173	Exit Signs	EXS	09	HW	Floor 09 General Building Hallway North	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000174	Exit Signs	EXS	09	HW	Floor 09 General Building Hallway By Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000175	Exit Signs	EXS	09	EV	Floor 09 General Building Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000176	Exit Signs	EXS	09	SV-EE	Floor 09 General Building Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000177	Exit Signs	EXS	09	ST	Floor 09 General Building By South stairwell Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000178	Exit Signs	EXS	09	OF	Floor 09 General Building By NW Office	Begheli	Not available	Not available
FL0061ZZ-000000179	Exit Signs	EXS	09	NT	Floor 09 General Building By North Office Door	Begheli	Not available	Not available
FL0061ZZ-000000180	Exit Signs	EXS	09	OF	Floor 09 General Building InSide officeS	Begheli	Not available	Not available
FL0061ZZ-000000181	Exit Signs	EXS	09	OF	Floor 09 Office By South West Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000182	Exit Signs	EXS	09	OF	Floor 09 Office By South Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000183	Exit Signs	EXS	09	OF	Floor 09 Office By Entrance Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000184	Exit Signs	EXS	09	OF	Floor 09 Office By East Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000185	Exit Signs	EXS	09	OF	Floor 09 Office By Hallway Close to East Exit	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000186	Exit Signs	EXS	10	HW	Floor 10 General Building Hallway By North stairwell Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000187	Exit Signs	EXS	10	HW	Floor 10 General Building Hallway North	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000188	Exit Signs	EXS	10	HW	Floor 10 General Building Hallway South	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000189	Exit Signs	EXS	10	HW	Floor 10 General Building Hallway By Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000190	Exit Signs	EXS	10	HW	Floor 10 General Building Hallway By Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000191	Exit Signs	EXS	10	EV	Floor 10 General Building Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000192	Exit Signs	EXS	10	SV-EE	Floor 10 General Building Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8

FL0061ZZ-000000193	Exit Signs	EXS	10	1021	Floor 10 General Building Room 1021 Inside the Closet	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000194	Exit Signs	EXS	10	HW	Floor 10 General Building Hallway By Main Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000195	Exit Signs	EXS	10	EX	Floor 10 General Building By Main Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000196	Exit Signs	EXS	10	1021	Floor 10 General Building Room 1021	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000197	Exit Signs	EXS	10	1023	Floor 10 General Building Room 1023	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000198	Exit Signs	EXS	10	1031	Floor 10 General Building Room 1031	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000199	Exit Signs	EXS	10	HW	Floor 10 General Building Hallway By North stairwell Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000200	Exit Signs	EXS	10	HW	Floor 10 General Building Hallway North	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000201	Exit Signs	EXS	10	HW	Floor 10 General Building Hallway South	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000202	Exit Signs	EXS	10	HW	Floor 10 General Building Hallway By Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000203	Exit Signs	EXS	10	HW	Floor 10 General Building Hallway By Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000204	Exit Signs	EXS	10	EV	Floor 10 General Building Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000205	Exit Signs	EXS	10	SV-EE	Floor 10 General Building Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000206	Exit Signs	EXS	11	NT	Floor 11 General Building North Side offices	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000207	Exit Signs	EXS	11	NT	Floor 11 General Building North Side offices Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000208	Exit Signs	EXS	11	NT	Floor 11 General Building North Side Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000209	Exit Signs	EXS	11	OF	Floor 11 General Building Offices Hallway North	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000210	Exit Signs	EXS	11	OF	Floor 11 General Building Offices Hallway South	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000211	Exit Signs	EXS	11	1131	Floor 11 General Building Room 1131 InSide office	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000212	Exit Signs	EXS	11	1131	Floor 11 General Building Room 1131 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000213	Exit Signs	EXS	11	HW	Floor 11 General Building Hallway By North stairwell Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000214	Exit Signs	EXS	11	HW	Floor 11 General Building Hallway North	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000215	Exit Signs	EXS	11	HW	Floor 11 General Building Hallway South	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000216	Exit Signs	EXS	11	HW	Floor 11 General Building Hallway By Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000217	Exit Signs	EXS	11	HW	Floor 11 General Building Hallway By Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8

FL0061ZZ-000000218	Exit Signs	EXS	11	EV	Floor 11 General Building Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000219	Exit Signs	EXS	11	SV-EE	Floor 11 General Building Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000220	Exit Signs	EXS	12	HW	Floor 12 General Building Hallway By North stairwell Door	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000221	Exit Signs	EXS	12	HW	Floor 12 General Building Hallway North	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000222	Exit Signs	EXS	12	HW	Floor 12 General Building Hallway South	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000223	Exit Signs	EXS	12	HW	Floor 12 General Building Hallway By Elevator Lobby	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000224	Exit Signs	EXS	12	HW	Floor 12 General Building Hallway By Service Elevator Lobby	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000225	Exit Signs	EXS	12	EV	Floor 12 General Building Elevator Lobby	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000226	Exit Signs	EXS	12	SV-EE	Floor 12 General Building Service Elevator Lobby	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000227	Exit Signs	EXS	12	LB	Floor 12 General Building Room 1204 Lobby	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000228	Exit Signs	EXS	12	OF	Floor 12 General Building Offices Hallway North	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000229	Exit Signs	EXS	12	OF	Floor 12 General Building Offices Hallway South	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000230	Exit Signs	EXS	12	OF	Floor 12 General Building Offices Hallway	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000231	Exit Signs	EXS	12	OF	Floor 12 General Building Offices Hallway	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000232	Exit Signs	EXS	12	HW	Floor 12 General Building Ofices Hallway	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000233	Exit Signs	EXS	12	SO	Floor 12 General Building Storage Room	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000234	Exit Signs	EXS	12	KT	Floor 12 General Building By food Room	LITHONIA	LQMSW3R EL N	EMCUA00188
FL0061ZZ-000000235	Exit Signs	EXS	13	HW	Floor 13 General Building Hallway By North stairwell Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000236	Exit Signs	EXS	13	HW	Floor 13 General Building Hallway North	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000237	Exit Signs	EXS	13	HW	Floor 13 General Building Hallway South	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000238	Exit Signs	EXS	13	HW	Floor 13 General Building Hallway By Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000239	Exit Signs	EXS	13	HW	Floor 13 General Building Hallway By Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000240	Exit Signs	EXS	13	EV	Floor 13 General Building Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000241	Exit Signs	EXS	13	SV-EE	Floor 13 General Building Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000242	Exit Signs	EXS	13	1304	Floor 13 General Building Room 1304	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000243	Exit Signs	EXS	13	LB	Floor 13 General Building Room 1312 Lobby Reception	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8

FL0061ZZ-000000244	Exit Signs	EXS	13	LB	Floor 13 General Building Room 1312 Lobby Reception	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000245	Exit Signs	EXS	13	1312	Floor 13 General Building Room 1312 Internal Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000246	Exit Signs	EXS	13	1312	Floor 13 General Building Room 1312 Internal Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000247	Exit Signs	EXS	13	1320	Floor 13 General Building Room 1320 Internal Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000248	Exit Signs	EXS	13	1320	Floor 13 General Building Room 1320 Internal Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000249	Exit Signs	EXS	13	1320	Floor 13 General Building Room 1320 By South Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000250	Exit Signs	EXS	14	HW	Floor 14 General Building Hallway By North stairwell Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000251	Exit Signs	EXS	14	HW	Floor 14 General Building Hallway North	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000252	Exit Signs	EXS	14	HW	Floor 14 General Building Hallway South	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000253	Exit Signs	EXS	14	HW	Floor 14 General Building Hallway By Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000254	Exit Signs	EXS	14	HW	Floor 14 General Building Hallway By Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000255	Exit Signs	EXS	14	EV	Floor 14 General Building Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000256	Exit Signs	EXS	14	SV-EE	Floor 14 General Building Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000257	Exit Signs	EXS	14	1401	Floor 14 General Building Room 1401 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000258	Exit Signs	EXS	14	1401	Floor 14 General Building Room 1401 interior	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000259	Exit Signs	EXS	14	1402	Floor 14 General Building Room 1402 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000260	Exit Signs	EXS	14	1404	Floor 14 General Building Room 1404 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000261	Exit Signs	EXS	14	1404	Floor 14 General Building Room 1404 interior	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000262	Exit Signs	EXS	14	1406	Floor 14 General Building Room 1406 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000263	Exit Signs	EXS	14	1409	Floor 14 General Building Room 1409 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000264	Exit Signs	EXS	14	1410	Floor 14 General Building Room 1410 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000265	Exit Signs	EXS	14	1412	Floor 14 General Building Room 1412 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000266	Exit Signs	EXS	16	LB	Floor 16 Lobby NE outSide Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000267	Exit Signs	EXS	16	LB	Floor 16 Lobby SE outSide Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8

FL0061ZZ-000000268	Exit Signs	EXS	16	SV-HW	Floor 16 General Building Service Hallway to Mechanical Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000269	Exit Signs	EXS	16	SV-HW	Floor 16 General Building Service Hallway to Main Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000270	Exit Signs	EXS	16	SV-HW	Floor 16 General Building Service Hallway to Parking Lot	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000271	Exit Signs	EXS	16	SV-HW	Floor 16 General Building Service Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000272	Exit Signs	EXS	16	LB	Floor 16 General Building Main Lobby to NE Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000273	Exit Signs	EXS	16	LB	Floor 16 General Building Main Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000274	Exit Signs	EXS	16	OF	Floor 16 Office Main Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000275	Exit Signs	EXS	16	OF	Floor 16 Office Service Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000276	Exit Signs	EXS	16	OF	Floor 16 Office Main Lobby to NE Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000277	Exit Signs	EXS	16	OF	Floor 16 Office Main Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000278	Exit Signs	EXS	16	OF	Floor 16 Office Main Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000279	Exit Signs	EXS	16	OF	Floor 16 Office NE outSide Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000280	Exit Signs	EXS	16	OF	Floor 16 Office SE outSide Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000281	Exit Signs	EXS	16	OF	Floor 16 Office Service Hallway to Mechanical Room	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000282	Exit Signs	EXS	16	OF	Floor 16 Office Service Hallway to Main Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000283	Exit Signs	EXS	16	OF	Floor 16 Office Service Hallway to Parking Lot	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000284	Exit Signs	EXS	16	OF	Floor 16 Office Main Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000285	Exit Signs	EXS	16	OF	Floor 16 Office Service Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000286	Exit Signs	EXS	16	OF	Floor 16 Office Main Lobby to NE Hallway	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000287	Exit Signs	EXS	16	OF	Floor 16 Office Main Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000288	Exit Signs	EXS	15	HW	Floor 15 General Building Hallway By North stairwell Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000289	Exit Signs	EXS	15	HW	Floor 15 General Building Hallway North	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000290	Exit Signs	EXS	15	HW	Floor 15 General Building Hallway South	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000291	Exit Signs	EXS	15	HW	Floor 15 General Building Hallway By Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000292	Exit Signs	EXS	15	HW	Floor 15 General Building Hallway By Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000293	Exit Signs	EXS	15	EV	Floor 15 General Building Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000294	Exit Signs	EXS	15	SV-EE	Floor 15 General Building Service Elevator Lobby	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000295	Exit Signs	EXS	15	JC	Floor 15 Judges chambers Exit Door North	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8

FL0061ZZ-000000296	Exit Signs	EXS	15	JC	Floor 15 Judges chambers Exit Door South	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000297	Exit Signs	EXS	15	1512	Floor 15 General Building Room 1512 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000298	Exit Signs	EXS	15	1514	Floor 15 General Building Room 1514 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000299	Exit Signs	EXS	15	1516	Floor 15 General Building Room 1516 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000300	Exit Signs	EXS	15	1519	Floor 15 General Building Room 1519 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000301	Exit Signs	EXS	15	1521	Floor 15 General Building Room 1521 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000302	Exit Signs	EXS	15	1523	Floor 15 General Building Room 1523 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000303	Exit Signs	EXS	15	1530	Floor 15 General Building Room 1530 Exit Door	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000304	Exit Signs	EXS	17	MC	Floor 17 Mechanical Equipment Room Entrance	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000305	Exit Signs	EXS	17	MC	Floor 17 Mechanical Equipment Room Roof entrance	GILBER INDUSTRIES INC.	LEDX-1-EM	32M8
FL0061ZZ-000000334	Fan, Axial	FAN-01	01	SW	Floor 01 Stairwell #1 Exhaust fan on North stairweel		Not available	Not available
FL0061ZZ-000000335	Fan, Axial	FAN-01	01	SW	Floor 01 Stairwell #2 Exhaust fan on North stairweel		Not available	Not available
FL0061ZZ-000000336	Fan, Axial	FAN-01			Roof General Building By the second floor roof	PENN	Not available	Not available
FL0061ZZ-000000337	Fan, Axial	FAN-01			Roof General Building By the second floor roof	PENN	Not available	Not available
FL0061ZZ-000000338	Fan, Axial	FAN-01			Roof General Building By the second floor roof	PENN	Not available	Not available
FL0061ZZ-000000339	Fan, Axial	FAN-01			Roof General Building By the second floor roof	Not available	Not available	Not available
FL0061ZZ-000000340	Fan, Axial	FAN-01			Roof General Building By the second floor roof	JENN AIR	Not available	Not available
FL0061ZZ-000000341	Fan, Axial	FAN-01			Roof General Building By the second floor roof	Not available	Not available	Not available
FL0061ZZ-000000342	Fan, Axial	FAN-01			Roof General Building By the second floor roof	American coolair corp.	CRBA36	M729640
FL0061ZZ-000000343	Fan, Axial	FAN-01	18	EE	Floor 18 Electrical Equipment Room on back left Side of the Room	WESTINGHOUSE	ATY-4370-4	110P449H01
FL0061ZZ-000000344	Fan, Axial	FAN-01	18	EE	Floor 18 Electrical Equipment Room on back left Side of the Room	WESTINGHOUSE		

FL0061ZZ-000000345	Fan, Axial	FAN-01	17	RF	Floor 17 Roof / Roof Installed Item South Side of the building	Greenheck	RSF-120-15-X	06G20662
FL0061ZZ-000000468	Fire Door - Swinging	FDR-01	01	EV	Floor 01 Throughout Entire Building Elevator Lobby to NE Hallway	Not available	Not available	Not available
FL0061ZZ-000000469	Fire Door - Swinging	FDR-01	02	EV	Floor 02 Throughout Entire Building Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000470	Fire Door - Swinging	FDR-01	02	SV-EE	Floor 02 Throughout Entire Building Service Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000471	Fire Door - Swinging	FDR-01	03	EV	Floor 03 Throughout Entire Building Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000472	Fire Door - Swinging	FDR-01	03	SV-EE	Floor 03 Throughout Entire Building Service Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000473	Fire Door - Swinging	FDR-01	04	EV	Floor 04 Throughout Entire Building Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000474	Fire Door - Swinging	FDR-01	04	SV-EE	Floor 04 Throughout Entire Building Service Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000475	Fire Door - Swinging	FDR-01	05	EV	Floor 05 Throughout Entire Building Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000476	Fire Door - Swinging	FDR-01	05	SV-EE	Floor 05 Throughout Entire Building Service Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000477	Fire Door - Swinging	FDR-01	06	EV	Floor 06 Throughout Entire Building Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000478	Fire Door - Swinging	FDR-01	06	SV-EE	Floor 06 Throughout Entire Building Service Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000479	Fire Door - Swinging	FDR-01	07	EV	Floor 07 Throughout Entire Building Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000480	Fire Door - Swinging	FDR-01	07	SV-EE	Floor 07 Throughout Entire Building Service Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000481	Fire Door - Swinging	FDR-01	08	EV	Floor 08 Throughout Entire Building Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000482	Fire Door - Swinging	FDR-01	08	SV-EE	Floor 08 Throughout Entire Building Service Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000483	Fire Door - Swinging	FDR-01	09	EV	Floor 09 Throughout Entire Building Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000484	Fire Door - Swinging	FDR-01	09	SV-EE	Floor 09 Throughout Entire Building Service Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000485	Fire Door - Swinging	FDR-01	10	EV	Floor 10 Throughout Entire Building Elevator Lobby to Hallway	Not available	Not available	Not available

FL0061ZZ-000000486	Fire Door - Swinging	FDR-01	10	SV-EE	Floor 10 Throughout Entire Building Service Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000487	Fire Door - Swinging	FDR-01	11	EV	Floor 11 Throughout Entire Building Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000488	Fire Door - Swinging	FDR-01	11	SV-EE	Floor 11 Throughout Entire Building Service Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000489	Fire Door - Swinging	FDR-01	12	EV	Floor 12 Throughout Entire Building Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000490	Fire Door - Swinging	FDR-01	12	SV-EE	Floor 12 Throughout Entire Building Service Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000491	Fire Door - Swinging	FDR-01	13	EV	Floor 13 Throughout Entire Building Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000492	Fire Door - Swinging	FDR-01	13	SV-EE	Floor 13 Throughout Entire Building Service Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000493	Fire Door - Swinging	FDR-01	14	EV	Floor 14 Throughout Entire Building Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000494	Fire Door - Swinging	FDR-01	14	SV-EE	Floor 14 Throughout Entire Building Service Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000495	Fire Door - Swinging	FDR-01	15	EV	Floor 15 Throughout Entire Building Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000496	Fire Door - Swinging	FDR-01	15	SV-EE	Floor 15 Throughout Entire Building Service Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000497	Fire Door - Swinging	FDR-01	16	EV	Floor 16 Throughout Entire Building Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000498	Fire Door - Swinging	FDR-01	16	SV-EE	Floor 16 Throughout Entire Building Service Elevator Lobby to Hallway	Not available	Not available	Not available
FL0061ZZ-000000381	Fire Extinguishers	FEX	01	CH	Floor 01 CHILLER Mechanical Room By Entrance Door	Buckeye	MOD 423	HZ 925919
FL0061ZZ-000000382	Fire Extinguishers	FEX	01	CH	Floor 01 CHILLER Mechanical Room Fire pump Room	Buckeye	MOD 411	SF 348669
FL0061ZZ-000000383	Fire Extinguishers	FEX	01	CH	Floor 01 CHILLER Mechanical Room Boiler Room	Buckeye	M 20 HI SABO ABC	JC 00045198
FL0061ZZ-000000384	Fire Extinguishers	FEX	01	CH	Floor 01 CHILLER Mechanical Room By CHILLER #1	Buckeye	M 10 HI SABO ABC	VE 803645
FL0061ZZ-000000385	Fire Extinguishers	FEX	01	CH	Floor 01 CHILLER Mechanical Room AHU #1 West Side	Buckeye	M 20 HI SABO ABC	JC 00045183
FL0061ZZ-000000386	Fire Extinguishers	FEX	01	CH	Floor 01 CHILLER Mechanical Room AHU #2 East Side	Buckeye	MOD 423	HZ 42901
FL0061ZZ-000000387	Fire Extinguishers	FEX	01	CH	Floor 01 CHILLER Mechanical Room F/A Room	Buckeye	M 20 HI SABO ABC	JC 0045204

FL0061ZZ-000000388	Fire Extinguishers	FEX	01	CH	Floor 01 CHILLER Mechanical Room Maintenance shop	Buckeye	5MB-6H	KR 839733
FL0061ZZ-000000389	Fire Extinguishers	FEX	01	HW-SW	Floor 01 General Building SW Hallway	Buckeye	A10H	WM 628388
FL0061ZZ-000000390	Fire Extinguishers	FEX	01	HW-SE	Floor 01 General Building SE Hallway	Buckeye	M 20 HI SABO ABC	VZ 42260
FL0061ZZ-000000391	Fire Extinguishers	FEX	01	HW-NT	Floor 01 General Building North Hallway	Buckeye	M 10 HI SABO ABC	HB 397850
FL0061ZZ-000000392	Fire Extinguishers	FEX	01	100	Floor 01 General Building Room 100	Buckeye	M 10 HI SABO ABC	VZ 149244
FL0061ZZ-000000393	Fire Extinguishers	FEX	01	102	Floor 01 General Building Room 102	Buckeye	A10H	WM 628493
FL0061ZZ-000000394	Fire Extinguishers	FEX	01	EV	Floor 01 General Building Elevator pit	Buckeye	M 10 HI SABO ABC	MR 828801
FL0061ZZ-000000395	Fire Extinguishers	FEX	01	EE	Floor 01 General Building Main Electrical Room	Buckeye	MOD 423	HZ 92920
FL0061ZZ-000000396	Fire Extinguishers	FEX	02	FC	Floor 02 Food Service, Break Room on the back Side of the Room	ANSUL	R102	S155490
FL0061ZZ-000000397	Fire Extinguishers	FEX	02	FC	Floor 02 Food Service, Break Room Back Side of the cafeteria	JL INDUSTRIES	10 MB-8H	PN 616857
FL0061ZZ-000000398	Fire Extinguishers	FEX	02	EE	Floor 02 General Building By Electrical Room	Buckeye	M10HSABO ABC	JB 00989015
FL0061ZZ-000000399	Fire Extinguishers	FEX	02	ST	Floor 02 General Building South Side	KIDDLE	PRO 10TCH-6	VL 380380
FL0061ZZ-000000400	Fire Extinguishers	FEX	03	NT	Floor 03 General Building North Side	Buckeye	M10HSABO ABC	JB 397867
FL0061ZZ-000000401	Fire Extinguishers	FEX	03	EE	Floor 03 General Building By Electrical Room	Not available	PRO 10TCH-6	VT 328938
FL0061ZZ-000000402	Fire Extinguishers	FEX	03	ST	Floor 03 General Building South Side	Buckeye	M10HSABO ABC	JB397103
FL0061ZZ-000000403	Fire Extinguishers	FEX	04	NT	Floor 04 General Building North Side	Buckeye	M10HSABO ABC	JB 397834
FL0061ZZ-000000404	Fire Extinguishers	FEX	04	EE	Floor 04 General Building By Electrical Room	Buckeye	M10HSABO ABC	JB 397160
FL0061ZZ-000000405	Fire Extinguishers	FEX	04	ST	Floor 04 General Building South Side	Buckeye	M10HSABO ABC	JB 397848
FL0061ZZ-000000406	Fire Extinguishers	FEX	05	NT	Floor 05 General Building North Side	Buckeye	M10HSABO ABC	JB 00989007
FL0061ZZ-000000407	Fire Extinguishers	FEX	05	EE	Floor 05 General Building By Electrical Room	Buckeye	M10HSABO ABC	JB 000989016
FL0061ZZ-000000408	Fire Extinguishers	FEX	05	ST	Floor 05 General Building South Side	Buckeye	M10HSABO ABC	JB 397831
FL0061ZZ-000000409	Fire Extinguishers	FEX	06	NT	Floor 06 General Building North Side	Buckeye	M10HSABO ABC	JB 397833
FL0061ZZ-000000410	Fire Extinguishers	FEX	06	EE	Floor 06 General Building By Electrical Room	Buckeye	M20HSABO ABC	JC 00045206
FL0061ZZ-000000411	Fire Extinguishers	FEX	06	ST	Floor 06 General Building South Side	KIDDLE	PRO 10TCH-6	VL 380405
FL0061ZZ-000000412	Fire Extinguishers	FEX	07	NT	Floor 07 General Building North Side	AMEREX	MOD 456	JC 383460
FL0061ZZ-000000413	Fire Extinguishers	FEX	07	EE	Floor 07 General Building By Electrical Room	Buckeye	M10HSABO ABC	JB 593936
FL0061ZZ-000000414	Fire Extinguishers	FEX	07	ST	Floor 07 General Building South Side	Buckeye	M10HSABO ABC	RX 752130
FL0061ZZ-000000415	Fire Extinguishers	FEX	08	NT	Floor 08 General Building North Side	Buckeye	M10HSABO ABC	JB 397858

FL0061ZZ-000000416	Fire Extinguishers	FEX	08	EE	Floor 08 General Building By Electrical Room	Buckeye	M10HSABO ABC	JB 397093
FL0061ZZ-000000417	Fire Extinguishers	FEX	08	ST	Floor 08 General Building South Side	Buckeye	M10HSABO ABC	JB 397075
FL0061ZZ-000000418	Fire Extinguishers	FEX	09	NT	Floor 09 General Building North Side	Buckeye	M10HSABO ABC	JB 397182
FL0061ZZ-000000419	Fire Extinguishers	FEX	09	EE	Floor 09 General Building By Electrical Room	Not available	MOD 456	SA 474281
FL0061ZZ-000000420	Fire Extinguishers	FEX	09	ST	Floor 09 General Building South Side	Buckeye	M10HSABO ABC	JB 00989975
FL0061ZZ-000000421	Fire Extinguishers	FEX	10	NT	Floor 10 General Building North Side	AMEREX	MOD 456	JC 383413
FL0061ZZ-000000422	Fire Extinguishers	FEX	10	EE	Floor 10 General Building By Electrical Room	Buckeye	M10HSABO ABC	JB 397845
FL0061ZZ-000000423	Fire Extinguishers	FEX	10	ST	Floor 10 General Building South Side	Buckeye	M10HSABO ABC	HJ 00083770
FL0061ZZ-000000424	Fire Extinguishers	FEX	11	NT	Floor 11 General Building North Side	AMEREX	MOD 456	HT 735107
FL0061ZZ-000000425	Fire Extinguishers	FEX	11	EE	Floor 11 General Building By Electrical Room	BADGER	M10HSABO ABC	XE 714211
FL0061ZZ-000000426	Fire Extinguishers	FEX	11	ST	Floor 11 General Building South Side	J L INDUSTRIES	M10HSABO ABC	WZ 553024
FL0061ZZ-000000427	Fire Extinguishers	FEX	12	NT	Floor 12 General Building North Side	Buckeye	M20HSABO ABC	JC 00045197
FL0061ZZ-000000428	Fire Extinguishers	FEX	12	EE	Floor 12 General Building By Electrical Room	Buckeye	M10HSABO ABC	JB 00989973
FL0061ZZ-000000429	Fire Extinguishers	FEX	12	ST	Floor 12 General Building South Side	Buckeye	M10HSABO ABC	JB 00989969
FL0061ZZ-000000430	Fire Extinguishers	FEX	13	NT	Floor 13 General Building North Side	JL INDUSTRIES	A 456	PM 863326
FL0061ZZ-000000431	Fire Extinguishers	FEX	13	EE	Floor 13 General Building By Electrical Room	Buckeye	M10HSABO ABC	JB 00989005
FL0061ZZ-000000432	Fire Extinguishers	FEX	13	ST	Floor 13 General Building South Side	Buckeye	M10HSABO ABC	JB 397862
FL0061ZZ-000000433	Fire Extinguishers	FEX	14	NT	Floor 14 General Building North Side	AMEREX	MOD 456	JB383425
FL0061ZZ-000000434	Fire Extinguishers	FEX	14	EE	Floor 14 General Building By Electrical Room	AMEREX	MOD 456	GA 270236
FL0061ZZ-000000435	Fire Extinguishers	FEX	14	ST	Floor 14 General Building South Side	Not available	M10HSABO ABC	JB 397185
FL0061ZZ-000000436	Fire Extinguishers	FEX	15	NT	Floor 15 General Building North Side	Buckeye	MOD 423	GJ 374066
FL0061ZZ-000000437	Fire Extinguishers	FEX	15	EE	Floor 15 General Building By Electrical Room	Buckeye	M10HSABO ABC	WD 287765
FL0061ZZ-000000438	Fire Extinguishers	FEX	15	ST	Floor 15 General Building South Side	Buckeye	MOD 423	GE 730491
FL0061ZZ-000000439	Fire Extinguishers	FEX	16	NT	Floor 16 General Building North Side	Buckeye	M10HSABO ABC	JB 00989014
FL0061ZZ-000000440	Fire Extinguishers	FEX	16	EE	Floor 16 General Building By Electrical Room	Buckeye	M10HSABO ABC	PS 322983
FL0061ZZ-000000441	Fire Extinguishers	FEX	16	ST	Floor 16 General Building South Side	Buckeye	M10HSABO ABC	PC 150961
FL0061ZZ-000000442	Fire Extinguishers	FEX	17	EN	Floor 17 General Building By Entrance Door	Buckeye	M10HSABO ABC	JB 00989007
FL0061ZZ-000000443	Fire Extinguishers	FEX	17	EE	Floor 17 General Building By Electrical Panelboard	Buckeye	M10HSABO ABC	YL 986850

FL0061ZZ-000000444	Fire Extinguishers	FEX	17	ST	Floor 17 General Building By South Door	Buckeye	M10HSABO ABC	JB 00989970
FL0061ZZ-000000445	Fire Extinguishers	FEX	17		Floor 17 General Building By the water tank	Buckeye	MOD 483	WM 628483
FL0061ZZ-000000446	Fire Extinguishers	FEX	17		Floor 17 General Building By the air handler filter Door	Buckeye	M10HSABO ABC	JB 397829
FL0061ZZ-000000447	Fire Extinguishers	FEX	18	EN	Floor 18 General Building By Entrance Door	Buckeye	M10HSABO ABC	JB 00989006
FL0061ZZ-000000448	Fire Extinguishers	FEX	18	EE	Floor 18 General Building In the Elevator Mechanical Room	Buckeye	M10HSABO ABC	JB 397826
FL0061ZZ-000000449	Fire Extinguishers	FEX	18		Floor 18 General Building By the Hallway	Buckeye	M10HSABO ABC	JB 397849
FL0061ZZ-000000450	Fire Extinguishers	FEX	18		Floor 18 General Building By frequency drive North Side	Buckeye	M10HSABO ABC	JB 397853
FL0061ZZ-000000451	Fire Extinguishers	FEX	18		Floor 18 General Building By frequency drive South Side	Buckeye	M10HSABO ABC	PV 684167
FL0061ZZ-000000452	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	Sentry	SY 0014	PE 489766
FL0061ZZ-000000453	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	Buckeye	M20HSABO ABC	JC 00045199
FL0061ZZ-000000454	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	Buckeye	M20HSABO ABC	JC 00045193
FL0061ZZ-000000455	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	Buckeye	M20HSABO ABC	JC 00045194
FL0061ZZ-000000456	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	JL INDUSTRIES	10 MB-8H	BL 644263
FL0061ZZ-000000457	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	Buckeye	MOD 423	HZ 92919
FL0061ZZ-000000458	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	Buckeye	M10HSABO ABC	JB 397862
FL0061ZZ-000000459	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	Buckeye	M10HSABO ABC	JB 397842
FL0061ZZ-000000460	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	Buckeye	M10HSABO ABC	JB 00989009
FL0061ZZ-000000461	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	Buckeye	M10HSABO ABC	JB 397086
FL0061ZZ-000000462	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	Buckeye	M10HSABO ABC	JB 397102
FL0061ZZ-000000463	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	Buckeye	M10HSABO ABC	JB 397845
FL0061ZZ-000000464	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	JL INDUSTRIES	10 MB-8H	PN 616857
FL0061ZZ-000000465	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	Buckeye	M10HSABO ABC	JB 00989962
FL0061ZZ-000000466	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	Buckeye	M10HSABO ABC	VN 644236
FL0061ZZ-000000467	Fire Extinguishers	FEX		SH	Ground Floor Shop / Factory SPARE	Buckeye	SY 1014	PE 497766
FL0061ZZ-000000346	Fire and Smoke Dampers	FSD	02	SW	Floor 02 Stairwell #1 On top of north outside hallway	Not available	Not available	Not available
FL0061ZZ-000000347	Fire and Smoke Dampers	FSD	02	SW	Floor 02 Stairwell #2 On top of south outside hallway	Not available	Not available	Not available
FL0061ZZ-000000348	Fire and Smoke Dampers	FSD	19	SW	Floor 19 Stairwell #1 On the north side of the building	Not available	Not available	Not available
FL0061ZZ-000000349	Fire and Smoke Dampers	FSD	17	SW	Floor 17 Stairwell #2 On the south side of the building	Not available	Not available	Not available
FL0061ZZ-000000499	Heat Pump, Air Cooled	HTP-1	01	138	Floor 01 ROOM 138	FHP	EMU 42-3	JD 6984

FL0061ZZ-000000511	Motor Control Center	MCC	01	CH	Floor 01 CHILLER Mechanical Room For CHILLER #2 water pump	AEROVOX	216f	Not available
FL0061ZZ-000000512	Motor Control Center	MCC	01	CH	Floor 01 CHILLER Mechanical Room For CHILLER #2 condenser water pump	AEROVOX	216f	Not available
FL0061ZZ-000000513	Motor Control Center	MCC	01	CH	Floor 01 CHILLER Mechanical Room For CHILLER #2 water pump	ALLEN BRADLE	Not available	Not available
FL0061ZZ-000000514	Motor Control Center	MCC	01	CH	Floor 01 CHILLER Mechanical Room For CHILLER #2 condenser water pump	ALLEN BRADLE	Not available	Not available
FL0061ZZ-000000515	Motor Control Center	MCC	01	CH	Floor 01 CHILLER Mechanical Room By CHILLER @1	SQUARE D	353-58G13	Not available
FL0061ZZ-000000516	Motor Control Center	MCC	01	MC	Floor 01 Mechanical Equipment Room	ABB Automation	ACH500	Not available
FL0061ZZ-000000517	Motor Control Center	MCC	01	MC	Floor 01 Mechanical Equipment Room	ABB Automation	ACH-500	Not available
FL0061ZZ-000000518	Motor Control Center	MCC	01	CH	Floor 01 CHILLER Mechanical Room	ABB Automation	ACH-500	Not available
FL0061ZZ-000000519	Motor Control Center	MCC	01	MC	Floor 01 Mechanical Equipment Room By AHU#1 Air Intake	ROLL-KLEEN	Not available	Not available
FL0061ZZ-000000520	Motor Control Center	MCC	01	MC	Floor 01 Mechanical Equipment Room By AHU#1 Air return intake	ROLL-KLEEN	Not available	Not available
FL0061ZZ-000000521	Motor Control Center	MCC	01	CH	Floor 01 CHILLER Mechanical Room FIRE ALARM CONTROL PANEL	FIRETROL	FTA1000-4475B-TS	
FL0061ZZ-000000522	Motor Control Center	MCC	17	MC	Floor 17 Mechanical Equipment Room Right Side of the Hallway	ABB Automation	ASC600	3432K3
FL0061ZZ-000000523	Motor Control Center	MCC	17	MC	Floor 17 Mechanical Equipment Room Right Side of the Hallway	ABB Automation	ASC600	3432K3
FL0061ZZ-000000524	Motor Control Center	MCC	17	MC	Floor 17 Mechanical Equipment Room Left Side of the Hallway	ABB Automation	ACH550-VC-015-4	
FL0061ZZ-000000533	Motor Control Center	MCC	01	CH	Floor 01 CHILLER Mechanical Room Fire alarm control panel	FIRETROL	FTA1000-4475B-TS	
FL0061ZZ-000000534	Motor Control Center	MCC	17	EE	Floor 17 Electrical Equipment Room Old Cooling tower switch	WESTINGHOUSE		451D253G09
FL0061ZZ-000000535	Motor Control Center	MCC	17	EE	Floor 17 Electrical Equipment Room Old Cooling tower switch	WESTINGHOUSE		451D253G09
FL0061ZZ-000000536	Motor Control Center	MCC	17	MC	Floor 17 Mechanical Equipment Room By the AHU #2 return Door	ROLL-KLEEN	Not available	Not available
FL0061ZZ-000000525	Motor, Fan	MOT-01		RF	Roof Roof / Roof Installed Item on top of the Elevator machine Room	BALDOR	M3733	F988
FL0061ZZ-000000526	Motor, Fan	MOT-01		RF	Roof Roof / Roof Installed Item on top of the Elevator machine Room	BALDOR	M3733	F988
FL0061ZZ-000000537	Motor, Fan	MOT-01	18	EE	Floor 18 Electrical Equipment Room on back left Side of the Room	DAYton	2N238G	AEGANE

FL0061ZZ-000000538	Motor, Fan	MOT-01	18	EE	Floor 18 Electrical Equipment Room on back left Side of the Room	DAYton	2N992B	Not available
FL0061ZZ-000000527	Motor, Pump	MOT-02	01	CH	Floor 01 CHILLER Mechanical Room CW-1	MARATHON ELE	HVK286TTDCA4026H	
FL0061ZZ-000000528	Motor, Pump	MOT-02	01	CH	Floor 01 CHILLER Mechanical Room CW-2	MARATHON ELE	EVN254TTDB4026BB	E254I
FL0061ZZ-000000529	Motor, Pump	MOT-02	01	CH	Floor 01 CHILLER Mechanical Room CHW-2	MARATHON ELE	EVN254TTDB4026BB	E254I
FL0061ZZ-000000530	Motor, Pump	MOT-02	01	CH	Floor 01 CHILLER Mechanical Room DIST-1	MARATHON ELE	EVB286TTD64026BB	B286T
FL0061ZZ-000000531	Motor, Pump	MOT-02	01	CH	Floor 01 CHILLER Mechanical Room DIST-2	MARATHON ELE	EVJ286TTD64026BB	B286T
FL0061ZZ-000000532	Motor, Pump	MOT-02	01	CH	Floor 01 CHILLER Mechanical Room F/A motor pump	LINCGUARD	NO INFORMATIon	361711
FL0061ZZ-000000500	Metering Devices	MTR		SP	Ground Floor Sally Port Electric cabinet By the guard desk	LANDIS - GYR	FPL TC-L2-402-60470-0	RV 9634H
FL0061ZZ-000000501	Metering Devices	MTR		SP	Ground Floor Sally Port Electric cabinet By the guard desk	LANDIS - GYR	FPL TC-L2-402-60470-0	rv 9054h
FL0061ZZ-000000502	Metering Devices	MTR		SP	Ground Floor Sally Port Gas meter By CHILLER#1 gate	ITRON Inc	5N	EWQ100GDLCN
FL0061ZZ-000000503	Metering Devices	MTR			Ground Floor outSide In the Sidewalk By the South Side of the building	SENSUS	NFS-61	644028
FL0061ZZ-000000504	Metering Devices	MTR			Ground Floor outSide In the Sidewalk By the South Side of the building	SENSUS	Not available	10406445
FL0061ZZ-000000505	Metering Devices	MTR			Ground Floor outSide In the Sidewalk By the North Side of the building	SENSUS	ROCKWELL	43268386
FL0061ZZ-000000506	Metering Devices	MTR			ground Floor outSide In the Sidewalk By the North Side of the building	SENSUS	Not available	416003
FL0061ZZ-000000507	Metering Devices	MTR	01	CH	Floor 01 CHILLER Mechanical Room Refrigerant gas monitor on CHILLER Room #2	Sherlock	Not available	Not available
FL0061ZZ-000000508	Metering Devices	MTR	01	CH	Floor 01 CHILLER Mechanical Room By CHILLER #2	DSC	PC 1500	F53CAN-610131-AL-E
FL0061ZZ-000000509	Metering Devices	MTR	01	CH	Floor 01 CHILLER Mechanical Room By CHILLER #2	TRANE	LR 83032	X39470413-01
FL0061ZZ-000000510	Metering Devices	MTR	17	RF	Floor 17 Roof / Roof Installed Item By the East Side of the Cooling tower	Neptune	Trident 10	31847880
FL0061ZZ-000000644	Powered Doors	PDR	01	CH	Floor 01 CHILLER Mechanical Room OPEN to the Parking Lot	OVERHEAD Door	GH-50-11-B2	1.914501e+014
FL0061ZZ-000000645	Powered Doors	PDR	01	PL	Floor 01 Parking Lot OPEN to FIRST STREET	MANARAS	Not available	BR-00089
FL0061ZZ-000000646	Powered Doors	PDR	01	PL	Floor 01 Parking Lot OPEN to FIRST STREET	MANARAS	Not available	BR-00090

FL0061ZZ-000000647	Pump	PMP	01	CH	Floor 01 CHILLER Mechanical Room F/A PUMP	READY BUFFALO	6X6DF	90-1444-DF6
FL0061ZZ-000000648	Pump	PMP	01	CH	Floor 01 CHILLER Mechanical Room F/A AUXILIARY PUMP	MTH		
FL0061ZZ-000000649	Pump, Re-Circulation	PMP-09	01	EE	Floor 01 Electrical Equipment Room North Side of the Room		1996421 BT	VSC8.625 BF LHR
FL0061ZZ-000000547	Panelboard, Lighting & Appliance	PNB	01	CH	Floor 01 CHILLER Mechanical Room By Domestic water pump	SQUARE D	NQQD 20L100CU	C80110-063-03
FL0061ZZ-000000548	Panelboard, Lighting & Appliance	PNB	01	CH	Floor 01 CHILLER Mechanical Room By Domestic water pump	CUTLER HAMME	PRL4B	6572C66G13
FL0061ZZ-000000549	Panelboard, Lighting & Appliance	PNB	01	CH	Floor 01 CHILLER Mechanical Room By South East Corner	WESTINGHOUSE	AG 85636	NA1B42-4L225
FL0061ZZ-000000550	Panelboard, Lighting & Appliance	PNB	01	CH	Floor 01 CHILLER Mechanical Room South Side of CHILLER #1	SQUARE D	NEHB E1	C480769-501
FL0061ZZ-000000551	Panelboard, Lighting & Appliance	PNB	01	CH	Floor 01 CHILLER Mechanical Room South Side of CHILLER #2	SQUARE D	MHC 235	0480769-503
FL0061ZZ-000000552	Panelboard, Lighting & Appliance	PNB	01	OF	Floor 01 Office Maintenance Office	WESTINGHOUSE	NA1B-32-4L225	118460
FL0061ZZ-000000553	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room North Side of the Electrical Room	WESTINGHOUSE	NH1836-4L225	85832
FL0061ZZ-000000554	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room East Side of the Electrical Room	WESTINGHOUSE	Not available	Not available
FL0061ZZ-000000555	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room Electrical Closet on FRonT OF MAIL Room	WESTINGHOUSE	NA1B32-4L225	Not available
FL0061ZZ-000000556	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room South Side of the Electrical Room	WESTINGHOUSE	Not available	Not available
FL0061ZZ-000000557	Panelboard, Lighting & Appliance	PNB	01		Floor 01 Outside By the loading duck	SQUARE D	QO6-12L100D	402-63-375-04
FL0061ZZ-000000558	Panelboard, Lighting & Appliance	PNB	02	FC	Floor 02 Food Service, Break Room on the back Side of the Room	SQUARE D	NQQD3400LAMB	MHC68VS
FL0061ZZ-000000559	Panelboard, Lighting & Appliance	PNB	02	EE	Floor 02 Electrical Equipment Room North Side of the Room	GENERAL ELEC	TL270SCU	MNP601257B
FL0061ZZ-000000560	Panelboard, Lighting & Appliance	PNB	02	EE	Floor 02 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	AG 85637	1737858A
FL0061ZZ-000000561	Panelboard, Lighting & Appliance	PNB	02	EE	Floor 02 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	AG 85638	1737858A
FL0061ZZ-000000562	Panelboard, Lighting & Appliance	PNB	02	EE	Floor 02 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	AG 85685	1737858A
FL0061ZZ-000000563	Panelboard, Lighting & Appliance	PNB	03	ET	Floor 03 Office East PART OF the Main Office	SQUARE D	NC44S	Not available
FL0061ZZ-000000564	Panelboard, Lighting & Appliance	PNB	03	ET	Floor 03 Office East PART OF the Main Office	SQUARE D	NC30S	Not available

FL0061ZZ-000000565	Panelboard, Lighting & Appliance	PNB	03	EE	Floor 03 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	NA1B32-4AB100	ATY-80930
FL0061ZZ-000000566	Panelboard, Lighting & Appliance	PNB	03	EE	Floor 03 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	NA1B32-4A100	ATY-80930
FL0061ZZ-000000567	Panelboard, Lighting & Appliance	PNB	03	EE	Floor 03 Electrical Equipment Room East Side of the Room	SQUARE D	Q0816L100DSCY	G04
FL0061ZZ-000000568	Panelboard, Lighting & Appliance	PNB	03	EE	Floor 03 Electrical Equipment Room South Side of the Room	WESTINGHOUSE	NH1B3D-4L100	ATY-80930
FL0061ZZ-000000569	Panelboard, Lighting & Appliance	PNB	03	EE	Floor 03 Electrical Equipment Room Phone Room	SQUARE D	NC44S	11491
FL0061ZZ-000000570	Panelboard, Lighting & Appliance	PNB	04	EE	Floor 04 Electrical Equipment Room South Side of the Room	WESTINGHOUSE	NH1B30-4L-100	ATY-80930
FL0061ZZ-000000571	Panelboard, Lighting & Appliance	PNB	04	EE	Floor 04 Electrical Equipment Room NOTYH East Side of the Room	SQUARE D	87B	350051
FL0061ZZ-000000572	Panelboard, Lighting & Appliance	PNB	04	EE	Floor 04 Electrical Equipment Room North Side of the Room	SQUARE D	NQODQ2	880110-064-01
FL0061ZZ-000000573	Panelboard, Lighting & Appliance	PNB	04	EE	Floor 04 Electrical Equipment Room North Side of the Room	SQUARE D	NQODQ2	880110-064-01
FL0061ZZ-000000574	Panelboard, Lighting & Appliance	PNB	05	EE	Floor 05 Electrical Equipment Room North East Side of the Room	SQUARE D	QDC342MQS	503
FL0061ZZ-000000575	Panelboard, Lighting & Appliance	PNB	05	EE	Floor 05 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	NA1B32-4AB100	ATY-8030
FL0061ZZ-000000576	Panelboard, Lighting & Appliance	PNB	05	EE	Floor 05 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	NA1B32-4AB101	ATY-8031
FL0061ZZ-000000577	Panelboard, Lighting & Appliance	PNB	05	EE	Floor 05 Electrical Equipment Room South Side of the Room	WESTINGHOUSE	NA1B32-4AB102	ATY-8031
FL0061ZZ-000000578	Panelboard, Lighting & Appliance	PNB	05	EE	Floor 05 Electrical Equipment Room 3rd Electrical Room South Side of the Main Electrical Room OF the FLOOR	SQUARE D	NH35TS	B80D43-240-01
FL0061ZZ-000000579	Panelboard, Lighting & Appliance	PNB	05	EE	Floor 05 Electrical Equipment Room 4th Electrical Room South Side of the Main Electrical Room OF the FLOOR	SQUARE D	NH35TS	80043-184-01
FL0061ZZ-000000580	Panelboard, Lighting & Appliance	PNB	05	EE	Floor 05 Electrical Equipment Room 6th Electrical Room South Side of the Main Electrical Room OF the FLOOR	SQUARE D	0480769-503	C80110-053-27
FL0061ZZ-000000581	Panelboard, Lighting & Appliance	PNB	05	EE	Floor 05 Electrical Equipment Room 7th Electrical Room South Side of the Main Electrical Room OF the FLOOR	GENERAL ELEC	TLM1612CCV	Not available
FL0061ZZ-000000582	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room South Side of the Room	WESTINGHOUSE	NH1B30-4L100	ATY80930

FL0061ZZ-000000583	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147P454H01
FL0061ZZ-000000584	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room East Side of the Room	WESTINGHOUSE	30-E-6186	147P454H01
FL0061ZZ-000000585	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	NA1B32-4AB100	ATY-80930
FL0061ZZ-000000586	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	NA1B32-4AB101	ATY-80930
FL0061ZZ-000000587	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room Electrical Room for computer Room	SQUARE D	MHC29S	B80043-240-01
FL0061ZZ-000000588	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room Electrical Room for computer Room	SQUARE D	R844	K-350051
FL0061ZZ-000000589	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room Electrical Room for computer Room	SQUARE D	R-307	K-350051
FL0061ZZ-000000590	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room Electrical Room for computer Room	SQUARE D	R299	K350051
FL0061ZZ-000000591	Panelboard, Lighting & Appliance	PNB	07	EE	Floor 07 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	AG-85688	1737858A
FL0061ZZ-000000592	Panelboard, Lighting & Appliance	PNB	07	EE	Floor 07 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	AG85660	1737858A
FL0061ZZ-000000593	Panelboard, Lighting & Appliance	PNB	07	EE	Floor 07 Electrical Equipment Room South Side of the Room	WESTINGHOUSE	AG 85770	1737858A
FL0061ZZ-000000594	Panelboard, Lighting & Appliance	PNB	07	EE	Floor 07 Electrical Equipment Room East Side of the Room	SIEMENS	I1X42MC250A	79-77611
FL0061ZZ-000000595	Panelboard, Lighting & Appliance	PNB	08	EE	Floor 08 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	AG-85688	1737858A
FL0061ZZ-000000596	Panelboard, Lighting & Appliance	PNB	08	EE	Floor 08 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	AG85660	1737858A
FL0061ZZ-000000597	Panelboard, Lighting & Appliance	PNB	08	EE	Floor 08 Electrical Equipment Room South Side of the Room	WESTINGHOUSE	AG 85770	1737858A
FL0061ZZ-000000598	Panelboard, Lighting & Appliance	PNB	08	EE	Floor 08 Electrical Equipment Room East Side of the Room	SIEMENS	I1X42MC250A	79-77609
FL0061ZZ-000000599	Panelboard, Lighting & Appliance	PNB	09	NT	Floor 09 Office North Side officeS	SQUARE D	NQDRNF	LLCDQ1130NC38S-3S
FL0061ZZ-000000600	Panelboard, Lighting & Appliance	PNB	09	NT	Floor 09 Office North Side officeS	SQUARE D	NQDRNF	LLCDQ1129NC32S-W12-2S
FL0061ZZ-000000601	Panelboard, Lighting & Appliance	PNB	09	EE	Floor 09 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	NA1B32-4AB100	ATY-80930
FL0061ZZ-000000602	Panelboard, Lighting & Appliance	PNB	09	EE	Floor 09 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	NA1B32-4AB101	ATY-80931
FL0061ZZ-000000603	Panelboard, Lighting & Appliance	PNB	09	EE	Floor 09 Electrical Equipment Room North East Side of the Room	SQUARE D	NC38S	11486

FL0061ZZ-000000604	Panelboard, Lighting & Appliance	PNB	09	EE	Floor 09 Electrical Equipment Room North East Side of the Room 900	SQUARE D	NC38S	11485
FL0061ZZ-000000605	Panelboard, Lighting & Appliance	PNB	09	EE	Floor 09 Electrical Equipment Room South East Side of the Room	SQUARE D	NC445	80045-104-01
FL0061ZZ-000000606	Panelboard, Lighting & Appliance	PNB	09	EE	Floor 09 Electrical Equipment Room North East Side of the Room	SQUARE D	MHC 265	R-3277
FL0061ZZ-000000607	Panelboard, Lighting & Appliance	PNB	09	EE	Floor 09 Electrical Equipment Room North East Side of the Room	SQUARE D	QOD-16L-100DSCV	GO4
FL0061ZZ-000000608	Panelboard, Lighting & Appliance	PNB	09	EE	Floor 09 Electrical Equipment Room North Side of the Room	MURRAY	LP0120DC	Not available
FL0061ZZ-000000609	Panelboard, Lighting & Appliance	PNB	10	EE	Floor 10 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	NAIB32 4AB100	ATY-80930
FL0061ZZ-000000610	Panelboard, Lighting & Appliance	PNB	10	EE	Floor 10 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	NAIB32 4AB100	ATY-80931
FL0061ZZ-000000611	Panelboard, Lighting & Appliance	PNB	10	EE	Floor 10 Electrical Equipment Room East Side of the Room	SQUARE D	NQOD442L225CU	E2
FL0061ZZ-000000612	Panelboard, Lighting & Appliance	PNB	10	EE	Floor 10 Electrical Equipment Room South East Side of the Room	V-L	FD 889199	79-77609
FL0061ZZ-000000613	Panelboard, Lighting & Appliance	PNB	10	EE	Floor 10 Electrical Equipment Room South Side of the Room	WESTINGHOUSE	NH1830-4L100	ATY-80930
FL0061ZZ-000000614	Panelboard, Lighting & Appliance	PNB	10	EE	Floor 10 Electrical Equipment Room 2nd electrical room by the south side of the phone room	SQUARE D	NH-35TS	not available
FL0061ZZ-000000615	Panelboard, Lighting & Appliance	PNB	10	EE	Floor 10 Electrical Equipment Room 4th electrical room by the south side of the phone room	SQUARE D	B-7114	not available
FL0061ZZ-000000616	Panelboard, Lighting & Appliance	PNB	11	EE	Floor 11 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	NA1B32-4AB99	AG85679
FL0061ZZ-000000617	Panelboard, Lighting & Appliance	PNB	11	EE	Floor 11 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	NA1B32-4AB100	AG85680
FL0061ZZ-000000618	Panelboard, Lighting & Appliance	PNB	11	EE	Floor 11 Electrical Equipment Room South Side of the Room	WESTINGHOUSE	NH1830-4L100	ATY-80930
FL0061ZZ-000000619	Panelboard, Lighting & Appliance	PNB	12	EE	Floor 12 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	NA1B32-4A8100	ATY-80930
FL0061ZZ-000000620	Panelboard, Lighting & Appliance	PNB	12	EE	Floor 12 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	NA1B32-4A8100	ATY-80930
FL0061ZZ-000000621	Panelboard, Lighting & Appliance	PNB	12	EE	Floor 12 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	NA1B32-4A8101	ATY-80931
FL0061ZZ-000000622	Panelboard, Lighting & Appliance	PNB	12	EE	Floor 12 Electrical Equipment Room East Side of the Room	CHALLENGER	3SB15	Not available
FL0061ZZ-000000623	Panelboard, Lighting & Appliance	PNB	13	EE	Floor 13 Electrical Equipment Room North East Side of the Room	SQUARE D	QOC430M	40262-622-01-G1

FL0061ZZ-000000624	Panelboard, Lighting & Appliance	PNB	13	EE	Floor 13 Electrical Equipment Room North East Side of the Room	WESTINGHOUSE	30-E-6186	147P45H01
FL0061ZZ-000000625	Panelboard, Lighting & Appliance	PNB	13	EE	Floor 13 Electrical Equipment Room South East Side of the Room	WESTINGHOUSE	30-E-6186	147P454H01
FL0061ZZ-000000626	Panelboard, Lighting & Appliance	PNB	13	EE	Floor 13 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	AG85777	1737858A
FL0061ZZ-000000627	Panelboard, Lighting & Appliance	PNB	14	EE	Floor 14 Electrical Equipment Room South Side of the Room	WESTINGHOUSE	AG-85688	1737858A
FL0061ZZ-000000628	Panelboard, Lighting & Appliance	PNB	14	EE	Floor 14 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	AG85660	1737858A
FL0061ZZ-000000629	Panelboard, Lighting & Appliance	PNB	14	EE	Floor 14 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	AG 85770	1737858A
FL0061ZZ-000000630	Panelboard, Lighting & Appliance	PNB	14	1400	Floor 14 Office Room 1400	GENERAL ELEC	TM42-45C	not available
FL0061ZZ-000000631	Panelboard, Lighting & Appliance	PNB	15	EE	Floor 15 Electrical Equipment Room South Side of the Room	WESTINGHOUSE	AC-85687	1737858A
FL0061ZZ-000000632	Panelboard, Lighting & Appliance	PNB	15	EE	Floor 15 Electrical Equipment Room North Side of the Room	SQUARE D	QOC16US	Not available
FL0061ZZ-000000633	Panelboard, Lighting & Appliance	PNB	15	EE	Floor 15 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	AG 85661	1737858A
FL0061ZZ-000000634	Panelboard, Lighting & Appliance	PNB	15	EE	Floor 15 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	AG 85769	1737858A
FL0061ZZ-000000635	Panelboard, Lighting & Appliance	PNB	16	EE	Floor 16 Electrical Equipment Room North East Side of the Room	SQUARE D	QOC342MQS	40273-830-02
FL0061ZZ-000000636	Panelboard, Lighting & Appliance	PNB	16	EE	Floor 16 Electrical Equipment Room South Side of the Room	SQUARE D	0480768-501	AB0030-284-01
FL0061ZZ-000000637	Panelboard, Lighting & Appliance	PNB	16	EE	Floor 16 Electrical Equipment Room South Side of the Room	WESTINGHOUSE	A-38566	NH 1330-4-100
FL0061ZZ-000000638	Panelboard, Lighting & Appliance	PNB	16	EE	Floor 16 Electrical Equipment Room North Side of the Room	GENERAL ELEC	TL 270SCU	MNP 601257B
FL0061ZZ-000000639	Panelboard, Lighting & Appliance	PNB	16	EE	Floor 16 Electrical Equipment Room North Side of the Room	WESTINGHOUSE	AG 857	1537858AN
FL0061ZZ-000000640	Panelboard, Lighting & Appliance	PNB	16	EE	Floor 16 Electrical Equipment Room South Side of the Room	FPE	11365 NR	Y81207Y-6
FL0061ZZ-000000641	Panelboard, Lighting & Appliance	PNB	16	EE	Floor 16 Electrical Equipment Room South Side of the Room	WESTINGHOUSE	Not available	147P454H01
FL0061ZZ-000000642	Panelboard, Lighting & Appliance	PNB	17	MC	Floor 17 Mechanical Equipment Room IN the MIDDLE OF the Room	WESTINGHOUSE	ATHD80930	3-CGX
FL0061ZZ-000000643	Panelboard, Lighting & Appliance	PNB	17	EE	Floor 17 Electrical Equipment Room Besides power control PANEL	WESTINGHOUSE	NO INFORMATIon	Not available
FL0061ZZ-000000733	Switchboard, Electrical	SWB	02	FC	Floor 02 Food Service, Kitchen on the back Side of the Room	SQUARE D	NQ0D442L400CU	
FL0061ZZ-000000734	Switchboard, Electrical	SWB	01	CH	Floor 01 CHILLER Mechanical Room CHILLER Room #2	SIEMENS	RC-III	6SO 18-50987-A01

FL0061ZZ-000000735	Switchboard, Electrical	SWB	01	CH	Floor 01 CHILLER Mechanical Room CHILLER Room #2	SIEMENS	RC-III	6SO 18-50987-A01
FL0061ZZ-000000736	Switchboard, Electrical	SWB	01	CH	Floor 01 CHILLER Mechanical Room By CHILLER #2 METERING DEVICE	ITE	700X563G1	Not available
FL0061ZZ-000000737	Tank, Fuel	TNK-01	01	PL	Floor 01 Parking Lot East Side of the Parking Lot	ConVAULT	Not available	Not available
FL0061ZZ-TNK-00001	Tank, Size=500, Contents: Diesel, Used for:	TNK-01						
FL0061ZZ-000000738	Tank, Water	TNK-04	17	MC	Floor 17 Mechanical Equipment Room South West Side of the FLOOR	WELL MATE	WM-35WB	1071120211
FL0061ZZ-000000739	Tank, Water	TNK-04	17	MC	Floor 17 Mechanical Equipment Room South West Side of the FLOOR	WELL MATE	WM-35WB	1071120204
FL0061ZZ-000000740	Tank, Water	TNK-04	17	MC	Floor 17 Mechanical Equipment Room South West Side of the FLOOR	WELL MATE	WM-35WB	1071120203
FL0061ZZ-000000741	Tank, Water	TNK-04	17	MC	Floor 17 Mechanical Equipment Room South West Side of the FLOOR	WELL MATE	WM-35WB	1071120212
FL0061ZZ-000000762	VAV (Variable Air Volume Boxes)	VAV	01		Floor 01 General Building On top of room 102	Not available	Not available	Not available
FL0061ZZ-000000763	VAV (Variable Air Volume Boxes)	VAV	01		Floor 01 General Building On top of Room 119	Not available	Not available	Not available
FL0061ZZ-000000764	VAV (Variable Air Volume Boxes)	VAV	01		Floor 01 General Building On the main lobby	Not available	Not available	Not available
FL0061ZZ-000000765	VAV (Variable Air Volume Boxes)	VAV	01		Floor 01 General Building On top of room 100	Not available	Not available	Not available
FL0061ZZ-000000766	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000767	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000768	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000769	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000770	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000771	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000772	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available

FL0061ZZ-000000773	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000774	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000775	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000776	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000777	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000778	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000779	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000780	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000781	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000782	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000783	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000784	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000785	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000786	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000787	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000788	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000789	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available

FL0061ZZ-000000790	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000791	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000792	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000793	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000794	VAV (Variable Air Volume Boxes)	VAV	02	OF	Floor 02 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000795	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000796	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000797	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000798	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000799	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000800	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000801	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000802	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000803	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000804	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000805	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000806	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available

FL0061ZZ-000000807	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000808	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000809	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000810	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000811	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000812	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000813	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000814	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000815	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000816	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000817	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000818	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000819	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000820	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000821	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000822	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000823	VAV (Variable Air Volume Boxes)	VAV	03	OF	Floor 03 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available

FL0061ZZ-000000824	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000825	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000826	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000827	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000828	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000829	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000830	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000831	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000832	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000833	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000834	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000835	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000836	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000837	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000838	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000839	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000840	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available

FL0061ZZ-000000841	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000842	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000843	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000844	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000845	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000846	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000847	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000848	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000849	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000850	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000851	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000852	VAV (Variable Air Volume Boxes)	VAV	04	OF	Floor 04 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000853	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000854	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000855	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000856	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000857	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available

FL0061ZZ-000000858	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000859	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000860	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000861	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000862	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000863	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000864	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000865	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000866	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000867	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000868	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000869	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000870	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000871	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000872	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000873	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000874	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available

FL0061ZZ-000000875	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000876	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000877	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000878	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000879	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000880	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000881	VAV (Variable Air Volume Boxes)	VAV	05	OF	Floor 05 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000882	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000883	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000884	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000885	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000886	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000887	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000888	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000889	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000890	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000891	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available

FL0061ZZ-000000892	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000893	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000894	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000895	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000896	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000897	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000898	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000899	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000900	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000901	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000902	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000903	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000904	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000905	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000906	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000907	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000908	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available

FL0061ZZ-000000909	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000910	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000911	VAV (Variable Air Volume Boxes)	VAV	06	OF	Floor 06 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000912	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000913	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000914	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000915	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000916	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000917	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000918	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000919	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000920	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000921	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000922	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000923	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000924	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000925	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available

FL0061ZZ-000000926	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000927	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000928	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000929	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000930	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000931	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000932	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000933	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000934	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000935	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000936	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000937	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000938	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000939	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000940	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000941	VAV (Variable Air Volume Boxes)	VAV	07	OF	Floor 07 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000000942	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available

FL0061ZZ-000000943	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000944	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000945	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000946	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000947	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000948	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000949	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000950	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000951	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000952	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000953	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000954	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000955	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000956	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000957	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000958	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000959	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available

FL0061ZZ-000000960	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000961	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000962	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000963	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000964	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000965	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000966	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000967	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000968	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000969	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000970	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000971	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000972	VAV (Variable Air Volume Boxes)	VAV	08	OF	Floor 08 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000973	VAV (Variable Air Volume Boxes)	VAV	08	HW	Floor 08 Throughout Entire Building by hallway	Not available	Not available	Not available
FL0061ZZ-000000974	VAV (Variable Air Volume Boxes)	VAV	08	HW	Floor 08 Throughout Entire Building by hallway	Not available	Not available	Not available
FL0061ZZ-000000975	VAV (Variable Air Volume Boxes)	VAV	08	HW	Floor 08 Throughout Entire Building by hallway	Not available	Not available	Not available
FL0061ZZ-000000976	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available

FL0061ZZ-000000977	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000978	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000979	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000980	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000000981	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000982	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000983	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000984	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000985	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000986	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000987	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000988	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000989	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000990	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000991	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000000992	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000993	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available

FL0061ZZ-000000994	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000995	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000996	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000997	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000998	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000000999	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000001000	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000001001	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000001002	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000001003	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000001004	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000001005	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000001006	VAV (Variable Air Volume Boxes)	VAV	09	OF	Floor 09 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000001007	VAV (Variable Air Volume Boxes)	VAV	09	HW	Floor 09 Throughout Entire Building by hallway	Not available	Not available	Not available
FL0061ZZ-000001008	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000001009	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000001010	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available

FL0061ZZ-000001011	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000001012	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000001013	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000001014	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by north side of the building	Not available	Not available	Not available
FL0061ZZ-000001015	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000001016	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000001017	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000001018	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000001019	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000001020	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000001021	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000001022	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000001023	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000001024	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000001025	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000001026	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000001027	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available

FL0061ZZ-000001028	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000001029	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by west side of the building	Not available	Not available	Not available
FL0061ZZ-000001030	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000001031	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000001032	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000001033	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000001034	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000001035	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000001036	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000001037	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000001038	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000001039	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000001040	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by east side of the building	Not available	Not available	Not available
FL0061ZZ-000001041	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000001042	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000001043	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available
FL0061ZZ-000001044	VAV (Variable Air Volume Boxes)	VAV	10	OF	Floor 10 Throughout Entire Building offices by south side of the building	Not available	Not available	Not available

FL0061ZZ-000001045	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001046	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001047	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001048	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001049	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001050	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001051	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001052	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001053	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001054	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001055	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001056	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001057	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001058	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001059	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001060	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001061	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available

FL0061ZZ-000001062	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001063	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001064	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001065	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001066	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001067	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001068	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001069	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001070	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001071	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001072	VAV (Variable Air Volume Boxes)	VAV	11	HW	Floor 11 Throughout Entire Building By Hallway	Not available	Not available	Not available
FL0061ZZ-000001073	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001074	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001075	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001076	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001077	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001078	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available

FL0061ZZ-000001079	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001080	VAV (Variable Air Volume Boxes)	VAV	11	OF	Floor 11 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001081	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001082	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001083	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001084	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001085	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001086	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001087	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001088	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001089	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001090	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001091	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001092	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001093	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001094	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001095	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available

FL0061ZZ-000001096	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001097	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001098	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001099	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001100	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001101	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001102	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001103	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001104	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001105	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001106	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001107	VAV (Variable Air Volume Boxes)	VAV	12	HW	Floor 12 Throughout Entire Building By Hallway	Not available	Not available	Not available
FL0061ZZ-000001108	VAV (Variable Air Volume Boxes)	VAV	12	HW	Floor 12 Throughout Entire Building By Hallway	Not available	Not available	Not available
FL0061ZZ-000001109	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001110	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001111	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001112	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available

FL0061ZZ-000001113	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001114	VAV (Variable Air Volume Boxes)	VAV	12	OF	Floor 12 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001115	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001116	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001117	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001118	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001119	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001120	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001121	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001122	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001123	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001124	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001125	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001126	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001127	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001128	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001129	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available

FL0061ZZ-000001130	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001131	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001132	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001133	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001134	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001135	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001136	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001137	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001138	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001139	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001140	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001141	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001142	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001143	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001144	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001145	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001146	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available

FL0061ZZ-000001147	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001148	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001149	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001150	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001151	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001152	VAV (Variable Air Volume Boxes)	VAV	13	OF	Floor 13 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001153	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001154	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001155	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001156	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001157	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001158	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001159	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001160	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001161	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001162	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001163	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available

FL0061ZZ-000001164	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001165	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001166	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001167	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001168	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001169	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001170	VAV (Variable Air Volume Boxes)	VAV	14	HW	Floor 14 Throughout Entire Building By Hallway	Not available	Not available	Not available
FL0061ZZ-000001171	VAV (Variable Air Volume Boxes)	VAV	14	HW	Floor 14 Throughout Entire Building By Hallway	Not available	Not available	Not available
FL0061ZZ-000001172	VAV (Variable Air Volume Boxes)	VAV	14	HW	Floor 14 Throughout Entire Building By Hallway	Not available	Not available	Not available
FL0061ZZ-000001173	VAV (Variable Air Volume Boxes)	VAV	14	HW	Floor 14 Throughout Entire Building By Hallway	Not available	Not available	Not available
FL0061ZZ-000001174	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001175	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001176	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001177	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001178	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001179	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001180	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001181	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available

FL0061ZZ-000001182	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001183	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001184	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001185	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001186	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001187	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001188	VAV (Variable Air Volume Boxes)	VAV	14	OF	Floor 14 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001189	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Office By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001190	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Office By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001191	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Office By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001192	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Office By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001193	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Office By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001194	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Office By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001195	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Office By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001196	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Office By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001197	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Office By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001198	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available

FL0061ZZ-000001199	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001200	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001201	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001202	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001203	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001204	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001205	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001206	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001207	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001208	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001209	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001210	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001211	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001212	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001213	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001214	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001215	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available

FL0061ZZ-000001216	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001217	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001218	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001219	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001220	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001221	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001222	VAV (Variable Air Volume Boxes)	VAV	15	OF	Floor 15 Throughout Entire Building Offices By South Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001223	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Office By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001224	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Office By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001225	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Office By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001226	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Office By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001227	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Office By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001228	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Office By North Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001229	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001230	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001231	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001232	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available

FL0061ZZ-000001233	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001234	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001235	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001236	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001237	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001238	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001239	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001240	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001241	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001242	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001243	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001244	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001245	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001246	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001247	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By South West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001248	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By South West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001249	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By South West Side of the BUILDING	Not available	Not available	Not available

FL0061ZZ-000001250	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By South West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001251	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By South West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001252	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By South West Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001253	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By South East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001254	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By South East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001255	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By South East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001256	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By South East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001257	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By South East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001258	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By South East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001259	VAV (Variable Air Volume Boxes)	VAV	16	OF	Floor 16 Throughout Entire Building Offices By South East Side of the BUILDING	Not available	Not available	Not available
FL0061ZZ-000001260	Water Heater, Electric	WHT-01	01	CH	Floor 01 CHILLER Mechanical Room Fire Alarm Pump Room	LOCHINVAR	ETX120PP	YE 3217191
FL0061ZZ-000001261	Water Treatment (Chemical)	WTM	01	CH	Floor 01 CHILLER Mechanical Room Close to the Entrance Door	Milton Roy	DC 4000	Not available

Date Run:

7/15/2014 3:27:35 PM

Brickell Plaza Federal Building, FL0079ZZ O&M Only
909 SE 1st AVE
Miami, FL 33130
145440 rentable square feet (rsf)

Equipment List by Building and Equipment ID - Detail

Total Record Counts: 360

Building: FL0079ZZ

Equipment ID	Equipment Description	Equipment Type	Floor	Room	Location	Manufacturer	Model No.	Serial No.
FL0079ZZ-000000036	Condenser, Air-Cooled	ACC			Floor 01 OUTSIDE, BACK OF BLDG.	GOODMAN	GSC130603BB	1108570369
FL0079ZZ-000000037	Condenser, Air-Cooled	ACC		NT	Roof Roof / Roof Installed Item Center North Roof	TRENTON	TCM012-T4A-A11V-0087	112302264
FL0079ZZ-000000038	Condenser, Air-Cooled	ACC		NT	Roof Roof / Roof Installed Item Center North Roof	RUSSELL	CAC-11-G	W09J48719601001
FL0079ZZ-000000039	Condenser, Air-Cooled	ACC		ST	Roof Roof / Roof Installed Item South Roof	LIEBERT	EFH067A-YL3	C1924N185273
FL0079ZZ-000000040	Condenser, Air-Cooled	ACC		ST	Roof Roof / Roof Installed Item South Roof	LIEBERT		D193(obliterated)
FL0079ZZ-000000041	Condenser, Air-Cooled	ACC		ST	Roof Roof / Roof Installed Item Center SOUTH Roof	RHEEM	13AJM36A01	8032W341011112
FL0079ZZ-000000042	Condenser, Air-Cooled	ACC		ST	Roof Roof / Roof Installed Item South Roof	LIEBERT	PFH037A-PL7	0923N184878
FL0079ZZ-000000043	Condenser, Air-Cooled	ACC		NT	Roof Roof / Roof Installed Item NORTH Roof	YORK	YCJD30S41S1A	W1D1945053
FL0079ZZ-000000012	Air Conditioner Package	ACU	03	MC	Floor 03 Mechanical Equipment Room North Center	GENERAL ELEC	BTC030B100CO	218830UI4
FL0079ZZ-000000013	Air Conditioner, Window	ACW		EV	Roof Elevator / Mechanical Penthouse Canter of building	Friedrich	WS13B30B-F	LHBX00366
FL0079ZZ-000000014	Air Conditioner, Window	ACW		EV	Roof Elevator / Mechanical Penthouse Center of building	Friedrich	WS13B30B-E	LGKS01379
FL0079ZZ-000000015	Air Conditioner, Window	ACW		EE	G2 Electrical Power Distribution Center (Primary Switchgear)	FRIEDRICH	KM18L30-D	LJD200117
FL0079ZZ-000000016	Air Handling Unit, 3 ton thru 24 ton	AHU-01	03	MC	Floor 03 Mechanical Equipment Room Center By elevator lobby	ACRONAIRE	BMCG020A	0000564115-R10-0461
FL0079ZZ-000000017	Air Handling Unit, 3 ton thru 24 ton	AHU-01	08	874	Floor 08 Office NORTH side of room 874	LIEBERT	FH114A-A10	134544B
FL0079ZZ-000000018	Air Handling Unit, 3 ton thru 24 ton	AHU-01	08	874	Floor 08 Office WEST side of room 874	LIEBERT	CF013A-A00 FH125A-A10	134544C
FL0079ZZ-000000019	Air Handling Unit, 3 ton thru 24 ton	AHU-01	07	736	Floor 07 Office Suite 736 ABOVE CEILING	LIEBERT	MMD36E7P0ED0	0923N184889
FL0079ZZ-000000020	Air Handling Unit, 3 ton thru 24 ton	AHU-01	07	710	Floor 07 Office 710 Computer room	LIEBERT	CF060E-C00	172671-002

FL0079ZZ-000000021	Air Handling Unit, 3 ton thru 24 ton	AHU-01	07	710	Floor 07 Office 710 Computer room	LIEBERT	FH199A-A00	not available
FL0079ZZ-000000022	Air Handling Unit, 3 ton thru 24 ton	AHU-01		NT	Roof Roof / Roof Installed Item North side	TRENTON	TCS010-S4A-2C	112303559
FL0079ZZ-000000023	Air Handling Unit, 3 ton thru 24 ton	AHU-01	09	MC	Floor 09 MECHANICAL EQUIPMENT ROOM	TRANE	SCMZ404	L2M664648
FL0079ZZ-000000024	Air Handling Unit, 25 ton thru 50 ton	AHU-02	09	MC	Floor 09 Mechanical Equipment Room SouthCenter	TRANE	SCMZ404	L2M664647
FL0079ZZ-000000025	Air Handling Unit, 25 ton thru 50 ton	AHU-02	08		Floor 08 Mechanical Equipment Room SouthCenter in COAST GUARD AREA	TRANE	SCMZ304B	L3B671239
FL0079ZZ-000000026	Air Handling Unit, 25 ton thru 50 ton	AHU-02	07	MC	Floor 07 Mechanical Equipment Room North Center	TRANE	SCMZ304	L2M664643
FL0079ZZ-000000027	Air Handling Unit, 25 ton thru 50 ton	AHU-02	07	MC	Floor 07 Mechanical Equipment Room SouthCenter	TRANE	SCMZ304	L2M664646
FL0079ZZ-000000028	Air Handling Unit, 25 ton thru 50 ton	AHU-02	06	MC	Floor 06 MECHANICAL EQUIPMENT ROOM	TRANE	SCMZ304	L2M664642
FL0079ZZ-000000029	Air Handling Unit, 25 ton thru 50 ton	AHU-02	06	MC	Floor 06 Mechanical Equipment Room SouthCenter	TRANE	SCMZ304	L2M664644
FL0079ZZ-000000030	Air Handling Unit, 25 ton thru 50 ton	AHU-02	05	MC	Floor 05 MECHANICAL EQUIPMENT ROOM	TRANE	SCMZ304	L2M664641
FL0079ZZ-000000031	Air Handling Unit, 25 ton thru 50 ton	AHU-02	05	MC	Floor 05 MECHANICAL EQUIPMENT ROOM	TRANE	SCMZ304	L2M664645
FL0079ZZ-000000032	Air Handling Unit, 25 ton thru 50 ton	AHU-02	04	MC	Floor 04 MECHANICAL EQUIPMENT ROOM	TRANE	SCMZ404	L2L664639
FL0079ZZ-000000033	Air Handling Unit, 25 ton thru 50 ton	AHU-02	04	MC	Floor 04 Mechanical Equipment Room SouthCenter	TRANE	SCMZ404	L2L664640
FL0079ZZ-000000128	Fire Detection and Alarm System	ALM	01	EE	Floor 01 Electrical Equipment Room NORTH SIDE OF THE ROOM	NOTIFIER	AM2020	not available
FL0079ZZ-000000170	Fire Detection and Alarm System	ALM	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) North side of the room	Silent knight	5230	not available
FL0079ZZ-000000300	Switch, Automatic Transfer	ATS		EE	G2 Electrical Power Distribution Center (Primary Switchgear)	KOHLER	k-166341-0150	k-23937
FL0079ZZ-000000301	Switch, Automatic Transfer	ATS		EE	G2 Electrical Power Distribution Center (Primary Switchgear)	KOHLER	k-166341-0225	23782
FL0079ZZ-000000302	Switch, Automatic Transfer	ATS		EE	G2 Electrical Power Distribution Center (Primary Switchgear)	GENERAL ELEC	TJ4005	
FL0079ZZ-000000303	Switch, Automatic Transfer	ATS		EE	G2 Electrical Power Distribution Center (Primary Switchgear)	GENERAL ELEC	TH4324	P-0118
FL0079ZZ-000000304	Switch, Automatic Transfer	ATS		EE	G2 Electrical Power Distribution Center (Primary Switchgear)	GENERAL ELEC	69752	not available
FL0079ZZ-000000305	Switch, Automatic Transfer	ATS	01	EE	Floor 01 Electrical Equipment Room NORTH SIDE OF THE ROOM	KOHLER	K166341-0400	K23948
FL0079ZZ-000000306	Switch, Automatic Transfer	ATS	03	EE	Floor 03 Electrical Equipment Room NORTH SIDE OF THE ROOM	ONAN	OTCU225-G/14G	A870866289
FL0079ZZ-000000034	Backflow Prevention Device	BFP		ST	Floor 01 OUTSIDE, SOUTH SIDE OF BLDG	WATTS	909RP	208441
FL0079ZZ-000000035	Boiler, Steam, Oil/Gas/Comb	BLR-ST2		BL	Roof Boiler Mechanical Room Center Roof	RHEEM	RB-1040CS	1272X41

FL0079ZZ-000000001	Air Compressor	CMP	09	MC	Floor 09 Mechanical Equipment Room North Center	TRANE	2FC88	2J012206
FL0079ZZ-000000002	Air Compressor	CMP	09	MC	Floor 09 Mechanical Equipment Room SouthCenter	TRANE	G2F5C88	2CO8A2238
FL0079ZZ-000000003	Air Compressor	CMP	08	MC	Floor 08 Mechanical Equipment Room SouthCenter	TRANE	2F5D68	A2L06A1260
FL0079ZZ-000000004	Air Compressor	CMP	07	MC	Floor 07 Mechanical Equipment Room North Center	TRANE	2F5D68	2M270002
FL0079ZZ-000000005	Air Compressor	CMP	07	MC	Floor 07 Mechanical Equipment Room SouthCenter	TRANE	2F5D68	A2LO6A1264
FL0079ZZ-000000006	Air Compressor	CMP	06	MC	Floor 06 Mechanical Equipment Room North Center	TRANE	2F5D68	NIK3053365
FL0079ZZ-000000007	Air Compressor	CMP	06	MC	Floor 06 Mechanical Equipment Room SouthCenter	TRANE	2F5D68	A68A06A2019
FL0079ZZ-000000008	Air Compressor	CMP	05	MC	Floor 05 Mechanical Equipment Room North Center	TRANE	2F5D68	A2L06A1270
FL0079ZZ-000000009	Air Compressor	CMP	05	MC	Floor 05 Mechanical Equipment Room SouthCenter	TRANE	2F5D68	AIL06A2058
FL0079ZZ-000000010	Air Compressor	CMP	04	MC	Floor 04 Mechanical Equipment Room North Center	TRANE	2F5D88	N2C40U6321
FL0079ZZ-000000011	Air Compressor	CMP	04	MC	Floor 04 Mechanical Equipment Room SouthCenter	TRANE	2F5C88	M65957
FL0079ZZ-000000044	Cooling Tower	CTR			Roof Roof / Roof Installed Item	MARLEY		NC8305F1SSNC-228195-A1
FL0079ZZ-000000307	Switch, Disconnect	DCT		SH	Basement, 1st Level Shop / Factory SW CORNER OF THE ROOM	GENERAL ELEC	15562	not available
FL0079ZZ-000000308	Switch, Disconnect	DCT		SH	Basement, 1st Level Shop / Factory SW CORNER OF THE ROOM	GENERAL ELEC	15562	not available
FL0079ZZ-000000309	Switch, Disconnect	DCT	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) By west side of the room	SQUARE D	40274-301-01	not available
FL0079ZZ-000000310	Switch, Disconnect	DCT	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) EAST SIDE OF THE ROOM	Crouse hints	hh362	not available
FL0079ZZ-000000311	Switch, Disconnect	DCT	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) EAST SIDE OF THE ROOM	GENERAL ELEC	not available	not available
FL0079ZZ-000000312	Switch, Disconnect	DCT	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) EAST SIDE OF THE ROOM	GENERAL ELEC	266227-a	not available
FL0079ZZ-000000313	Switch, Disconnect	DCT	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) By west side of the room	GENERAL ELEC	185682	not available

FL0079ZZ-000000314	Switch, Disconnect	DCT	01	EE	Floor 01 Electrical Equipment Room WEST SIDE OF THE ROOM	ARMOR CLAD	363r	not available
FL0079ZZ-000000315	Switch, Disconnect	DCT	01	EE	Floor 01 Electrical Equipment Room WEST SIDE OF THE ROOM	ARMOR CLAD	h6h	not available
FL0079ZZ-000000316	Switch, Disconnect	DCT	01	EE	Floor 01 Electrical Equipment Room WEST SIDE OF THE ROOM	GENERAL ELEC	np266227-b	not available
FL0079ZZ-000000317	Switch, Disconnect	DCT	02	EE	Floor 02 Electrical Power Distribution Center (Primary Switchgear) Garage 2nd level	GENERAL ELEC	NOt available	266209C
FL0079ZZ-000000318	Switch, Disconnect	DCT	02	EE	Floor 02 Electrical Power Distribution Center (Primary Switchgear) Garage 2nd level	GENERAL ELEC	not available	266209C
FL0079ZZ-000000319	Switch, Disconnect	DCT	03	EE	Floor 03 Electrical Equipment Room NORTH SIDE OF THE ROOM	WESTINGHOUSE	SKDN400	not available
FL0079ZZ-000000320	Switch, Disconnect	DCT	04	EE	Floor 04 Electrical Equipment Room EAST SIDE OF THE ROOM	Armor chad	ac464r	not available
FL0079ZZ-000000321	Switch, Disconnect	DCT	04	EE	Floor 04 Electrical Equipment Room EAST SIDE OF THE ROOM	Armor chad	ac364r	not available
FL0079ZZ-000000322	Switch, Disconnect	DCT	04	MC	Floor 04 Mechanical Equipment Room NORTH SIDE OF THE ROOM	GENERAL ELEC	ccb	ak116167
FL0079ZZ-000000323	Switch, Disconnect	DCT	05	533	Floor 05 Control Center By room 533	ESU	266209-e	not available
FL0079ZZ-000000324	Switch, Disconnect	DCT	05	EE	Floor 05 Electrical Equipment Room WEST SIDE OF THE ROOM	GENERAL ELEC	75C14139H-P103	not available
FL0079ZZ-000000325	Switch, Disconnect	DCT	05	MC	Floor 05 Mechanical Equipment Room NORTH SIDE OF THE ROOM	GENERAL ELEC	266209-F	not available
FL0079ZZ-000000326	Switch, Disconnect	DCT	05	MC	Floor 05 Mechanical Equipment Room NORTH SIDE OF THE ROOM	SQUARE D	40275-811-02	not available
FL0079ZZ-000000327	Switch, Disconnect	DCT	06	MC	Floor 06 Mechanical Equipment Room	GENERAL ELEC	not available	NP1578000E
FL0079ZZ-000000328	Switch, Disconnect	DCT	06	MC	Floor 06 Mechanical Equipment Room	SQUARE D	not available	C-40274-289-06
FL0079ZZ-000000329	Switch, Disconnect	DCT	07	MC	Floor 07 Mechanical Equipment Room NORTH SIDE OF THE ROOM	SQUARE D	40274-259-06	not available
FL0079ZZ-000000330	Switch, Disconnect	DCT	07	MC	Floor 07 Mechanical Equipment Room NORTH SIDE OF THE ROOM	SQUARE D	40275-930-01	not available
FL0079ZZ-000000331	Switch, Disconnect	DCT	08	EE	Floor 08 Electrical Equipment Room NORTH SIDE OF THE ROOM	GENERAL ELEC	AC 363R	171379
FL0079ZZ-000000332	Switch, Disconnect	DCT	08	EE	Floor 08 Electrical Equipment Room SOUTH SIDE OF THE ROOM	GENERAL ELEC	AC464R	171379
FL0079ZZ-000000333	Switch, Disconnect	DCT	08	MC	Floor 08 Mechanical Equipment Room SOUTH SIDE OF THE ROOM	SQUARE D	not available	not available
FL0079ZZ-000000334	Transformer, Dry	DTT		SH	Basement, 1st Level Shop / Factory SW CORNER OF THE ROOM	GENERAL ELEC	9T23B3873	475A541WAG001_R0

FL0079ZZ-000000335	Transformer, Dry	DTT	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) North side of the room	GENERAL ELEC	9T21A4009DA	BJ
FL0079ZZ-000000336	Transformer, Dry	DTT	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) North side of the room	GENERAL ELEC	9T23B3872	475AS41XAG002_R0
FL0079ZZ-000000337	Transformer, Dry	DTT	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) North side of the room	GENERAL ELEC	9T23B3873	475A541WAG002_R0
FL0079ZZ-000000338	Transformer, Dry	DTT	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) EAST SIDE OF THE ROOM	GS	T2H_45_SER_C	not available
FL0079ZZ-000000339	Transformer, Dry	DTT	09	EE	FLOOR 09 Electrical Equipment Room EAST SIDE OF THE ROOM	GENERAL ELEC	9T23A3874	A
FL0079ZZ-000000340	Transformer, Dry	DTT	01		Floor 01 FIRE ALARM Room NORTH SIDE OF THE ROOM	ACME	T1A-53312-3S	not available
FL0079ZZ-000000341	Transformer, Dry	DTT	01		Floor 01 FIRE ALARM Room NORTH SIDE OF THE ROOM	ACME	T-1-53311-1	not available
FL0079ZZ-000000342	Transformer, Dry	DTT	09	EE	FLOOR 09 Electrical Equipment Room	WESTINGHOUSE	V48M28E12B	J88AXX009
FL0079ZZ-000000343	Transformer, Dry	DTT	03	EE	Floor 03 Electrical Equipment Room NORTH SIDE OF THE ROOM	GENERAL ELEC	9T23B3875G03	475A572JAG001_R0
FL0079ZZ-000000344	Transformer, Dry	DTT	03	EE	Floor 03 Electrical Equipment Room NORTH SIDE OF THE ROOM	GENERAL ELEC	9T23B3872	475A541XAG002_R0
FL0079ZZ-000000345	Transformer, Dry	DTT	04	EE	Floor 04 Electrical Equipment Room WEST SIDE OF THE ROOM	SQUARE D	45T3H	33749-17212-058
FL0079ZZ-000000346	Transformer, Dry	DTT	04	EE	Floor 04 Electrical Equipment Room WEST SIDE OF THE ROOM	GENERAL ELEC	9T23_B-3875	LH
FL0079ZZ-000000347	Transformer, Dry	DTT	05	534	Floor 05 Control Center By room 534	ACME	T-IA-53314-35	not available
FL0079ZZ-000000348	Transformer, Dry	DTT	05	532	Floor 05 Control Center By room 532	GS	S5H25	not available
FL0079ZZ-000000349	Transformer, Dry	DTT	05	EE	Floor 05 Electrical Equipment Room WEST SIDE OF THE ROOM	SQUARE D	45T3H	33749-17212-058
FL0079ZZ-000000350	Transformer, Dry	DTT	06	EE	Floor 06 Electrical Equipment Room SOUTH SIDE OF THE ROOM	GENERAL ELEC	9t23b3875	B LH
FL0079ZZ-000000351	Transformer, Dry	DTT	06	EE	Floor 06 Electrical Equipment Room	GENERAL ELEC	364R	not available
FL0079ZZ-000000352	Transformer, Dry	DTT	08	EE	Floor 08 Electrical Equipment Room WEST SIDE OF THE ROOM	GENERAL ELEC	9T23_B_3874	L17 LH
FL0079ZZ-000000057	Emergency Lighting	ELT	01	PK	Floor 01 Parking By south side	LITHONIA	el7632 cny	not available
FL0079ZZ-000000058	Emergency Lighting	ELT	01	SW	Floor 01 General Building By elevator lobby STAIRWAYS	LIGHTALARMS	7185	not available
FL0079ZZ-000000059	Emergency Lighting	ELT	02	SW	Floor 02 General Building By elevator lobby STAIRWAYS	LIGHTALARMS	7185	not available

FL0079ZZ-000000060	Emergency Lighting	ELT	02	SW-N	Floor 02 General Building By stairway north	Crystal Lake	2ET6S8-7	not available
FL0079ZZ-000000061	Emergency Lighting	ELT	04	SW	Floor 04 Stairwell #3 By stairway south	LITHONIA	el7632 cny	not available
FL0079ZZ-000000062	Emergency Lighting	ELT	04	SW	Floor 04 General Building By elevator lobby STAIRWAYS	LIGHTALARMS	7185	not available
FL0079ZZ-000000063	Emergency Lighting	ELT	04	SW	Floor 04 General Building By elevator lobby STAIRWAYS	LIGHTALARMS	7185	not available
FL0079ZZ-000000064	Emergency Lighting	ELT	05	SW	Floor 05 Stairwell #3 By stairway south	LITHONIA	el7632 cny	not available
FL0079ZZ-000000065	Emergency Lighting	ELT	05	SW	Floor 05 Stairwell #3 By stairway south	LITHONIA	el7632 cny	not available
FL0079ZZ-000000066	Emergency Lighting	ELT	05	SW	Floor 05 General Building By elevator lobby STAIRWAYS	LIGHTALARMS	7185	not available
FL0079ZZ-000000067	Emergency Lighting	ELT	06	SW	Floor 06 General Building By elevator lobby STAIRWAYS	LIGHTALARMS	7185	not available
FL0079ZZ-000000068	Emergency Lighting	ELT	06	SW	Floor 06 General Building By elevator lobby STAIRWAYS	LIGHTALARMS	7185	not available
FL0079ZZ-000000069	Emergency Lighting	ELT	06	SW	Floor 06 Stairwell #3 By stairway south	LITHONIA	el7632 cny	not available
FL0079ZZ-000000070	Emergency Lighting	ELT	07	SW	Floor 07 General Building By elevator lobby STAIRWAYS	LITHONIA	ELT-632LNY	not available
FL0079ZZ-000000071	Emergency Lighting	ELT	07	SW	Floor 07 Stairwell #3 By stairway south	LITHONIA	el7632 cny	not available
FL0079ZZ-000000072	Emergency Lighting	ELT	08	SW	Floor 08 General Building By elevator lobby STAIRWAYS	LIGHTALARMS	7185	not available
FL0079ZZ-000000073	Emergency Lighting	ELT	08	SW	Floor 08 Stairwell #3 By stairway south	LITHONIA	el7632 cny	not available
FL0079ZZ-000000074	Emergency Lighting	ELT	09	SW	Floor 09 Stairwell #3 By stairway south	LITHONIA	el7632 cny	not available
FL0079ZZ-000000075	Emergency Lighting	ELT	09	SW	Floor 09 General Building By elevator lobby STAIRWAYS	LIGHTALARMS	7185	not available
FL0079ZZ-000000055	Emergency Diesel Generator	EMG-01	03	MC	Floor 03 Mechanical Equipment Room By 3rd floor parking ngarage	KOHLER	500R0Z71	230212
FL0079ZZ-000000056	Emergency Diesel Generator	EMG-01	03	MC	Floor 03 Mechanical Equipment Room By 3rd floor parking ngarage	CATERPILLAR	3304 SR-4	44BH5960
FL0079ZZ-000000285	Panelboard, Power Distribution	EPB	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) By east wall of the room	GENERAL ELEC	TH4324	P-0118
FL0079ZZ-000000286	Panelboard, Power Distribution	EPB	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) By west side of the room	SQUARE D	MHC26S	
FL0079ZZ-000000287	Panelboard, Power Distribution	EPB	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) By west side of the room	NOT AVAILABLE	A16N16ALP	not available
FL0079ZZ-000000288	Panelboard, Power Distribution	EPB	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) North side of the room	GENERAL ELEC	606332	

FL0079ZZ-000000289	Panelboard, Power Distribution	EPB	01	EE	G2 Electrical Power Distribution Center (Primary Switchgear)	GENERAL ELEC	23925	23925
FL0079ZZ-000000290	Panelboard, Power Distribution	EPB		EE	G2 Electrical Power Distribution Center (Primary Switchgear)	GENERAL ELEC	606333	606333
FL0079ZZ-000000291	Panelboard, Power Distribution	EPB		EE	G2 Electrical Power Distribution Center (Primary Switchgear)	GENERAL ELEC	605296	605296
FL0079ZZ-000000045	Drinking Fountain, Packaged	EWC	04	EV	Floor 04 General Building By elevator lobby	ELKAY	EHF-8-1	870740004
FL0079ZZ-000000046	Drinking Fountain, Packaged	EWC	04	EV	Floor 04 General Building By elevator lobby	ELKAY	EHF-8-1	870740004
FL0079ZZ-000000047	Drinking Fountain, Packaged	EWC	05	EV	Floor 05 General Building By elevator lobby	ELKAY	EHF-8-1	870740004
FL0079ZZ-000000048	Drinking Fountain, Packaged	EWC	05	EV	Floor 05 General Building By elevator lobby	ELKAY	EHF-8-1	870740004
FL0079ZZ-000000049	Drinking Fountain, Packaged	EWC	06	EV	Floor 06 General Building By elevator lobby	ELKAY	EHF-8-1	870740004
FL0079ZZ-000000050	Drinking Fountain, Packaged	EWC	06	EV	Floor 06 General Building By elevator lobby	ELKAY	EHF-8-1	870740004
FL0079ZZ-000000051	Drinking Fountain, Packaged	EWC	07	EV	Floor 07 General Building By elevator lobby	ELKAY	EHF-8-1	870740004
FL0079ZZ-000000052	Drinking Fountain, Packaged	EWC	07	EV	Floor 07 General Building By elevator lobby	ELKAY	EHF-8-1	870740004
FL0079ZZ-000000053	Drinking Fountain, Packaged	EWC	08	EV	Floor 08 General Building By elevator lobby	ELKAY	EHF-8-1	870740004
FL0079ZZ-000000054	Drinking Fountain, Packaged	EWC	08	EV	Floor 08 General Building By elevator lobby	ELKAY	EHF-8-1	870740004
FL0079ZZ-000000076	Exit Signs	EXS	01	EV	Floor 01 General Building By elevator fire door	LITHONIA	LQMS1R	f7710090
FL0079ZZ-000000077	Exit Signs	EXS	04	LB	Floor 04 Lobby By hallway	LITHONIA	LQMS1R	not available
FL0079ZZ-000000078	Exit Signs	EXS	04	HW	Floor 04 General Building By hallway south	LITHONIA	LQMS1R	not available
FL0079ZZ-000000079	Exit Signs	EXS	04	FT	Floor 04 General Building By the Gym	LITHONIA	LQMS1R	not available
FL0079ZZ-000000080	Exit Signs	EXS	04	490	Floor 04 General Building By the room 490	LITHONIA	LQMS1R	not available
FL0079ZZ-000000081	Exit Signs	EXS	04	487	Floor 04 General Building By the room 487	LITHONIA	LQMS1R	not available
FL0079ZZ-000000082	Exit Signs	EXS	04	EV	Floor 04 General Building By elevator fire door	LITHONIA	LQMS1R	f771085
FL0079ZZ-000000083	Exit Signs	EXS	04	EV	Floor 04 General Building By elevator lobby	LITHONIA	lqms2r	not available
FL0079ZZ-000000084	Exit Signs	EXS	04	SW	Floor 04 Stairwell #3 By south stairwell	LITHONIA	lqms2r	not available
FL0079ZZ-000000085	Exit Signs	EXS	05	EV	Floor 05 General Building By elevator fire door	LITHONIA	LQMS1R	f771087

FL0079ZZ-000000086	Exit Signs	EXS	05	PK	Floor 05 Parking NORTH SIDE OF THE BUILDING	LITHONIA	lqms2r	not available
FL0079ZZ-000000087	Exit Signs	EXS	05	PK	Floor 05 Parking NORTH SIDE OF THE BUILDING	LITHONIA	lqms2r	not available
FL0079ZZ-000000088	Exit Signs	EXS	05	SW	Floor 05 Stairwell #2 By elevator lobby	LITHONIA	LQMS1R	not available
FL0079ZZ-000000089	Exit Signs	EXS	06	636	Floor 06 Office ROOM 636	LITHONIA	not available	not available
FL0079ZZ-000000090	Exit Signs	EXS	06	636	Floor 06 Office ROOM 636	LITHONIA	not available	not available
FL0079ZZ-000000091	Exit Signs	EXS	06	636	Floor 06 Office ROOM 636	LITHONIA	not available	not available
FL0079ZZ-000000092	Exit Signs	EXS	06	636	Floor 06 Office ROOM 636	LITHONIA	not available	not available
FL0079ZZ-000000093	Exit Signs	EXS	06	636	Floor 06 Office ROOM 636	LITHONIA	not available	not available
FL0079ZZ-000000094	Exit Signs	EXS	06	636	Floor 06 Office ROOM 636	LITHONIA	not available	not available
FL0079ZZ-000000095	Exit Signs	EXS	06	636	Floor 06 Office ROOM 636	LITHONIA	not available	not available
FL0079ZZ-000000096	Exit Signs	EXS	06	606	Floor 06 Office ROOM 606	LITHONIA	not available	not available
FL0079ZZ-000000097	Exit Signs	EXS	06	606	Floor 06 Office ROOM 606	LITHONIA	not available	not available
FL0079ZZ-000000098	Exit Signs	EXS	06	606	Floor 06 Office ROOM 606	LITHONIA	not available	not available
FL0079ZZ-000000099	Exit Signs	EXS	06	606	Floor 06 Office ROOM 606	LITHONIA	not available	not available
FL0079ZZ-000000100	Exit Signs	EXS	06	606	Floor 06 Office ROOM 606	LITHONIA	not available	not available
FL0079ZZ-000000101	Exit Signs	EXS	06	606	Floor 06 Office ROOM 606	LITHONIA	not available	not available
FL0079ZZ-000000102	Exit Signs	EXS	06	606	Floor 06 Office ROOM 606	LITHONIA	not available	not available
FL0079ZZ-000000103	Exit Signs	EXS	06	606	Floor 06 Office ROOM 606	LITHONIA	not available	not available
FL0079ZZ-000000104	Exit Signs	EXS	06	PK	Floor 06 Parking South side of the building	LITHONIA	lqms2r	not available
FL0079ZZ-000000105	Exit Signs	EXS	06	EV	Floor 06 General Building By elevator fire door	LITHONIA	LQMS1R	f771084
FL0079ZZ-000000106	Exit Signs	EXS	06	PK	Floor 06 Parking South side of the building	LITHONIA	lqms2r	not available
FL0079ZZ-000000107	Exit Signs	EXS	07	LB	Floor 07 General Building lobby east	LITHONIA	lqms2r	not available
FL0079ZZ-000000108	Exit Signs	EXS	07	LB	Floor 07 General Building lobby south	LITHONIA	lqms2r	not available
FL0079ZZ-000000109	Exit Signs	EXS	07	LB	Floor 07 General Building lobby west	LITHONIA	lqms2r	not available
FL0079ZZ-000000110	Exit Signs	EXS	07	HW	Floor 07 General Building hallway north	LITHONIA	lqms2r	not available
FL0079ZZ-000000111	Exit Signs	EXS	07	HW	Floor 07 General Building hallway north stairway	LITHONIA	lqms2r	not available
FL0079ZZ-000000112	Exit Signs	EXS	07	HW	Floor 07 General Building hallway south stairway	LITHONIA	lqms2r	not available
FL0079ZZ-000000113	Exit Signs	EXS	08	EV	Floor 08 Lobby ELEVATOR LOBBY	LITHONIA	LQMS1R	not available
FL0079ZZ-000000114	Exit Signs	EXS	08	HW	Floor 08 General Building HALLWAY	LITHONIA	LQMS1R	not available
FL0079ZZ-000000115	Exit Signs	EXS	07	EV	Floor 07 General Building By elevator fire door	LITHONIA	LQMS1R	f771089
FL0079ZZ-000000116	Exit Signs	EXS	08	EV	Floor 08 General Building By elevator fire door	LITHONIA	LQMS1R	f771087

FL0079ZZ-000000117	Exit Signs	EXS	08	EB	Floor 08 General Building Trought the hallway	LITHONIA	lqms2r	not available
FL0079ZZ-000000118	Exit Signs	EXS	08	EB	Floor 08 General Building Trought the hallway	LITHONIA	lqms2r	not available
FL0079ZZ-000000119	Exit Signs	EXS	08	EB	Floor 08 General Building Trought the hallway	LITHONIA	lqms2r	not available
FL0079ZZ-000000120	Exit Signs	EXS	08	EB	Floor 08 General Building Trought the hallway	LITHONIA	lqms2r	not available
FL0079ZZ-000000121	Exit Signs	EXS	08	EB	Floor 08 General Building Trought the hallway	LITHONIA	lqms2r	not available
FL0079ZZ-000000122	Exit Signs	EXS	08	EB	Floor 08 General Building Trought the hallway	LITHONIA	lqms2r	not available
FL0079ZZ-000000123	Exit Signs	EXS	08	EB	Floor 08 General Building Trought the hallway	LITHONIA	lqms2r	not available
FL0079ZZ-000000124	Exit Signs	EXS	08	EB	Floor 08 General Building Trought the hallway	LITHONIA	lqms2r	not available
FL0079ZZ-000000125	Fan, AXIAL	FAN-01			Ground Floor FIRE PUMP ROOM			not available
FL0079ZZ-000000130	Fire Door - Swinging	FDR-01	01	ET	Floor 01 General Building By east side of the building	WARNOCK HERSEY	not available	wh 1380
FL0079ZZ-000000131	Fire Door - Swinging	FDR-01	01	PK	Floor 01 Parking SOUTH SIDE OF THE BUILDING	WARNOCK HERSEY	not available	001324
FL0079ZZ-000000132	Fire Door - Swinging	FDR-01	09	ST	Floor 09 General Building By south side of the building	WARNOCK HERSEY	not available	001348
FL0079ZZ-000000133	Fire Door - Swinging	FDR-01	02	PK	Floor 02 Parking SOUTH SIDE OF THE BUILDING	WARNOCK HERSEY	not available	001347
FL0079ZZ-000000134	Fire Door - Swinging	FDR-01	03	PK	Floor 03 Parking SOUTH SIDE OF THE BUILDING	WARNOCK HERSEY	not available	001349
FL0079ZZ-000000135	Fire Door - Swinging	FDR-01	02	WT	Floor 02 General Building by west side of the building	WARNOCK HERSEY	not available	0001343
FL0079ZZ-000000136	Fire Door - Swinging	FDR-01	03	WT	Floor 03 General Building by west side of the building	WARNOCK HERSEY	not available	001341
FL0079ZZ-000000137	Fire Door - Swinging	FDR-01	04	WT	Floor 04 General Building by west side of the building	WARNOCK HERSEY	not available	001346
FL0079ZZ-000000138	Fire Door - Swinging	FDR-01	04	SW	Floor 04 Stairwell #2 By elevator lobby	WARNOCK HERSEY	not available	F771085
FL0079ZZ-000000139	Fire Door - Swinging	FDR-01	04	SW	Floor 04 Stairwell #3 By south stairwell	WARNOCK HERSEY	not available	F771059wh02h235
FL0079ZZ-000000140	Fire Door - Swinging	FDR-01	04	NT	Floor 04 General Building By north side of the building	WARNOCK HERSEY	not available	001321
FL0079ZZ-000000141	Fire Door - Swinging	FDR-01	04	PK	Floor 04 Parking SOUTH SIDE OF THE BUILDING	WARNOCK HERSEY	not available	001059
FL0079ZZ-000000142	Fire Door - Swinging	FDR-01	04	PK	Floor 04 Parking SOUTH SIDE OF THE BUILDING	WARNOCK HERSEY	not available	001325
FL0079ZZ-000000143	Fire Door - Swinging	FDR-01	04	SW	Floor 04 Stairwell #3 By south stairwell	WARNOCK HERSEY	not available	001334
FL0079ZZ-000000144	Fire Door - Swinging	FDR-01	05	PK	Floor 05 Parking SOUTH SIDE OF THE BUILDING	WARNOCK HERSEY	not available	001345
FL0079ZZ-000000145	Fire Door - Swinging	FDR-01	05	SW	Floor 05 Stairwell #1 By north stairwell	WARNOCK HERSEY	F771087	not available
FL0079ZZ-000000146	Fire Door - Swinging	FDR-01	05	SW	Floor 05 Stairwell #1 By north stairwell	WARNOCK HERSEY	F771087	not available
FL0079ZZ-000000147	Fire Door - Swinging	FDR-01	05	SW	Floor 05 Stairwell #3 By south stairwell	WARNOCK HERSEY	wh-001069	wh 024234

FL0079ZZ-000000148	Fire Door - Swinging	FDR-01	05	SW	Floor 05 Stairwell #3 By south stairwell	WARNOCK HERSEY	wh 1376	wh 001334
FL0079ZZ-000000149	Fire Door - Swinging	FDR-01	05	ET	Floor 05 General Building by east side of the building	WARNOCK HERSEY	not available	001344
FL0079ZZ-000000150	Fire Door - Swinging	FDR-01	06	WT	Floor 06 General Building by west side of the building	WARNOCK HERSEY	not available	001338
FL0079ZZ-000000151	Fire Door - Swinging	FDR-01	05	NT	Floor 05 General Building By north side of the building	WARNOCK HERSEY	not available	001340
FL0079ZZ-000000152	Fire Door - Swinging	FDR-01	05	NT	Floor 05 General Building By north side of the building	WARNOCK HERSEY	not available	024213
FL0079ZZ-000000153	Fire Door - Swinging	FDR-01	06	NT	Floor 06 General Building By north side of the building	WARNOCK HERSEY	not available	001337
FL0079ZZ-000000154	Fire Door - Swinging	FDR-01	06	NT	Floor 06 General Building By north side of the building	WARNOCK HERSEY	not available	024214
FL0079ZZ-000000155	Fire Door - Swinging	FDR-01	08	NT	Floor 08 General Building By north side of the building	WARNOCK HERSEY	not available	001323
FL0079ZZ-000000156	Fire Door - Swinging	FDR-01	06	PK	Floor 06 Parking SOUTH SIDE OF THE BUILDING	WARNOCK HERSEY	not available	001326
FL0079ZZ-000000157	Fire Door - Swinging	FDR-01	06	SW	Floor 06 Stairwell #1 By north stairwell	WARNOCK HERSEY	W1371	not available
FL0079ZZ-000000158	Fire Door - Swinging	FDR-01	06	SW	Floor 06 Stairwell #1 By north stairwell	WARNOCK HERSEY	WH 001080	not available
FL0079ZZ-000000159	Fire Door - Swinging	FDR-01	07	SW	Floor 07 Stairwell #1 by north stairways	WARNOCK HERSEY	r6953	771089
FL0079ZZ-000000160	Fire Door - Swinging	FDR-01	07	SW	Floor 07 Stairwell #1 by north stairways	WARNOCK HERSEY	r6954	771089
FL0079ZZ-000000161	Fire Door - Swinging	FDR-01	07	SW	Floor 07 Stairwell #2 By south stairwell	WARNOCK HERSEY	not available	001339
FL0079ZZ-000000162	Fire Door - Swinging	FDR-01	06	SW	Floor 06 Stairwell #2 By elevator lobby	WARNOCK HERSEY	W1372	not available
FL0079ZZ-000000163	Fire Door - Swinging	FDR-01	07	SW	Floor 07 Stairwell #3 By north side of the building	WARNOCK HERSEY	not available	001322
FL0079ZZ-000000164	Fire Door - Swinging	FDR-01	06	SW	Floor 06 Stairwell #3 By south stairwell	WARNOCK HERSEY	not available	001350
FL0079ZZ-000000165	Fire Door - Swinging	FDR-01	06	SW	Floor 06 Stairwell #3 By south stairwell	WARNOCK HERSEY	WH 001066	not available
FL0079ZZ-000000166	Fire Door - Swinging	FDR-01	07	SW	Floor 07 Stairwell #3 By north side of the building	WARNOCK HERSEY	not available	024211
FL0079ZZ-000000167	Fire Door - Swinging	FDR-01	08	SW	Floor 08 Stairwell #3 By north side of the building	WARNOCK HERSEY	not available	001352
FL0079ZZ-000000168	Fire Door - Swinging	FDR-01	09	SW	Floor 09 Stairwell #3 By north stairwell	WARNOCK HERSEY	not available	001348
FL0079ZZ-000000169	Fire Door - Swinging	FDR-01	08	SW	Floor 08 Stairwell #3 By north stairwell	WARNOCK HERSEY	1350	not available
FL0079ZZ-000000129	Fire Door - Sliding & Rolling	FDR-02	01	LB	Floor 01 Lobby Main entrance door	Horton	not available	not available
FL0079ZZ-000000171	Fire Extinguishers	FEX	01	SW	Floor 01 General Building stairwell by the elevators	Buckeye	not available	JB - 397102
FL0079ZZ-000000172	Fire Extinguishers	FEX	01	HW-NT	Floor 01 General Building north hallway	Buckeye	not available	JB - 397852
FL0079ZZ-000000173	Fire Extinguishers	FEX	01	ST	Floor 01 General Building south hallway	Buckeye	not available	DG - 644480
FL0079ZZ-000000174	Fire Extinguishers	FEX	01	SW-S	Floor 01 General Building south stairwell	Buckeye	not available	JB - 397081
FL0079ZZ-000000175	Fire Extinguishers	FEX	01	LB	Floor 01 General Building by lobby	Amerex	not available	JC - 00045197

FL0079ZZ-000000176	Fire Extinguishers	FEX	01	PK	Floor 01 General Building Parking garage	Buckeye	not available	JC - 45181
FL0079ZZ-000000177	Fire Extinguishers	FEX	01	PK	Floor 01 General Building Parking garage	Amerex	not available	JC - 45182
FL0079ZZ-000000178	Fire Extinguishers	FEX	02	PK	Floor 02 General Building Parking garage	Buckeye	not available	JB - 397080
FL0079ZZ-000000179	Fire Extinguishers	FEX	02	PK	Floor 02 General Building Parking garage	Buckeye	not available	JB - 397087
FL0079ZZ-000000180	Fire Extinguishers	FEX	03	PK	Floor 03 General Building Parking garage	Amerex	not available	JB - 397067
FL0079ZZ-000000181	Fire Extinguishers	FEX	03	PK	Floor 03 General Building Parking garage	Buckeye	not available	JB - 397108
FL0079ZZ-000000182	Fire Extinguishers	FEX	04	PK	Floor 04 General Building Parking garage	Buckeye	not available	JB - 397097
FL0079ZZ-000000183	Fire Extinguishers	FEX	04	PK	Floor 04 General Building Parking garage	Amerex	not available	TF-352371
FL0079ZZ-000000184	Fire Extinguishers	FEX	04	PK	Floor 04 General Building Parking garage	Buckeye	not available	JC - 45184
FL0079ZZ-000000185	Fire Extinguishers	FEX	04	PK	Floor 04 General Building Parking garage	Buckeye	not available	HZ - 675004
FL0079ZZ-000000186	Fire Extinguishers	FEX	04	PK	Floor 04 General Building Parking garage	Amerex	not available	JB - 397092
FL0079ZZ-000000187	Fire Extinguishers	FEX	04	SW	Floor 04 General Building stairwell by the elevators	Amerex	not available	MN - 801484
FL0079ZZ-000000188	Fire Extinguishers	FEX	04	HW-NT	Floor 04 General Building north hallway	Amerex	not available	MN - 801485
FL0079ZZ-000000189	Fire Extinguishers	FEX	04	ST	Floor 04 General Building south hallway	Buckeye	not available	JB - 397095
FL0079ZZ-000000190	Fire Extinguishers	FEX	04	SW-S	Floor 04 General Building south stairwell	Buckeye	not available	JB - 397071
FL0079ZZ-000000191	Fire Extinguishers	FEX	04	air handle	Floor 04 General Building by the air handler room	Amerex	not available	JC - 45186
FL0079ZZ-000000192	Fire Extinguishers	FEX	04	EE	Floor 04 General Building by electrical room	Buckeye	not available	HW - 79957
FL0079ZZ-000000193	Fire Extinguishers	FEX	04	LB	Floor 04 General Building by lobby	Buckeye	not available	KZ-281263
FL0079ZZ-000000194	Fire Extinguishers	FEX	05	SW	Floor 05 General Building stairwell by the elevators	Amerex	not available	JB - 3977096
FL0079ZZ-000000195	Fire Extinguishers	FEX	05	HW-NT	Floor 05 General Building north hallway	Buckeye	not available	JB - 397073
FL0079ZZ-000000196	Fire Extinguishers	FEX	05	ST	Floor 05 General Building south hallway	Buckeye	not available	JC - 45192
FL0079ZZ-000000197	Fire Extinguishers	FEX	05	SW-S	Floor 05 General Building south stairwell	Buckeye	not available	JB - 397101
FL0079ZZ-000000198	Fire Extinguishers	FEX	05	air handle	Floor 05 General Building by the air handler room	Buckeye	not available	HT - 735107
FL0079ZZ-000000199	Fire Extinguishers	FEX	05	EE	Floor 05 General Building by electrical room	Buckeye	not available	JB - 397163
FL0079ZZ-000000200	Fire Extinguishers	FEX	05	LB	Floor 05 General Building by lobby	Buckeye	not available	JB - 989971
FL0079ZZ-000000201	Fire Extinguishers	FEX	05	817	Floor 05 General Building by command center room 817	Amerex	not available	JB - 989966
FL0079ZZ-000000202	Fire Extinguishers	FEX	05	HW	Floor 05 General Building by hallway	Amerex	not available	JB - 989976
FL0079ZZ-000000203	Fire Extinguishers	FEX	05	HW	Floor 05 General Building by hallway	Amerex	not available	JB - 989968
FL0079ZZ-000000204	Fire Extinguishers	FEX	06	SW-N	Floor 06 General Building By North stairwell	Buckeye	not available	JB - 397099

FL0079ZZ-000000205	Fire Extinguishers	FEX	06	SW-S	Floor 06 General Building By south stairwell	Buckeye	not available	JB - 397107
FL0079ZZ-000000206	Fire Extinguishers	FEX	06	air handle	Floor 06 General Building by air handler room	Amerex	not available	JC - 45188
FL0079ZZ-000000207	Fire Extinguishers	FEX	06	EE	Floor 06 General Building By electrical room	Amerex	not available	JB - 397063
FL0079ZZ-000000208	Fire Extinguishers	FEX	06	EV	Floor 06 General Building By elevator lobby	Amerex	not available	HT - 735079
FL0079ZZ-000000209	Fire Extinguishers	FEX	07	SW	Floor 07 General Building stairwell by the elevators	Buckeye	not available	JB - 397085
FL0079ZZ-000000210	Fire Extinguishers	FEX	07	HW-NT	Floor 07 General Building north hallway	Buckeye	not available	JB - 397098
FL0079ZZ-000000211	Fire Extinguishers	FEX	07	ST	Floor 07 General Building south hallway	Buckeye	not available	JC - 45187
FL0079ZZ-000000212	Fire Extinguishers	FEX	07	SW-S	Floor 07 General Building south stairwell	Buckeye	not available	JB - 397072
FL0079ZZ-000000213	Fire Extinguishers	FEX	07	air handle	Floor 07 General Building by the air handler room	Buckeye	not available	JB - 397090
FL0079ZZ-000000214	Fire Extinguishers	FEX	07	EE	Floor 07 General Building by electrical room	Buckeye	not available	JB - 397069
FL0079ZZ-000000215	Fire Extinguishers	FEX	07	LB	Floor 07 General Building by lobby	Buckeye	not available	90 - 121257
FL0079ZZ-000000216	Fire Extinguishers	FEX	07	817	Floor 07 General Building by command center room 817	Buckeye	not available	90 - 1211250
FL0079ZZ-000000217	Fire Extinguishers	FEX	07	HW	Floor 07 General Building by hallway	Buckeye	not available	JC - 45191
FL0079ZZ-000000218	Fire Extinguishers	FEX	08	SW	Floor 08 General Building stairwell by the elevators	Buckeye	not available	HT - 828267
FL0079ZZ-000000219	Fire Extinguishers	FEX	08	HW-NT	Floor 08 General Building north hallway	Amerex	not available	HT - 730667
FL0079ZZ-000000220	Fire Extinguishers	FEX	08	ST	Floor 08 General Building south hallway	Buckeye	not available	TF-353113
FL0079ZZ-000000221	Fire Extinguishers	FEX	08	SW-S	Floor 08 General Building south stairwell	Buckeye	not available	JC - 45185
FL0079ZZ-000000222	Fire Extinguishers	FEX	08	air handle	Floor 08 General Building by the air handler room	Buckeye	not available	JB - 397077
FL0079ZZ-000000223	Fire Extinguishers	FEX	08	EE	Floor 08 General Building by electrical room	Amerex	not available	HT - 735111
FL0079ZZ-000000224	Fire Extinguishers	FEX	08	LB	Floor 08 General Building by lobby	Buckeye	not available	JB - 397074
FL0079ZZ-000000225	Fire Extinguishers	FEX	08	817	Floor 08 General Building by command center room 817	Amerex	not available	JB - 397084
FL0079ZZ-000000226	Fire Extinguishers	FEX	09	air handle	Floor 09 General Building by the air handler room	Buckeye	not available	JB - 397082
FL0079ZZ-000000227	Fire Extinguishers	FEX	09	EE	Floor 09 General Building by electrical room	Buckeye	not available	JB - 397083
FL0079ZZ-000000228	Fire Extinguishers	FEX	09	LB	Floor 09 General Building by lobby	Buckeye	not available	JC - 45190
FL0079ZZ-000000229	Fire Extinguishers	FEX	09	817	Floor 09 General Building by command center room 817	Buckeye	not available	JB - 397114
FL0079ZZ-000000230	Fire Extinguishers	FEX	09	SW	Floor 09 General Building stairwell by the elevators	Buckeye	not available	JB - 397091

FL0079ZZ-000000231	Fire Extinguishers	FEX		MC	Penthouse General Building By mechanicl room	Buckeye	not available	JB - 397105
FL0079ZZ-000000126	Fences and Gates	FNG		ST	Floor 01 Parking By south side of the building	not available	GSL7511B2 / RAM1000	070220100000019 / 37494
FL0079ZZ-000000127	Fences and Gates	FNG		WT	Floor 01 Parking By west side of the building	not available	not available	not available
FL0079ZZ-000000232	Fire Pump, Electric-Drive	FPM-01	01		FLOOR 01 FIRE PUMP ROOM	AURORA	AH326TSTDR70 0013DW 4-481-11C	72-80951
FL0079ZZ-000000292	Parking Arm Gates	PAG		EN	Ground Floor Outside Rear entrance to garage	NOT AVAILABLE	NOT AVAILABLE	NOT AVAILABLE
FL0079ZZ-000000293	Pump	PMP	01	MC	Floor 01 Mechanical Equipment Room EAST SIDE OF THE ROOM	AURORA	72-91009-1 344-BF	72-91009-1
FL0079ZZ-000000294	Pump	PMP	01	MC	Floor 01 Mechanical Equipment Room EAST SIDE OF THE ROOM	AURORA	72-91009-2 344-BF	72-91009-2
FL0079ZZ-000000298	Pump, Chemical Feed	PMP			Roof Roof / Roof Installed Item Roof Center	MILTON ROY	P151-392TI	0503936033-2
FL0079ZZ-000000295	Pump, Condensate	PMP-03			Roof Roof / Roof Installed Item Roof Center	AURORA	413BF	733894
FL0079ZZ-000000296	Pump, Condensate	PMP-03			Roof Roof / Roof Installed Item Roof Center	AURORA		
FL0079ZZ-000000297	Pump, Circulating, Hot Water	PMP-HW			Roof Roof / Roof Installed Item Roof Center	AURORA	72-11657	342-BF
FL0079ZZ-000000233	Panelboard, Lighting & Appliance	PNB		SH	Basement, 1st Level Shop / Factory SW CORNER OF THE ROOM	GENERAL ELEC	AQF3382AB	162-30077543
FL0079ZZ-000000234	Panelboard, Lighting & Appliance	PNB		SH	Basement, 1st Level Shop / Factory NW CORNER OF THE ROOM	GENERAL ELEC	TL-LO-415C	EE 974691
FL0079ZZ-000000235	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) By west side of the room	WESTINGHOUSE	SEDN100	not available
FL0079ZZ-000000236	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) By west side of the room	NOT AVAILABLE	TE-4000XHP	400050
FL0079ZZ-000000237	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) North side of the room	SQUARE D	MHC-265	not available
FL0079ZZ-000000238	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Power Distribution Center (Primary Switchgear) EAST SIDE OF THE ROOM	NOT AVAILABLE	not available	not available
FL0079ZZ-000000239	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room North side of the room	GENERAL ELEC	nlab	#5
FL0079ZZ-000000240	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room EAST SIDE OF THE ROOM	GENERAL ELEC	nhb	2a

FL0079ZZ-000000241	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room North side of the room	GENERAL ELEC	nlar	5b
FL0079ZZ-000000242	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room EAST SIDE OF THE ROOM	GENERAL ELEC	nhb	2a
FL0079ZZ-000000243	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room EAST SIDE OF THE ROOM	SQUARE D	qoc442l	g2mm2ml315ocu2
FL0079ZZ-000000244	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room EAST SIDE OF THE ROOM	SQUARE D	qoc342mf	ser 1
FL0079ZZ-000000245	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room EAST SIDE OF THE ROOM	GENERAL ELEC	tm18410c	
FL0079ZZ-000000246	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room NORTH SIDE OF THE ROOM	SQUARE D	NQOD424L100CU	not available
FL0079ZZ-000000247	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room NORTH SIDE OF THE ROOM	SQUARE D	MHC2OS	not available
FL0079ZZ-000000248	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room NORTH SIDE OF THE ROOM	SQUARE D	NH26TS	not available
FL0079ZZ-000000249	Panelboard, Lighting & Appliance	PNB	04	EE	Floor 04 Electrical Equipment Room EAST SIDE OF THE ROOM	GENERAL ELEC	nlab	av 603468
FL0079ZZ-000000250	Panelboard, Lighting & Appliance	PNB	04	EE	Floor 04 Electrical Equipment Room EAST SIDE OF THE ROOM	GENERAL ELEC	TM30-413	CM001
FL0079ZZ-000000251	Panelboard, Lighting & Appliance	PNB	04	EE	Floor 04 Electrical Equipment Room EAST SIDE OF THE ROOM	GENERAL ELEC	NHB	16H33
FL0079ZZ-000000252	Panelboard, Lighting & Appliance	PNB	04	EE	Floor 04 Electrical Equipment Room WEST SIDE OF THE ROOM	SIEMENS	c2888	g2mm2ml315ocu2
FL0079ZZ-000000253	Panelboard, Lighting & Appliance	PNB	04	EE	Floor 04 Electrical Equipment Room NORTH SIDE OF THE ROOM	GENERAL ELEC	NLAB	AW-15866
FL0079ZZ-000000254	Panelboard, Lighting & Appliance	PNB	04	EE	Floor 04 Electrical Equipment Room WEST SIDE OF THE ROOM	GENERAL ELEC	NHB	AW16429
FL0079ZZ-000000255	Panelboard, Lighting & Appliance	PNB	05	532	Floor 05 Control Center By room 532	SQUARE D	qoch40m	not available
FL0079ZZ-000000256	Panelboard, Lighting & Appliance	PNB	05	EE	Floor 05 Electrical Equipment Room WEST SIDE OF THE ROOM	GENERAL ELEC	NLAB	AW15919
FL0079ZZ-000000257	Panelboard, Lighting & Appliance	PNB	05	EE	Floor 05 Electrical Equipment Room NORTH SIDE OF THE ROOM	GENERAL ELEC	NLAB	AV603469
FL0079ZZ-000000258	Panelboard, Lighting & Appliance	PNB	05	EE	Floor 05 Electrical Equipment Room NORTH SIDE OF THE ROOM	GENERAL ELEC	FLM2012C	mod 1
FL0079ZZ-000000259	Panelboard, Lighting & Appliance	PNB	05	EE	Floor 05 Electrical Equipment Room NORTH SIDE OF THE ROOM	GENERAL ELEC	NHB	AW16432
FL0079ZZ-000000260	Panelboard, Lighting & Appliance	PNB	05	EE	Floor 05 Electrical Equipment Room WEST SIDE OF THE ROOM	GENERAL ELEC	TM30-41AC	mod 1
FL0079ZZ-000000261	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room SOUTH SIDE OF THE ROOM	GENERAL ELEC	not available	16461
FL0079ZZ-000000262	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room SOUTH SIDE OF THE ROOM	GENERAL ELEC	not available	16462
FL0079ZZ-000000263	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room	GENERAL ELEC	not available	464R

FL0079ZZ-000000264	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room SOUTH SIDE OF THE ROOM	GENERAL ELEC	not available	603470
FL0079ZZ-000000265	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room NORTH SIDE OF THE ROOM	GENERAL ELEC	not available	15916
FL0079ZZ-000000266	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room NORTH SIDE OF THE ROOM	SQUARE D	QOC442L	G2
FL0079ZZ-000000267	Panelboard, Lighting & Appliance	PNB	06	EE	Floor 06 Electrical Equipment Room NORTH SIDE OF THE ROOM	CHALLANGER	3SLB10	not available
FL0079ZZ-000000268	Panelboard, Lighting & Appliance	PNB	07	MC	Floor 07 Mechanical Equipment Room NORTH SIDE OF THE ROOM	CHALLANGER	1K705001	not available
FL0079ZZ-000000269	Panelboard, Lighting & Appliance	PNB	07	EE	Floor 07 Electrical Equipment Room WEST SIDE OF THE ROOM	GENERAL ELEC	AC484-R	not available
FL0079ZZ-000000270	Panelboard, Lighting & Appliance	PNB	07	EE	Floor 07 Electrical Equipment Room WEST SIDE OF THE ROOM	GENERAL ELEC	AF765	not available
FL0079ZZ-000000271	Panelboard, Lighting & Appliance	PNB	07	EE	Floor 07 Electrical Equipment Room NORTH SIDE OF THE ROOM	ITE	not available	not available
FL0079ZZ-000000272	Panelboard, Lighting & Appliance	PNB	07	EE	Floor 07 Electrical Equipment Room NORTH SIDE OF THE ROOM	GENERAL ELEC	not available	15816
FL0079ZZ-000000273	Panelboard, Lighting & Appliance	PNB	07	EE	Floor 07 Electrical Equipment Room NORTH SIDE OF THE ROOM	GENERAL ELEC	not available	603541
FL0079ZZ-000000274	Panelboard, Lighting & Appliance	PNB	07	EE	Floor 07 Electrical Equipment Room NORTH SIDE OF THE ROOM	SQUARE D	QOC4421	not available
FL0079ZZ-000000275	Panelboard, Lighting & Appliance	PNB	07	EE	Floor 07 Electrical Equipment Room EAST SIDE OF THE ROOM	GENERAL ELEC	not available	16430
FL0079ZZ-000000276	Panelboard, Lighting & Appliance	PNB	07	EE	Floor 07 Electrical Equipment Room EAST SIDE OF THE ROOM	GENERAL ELEC	not available	16430
FL0079ZZ-000000277	Panelboard, Lighting & Appliance	PNB	07	EE	Floor 07 Electrical Equipment Room EAST SIDE OF THE ROOM	GENERAL ELEC	not available	990811
FL0079ZZ-000000278	Panelboard, Lighting & Appliance	PNB	08	EE	Floor 08 Electrical Equipment Room WEST SIDE OF THE ROOM	GENERAL ELEC	NHB 16420	not available
FL0079ZZ-000000279	Panelboard, Lighting & Appliance	PNB	08	EE	Floor 08 Electrical Equipment Room SOUTH SIDE OF THE ROOM	GENERAL ELEC	NHB 16458	not available
FL0079ZZ-000000280	Panelboard, Lighting & Appliance	PNB	08	EE	Floor 08 Electrical Equipment Room SOUTH SIDE OF THE ROOM	WESTINGHOUSE	YS2060	267P414H02
FL0079ZZ-000000281	Panelboard, Lighting & Appliance	PNB	08	EE	Floor 08 Electrical Equipment Room SOUTH SIDE OF THE ROOM	GENERAL ELEC	NLAB 171358	603356
FL0079ZZ-000000282	Panelboard, Lighting & Appliance	PNB	08	EE	Floor 08 Electrical Equipment Room NORTH SIDE OF THE ROOM	GENERAL ELEC	NLAB 171359	15857
FL0079ZZ-000000283	Panelboard, Lighting & Appliance	PNB	08	EE	Floor 08 Electrical Equipment Room NORTH SIDE OF THE ROOM	WESTINGHOUSE	TAC 40035	DG 473499
FL0079ZZ-000000284	Panelboard, Lighting & Appliance	PNB	08	EE	Floor 08 Electrical Equipment Room NORTH SIDE OF THE ROOM	SQUARE D	03894331-593	80110 05327
FL0079ZZ-000000299	Sump Pump	SMP		LB	Ground Floor Pit Lobby under elevator 3	NOT AVAILABLE	NOT AVAILABLE	NOT AVAILABLE
FL0079ZZ-TNK-00001	Tank, Size=1900, Contents: Diesel	TNK-01						
FL0079ZZ-TNK-00002	Tank, Size=50, Contents: Diesel, Used for:	TNK-01						

FL0079ZZ-000000353	UPS (Uninterruptable Power Supply)	UPS	01	EE	Floor 01 Electrical Equipment Room NORTH SIDE OF THE ROOM	CLORIDE	not available	not available
FL0079ZZ-000000354	Variable Frequency Drive	VFD	09	AIR HANDLE	FLOOR 09 AIR HANDLER ROOM EAST SIDE OF THE ROOM	DANFOSS	178B3048	001230H226
FL0079ZZ-000000355	Water Heater, Electric	WHT-01	04	484	Floor 04 Office ROOM 484	A.O.SMITH	ECT_120_200	K07M009612
FL0079ZZ-000000356	Water Heater, Electric	WHT-01	04	JT	Floor 04 General Building Janitor room By men's Bathroom	A.O. SMITH	not available	not available
FL0079ZZ-000000357	Water Heater, Electric	WHT-01	05	JT	Floor 05 General Building Janitor room By men's Bathroom	A.O. SMITH	PE40-2_C	B23277
FL0079ZZ-000000358	Water Heater, Electric	WHT-01	07	JT	Floor 07 General Building Janitor room By men's Bathroom	RUUD	PE40-2	993823271

Date Run:

7/15/2014 2:44:16 PM

US Courthouse FL0089ZZ **O&M**
299 E Broward Blvd
Ft Lauderdale, FL 33301
169093 rentable square feet (rsf)

NATIONALCMMS
FOUNDATION FOR MAINTENANCE EXCELLENCE

Equipment List by Building and Equipment ID - Detail

Total Record Counts: 553

Building: FL0089ZZ

Equipment ID	Equipment Description	Equipment Type	Floor	Room	Location	Manufacturer	Model No.	Serial No.
FL0089ZZ-000000021	Condenser, Air-Cooled	ACC		RF	Roof Roof / Roof Installed Item Outside of chiller room	RHEEM	RANL-018JAZ	7384W111100007
FL0089ZZ-000000022	Condenser, Air-Cooled	ACC	03		Floor 03 Outside On balcony	Sanyo	CM2472	53682
FL0089ZZ-000000023	Condenser, Air-Cooled	ACC	03		Floor 03 Outside On balcony	Sanyo	CM2472	53182
FL0089ZZ-000000002	Air Dryer	ADR	01	WT	Floor 01 Mechanical Equipment Room 1ST FLOOR WEST SIDE	HANKISON	PR15	0352-1A-9811-777G
FL0089ZZ-000000003	Air Handling Unit, 3 ton thru 24 ton	AHU-01	01	NW	Floor 01 Mechanical Equipment Room Northwest side 1st floor	TRANE	MCCB05OUAOCOUB	K06G81410
FL0089ZZ-000000004	Air Handling Unit, 3 ton thru 24 ton	AHU-01	01	NW	Floor 01 Mechanical Equipment Room Northwest side 1st floor	TRANE	MCCB05OUAOCOUB	K06G81410
FL0089ZZ-000000005	Air Handling Unit, 3 ton thru 24 ton	AHU-01	01	SW	Floor 01 Mechanical Equipment Room southwest side 1st floor	CARRIER AIR	39ED26	772709226
FL0089ZZ-000000006	Air Handling Unit, 3 ton thru 24 ton	AHU-01	02	ET	Floor 02 Mechanical Equipment Room 2nd Floor eastside mech room	CARRIER AIR	39ED32	773409371
FL0089ZZ-000000007	Air Handling Unit, 3 ton thru 24 ton	AHU-01	03	CB	Floor 03 Cell Block 3rd west marshales cell hallway	CARRIER AIR	39BA050D16	773877021
FL0089ZZ-000000008	Air Handling Unit, 3 ton thru 24 ton	AHU-01	03	CB	Floor 03 Cell Block 4th west marshales cell hallway	CARRIER AIR	No Model #	No Serial #
FL0089ZZ-000000009	Air Handling Unit, 3 ton thru 24 ton	AHU-01	03	MC	Floor 03 Mechanical Equipment Room 3rd west mechanical room	CARRIER AIR	No Model #	No Serial #
FL0089ZZ-000000010	Air Handling Unit, 3 ton thru 24 ton	AHU-01	03	ET	Floor 03 Mechanical Equipment Room 3rd Floor East side mech room	CARRIER AIR	No Model #	No Serial #
FL0089ZZ-000000011	Air Handling Unit, 3 ton thru 24 ton	AHU-01	03	ET	Floor 03 Mechanical Equipment Room 3rd Floor eastside mech room	TRANE	MCCB035UAOCOUA	K06G81415
FL0089ZZ-000000012	Air Handling Unit, 3 ton thru 24 ton	AHU-01	04	WT	Floor 04 Mechanical Equipment Room 4th Floor westside mech room	CARRIER AIR	No Model #	No Serial #

FL0089ZZ-000000013	Air Handling Unit, 3 ton thru 24 ton	AHU-01	04	ET	Floor 04 Mechanical Equipment Room 4th Floor eastside mech room	CARRIER AIR	No Model #	No Serial #
FL0089ZZ-000000014	Air Handling Unit, 3 ton thru 24 ton	AHU-01			Penthouse Chiller Mechanical Room Hanging in chiller room (East)	CARRIER AIR	No Model #	No Serial #
FL0089ZZ-000000015	Air Handling Unit, 3 ton thru 24 ton	AHU-01			Penthouse Elevator / Mechanical Penthouse Hanging in elevator mach room	CARRIER AIR	No Model #	No Serial #
FL0089ZZ-000000016	Air Handling Unit, Computer Room	AHU-04	04		Floor 04 Control Center Hanging in server room	RHEEM	RHSL-HM1817JA	W081126016
FL0089ZZ-000000017	Air Handling Unit, Computer Room	AHU-04	03	MS	Floor 03 Control Center 3rd floor Marshall's office rm 312	Sanyo	KMS0972	01074 82
FL0089ZZ-000000018	Air Handling Unit, Computer Room	AHU-04	03	MS	Floor 03 Control Center 3rd floor Marshall's (Open Area)	Sanyo	KMS0972	01090 82
FL0089ZZ-000000122	Fire Detection and Alarm System	ALM	01	MC	Floor 01 Mechanical Equipment Room Mechanical room westside 1st floor	JOSLYN CLARK	DGA144-4	304932
FL0089ZZ-000000123	Fire Detection and Alarm System	ALM	01	LB	Floor 01 Lobby Northwest side 1st floor	Honeywell	LD3	No Serial #
FL0089ZZ-000000124	Fire Detection and Alarm System	ALM	01	OF	Floor 01 Office 1st floor eastside room 104	Honeywell		
FL0089ZZ-000000308	Switch, Automatic Transfer	ATS	01		Floor 01 Mechanical Equipment Room Back wall by prisoner elevator mach. Rm	Simplex	No Model #	31648-1
FL0089ZZ-000000309	Switch, Automatic Transfer	ATS	01		Floor 01 Mechanical Equipment Room Back wall by prisoner elevator mach. Rm	Simplex	No Model #	31648-2
FL0089ZZ-000000019	Backflow Prevention Device	BFP		PL	Basement, 1st Level Parking Lot Northside middle of parking	WILKINS	375	L48213
FL0089ZZ-000000020	Backflow Prevention Device	BFP		PL	Basement, 1st Level Parking Lot Southside middle of parking	WILKINS	375	L48216
FL0089ZZ-000000001	Air Compressor	CMP	01	WT	Floor 01 Mechanical Equipment Room 2nd FLOOR WEST SIDE	HONEYWELL	241G6F2COD	325-14-988026-027-L
FL0089ZZ-000000024	Cooling tower	CTR		CH	Roof Chiller Mechanical Room thru chiller room thru door behind generator	Marley		NC4001SP O51520-001-93A
FL0089ZZ-000000025	Cooling tower	CTR		CH	Roof Chiller Mechanical Room thru chiller room thru door behind generator	Marley		NC4001SP 051520-002-93B
FL0089ZZ-000000310	Switch, Disconnect	DCT	01	EE	Floor 01 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	No Model #	B-40274-075-01
FL0089ZZ-000000311	Switch, Disconnect	DCT	01	MC	Floor 01 Mechanical Equipment Room Mechanical room WEST SIDE	SQUARE D	HNF363	NO Serial #
FL0089ZZ-000000312	Switch, Disconnect	DCT	01	MC	Floor 01 Mechanical Equipment Room Mechanical room WEST SIDE	SQUARE D	D-223N	NO Serial #

FL0089ZZ-000000313	Switch, Disconnect	DCT	02	PR	Floor 02 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	D-U321	NO Serial #
FL0089ZZ-000000314	Switch, Disconnect	DCT	03	MC	Floor 03 Mechanical Equipment Room Mechanical room EAST SIDE	SQUARE D	40276-001-02	NO Serial #
FL0089ZZ-000000315	Switch, Disconnect	DCT	03	MC	Floor 03 Mechanical Equipment Room Mechanical room EAST SIDE	SQUARE D	40275-995-02	NO Serial #
FL0089ZZ-000000316	Switch, Disconnect	DCT	03	PR	Floor 03 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	B-40274-075-01	NO Serial #
FL0089ZZ-000000317	Switch, Disconnect	DCT	04	PR	Floor 04 Electrical Equipment Room Telephone room WEST SIDE	G.E	NP 266209-D	NO Serial #
FL0089ZZ-000000318	Switch, Disconnect	DCT	04	PR	Floor 04 Electrical Equipment Room Telephone room WEST SIDE	G.E	NP 266208	NO Serial #
FL0089ZZ-000000319	Switch, Disconnect	DCT	04	OT	Floor 04 Outside next to package unit east side	SQUARE D	A-40274-384-01	NO Serial #
FL0089ZZ-000000320	Switch, Disconnect	DCT	04	OT	Floor 04 Outside next to package unit west side	SIEMENS	NR423	NO Serial #
FL0089ZZ-000000321	Switch, Disconnect	DCT		CH	Penthouse Chiller Mechanical Room next to generator	G.E	No Model #	NO Serial #
FL0089ZZ-000000322	Switch, Disconnect	DCT		CH	Penthouse Chiller Mechanical Room next to generator	G.E	No Model #	NO Serial #
FL0089ZZ-000000323	Switch, Disconnect	DCT		CH	Penthouse Chiller Mechanical Room next to generator	G.E	No Model #	NO Serial #
FL0089ZZ-000000324	Switch, Disconnect	DCT		CH	Penthouse Chiller Mechanical Room next to generator	G.E	No Model #	NO Serial #
FL0089ZZ-000000325	Switch, Disconnect	DCT		CH	Penthouse Chiller Mechanical Room next to generator	G.E	No Model #	NO Serial #
FL0089ZZ-000000326	Switch, Disconnect	DCT		CH	Penthouse Chiller Mechanical Room next to chiller	SQUARE D	40274-278-02	NO Serial #
FL0089ZZ-000000327	Switch, Disconnect	DCT		CH	Penthouse Chiller Mechanical Room next to chiller	SQUARE D	40274-278-03	NO Serial #
FL0089ZZ-000000328	Switch, Disconnect	DCT		CH	Penthouse Chiller Mechanical Room next to chiller	SQUARE D	30009-418-01D	NO Serial #
FL0089ZZ-000000329	Switch, Disconnect	DCT		CH	Penthouse Chiller Mechanical Room next to chiller	SQUARE D	30009-418-01D	NO Serial #
FL0089ZZ-000000330	Switch, Disconnect	DCT		CH	Penthouse Chiller Mechanical Room next to chiller	SQUARE D	40275-950-02	NO Serial #
FL0089ZZ-000000331	Switch, Disconnect	DCT		OT	Penthouse Outside outside next to cooling tower	SIEMENS	NFR321	NO Serial #
FL0089ZZ-000000332	Switch, Disconnect	DCT		OT	Penthouse Outside outside next to cooling tower	SIEMENS	NFR322	NO Serial #
FL0089ZZ-000000333	Switch, Disconnect	DCT		ET	Penthouse Elevator / Mechanical Penthouse EAST SIDE inside elevator machine room	G.E	No Model #	NO Serial #

FL0089ZZ-000000110	Exterior Doors	DOR	04	DR	Floor 04 General Building SLIDING DOOR 4TH WEST	STANLEY	A265275	No Serial #
FL0089ZZ-000000111	EXterior Doors	DOR	04	DR	Floor 04 General Building SLIDING DOOR 4TH EAST	STANLEY	A265275	NO Serial #
FL0089ZZ-000000112	Exterior Doors	DOR	03	PW	Floor 03 General Building POWER OPERATED 3RD EAST	HORTONS	No Model #	NO Serial #
FL0089ZZ-000000113	Exterior Doors	DOR	03	PW	Floor 03 General Building POWER OPERATED 3RD WEST	STANLEY	A265275	NO Serial #
FL0089ZZ-000000114	Exterior Doors	DOR	02	DR	Floor 02 General Building Sliding Door 2nd east	STANLEY	A265275	NO Serial #
FL0089ZZ-000000115	Exterior Doors	DOR	02	207	Floor 02 General Building Sliding door room 207	STANLEY	A265275	NO Serial #
FL0089ZZ-000000116	Exterior Doors	DOR	02	203	Floor 02 General Building Sliding door room 203	STANLEY	A265275	NO Serial #
FL0089ZZ-000000117	Exterior Doors	DOR	02	202	Floor 02 General Building Sliding door room 202	STANLEY	A265275	NO Serial #
FL0089ZZ-000000118	Exterior Doors	DOR	02	PW	Floor 02 General Building Power operated 2nd west	HORTONS	No Model #	NO Serial #
FL0089ZZ-000000119	Exterior Doors	DOR	01	PW	Floor 01 General Building Power operated 1st west Front	HORTONS	No Model #	No Serial #
FL0089ZZ-000000120	Exterior Doors	DOR	01	PW	Floor 01 General Building Power operated 1st west Back	STANLEY	A265275	No Serial #
FL0089ZZ-000000121	Exterior Doors	DOR	01	PW	Floor 01 General Building Power operated 1st west Back	HORTONS	No Model #	No Serial #
FL0089ZZ-000000346	Transformer, Dry	DTT	01	PR	Floor 01 Electrical Equipment Room Telephone room by mail room EAST SIDE	SQUARE D	30T3HF	33349-17222-006
FL0089ZZ-000000347	Transformer, Dry	DTT	01	PR	Floor 01 Electrical Equipment Room Telephone room by mail room EAST SIDE	SQUARE D	112T3HF	33349-17222-001
FL0089ZZ-000000348	Transformer, Dry	DTT	01	PR	Floor 01 Electrical Equipment Room Telephone room by mail room EAST SIDE	SQUARE D	75T3HF	33349-17222-008
FL0089ZZ-000000349	Transformer, Dry	DTT	01	EE	Floor 01 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	75T3HF	33349-17222-008
FL0089ZZ-000000350	Transformer, Dry	DTT	01	EE	Floor 01 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	112T3HF	128710-2
FL0089ZZ-000000351	Transformer, Dry	DTT	01	EE	Floor 01 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	45T3H	33749-17212-030
FL0089ZZ-000000352	Transformer, Dry	DTT	01	MC	Floor 01 Mechanical Equipment Room Mechanical room WEST SIDE AHU 201	SIEMENS	3F3YO45	NO Serial #

FL0089ZZ-000000353	Transformer, Dry	DTT	01	MC	Floor 01 Mechanical Equipment Room Mechanical room WEST SIDE AHU 101,102	SQUARE D	30T3HF	33349-17222-006
FL0089ZZ-000000354	Transformer, Dry	DTT	01	MC	Floor 01 Mechanical Equipment Room Mechanical room WEST SIDE AHU 101,102	ACME	T-3-53313-3S	NO Serial #
FL0089ZZ-000000355	Transformer, Dry	DTT	02	PR	Floor 02 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	EE30T3H	NO Serial #
FL0089ZZ-000000356	Transformer, Dry	DTT	02	PR	Floor 02 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	75T3HF	34349-17222-008
FL0089ZZ-000000357	Transformer, Dry	DTT	03	PR	Floor 03 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	75T3HF	34349-17222-008
FL0089ZZ-000000358	Transformer, Dry	DTT	03	MC	Floor 03 Mechanical Equipment Room Mechanical room EAST SIDE	SQUARE D	30T3H	NO Serial #
FL0089ZZ-000000359	Transformer, Dry	DTT	03	MC	Floor 03 Mechanical Equipment Room Mechanical room EAST SIDE	SQUARE D	75T3H	NO Serial #
FL0089ZZ-000000360	Transformer, Dry	DTT	03	PR	Floor 03 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	45T3H	33749-17212-030
FL0089ZZ-000000361	Transformer, Dry	DTT	03	PR	Floor 03 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	75T3HF	34349-17222-008
FL0089ZZ-000000362	Transformer, Dry	DTT	03	PR	Floor 03 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	15T3H	NO Serial #
FL0089ZZ-000000363	Transformer, Dry	DTT	04	PR	Floor 04 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	75T3HF	34349-17222-008
FL0089ZZ-000000364	Transformer, Dry	DTT	04	PR	Floor 04 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	45T3H	33749-17212-030
FL0089ZZ-000000365	Transformer, Dry	DTT	04	PR	Floor 04 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	75T3HF	34349-17222-008
FL0089ZZ-000000366	Transformer, Dry	DTT	04	PR	Floor 04 Electrical Equipment Room Telephone room WEST SIDE	ACME	No Model #	A1 700949
FL0089ZZ-000000367	Transformer, Dry	DTT		CH	Penthouse Chiller Mechanical Room Chiller room	CHALLENGER	152-415	NO Serial #
FL0089ZZ-000000290	Panelboard, Power Distribution	EPB	01		Floor 01 Mechanical Equipment Room Back wall by prisoner elevator mach. Rm	SQUARE D	QW-40134-7H2	NO Serial #
FL0089ZZ-000000291	Panelboard, Power Distribution	EPB	01		Floor 01 Mechanical Equipment Room Back wall by prisoner elevator mach. Rm	SQUARE D	QW-40134-7H1	NO Serial #

FL0089ZZ-000000026	Exit Signs	EXS	01	ET	Floor 01 Lobby 1st floor esatside lobby	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000027	Exit Signs	EXS	01	ET	Floor 01 Lobby 1st floor eastside lobby	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000028	Exit Signs	EXS	01	101	Floor 01 Office ROOM 101	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000029	Exit Signs	EXS	01	KT	Floor 01 Food Service, Kitchen Room 102	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000030	Exit Signs	EXS	01	106	Floor 01 Office room 106	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000031	Exit Signs	EXS	01	106	Floor 01 Office Room 106	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000032	Exit Signs	EXS	01	108	Floor 01 Office Room 108	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000033	Exit Signs	EXS	01	108	Floor 01 Office Room 108	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000034	Exit Signs	EXS	01	108	Floor 01 Office Room 108	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000035	Exit Signs	EXS	01	109	Floor 01 Office Room 109	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000036	Exit Signs	EXS	01	109	Floor 01 Office Room 109	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000037	Exit Signs	EXS	01	11	Floor 01 Office Room 110	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000038	Exit Signs	EXS	01	11	Floor 01 Office Room 112	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000039	Exit Signs	EXS	01	11	Floor 01 Office Room 112	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000040	Exit Signs	EXS	01	11	Floor 01 Office Room 113	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000041	Exit Signs	EXS	01	11	Floor 01 Office Room 114	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000042	Exit Signs	EXS	01	11	Floor 01 Office Room 114	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000043	Exit Signs	EXS	01	12	Floor 01 Office Room 120	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000044	Exit Signs	EXS	01	13	Floor 01 Office Room 133	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000045	Exit Signs	EXS	01	13	Floor 01 Office Room 133	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000046	Exit Signs	EXS	01	13	Floor 01 Office Room 133	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000047	Exit Signs	EXS	01	14	Floor 01 Office Room 140	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000048	Exit Signs	EXS	01	14	Floor 01 Office Room 140	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000049	Exit Signs	EXS	01	14	Floor 01 Office Room 140	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000050	Exit Signs	EXS	01	20	Floor 01 Office Room 201	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000051	Exit Signs	EXS	02	20	Floor 02 Office Room 201	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000052	Exit Signs	EXS	02	20	Floor 02 Office Room 202 a	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000053	Exit Signs	EXS	02	20	Floor 02 Office Room 202 B	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000054	Exit Signs	EXS	02	20	Floor 02 Office Room 202 B	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000055	Exit Signs	EXS	02	20	Floor 02 Office Room 203 B	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000056	Exit Signs	EXS	02	20	Floor 02 Office Room 203 B	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000057	Exit Signs	EXS	02	20	Floor 02 Office Room 203 A	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000058	Exit Signs	EXS	02	20	Floor 02 Office Room 204 A	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000059	Exit Signs	EXS	02	20	Floor 02 Office Room 204 B	GILBERT	LEDX-1-FM	961028164

FL0089ZZ-000000060	Exit Signs	EXS	02	20	Floor 02 Office Room 204 B	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000061	Exit Signs	EXS	02	20	Floor 02 Office Room 205 D	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000062	Exit Signs	EXS	02	20	Floor 02 Office Room 205 D	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000063	Exit Signs	EXS	02	CR	Floor 02 Courtroom Courtroom for 205 D	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000064	Exit Signs	EXS	02	20	Floor 02 Office Room 205 E	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000065	Exit Signs	EXS	02	20	Floor 02 Office Room 205 F	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000066	Exit Signs	EXS	02	20	Floor 02 Office Room 205 F	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000067	Exit Signs	EXS	02	CR	Floor 02 Courtroom Courtroom for 205 F	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000068	Exit Signs	EXS	02	20	Floor 02 Office Room 207 A	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000069	Exit Signs	EXS	02	20	Floor 02 Office Room 207 A	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000070	Exit Signs	EXS	02	207B	Floor 02 Courtroom 207 B Courtroom	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000071	Exit Signs	EXS	02	ET	Floor 02 Lobby 2nd eastside lobby	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000072	Exit Signs	EXS	02	WT	Floor 02 Lobby 2nd westsdie lobby	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000073	Exit Signs	EXS	03	ET	Floor 03 Lobby 3rd floor eastside lobby	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000074	Exit Signs	EXS	03	WT	Floor 03 Lobby 3rd floor westside lobby	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000075	Exit Signs	EXS	03	30	Floor 03 Office Room 302	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000076	Exit Signs	EXS	03	30	Floor 03 Office Room 302	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000077	Exit Signs	EXS	03	30	Floor 03 Office Room 306	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000078	Exit Signs	EXS	03	30	Floor 03 Office Room 306	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000079	Exit Signs	EXS	03	30	Floor 03 Office Room 308	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000080	Exit Signs	EXS	03	31	Floor 03 Office Room 310	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000081	Exit Signs	EXS	03	31	Floor 03 Office Room 310	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000082	Exit Signs	EXS	03	31	Floor 03 Office Room 312	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000083	Exit Signs	EXS	03	31	Floor 03 Office Room 312	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000084	Exit Signs	EXS	03	31	Floor 03 Office Room 312	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000085	Exit Signs	EXS	03	31	Floor 03 Office Room 314	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000086	Exit Signs	EXS	03	32	Floor 03 Office Room 320	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000087	Exit Signs	EXS	03	32	Floor 03 Office Room 322	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000088	Exit Signs	EXS	03	32	Floor 03 Office Room 323	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000089	Exit Signs	EXS	03	32	Floor 03 Office Room 326	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000090	Exit Signs	EXS	04	WT	Floor 04 Lobby 4th floor westside lobby	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000091	Exit Signs	EXS	04	ET	Floor 04 Lobby 4th floor eastside lobby	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000092	Exit Signs	EXS	04	40	Floor 04 Office Room 401	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000093	Exit Signs	EXS	04	40	Floor 04 Office Room 401	GILBERT	LEDX-1-FM	961028164

FL0089ZZ-000000094	Exit Signs	EXS	04	40	Floor 04 Office Room 403	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000095	Exit Signs	EXS	04	40	Floor 04 Office Room 403	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000096	Exit Signs	EXS	04	40	Floor 04 Office Room 404	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000097	Exit Signs	EXS	04	40	Floor 04 Office Room 404	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000098	Exit Signs	EXS	04	40	Floor 04 Office Room 405	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000099	Exit Signs	EXS	04	40	Floor 04 Office Room 405	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000100	Exit Signs	EXS	04	40	Floor 04 Office Room 406	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000101	Exit Signs	EXS	04	40	Floor 04 Office Room 407	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000102	Exit Signs	EXS	04	40	Floor 04 Office Room 408	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000103	Exit Signs	EXS	04	40	Floor 04 Office Room 409	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000104	Exit Signs	EXS	04	40	Floor 04 Office Room 409	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000105	Exit Signs	EXS	04	OF	Floor 04 Office Room 410	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000106	Exit Signs	EXS	04	41	Floor 04 Office Room 410	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000107	Exit Signs	EXS	04	41	Floor 04 Office Room 410	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000108	Exit Signs	EXS	04	41	Floor 04 Office Room 411	GILBERT	LEDX-1-FM	961028164
FL0089ZZ-000000109	Expansion Tank	EXT		CH	Penthouse Chiller Mechanical Room hanging above chiller	n/a	No Model #	No Serial #
FL0089ZZ-000000125	Fire Door - Sliding & Rolling	FDR-02	01	OT	Floor 01 Outside 1st floor westside	No Name	No Model #	No Serial #
FL0089ZZ-000000126	Fire Door - Sliding & Rolling	FDR-02	02	OT	Floor 02 Outside 2nd floor westside	No Name	No Model #	No Serial #
FL0089ZZ-000000127	Fire Door - Sliding & Rolling	FDR-02	02	OT	Floor 02 Outside 2nd floor eastside	No Name	No Model #	No Serial #
FL0089ZZ-000000128	Fire Door - Sliding & Rolling	FDR-02	03	OT	Floor 03 Outside 3rd floor westside	No Name	No Model #	No Serial #
FL0089ZZ-000000129	Fire Extinguishers	FEX	01	10	Floor 01 Office Room 108	Buckeye	M-1OHI SA ABC	JP00715587
FL0089ZZ-000000130	Fire Extinguishers	FEX	01	10	Floor 01 Office Room 108	Buckeye	M-1OHI SA ABC	F00320664
FL0089ZZ-000000131	Fire Extinguishers	FEX	01	10	Floor 01 Office Room 108	Buckeye	M-1OHI SA ABC	LW80664
FL0089ZZ-000000132	Fire Extinguishers	FEX	01	10	Floor 01 Office Room 109	Buckeye	M-1OHI SA ABC	LW808803
FL0089ZZ-000000133	Fire Extinguishers	FEX	01	11	Floor 01 Office Room 114	Buckeye	M-1OHI SA ABC	JP00715462
FL0089ZZ-000000134	Fire Extinguishers	FEX	01	MS	Floor 01 Office Marshall's GYM	Buckeye	M-1OHI SA ABC	JP00715586
FL0089ZZ-000000135	Fire Extinguishers	FEX	01	14	Floor 01 Office Room 140	Buckeye	M-1OHI SA ABC	KN00023253
FL0089ZZ-000000136	Fire Extinguishers	FEX	01	14	Floor 01 Office Room 140	Buckeye	M-1OHI SA ABC	KN08923262
FL0089ZZ-000000137	Fire Extinguishers	FEX	01	14	Floor 01 Office Room 140	Buckeye	M-1OHI SA ABC	KE90837914
FL0089ZZ-000000138	Fire Extinguishers	FEX	01	ET	Floor 01 Lobby 1steastside elevator lobby	Buckeye	M-1OHI SA ABC	JX90396393
FL0089ZZ-000000139	Fire Extinguishers	FEX	01	WT	Floor 01 Lobby 1st westside entrance lobby	Buckeye	M-1OHI SA ABC	JX00396373
FL0089ZZ-000000140	Fire Extinguishers	FEX	01	WT	Floor 01 Lobby 1st westsideelevator lobby	Buckeye	M-1OHI SA ABC	JX00396395

FL0089ZZ-000000141	Fire Extinguishers	FEX	01	MC	Floor 01 Mechanical Equipment Room Mechanical room northwestside 1st floor	Buckeye	M-1OHI SA ABC	CB223748
FL0089ZZ-000000142	Fire Extinguishers	FEX	01	MC	Floor 01 Mechanical Equipment Room Mechanical room southwest side 1st floor	Buckeye	M-1OHI SA ABC	KF00329666
FL0089ZZ-000000143	Fire Extinguishers	FEX	01	EV	Floor 01 Mechanical Equipment Room 1st floor elevator room	Buckeye	M-1OHI SA ABC	JX6636387
FL0089ZZ-000000144	Fire Extinguishers	FEX	02	JU	Floor 02 Office 2nd Jurry assembly room 201	Buckeye	M-1OHI SA ABC	JX00396386
FL0089ZZ-000000145	Fire Extinguishers	FEX	02	OF	Floor 02 Office Judge Snow	Buckeye	M-1OHI SA ABC	CY152958
FL0089ZZ-000000146	Fire Extinguishers	FEX	02	OF	Floor 02 Office Judge Gunzalez	Buckeye	M-1OHI SA ABC	JX00396398
FL0089ZZ-000000147	Fire Extinguishers	FEX	02	OF	Floor 02 Office Judge Dimitrouleas	Buckeye	M-1OHI SA ABC	JX00396374
FL0089ZZ-000000148	Fire Extinguishers	FEX	02	WT	Floor 02 Lobby 2nd floor westside Elevator lobby	Buckeye	M-1OHI SA ABC	CA307832
FL0089ZZ-000000149	Fire Extinguishers	FEX	02	WT	Floor 02 Lobby 2nd floor westside Elevator lobby	Buckeye	M-1OHI SA ABC	KF09328651
FL0089ZZ-000000150	Fire Extinguishers	FEX	02	WT	Floor 02 Lobby 2nd floor westside Elevator lobby	Buckeye	M-1OHI SA ABC	KF90329650
FL0089ZZ-000000151	Fire Extinguishers	FEX	02	SW	Floor 02 Stairwell #2 2nd floor westside stairwell	Buckeye	M-1OHI SA ABC	KF00320656
FL0089ZZ-000000152	Fire Extinguishers	FEX	02	ET	Floor 02 Lobby 2nd eastside elevator lobby	Buckeye	M-1OHI SA ABC	JX00396397
FL0089ZZ-000000153	Fire Extinguishers	FEX	02	WT	Floor 02 Mechanical Equipment Room 2nd westside mechanicale room	Buckeye	M-1OHI SA ABC	KF693155
FL0089ZZ-000000154	Fire Extinguishers	FEX	02	ET	Floor 02 Mechanical Equipment Room 2nd eastside mechanical room	Buckeye	M-1OHI SA ABC	944015
FL0089ZZ-000000155	Fire Extinguishers	FEX	03	ET	Floor 03 Office 3rd floor eastside G.S.A. room 302	Buckeye	M-1OHI SA ABC	KF00320640
FL0089ZZ-000000156	Fire Extinguishers	FEX	03	ET	Floor 03 Office 3rd floor eastside Judge Ray room 306	Buckeye	M-1OHI SA ABC	JX00356388
FL0089ZZ-000000157	Fire Extinguishers	FEX	03	ET	Floor 03 Office 3rd east side DCAA room 322	Buckeye	M-1OHI SA ABC	JX00396394
FL0089ZZ-000000158	Fire Extinguishers	FEX	03	MS	Floor 03 Mechanical Equipment Room 3rd floor Marshall's cell block mech rm 312	Buckeye	M-1OHI SA ABC	CY153942
FL0089ZZ-000000159	Fire Extinguishers	FEX	03	ET	Floor 03 Lobby 3rd floor eastside lobby	Buckeye	M-1OHI SA ABC	CY153703
FL0089ZZ-000000160	Fire Extinguishers	FEX	03	WT	Floor 03 Lobby 3rd floor westside lobby	Buckeye	M-1OHI SA ABC	LW805339
FL0089ZZ-000000161	Fire Extinguishers	FEX	03	SW	Floor 03 Stairwell #3 3rd floor westside stairs	Buckeye	M-1OHI SA ABC	CA307811
FL0089ZZ-000000162	Fire Extinguishers	FEX	03	ET	Floor 03 Mechanical Equipment Room 3rd Floor eastside mech room	Buckeye	M-1OHI SA ABC	CY153384

FL0089ZZ-000000163	Fire Extinguishers	FEX	03	WT	Floor 03 Mechanical Equipment Room 3rd Floor westside mech room	Buckeye	M-1OHI SA ABC	KFO0320660
FL0089ZZ-000000164	Fire Extinguishers	FEX	04	41	Floor 04 Office 4th floor room 410 by the door	Buckeye	M-1OHI SA ABC	JX00396385
FL0089ZZ-000000165	Fire Extinguishers	FEX	04	409	Floor 04 Office 4th floor room 409 by font door	Buckeye	M-1OHI SA ABC	KF96329670
FL0089ZZ-000000166	Fire Extinguishers	FEX	04	408	Floor 04 Office 4th floor room 408 back of office	Buckeye	M-1OHI SA ABC	KF90329654
FL0089ZZ-000000167	Fire Extinguishers	FEX	04	408	Floor 04 Office 4th floor room 408 right of office	Buckeye	M-1OHI SA ABC	JP90715574
FL0089ZZ-000000168	Fire Extinguishers	FEX	04	406	Floor 04 Office 4th floor room 406 front of office	Buckeye	M-1OHI SA ABC	CB223746
FL0089ZZ-000000169	Fire Extinguishers	FEX	04	405	Floor 04 Office 4th floor room 405 front office on left	Buckeye	M-1OHI SA ABC	CY153960
FL0089ZZ-000000170	Fire Extinguishers	FEX	04	405	Floor 04 Office 4th floor room 405 over sink in hallway	Buckeye	M-1OHI SA ABC	CY458317
FL0089ZZ-000000171	Fire Extinguishers	FEX	04	405	Floor 04 Office 4th floor room 405 middle collum in back	Buckeye	M-1OHI SA ABC	CY550814
FL0089ZZ-000000172	Fire Extinguishers	FEX	04	405	Floor 04 Office 4th floor room 405 next to back door	Buckeye	M-1OHI SA ABC	CY007841
FL0089ZZ-000000173	Fire Extinguishers	FEX	04	404	Floor 04 Office 4th floor room 404 by front door	Buckeye	M-1OHI SA ABC	JPOO715573
FL0089ZZ-000000174	Fire Extinguishers	FEX	04	ET	Floor 04 Lobby 4th floor eastside lobby	Buckeye	M-1OHI SA ABC	KF00320671
FL0089ZZ-000000175	Fire Extinguishers	FEX	04	WT	Floor 04 Lobby 4th floor westside lobby	Buckeye	M-1OHI SA ABC	JX00396400
FL0089ZZ-000000176	Fire Extinguishers	FEX	04	SW	Floor 04 Stairwell #4 4th floor westside stairs	Buckeye	M-1OHI SA ABC	KF00320666
FL0089ZZ-000000177	Fire Extinguishers	FEX	04	WT	Floor 04 Mechanical Equipment Room 4th Floor westside mech room	Buckeye	M-1OHI SA ABC	HU784413
FL0089ZZ-000000178	Fire Extinguishers	FEX	04	ET	Floor 04 Mechanical Equipment Room 4th Floor eastside mech room	Buckeye	M-1OHI SA ABC	JX09396381
FL0089ZZ-000000179	Fire Extinguishers	FEX		CH	Penthouse Chiller Mechanical Room Roof chiller room by the door	Buckeye	M-1OHI SA ABC	LW806693
FL0089ZZ-000000180	Fire Extinguishers	FEX		ET	Penthouse Chiller Mechanical Room Roof eastside elevator mech room	Buckeye	M-1OHI SA ABC	KFO032984
FL0089ZZ-000000181	Fire Extinguishers	FEX		WT	Penthouse Chiller Mechanical Room Roof westside elevator mech room	Buckeye	M-1OHI SA ABC	CY115303
FL0089ZZ-000000182	Fire Extinguishers	FEX		PK	Basement, 1st Level Office Office parking eastside	Buckeye	M-1OHI SA ABC	CA307795
FL0089ZZ-000000183	Fire Extinguishers	FEX		PK	Basement, 1st Level Office Office parking eastside	Buckeye	M-1OHI SA ABC	KF60320674
FL0089ZZ-000000184	Fire Extinguishers	FEX		PK	Basement, 1st Level Office Office parking eastside	Buckeye	M-1OHI SA ABC	CY153945
FL0089ZZ-000000185	Fire Pump, Electric-Drive	FPM-01	01	MC	Floor 01 Mechanical Equipment Room Mechanical room westside 1st floor	No Name	No Model #	No Serial #

FL0089ZZ-000000186	Fire Pump, Electric-Drive	FPM-01	01	MC	Floor 01 Mechanical Equipment Room Mechanical room westside 1st floor	Lineguard Dripproof	TV-2629	1780491
FL0089ZZ-000000187	Fuel-Gas Detection Sensors	GDS		CH	Penthouse Chiller Mechanical Room Mounted on wall southeast corner	Chillgard	TGM4-Chillgard	133888-7
FL0089ZZ-000000188	Fuel-Gas Detection Sensors	GDS		CH	Penthouse Chiller Mechanical Room Mounted on wall southeast corner	Chillgard	UNTGSR221K	134563-28
FL0089ZZ-000000189	Fuel-Gas Detection Sensors	GDS		CH	Penthouse Chiller Mechanical Room Mounted on wall southeast corner	Chillgard	4955-1280	No Serial #
FL0089ZZ-000000190	Fuel-Gas Detection Sensors	GDS	01	OF	Floor 01 1ST FLOOR FPS OFFICE ROOM 104	PNEUMERATOR	LC1001	A2813-2
FL0089ZZ-000000191	Motor	MOT		CH	Penthouse Mechanical Equipment Room Chiller room condencer	BALDOR	No Model #	No Serial #
FL0089ZZ-000000192	Motor	MOT		CH	Penthouse Mechanical Equipment Room Chiller room condencer	BALDOR	No Model #	No Serial #
FL0089ZZ-000000193	Motor	MOT		CH	Penthouse Mechanical Equipment Room Chiller room chilled water	U. S. ELECTR	R352	No Serial #
FL0089ZZ-000000194	Motor	MOT		CH	Penthouse Mechanical Equipment Room Chiller room chilled water	BALDOR	No Model #	No Serial #
FL0089ZZ-000000195	Motor	MOT		COOLINGT	Penthouse Mechanical Equipment Room Cooling tower	BALDOR	No Model #	No Serial #
FL0089ZZ-000000196	Motor	MOT		COOLINGT	Penthouse Mechanical Equipment Room Cooling tower	BALDOR	No Model #	No Serial #
FL0089ZZ-000000197	Motor	MOT	01	MC	Floor 01 Mechanical Equipment Room AHU 101	BALDOR		
FL0089ZZ-000000198	Motor	MOT	01	MC	Floor 01 Mechanical Equipment Room AHU102	BALDOR		
FL0089ZZ-000000199	Motor	MOT	01	MC	Floor 01 Mechanical Equipment Room AHU 201	WEG	020180T3E256T	No Serial #
FL0089ZZ-000000200	Motor	MOT	03	MC	Floor 03 Mechanical Equipment Room AHU 202	GE	5K49PN8049	No Serial #
FL0089ZZ-000000201	Motor	MOT	03	MC	Floor 03 Mechanical Equipment Room AHU 203	BALDOR	5K49PN8050	No Serial #
FL0089ZZ-000000202	Motor	MOT	03	MC	Floor 03 Mechanical Equipment Room AHU 205	MARATHON	JQH56T17D3302 A P	No Serial #
FL0089ZZ-000000203	Motor	MOT	02	MC	Floor 02 Mechanical Equipment Room AHU 206	BALDOR	No Model #	No Serial #
FL0089ZZ-000000204	Motor	MOT	03	MC	Floor 03 Mechanical Equipment Room AHU 301	BALDOR	No Model #	No Serial #
FL0089ZZ-000000205	Motor	MOT	03	MC	Floor 03 Mechanical Equipment Room AHU 302	A.O. SMITH	07-850721-01-OJ	No Serial #
FL0089ZZ-000000206	Motor	MOT	04	MC	Floor 04 Mechanical Equipment Room AHU 401	U. S. ELECTR	No Model #	No Serial #

FL0089ZZ-000000207	Motor	MOT	04	MC	Floor 04 Mechanical Equipment Room AHU 402	BALDOR	No Model #	No Serial #
FL0089ZZ-000000208	Motor	MOT		MC	Penthouse Mechanical Equipment Room AHU 501	BALDOR	No Model #	No Serial #
FL0089ZZ-000000209	Motor	MOT		MC	Penthouse Mechanical Equipment Room AHU 502	BALDOR	No Model #	No Serial #
FL0089ZZ-000000210	Motor	MOT		CH	Roof Outside CHILLER ROOM ROOF	DAYTON	4HX85A	No Serial #
FL0089ZZ-000000211	Motor	MOT			Roof Outside ROOF	DAYTON	4HX85A	No Serial #
FL0089ZZ-000000212	Motor	MOT			Roof Outside ROOF	DAYTON	4HX85A	No Serial #
FL0089ZZ-000000292	Pump	PMP			Basement, 1st Level Next to Judges elevator on the west side garage	GENERAL ELEC	5KC38LG923	NO Serial #
FL0089ZZ-000000293	Pump, Chemical Feed	PMP		CH	Penthouse Chiller Mechanical Room mounted on wall behind condeser pumps	Olmi	DC4000-1	20020415500
FL0089ZZ-000000294	Pump, Chemical Feed	PMP		CH	Penthouse Chiller Mechanical Room mounted on wall behind condeser pumps	Olmi	P151-392TI	990212850
FL0089ZZ-000000295	Pump, Chilled Water	PMP-02		CH	Penthouse Chiller Mechanical Room CHILLER ROOM	TACO	No Model #	No Serial #
FL0089ZZ-000000296	Pump, Chilled Water	PMP-02		CH	Penthouse Chiller Mechanical Room CHILLER ROOM	TACO	No Model #	No Serial #
FL0089ZZ-000000297	Pump, Condensate	PMP-03	03	CC	Floor 03 Control Center Under air handler rm 312	LITTLE GIANT	VCMA-20ULS	No Serial #
FL0089ZZ-000000298	Pump, Condenser	PMP-06		CH	Penthouse Chiller Mechanical Room CHILLER ROOM	TACO	E3008E2H1E2L0A	No Serial #
FL0089ZZ-000000299	Pump, Condenser	PMP-06		CH	Penthouse Chiller Mechanical Room CHILLER ROOM	TACO	E3008E2H1E2L0A	No Serial #
FL0089ZZ-000000215	Panelboard, Lighting & Appliance	PNB	01	CA	Floor 01 Electrical Equipment Room Inside café equipment room	SQUARE D	NQOB-46456-2B	NO Serial #
FL0089ZZ-000000216	Panelboard, Lighting & Appliance	PNB	01	CA	Floor 01 Electrical Equipment Room Inside café equipment room	SQUARE D	QOC12	NO Serial #
FL0089ZZ-000000217	Panelboard, Lighting & Appliance	PNB	01	PR	Floor 01 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	HCN-40134-6G2	NO Serial #
FL0089ZZ-000000218	Panelboard, Lighting & Appliance	PNB	01	PR	Floor 01 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NQOB-40134-3C	NO Serial #
FL0089ZZ-000000219	Panelboard, Lighting & Appliance	PNB	01	PR	Floor 01 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NQOB-40134-5F	NO Serial #
FL0089ZZ-000000220	Panelboard, Lighting & Appliance	PNB	01	PR	Floor 01 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	30072-001-33B	NO Serial #
FL0089ZZ-000000221	Panelboard, Lighting & Appliance	PNB	01	PR	Floor 01 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NQOB-40134-4E	NO Serial #

FL0089ZZ-000000222	Panelboard, Lighting & Appliance	PNB	01	PR	Floor 01 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	HCM-40134-6G7	NO Serial #
FL0089ZZ-000000223	Panelboard, Lighting & Appliance	PNB	01	PR	Floor 01 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NQOB-40134-4E	NO Serial #
FL0089ZZ-000000224	Panelboard, Lighting & Appliance	PNB	01	PR	Floor 01 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NQOB-40134-4E	NO Serial #
FL0089ZZ-000000225	Panelboard, Lighting & Appliance	PNB	01	PR	Floor 01 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NH1B-40134-8J3	NO Serial #
FL0089ZZ-000000226	Panelboard, Lighting & Appliance	PNB	01	PR	Floor 01 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NQOB-40134-4D	NO Serial #
FL0089ZZ-000000227	Panelboard, Lighting & Appliance	PNB	01	PR	Floor 01 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NQOB-40134-4D	NO Serial #
FL0089ZZ-000000228	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	40134-6G4	NO Serial #
FL0089ZZ-000000229	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	NQOB-40134	NO Serial #
FL0089ZZ-000000230	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	NQOB-40134-5F	NO Serial #
FL0089ZZ-000000231	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	NQOD-430L225CU	NO Serial #
FL0089ZZ-000000232	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	NH1B-40134-8J3	NO Serial #
FL0089ZZ-000000233	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	NQOB-40134-4D	NO Serial #
FL0089ZZ-000000234	Panelboard, Lighting & Appliance	PNB	01	EE	Floor 01 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	NQOB-40134-4E	NO Serial #
FL0089ZZ-000000235	Panelboard, Lighting & Appliance	PNB	01	MC	Floor 01 Mechanical Equipment Room Mechanical room 201	SQUARE D	HCM-40134-6G1	NO Serial #
FL0089ZZ-000000236	Panelboard, Lighting & Appliance	PNB	01	MC	Floor 01 Mechanical Equipment Room Mechanical room 201	SQUARE D	30072-151-36	NO Serial #
FL0089ZZ-000000237	Panelboard, Lighting & Appliance	PNB	01	MC	Floor 01 Mechanical Equipment Room Mechanical room 201	SIEMENS	I1X42MC25OC	NO Serial #
FL0089ZZ-000000238	Panelboard, Lighting & Appliance	PNB	01	PR	Floor 01 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	NQOB-124	NO Serial #

FL0089ZZ-000000239	Panelboard, Lighting & Appliance	PNB	01	MC	Floor 01 Mechanical Equipment Room Mechanical room 101,102	SQUARE D	QOC16	NO Serial #
FL0089ZZ-000000240	Panelboard, Lighting & Appliance	PNB	01	MC	Floor 01 Mechanical Equipment Room Mechanical room 101,102	SQUARE D	NQOB-40134-9K2	NO Serial #
FL0089ZZ-000000241	Panelboard, Lighting & Appliance	PNB	01	MC	Floor 01 Mechanical Equipment Room Mechanical room 101,102	SQUARE D	NQOB-40134-4E	NO Serial #
FL0089ZZ-000000242	Panelboard, Lighting & Appliance	PNB	01	MC	Floor 01 Mechanical Equipment Room Mechanical room 101,102	SQUARE D	NQOB-40134-5F	NO Serial #
FL0089ZZ-000000243	Panelboard, Lighting & Appliance	PNB	01	MC	Floor 01 Mechanical Equipment Room Mechanical room 101,102	SQUARE D	NQOB-40134-4D	NO Serial #
FL0089ZZ-000000244	Panelboard, Lighting & Appliance	PNB	01	MC	Floor 01 Mechanical Equipment Room Mechanical room 101,102	SQUARE D	B-40274-194-01	NO Serial #
FL0089ZZ-000000245	Panelboard, Lighting & Appliance	PNB	01	MC	Floor 01 Mechanical Equipment Room Mechanical room 101,102	SQUARE D	B-40274-225-01	NO Serial #
FL0089ZZ-000000246	Panelboard, Lighting & Appliance	PNB	01	MC	Floor 01 Mechanical Equipment Room Mechanical room 101,102	I.T.E	G1624ML1125	NO Serial #
FL0089ZZ-000000247	Panelboard, Lighting & Appliance	PNB	02	PR	Floor 02 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NQ43OL1C	NO Serial #
FL0089ZZ-000000248	Panelboard, Lighting & Appliance	PNB	02	PR	Floor 02 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NQOB-40134-9K1	NO Serial #
FL0089ZZ-000000249	Panelboard, Lighting & Appliance	PNB	02	EE	Floor 02 Electrical Equipment Room Electrical room EAST SIDE	SQUARE D	NQOB-40134-5F	NO Serial #
FL0089ZZ-000000250	Panelboard, Lighting & Appliance	PNB	02	EE	Floor 02 Electrical Equipment Room Electrical room EAST SIDE	SQUARE D	NQOB-40134-5F	NO Serial #
FL0089ZZ-000000251	Panelboard, Lighting & Appliance	PNB	02	EE	Floor 02 Electrical Equipment Room Electrical room EAST SIDE	SQUARE D	HCM-40134-6G7	NO Serial #
FL0089ZZ-000000252	Panelboard, Lighting & Appliance	PNB	02	EE	Floor 02 Electrical Equipment Room Electrical room EAST SIDE	SQUARE D	NH1B-40134-8J4	NO Serial #
FL0089ZZ-000000253	Panelboard, Lighting & Appliance	PNB	02	EE	Floor 02 Electrical Equipment Room Electrical room EAST SIDE	ChALLENGER	3SB15(30-42)S	NO Serial #
FL0089ZZ-000000254	Panelboard, Lighting & Appliance	PNB	02	EE	Floor 02 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	NQOB-40134-5F	NO Serial #
FL0089ZZ-000000255	Panelboard, Lighting & Appliance	PNB	02	EE	Floor 02 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	NQOB-40134-4E	NO Serial #

FL0089ZZ-000000256	Panelboard, Lighting & Appliance	PNB	02	EE	Floor 02 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	NQOD430OL100	NO Serial #
FL0089ZZ-000000257	Panelboard, Lighting & Appliance	PNB	02	EE	Floor 02 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	HCM-40134-6G6	NO Serial #
FL0089ZZ-000000258	Panelboard, Lighting & Appliance	PNB	02	EE	Floor 02 Electrical Equipment Room Electrical room WEST SIDE	SQUARE D	NH1B-40134-8J3	NO Serial #
FL0089ZZ-000000259	Panelboard, Lighting & Appliance	PNB	03	PR	Floor 03 Electrical Equipment Room Telephone room EAST SIDE	CHALLENGER	YS2036	NO Serial #
FL0089ZZ-000000260	Panelboard, Lighting & Appliance	PNB	03	PR	Floor 03 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NH1B-40134-8J4	NO Serial #
FL0089ZZ-000000261	Panelboard, Lighting & Appliance	PNB	03	PR	Floor 03 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NQOB-40134-4E	NO Serial #
FL0089ZZ-000000262	Panelboard, Lighting & Appliance	PNB	03	PR	Floor 03 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NQOB-40134-5F	NO Serial #
FL0089ZZ-000000263	Panelboard, Lighting & Appliance	PNB	03	MC	Floor 03 Mechanical Equipment Room Mechanical room EAST SIDE	SQUARE D	HCM-40134-6G9	NO Serial #
FL0089ZZ-000000264	Panelboard, Lighting & Appliance	PNB	03	MC	Floor 03 Mechanical Equipment Room Mechanical room EAST SIDE	SQUARE D	1221276312	NO Serial #
FL0089ZZ-000000265	Panelboard, Lighting & Appliance	PNB	03	MC	Floor 03 Mechanical Equipment Room Mechanical room EAST SIDE	SQUARE D	1221276312	NO Serial #
FL0089ZZ-000000266	Panelboard, Lighting & Appliance	PNB	03	PR	Floor 03 Electrical Equipment Room Telephone room WEST SIDE	SIEMENS	UBA30-24B	NO Serial #
FL0089ZZ-000000267	Panelboard, Lighting & Appliance	PNB	03	PR	Floor 03 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	NH1B-40134-8J3	NO Serial #
FL0089ZZ-000000268	Panelboard, Lighting & Appliance	PNB	03	PR	Floor 03 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	NQOB-40134-4E	NO Serial #
FL0089ZZ-000000269	Panelboard, Lighting & Appliance	PNB	03	PR	Floor 03 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	NQOB-40134-5F	NO Serial #
FL0089ZZ-000000270	Panelboard, Lighting & Appliance	PNB	03	PR	Floor 03 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	HCM-40134-6G5	NO Serial #
FL0089ZZ-000000271	Panelboard, Lighting & Appliance	PNB	03	PR	Floor 03 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	NQOD430OL225 CU	NO Serial #
FL0089ZZ-000000272	Panelboard, Lighting & Appliance	PNB	04	PR	Floor 04 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	HCM-40134-6G8	NO Serial #

FL0089ZZ-000000273	Panelboard, Lighting & Appliance	PNB	04	PR	Floor 04 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NQOB-40134-9K1	NO Serial #
FL0089ZZ-000000274	Panelboard, Lighting & Appliance	PNB	04	PR	Floor 04 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NQOB-40134-5F	NO Serial #
FL0089ZZ-000000275	Panelboard, Lighting & Appliance	PNB	04	PR	Floor 04 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NQOB-40134-4E	NO Serial #
FL0089ZZ-000000276	Panelboard, Lighting & Appliance	PNB	04	PR	Floor 04 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NQOD430M100 CU	NO Serial #
FL0089ZZ-000000277	Panelboard, Lighting & Appliance	PNB	04	PR	Floor 04 Electrical Equipment Room Telephone room EAST SIDE	SQUARE D	NH1B-40134-8J4	NO Serial #
FL0089ZZ-000000278	Panelboard, Lighting & Appliance	PNB	04	PR	Floor 04 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	QOC430M	NO Serial #
FL0089ZZ-000000279	Panelboard, Lighting & Appliance	PNB	04	PR	Floor 04 Electrical Equipment Room Telephone room WEST SIDE	GENERAL ELEC	AF25S	NO Serial #
FL0089ZZ-000000280	Panelboard, Lighting & Appliance	PNB	04	PR	Floor 04 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	NQOB-40134-5F	NO Serial #
FL0089ZZ-000000281	Panelboard, Lighting & Appliance	PNB	04	PR	Floor 04 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	NQOB-40134-4E	NO Serial #
FL0089ZZ-000000282	Panelboard, Lighting & Appliance	PNB	04	PR	Floor 04 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	HCM-40134-6G6	NO Serial #
FL0089ZZ-000000283	Panelboard, Lighting & Appliance	PNB	04	PR	Floor 04 Electrical Equipment Room Telephone room WEST SIDE	SQUARE D	NH1B-40134-8J4	NO Serial #
FL0089ZZ-000000284	Panelboard, Lighting & Appliance	PNB		CH	Penthouse Chiller Mechanical Room WEST SIDE	SQUARE D	NQOB-40134-5F	NO Serial #
FL0089ZZ-000000285	Panelboard, Lighting & Appliance	PNB		CH	Penthouse Chiller Mechanical Room WEST SIDE	SQUARE D	NH1B-40134-8J5	NO Serial #
FL0089ZZ-000000286	Panelboard, Lighting & Appliance	PNB		CH	Penthouse Chiller Mechanical Room WEST SIDE	SQUARE D	HCWM-40134-6G3	NO Serial #
FL0089ZZ-000000287	Panelboard, Lighting & Appliance	PNB		NW	Basement Electrical Equipment Room Northwest corner by prisoner entrance	SQUARE D	NQOB-40134-4E	NO Serial #
FL0089ZZ-000000288	Panelboard, Lighting & Appliance	PNB		NW	Basement Electrical Equipment Room Northwest corner by prisoner entrance	SQUARE D	NH1B-40134-8J1	NO Serial #
FL0089ZZ-000000289	Panelboard, Lighting & Appliance	PNB		NW	Basement Electrical Equipment Room Northwest corner by prisoner entrance	SQUARE D	NH1B-40134-8J2	NO Serial #
FL0089ZZ-000000213	Package Unit, Air Cooled	RTU	04	RF	Floor 04 Outside Roof of Judge Zlock courtroom	CARRIER AIR	50HJ-008-SV521	1597G30430

FL0089ZZ-000000214	Package Unit, Air Cooled	RTU	04	RF	Floor 04 Outside Roof of Judge Gonzalez courtroom	CARRIER AIR	50HJ-006-V531	1009G40307
FL0089ZZ-000000300	Sump Pump	SMP		MC	Basement, 1st Level Mechanical Equipment Room South west corner of garage	DAYTON	3BB86	CFQ2108
FL0089ZZ-000000301	Sump Pump	SMP		EV	Basement, 1st Level Elevator Eastside Sump Pump	No Name	2AHS-051A	909
FL0089ZZ-000000302	Sump Pump	SMP		EV	Basement, 1st Level Elevator Westside Sump Pump	No Name	2AHS-051A	909
FL0089ZZ-000000303	Sump Pump	SMP		SW	Basement, 1st Level South west corner of garage in ground tank	No Name	No Model #	NO Serial #
FL0089ZZ-000000304	Sump Pump	SMP		SW	Basement, 1st Level South west corner of garage in ground tank	No Name	No Model #	NO Serial #
FL0089ZZ-000000305	Sump Pump	SMP		NE	Basement, 1st Level North east corner of garage in ground tank	No Name	No Model #	NO Serial #
FL0089ZZ-000000306	Sump Pump	SMP		NE	Basement, 1st Level North east corner of garage in ground tank	No Name	No Model #	NO Serial #
FL0089ZZ-000000307	Sump Pump	SMP		NW	Basement, 1st Level Northwest corner of garage next to diesel tank	Zoeller	No Model #	NO Serial #
FL0089ZZ-000000334	Switchboard, Electrical	SWB	01		Floor 01 Mechanical Equipment Room Back wall by prisoner elevator mach. Rm	SQUARE D	42-40134-1A	NO Serial #
FL0089ZZ-000000335	Switchboard, Electrical	SWB	01		Floor 01 Mechanical Equipment Room Back wall by prisoner elevator mach. Rm	SQUARE D	988439	NO Serial #
FL0089ZZ-000000336	Switchboard, Electrical	SWB	01		Floor 01 Mechanical Equipment Room Back wall by prisoner elevator mach. Rm	SQUARE D	988438	NO Serial #
FL0089ZZ-000000337	Switchboard, Electrical	SWB	01		Floor 01 Mechanical Equipment Room Back wall by prisoner elevator mach. Rm	SQUARE D	988437	NO Serial #
FL0089ZZ-000000338	Switchboard, Electrical	SWB	01		Floor 01 Mechanical Equipment Room Back wall by prisoner elevator mach. Rm	SQUARE D	988436	NO Serial #
FL0089ZZ-000000339	Switchboard, Electrical	SWB	01		Floor 01 Mechanical Equipment Room Back wall by prisoner elevator mach. Rm	SQUARE D	42-40134-2B	NO Serial #
FL0089ZZ-000000340	Switchboard, Electrical	SWB	01		Floor 01 Mechanical Equipment Room Back wall by prisoner elevator mach. Rm	SQUARE D	831552	NO Serial #
FL0089ZZ-000000341	Switchboard, Electrical	SWB	02	EE	Floor 02 Mechanical Equipment Room Electrical room EAST SIDE	Strand Century	A66614	NO Serial #
FL0089ZZ-000000342	Switchboard, Electrical	SWB	02	EE	Floor 02 Mechanical Equipment Room Electrical room WEST SIDE	Strand Century	A66614	NO Serial #

FL0089ZZ-000000343	Switchboard, Electrical	SWB	02	EE	Floor 02 Mechanical Equipment Room Electrical room WEST SIDE	Strand Century	A66614	NO Serial #
FL0089ZZ-000000344	Tank, Fuel	TNK-01		CH	Penthouse Chiller Mechanical Room Behind generator	simplx	No Model #	No Serial #
FL0089ZZ-000000345	Tank, Fuel	TNK-01		NW	Basement, 1st Level Northwest corner of garage diesel tank	Hoover	1000VT	NO Serial #
FL0089ZZ-TNK-00002	Tank, Size=1000, Contents: Diesel	TNK-01						
FL0089ZZ-TNK-00001	Tank, Contents: Diesel	UST						
FL0089ZZ-000000383	VAV (Variable Air Volume Boxes)	VAV	04		Floor 04	TITUS	ESV-3000	No Serial #
FL0089ZZ-000000384	VAV (Variable Air Volume Boxes)	VAV	04		Floor 04	SERIES 200	NO Model #	NO Serial #
FL0089ZZ-000000385	VAV (Variable Air Volume Boxes)	VAV	04		Floor 04	TITUS	PESV- 150	NO Serial #
FL0089ZZ-000000386	VAV (Variable Air Volume Boxes)	VAV	01	ET	Floor 01 Office 1ST FLOOR EASTSIDE LOBBY	No Name	No Model #	No Serial #
FL0089ZZ-000000387	VAV (Variable Air Volume Boxes)	VAV	01	CA	Floor 01 Office CAFÉ	No Name	No Model #	No Serial #
FL0089ZZ-000000388	VAV (Variable Air Volume Boxes)	VAV	01	101	Floor 01 Office ROOM 101	No Name	No Model #	No Serial #
FL0089ZZ-000000389	VAV (Variable Air Volume Boxes)	VAV	01	10	Floor 01 Office ROOM 104	No Name	No Model #	No Serial #
FL0089ZZ-000000390	VAV (Variable Air Volume Boxes)	VAV	01	10	Floor 01 Office ROOM 108	No Name	No Model #	No Serial #
FL0089ZZ-000000391	VAV (Variable Air Volume Boxes)	VAV	01	10	Floor 01 Office ROOM 108	No Name	No Model #	No Serial #
FL0089ZZ-000000392	VAV (Variable Air Volume Boxes)	VAV	01	10	Floor 01 Office ROOM 108	No Name	No Model #	No Serial #
FL0089ZZ-000000393	VAV (Variable Air Volume Boxes)	VAV	01	10	Floor 01 Office ROOM 108	No Name	No Model #	No Serial #
FL0089ZZ-000000394	VAV (Variable Air Volume Boxes)	VAV	01	10	Floor 01 Office ROOM 108	No Name	No Model #	No Serial #
FL0089ZZ-000000395	VAV (Variable Air Volume Boxes)	VAV	01	10	Floor 01 Office ROOM 108	No Name	No Model #	No Serial #
FL0089ZZ-000000396	VAV (Variable Air Volume Boxes)	VAV	01	10	Floor 01 Office ROOM 108	No Name	No Model #	No Serial #
FL0089ZZ-000000397	VAV (Variable Air Volume Boxes)	VAV	01	10	Floor 01 Office ROOM 108	No Name	No Model #	No Serial #
FL0089ZZ-000000398	VAV (Variable Air Volume Boxes)	VAV	01	10	Floor 01 Office ROOM 108	No Name	No Model #	No Serial #
FL0089ZZ-000000399	VAV (Variable Air Volume Boxes)	VAV	01	10	Floor 01 Office ROOM 108	No Name	No Model #	No Serial #
FL0089ZZ-000000400	VAV (Variable Air Volume Boxes)	VAV	01	109	Floor 01 Office ROOM109	No Name	No Model #	No Serial #
FL0089ZZ-000000401	VAV (Variable Air Volume Boxes)	VAV	01	10	Floor 01 Office ROOM 109	No Name	No Model #	No Serial #
FL0089ZZ-000000402	VAV (Variable Air Volume Boxes)	VAV	01	10	Floor 01 Office ROOM 109	No Name	No Model #	No Serial #
FL0089ZZ-000000403	VAV (Variable Air Volume Boxes)	VAV	01	14	Floor 01 Office ROOM 140	No Name	No Model #	No Serial #
FL0089ZZ-000000404	VAV (Variable Air Volume Boxes)	VAV	01	14	Floor 01 Office ROOM 141	No Name	No Model #	No Serial #
FL0089ZZ-000000405	VAV (Variable Air Volume Boxes)	VAV	01	11	Floor 01 Office ROOM 110	No Name	No Model #	No Serial #
FL0089ZZ-000000406	VAV (Variable Air Volume Boxes)	VAV	01	11	Floor 01 Office ROOM 110	No Name	No Model #	No Serial #
FL0089ZZ-000000407	VAV (Variable Air Volume Boxes)	VAV	01	11	Floor 01 Office ROOM 110	No Name	No Model #	No Serial #
FL0089ZZ-000000408	VAV (Variable Air Volume Boxes)	VAV	01	10	Floor 01 Office ROOM 109	No Name	No Model #	No Serial #
FL0089ZZ-000000409	VAV (Variable Air Volume Boxes)	VAV	01	11	Floor 01 Office ROOM 113	No Name	No Model #	No Serial #
FL0089ZZ-000000410	VAV (Variable Air Volume Boxes)	VAV	01	11	Floor 01 Office ROOM 113	No Name	No Model #	No Serial #
FL0089ZZ-000000411	VAV (Variable Air Volume Boxes)	VAV	01	11	Floor 01 Office ROOM 113	No Name	No Model #	No Serial #

FL0089ZZ-000000412	VAV (Variable Air Volume Boxes)	VAV	01	11	Floor 01 Office ROOM 113	No Name	No Model #	No Serial #
FL0089ZZ-000000413	VAV (Variable Air Volume Boxes)	VAV	01	11	Floor 01 Office ROOM 114	No Name	No Model #	No Serial #
FL0089ZZ-000000414	VAV (Variable Air Volume Boxes)	VAV	01	11	Floor 01 Office ROOM 114	No Name	No Model #	No Serial #
FL0089ZZ-000000415	VAV (Variable Air Volume Boxes)	VAV	01	13	Floor 01 Office ROOM 130	No Name	No Model #	No Serial #
FL0089ZZ-000000416	VAV (Variable Air Volume Boxes)	VAV	01	13	Floor 01 Office ROOM 130	No Name	No Model #	No Serial #
FL0089ZZ-000000417	VAV (Variable Air Volume Boxes)	VAV	01	12	Floor 01 Office ROOM 125	No Name	No Model #	No Serial #
FL0089ZZ-000000418	VAV (Variable Air Volume Boxes)	VAV	01	12	Floor 01 Office ROOM 120	No Name	No Model #	No Serial #
FL0089ZZ-000000419	VAV (Variable Air Volume Boxes)	VAV	01	12	Floor 01 Office ROOM 123	No Name	No Model #	No Serial #
FL0089ZZ-000000420	VAV (Variable Air Volume Boxes)	VAV	01	11	Floor 01 Office ROOM 112	No Name	No Model #	No Serial #
FL0089ZZ-000000421	VAV (Variable Air Volume Boxes)	VAV	01	11	Floor 01 Office ROOM 112	No Name	No Model #	No Serial #
FL0089ZZ-000000422	VAV (Variable Air Volume Boxes)	VAV	01	11	Floor 01 Office ROOM 112	No Name	No Model #	No Serial #
FL0089ZZ-000000423	VAV (Variable Air Volume Boxes)	VAV	01	11	Floor 01 Office ROOM 112	No Name	No Model #	No Serial #
FL0089ZZ-000000424	VAV (Variable Air Volume Boxes)	VAV	01	11	Floor 01 Office ROOM 112	No Name	No Model #	No Serial #
FL0089ZZ-000000425	VAV (Variable Air Volume Boxes)	VAV	01	11	Floor 01 Office ROOM 112	No Name	No Model #	No Serial #
FL0089ZZ-000000426	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 202B	No Name	No Model #	No Serial #
FL0089ZZ-000000427	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 202B	No Name	No Model #	No Serial #
FL0089ZZ-000000428	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 202B	No Name	No Model #	No Serial #
FL0089ZZ-000000429	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 202B	No Name	No Model #	No Serial #
FL0089ZZ-000000430	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 202B	No Name	No Model #	No Serial #
FL0089ZZ-000000431	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 202B	No Name	No Model #	No Serial #
FL0089ZZ-000000432	VAV (Variable Air Volume Boxes)	VAV	02	CR	Floor 02 Courtroom ROOM 202A	No Name	No Model #	No Serial #
FL0089ZZ-000000433	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 201	No Name	No Model #	No Serial #
FL0089ZZ-000000434	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 201	No Name	No Model #	No Serial #
FL0089ZZ-000000435	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 201	No Name	No Model #	No Serial #
FL0089ZZ-000000436	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 201	No Name	No Model #	No Serial #
FL0089ZZ-000000437	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 201	No Name	No Model #	No Serial #
FL0089ZZ-000000438	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 207B	No Name	No Model #	No Serial #
FL0089ZZ-000000439	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 207B	No Name	No Model #	No Serial #
FL0089ZZ-000000440	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 207B	No Name	No Model #	No Serial #
FL0089ZZ-000000441	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 207B	No Name	No Model #	No Serial #
FL0089ZZ-000000442	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 207B	No Name	No Model #	No Serial #
FL0089ZZ-000000443	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 207B	No Name	No Model #	No Serial #
FL0089ZZ-000000444	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 207B	No Name	No Model #	No Serial #
FL0089ZZ-000000445	VAV (Variable Air Volume Boxes)	VAV	02	CR	Floor 02 Courtroom ROOM 207A	No Name	No Model #	No Serial #

FL0089ZZ-000000446	VAV (Variable Air Volume Boxes)	VAV	02	CR	Floor 02 Courtroom ROOM 207A	No Name	No Model #	No Serial #
FL0089ZZ-000000447	VAV (Variable Air Volume Boxes)	VAV	02	CR	Floor 02 Courtroom ROOM 207A	No Name	No Model #	No Serial #
FL0089ZZ-000000448	VAV (Variable Air Volume Boxes)	VAV	02	CR	Floor 02 Courtroom ROOM 207A	No Name	No Model #	No Serial #
FL0089ZZ-000000449	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 207 JURRY	No Name	No Model #	No Serial #
FL0089ZZ-000000450	VAV (Variable Air Volume Boxes)	VAV	02	CR	Floor 02 Courtroom ROOM 204B	No Name	No Model #	No Serial #
FL0089ZZ-000000451	VAV (Variable Air Volume Boxes)	VAV	02	CR	Floor 02 Courtroom ROOM 204B	No Name	No Model #	No Serial #
FL0089ZZ-000000452	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 204A	No Name	No Model #	No Serial #
FL0089ZZ-000000453	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 204A	No Name	No Model #	No Serial #
FL0089ZZ-000000454	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 203A	No Name	No Model #	No Serial #
FL0089ZZ-000000455	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 203A	No Name	No Model #	No Serial #
FL0089ZZ-000000456	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 203A	No Name	No Model #	No Serial #
FL0089ZZ-000000457	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 203A	No Name	No Model #	No Serial #
FL0089ZZ-000000458	VAV (Variable Air Volume Boxes)	VAV	02	CR	Floor 02 Courtroom ROOM 203B	No Name	No Model #	No Serial #
FL0089ZZ-000000459	VAV (Variable Air Volume Boxes)	VAV	02	CR	Floor 02 Courtroom ROOM 203B	No Name	No Model #	No Serial #
FL0089ZZ-000000460	VAV (Variable Air Volume Boxes)	VAV	02	CR	Floor 02 Courtroom ROOM 203B	No Name	No Model #	No Serial #
FL0089ZZ-000000461	VAV (Variable Air Volume Boxes)	VAV	02	CR	Floor 02 Courtroom ROOM 203B	No Name	No Model #	No Serial #
FL0089ZZ-000000462	VAV (Variable Air Volume Boxes)	VAV	02	CR	Floor 02 Courtroom ROOM 203B	No Name	No Model #	No Serial #
FL0089ZZ-000000463	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 203B JURRY ROOM	No Name	No Model #	No Serial #
FL0089ZZ-000000464	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 205F	No Name	No Model #	No Serial #
FL0089ZZ-000000465	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 205F	No Name	No Model #	No Serial #
FL0089ZZ-000000466	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 205F	No Name	No Model #	No Serial #
FL0089ZZ-000000467	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 205F	No Name	No Model #	No Serial #
FL0089ZZ-000000468	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 205F	No Name	No Model #	No Serial #
FL0089ZZ-000000469	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 205F	No Name	No Model #	No Serial #
FL0089ZZ-000000470	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 205F JURRY ROOM	No Name	No Model #	No Serial #
FL0089ZZ-000000471	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 205D	No Name	No Model #	No Serial #
FL0089ZZ-000000472	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 205D	No Name	No Model #	No Serial #
FL0089ZZ-000000473	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 205D	No Name	No Model #	No Serial #
FL0089ZZ-000000474	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 205E	No Name	No Model #	No Serial #
FL0089ZZ-000000475	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 205E	No Name	No Model #	No Serial #
FL0089ZZ-000000476	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 205E	No Name	No Model #	No Serial #
FL0089ZZ-000000477	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 205E	No Name	No Model #	No Serial #
FL0089ZZ-000000478	VAV (Variable Air Volume Boxes)	VAV	02	20	Floor 02 Office ROOM 205E	No Name	No Model #	No Serial #

FL0089ZZ-000000479	VAV (Variable Air Volume Boxes)	VAV	02	WT	Floor 02 Lobby 2ND FLOOR WESTSIDE LOBBY	No Name	No Model #	No Serial #
FL0089ZZ-000000480	VAV (Variable Air Volume Boxes)	VAV	02	WT	Floor 02 Lobby 2ND FLOOR WESTSIDE LOBBY	No Name	No Model #	No Serial #
FL0089ZZ-000000481	VAV (Variable Air Volume Boxes)	VAV	02	WT	Floor 02 Lobby 2ND FLOOR WESTSIDE LOBBY	No Name	No Model #	No Serial #
FL0089ZZ-000000482	VAV (Variable Air Volume Boxes)	VAV	03	30	Floor 03 Office ROOM 302	No Name	No Model #	No Serial #
FL0089ZZ-000000483	VAV (Variable Air Volume Boxes)	VAV	03	30	Floor 03 Office ROOM 302	No Name	No Model #	No Serial #
FL0089ZZ-000000484	VAV (Variable Air Volume Boxes)	VAV	03	30	Floor 03 Office ROOM 302	No Name	No Model #	No Serial #
FL0089ZZ-000000485	VAV (Variable Air Volume Boxes)	VAV	03	30	Floor 03 Office ROOM 304	No Name	No Model #	No Serial #
FL0089ZZ-000000486	VAV (Variable Air Volume Boxes)	VAV	03	30	Floor 03 Office ROOM 306	No Name	No Model #	No Serial #
FL0089ZZ-000000487	VAV (Variable Air Volume Boxes)	VAV	03	30	Floor 03 Office ROOM 306	No Name	No Model #	No Serial #
FL0089ZZ-000000488	VAV (Variable Air Volume Boxes)	VAV	03	30	Floor 03 Office ROOM 306	No Name	No Model #	No Serial #
FL0089ZZ-000000489	VAV (Variable Air Volume Boxes)	VAV	03	30	Floor 03 Office ROOM 306	No Name	No Model #	No Serial #
FL0089ZZ-000000490	VAV (Variable Air Volume Boxes)	VAV	03	CR	Floor 03 Courtroom ROOM 308	No Name	No Model #	No Serial #
FL0089ZZ-000000491	VAV (Variable Air Volume Boxes)	VAV	03	CR	Floor 03 Courtroom ROOM 308	No Name	No Model #	No Serial #
FL0089ZZ-000000492	VAV (Variable Air Volume Boxes)	VAV	03	31	Floor 03 Office ROOM 312	No Name	No Model #	No Serial #
FL0089ZZ-000000493	VAV (Variable Air Volume Boxes)	VAV	03	31	Floor 03 Office ROOM 312	No Name	No Model #	No Serial #
FL0089ZZ-000000494	VAV (Variable Air Volume Boxes)	VAV	03	31	Floor 03 Office ROOM 312	No Name	No Model #	No Serial #
FL0089ZZ-000000495	VAV (Variable Air Volume Boxes)	VAV	03	31	Floor 03 Office ROOM 312	No Name	No Model #	No Serial #
FL0089ZZ-000000496	VAV (Variable Air Volume Boxes)	VAV	03	31	Floor 03 Office ROOM 312	No Name	No Model #	No Serial #
FL0089ZZ-000000497	VAV (Variable Air Volume Boxes)	VAV	03	31	Floor 03 Office ROOM 312	No Name	No Model #	No Serial #
FL0089ZZ-000000498	VAV (Variable Air Volume Boxes)	VAV	03	WT	Floor 03 Lobby 3RD FLOOR WESTSIDE ELEVATOR LOBBY	No Name	No Model #	No Serial #
FL0089ZZ-000000499	VAV (Variable Air Volume Boxes)	VAV	03	31	Floor 03 Office ROOM 314	No Name	No Model #	No Serial #
FL0089ZZ-000000500	VAV (Variable Air Volume Boxes)	VAV	03	32	Floor 03 Office ROOM 320	No Name	No Model #	No Serial #
FL0089ZZ-000000501	VAV (Variable Air Volume Boxes)	VAV	03	32	Floor 03 Office ROOM 320	No Name	No Model #	No Serial #
FL0089ZZ-000000502	VAV (Variable Air Volume Boxes)	VAV	03	LB	Floor 03 Lobby 322 LOBBY	No Name	No Model #	No Serial #
FL0089ZZ-000000503	VAV (Variable Air Volume Boxes)	VAV	03	32	Floor 03 Office ROOM 322	No Name	No Model #	No Serial #
FL0089ZZ-000000504	VAV (Variable Air Volume Boxes)	VAV	03	32	Floor 03 Office ROOM 322	No Name	No Model #	No Serial #
FL0089ZZ-000000505	VAV (Variable Air Volume Boxes)	VAV	03	33	Floor 03 Office ROOM 330	No Name	No Model #	No Serial #
FL0089ZZ-000000506	VAV (Variable Air Volume Boxes)	VAV	04	WT	Floor 04 Lobby 4TH FLOOR WESTSIDE ELEVATOR LOBBY	No Name	No Model #	No Serial #
FL0089ZZ-000000507	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 401	No Name	No Model #	No Serial #
FL0089ZZ-000000508	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 401	No Name	No Model #	No Serial #
FL0089ZZ-000000509	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 401	No Name	No Model #	No Serial #

FL0089ZZ-000000510	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 401	No Name	No Model #	No Serial #
FL0089ZZ-000000511	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 401	No Name	No Model #	No Serial #
FL0089ZZ-000000512	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 403	No Name	No Model #	No Serial #
FL0089ZZ-000000513	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 403	No Name	No Model #	No Serial #
FL0089ZZ-000000514	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 404	No Name	No Model #	No Serial #
FL0089ZZ-000000515	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 404	No Name	No Model #	No Serial #
FL0089ZZ-000000516	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 404	No Name	No Model #	No Serial #
FL0089ZZ-000000517	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 405	No Name	No Model #	No Serial #
FL0089ZZ-000000518	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 405	No Name	No Model #	No Serial #
FL0089ZZ-000000519	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 405	No Name	No Model #	No Serial #
FL0089ZZ-000000520	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 405	No Name	No Model #	No Serial #
FL0089ZZ-000000521	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 405	No Name	No Model #	No Serial #
FL0089ZZ-000000522	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 405	No Name	No Model #	No Serial #
FL0089ZZ-000000523	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 405	No Name	No Model #	No Serial #
FL0089ZZ-000000524	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 405	No Name	No Model #	No Serial #
FL0089ZZ-000000525	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 406	No Name	No Model #	No Serial #
FL0089ZZ-000000526	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 408	No Name	No Model #	No Serial #
FL0089ZZ-000000527	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 408	No Name	No Model #	No Serial #
FL0089ZZ-000000528	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 408	No Name	No Model #	No Serial #
FL0089ZZ-000000529	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 409	No Name	No Model #	No Serial #
FL0089ZZ-000000530	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 409	No Name	No Model #	No Serial #
FL0089ZZ-000000531	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 409	No Name	No Model #	No Serial #
FL0089ZZ-000000532	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 409	No Name	No Model #	No Serial #
FL0089ZZ-000000533	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 409	No Name	No Model #	No Serial #
FL0089ZZ-000000534	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 409	No Name	No Model #	No Serial #
FL0089ZZ-000000535	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 409	No Name	No Model #	No Serial #
FL0089ZZ-000000536	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 409	No Name	No Model #	No Serial #
FL0089ZZ-000000537	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 409	No Name	No Model #	No Serial #
FL0089ZZ-000000538	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 409	No Name	No Model #	No Serial #
FL0089ZZ-000000539	VAV (Variable Air Volume Boxes)	VAV	04	40	Floor 04 Office ROOM 409	No Name	No Model #	No Serial #
FL0089ZZ-000000540	VAV (Variable Air Volume Boxes)	VAV	04	41	Floor 04 Office ROOM 410	No Name	No Model #	No Serial #
FL0089ZZ-000000541	VAV (Variable Air Volume Boxes)	VAV	04	41	Floor 04 Office ROOM 410	No Name	No Model #	No Serial #
FL0089ZZ-000000542	VAV (Variable Air Volume Boxes)	VAV	04	41	Floor 04 Office ROOM 410	No Name	No Model #	No Serial #
FL0089ZZ-000000543	VAV (Variable Air Volume Boxes)	VAV	04	41	Floor 04 Office ROOM 411	No Name	No Model #	No Serial #

FL0089ZZ-000000374	Variable Frequency Drive	VFD		CH	Penthouse Chiller Mechanical Room Chilled water pumps	IDM CONTROLES P5 SERRIES	CIMR-P5U4015	No Serial #
FL0089ZZ-000000375	Variable Frequency Drive	VFD	01	MC	Floor 01 Mechanical Equipment Room AHU 101	TRANE	TR16042GT4CN 1STRODLF	050031H286
FL0089ZZ-000000376	Variable Frequency Drive	VFD	01	MC	Floor 01 Mechanical Equipment Room AHU 102	TRANE	TR16042GT4CN 1STRODLF	040931H246
FL0089ZZ-000000377	Variable Frequency Drive	VFD	01	MC	Floor 01 Mechanical Equipment Room AHU 201	IDM CONTROLES P5 SERRIES	CIMR-P5U4011	No Serial #
FL0089ZZ-000000378	Variable Frequency Drive	VFD	02	MC	Floor 02 Mechanical Equipment Room AHU 206	IDM CONTROLES P5 SERRIES	CIMR-P5U4015	No Serial #
FL0089ZZ-000000379	Variable Frequency Drive	VFD	03	MC	Floor 03 Mechanical Equipment Room AHU 301	IDM CONTROLES P5 SERRIES	CIMR-P5U47P5	No Serial #
FL0089ZZ-000000380	Variable Frequency Drive	VFD	03	MC	Floor 03 Mechanical Equipment Room AHU 302	TRANE	178B5548	047331H296
FL0089ZZ-000000381	Variable Frequency Drive	VFD	04	MC	Floor 04 Mechanical Equipment Room AHU 401	IDM CONTROLES P5 SERRIES	CIMR-P5U4015	No Serial #
FL0089ZZ-000000382	Variable Frequency Drive	VFD	04	MC	Floor 04 Mechanical Equipment Room AHU 402	IDM CONTROLES P5 SERRIES	CIMR-P5U4016	No Serial #
FL0089ZZ-000000368	Valves	VLV	01	MC	Floor 01 Mechanical Equipment Room Mechanical room westside 1st floor	Dresser kennedy	6-175	406095
FL0089ZZ-000000369	Valves	VLV	01	MC	Floor 01 Mechanical Equipment Room Mechanical room westside 1st floor	Dresser kennedy	6-176	406095
FL0089ZZ-000000370	Valves	VLV	01	MC	Floor 01 Mechanical Equipment Room Mechanical room westside 1st floor	Kuhns	FM-175W	No Serial #
FL0089ZZ-000000371	Valves	VLV	01	MC	Floor 01 Mechanical Equipment Room Mechanical room westside 1st floor	Kuhns	FM-175W	No Serial #
FL0089ZZ-000000372	Valves	VLV	01	MC	Floor 01 Mechanical Equipment Room Mechanical room westside 1st floor	Kuhns	FM-175W	No Serial #
FL0089ZZ-000000373	Valves	VLV	01	MC	Floor 01 Mechanical Equipment Room Mechanical room westside 1st floor	Kuhns	FM-175W	No Serial #
FL0089ZZ-000000544	Water Heater, Electric	WHT-01	01	ET	Floor 01 Restroom 1st floor eastside restrooms	INSTANT - FLOW	S-46IL	173202
FL0089ZZ-000000545	Water Heater, Electric	WHT-01	02	ET	Floor 02 Restroom 2nd floor eastside restrooms	RUDD	RP40-2	RU-1278M136
FL0089ZZ-000000546	Water Heater, Electric	WHT-01	03	ET	Floor 03 Restroom 3rd floor eastside restrooms	RHEEM	81V-300	R-0792B06097
FL0089ZZ-000000547	Water Heater, Electric	WHT-01	04	ET	Floor 04 Restroom 4th floor eastside restrooms	RHEEM	82V30-2	RH-0109B26276
FL0089ZZ-000000548	Water Heater, Electric	WHT-01	04	WT	Floor 04 Restroom 4th floor westside restrooms	RUDD	PE-30-2 A	RU-0489B29617

FL0089ZZ-000000549	Water Heater, Electric	WHT-01	03	WT	Floor 03 Restroom 3rd floor westside restrooms	HOTPOINT	HE40M01SAG	HP-1111B21458
FL0089ZZ-000000550	Water Heater, Electric	WHT-01	02	WT	Floor 02 Restroom 2nd floor westside restrooms	RUDD	RP-30-1	RDU-0578M33296
FL0089ZZ-000000551	Water Heater, Electric	WHT-01	01	WT	Floor 01 Restroom 1st floor westside restrooms	G.E	GE30T06AAG	GE-0112B011129

Date Run:

7/15/2014 2:52:12 PM

James L King Federal Justice Building FL1021ZZ O&M Only
99 NE 4th St
Miami, FL 33130
264768 Rentable square feet (rsf)

NATIONALCMMS
FOUNDATION FOR MAINTENANCE EXCELLENCE

Equipment List by Building and Equipment ID - Detail

Total Record Counts: 1065

Building: FL1021ZZ

FL1021ZZ-000000044	Condenser, Air-Cooled	ACC	GF	CC	FL1021ZZ-GF-Control Center CSO's Office	TRANE	TTP024C100A3	L412A21FF
FL1021ZZ-000000045	Condenser, Air-Cooled	ACC	GF	PL	FL1021ZZ-GF-Parking Lot Center North side of the building.	LIEBERT SYST	DCDF308-A	0905C18961
FL1021ZZ-000000046	Condenser, Air-Cooled	ACC	RF	WT	FL1021ZZ-RF-West	TRANE	2TTB3048A1000AA	723128A2F
FL1021ZZ-000000047	Condenser, Air-Cooled	ACC	RF	WT	FL1021ZZ-RF-West	TRANE	2TTB3048A1000AA	723127L2F
FL1021ZZ-000000002	Air Conditioner Package	ACU	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	YORK	N/A	N/A
FL1021ZZ-000000003	Air Conditioner Package	ACU	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	YORK	N/A	N/A
FL1021ZZ-000000004	Air Conditioner Package	ACU	02	204	FL1021ZZ-02-Office 204-Graphics Design	COIL COMPANY INC	6C18AC	3603681
FL1021ZZ-000000005	Air Conditioner Package	ACU	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room Not in Use (old equipment)	YORK	D2EA180A45A	NFAP100184
FL1021ZZ-000000006	Air Conditioner Package	ACU	RF	EV	FL1021ZZ-RF-Elevator / Mechanical Penthouse Elevator 7 Mechanical Room	YORK	D1HH024A06	KNXP124040
FL1021ZZ-000000007	Air Dryer	ADR	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	COMPRESSOR AIR DRYER	ACP25RD	0317A-1-9110-1210N
FL1021ZZ-000000036	Air Handling Unit, 3 ton thru 24 ton	AHU-01	GF	CC	FL1021ZZ-GF-Control Center CSO's Office	TRANE	TWE024P13FAO	N043WL41V
FL1021ZZ-000000037	Air Handling Unit, 3 ton thru 24 ton	AHU-01	RF	EV	FL1021ZZ-RF-Elevator / Mechanical Penthouse Elevator From 1-6 Mechanical room	TRANE	2TEC3F48B1000AA	7024KR32V
FL1021ZZ-000000038	Air Handling Unit, 3 ton thru 24 ton	AHU-01	RF	EV	FL1021ZZ-RF-Elevator / Mechanical Penthouse Elevator From 1-6 Mechanical room	TRANE	2TEC3F48B1000AA	71542KJ2V
FL1021ZZ-000000008	Air Handling Unit, 25 ton thru 50 ton	AHU-02	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	YORK	CS156VAF	91-824636A

FL1021ZZ-000000009	Air Handling Unit, 25 ton thru 50 ton	AHU-02	02	MC	FL1021ZZ-02-Mechanical Equipment Room	YORK	CS402SHAF D	91-824636E
FL1021ZZ-000000010	Air Handling Unit, 25 ton thru 50 ton	AHU-02	03	MC	FL1021ZZ-03-Mechanical Equipment Room	YORK	CS402SHAF D	91-824636F
FL1021ZZ-000000011	Air Handling Unit, 25 ton thru 50 ton	AHU-02	04	MC	FL1021ZZ-04-Mechanical Equipment Room	YORK	CS402SHAF D	91-824636G
FL1021ZZ-000000012	Air Handling Unit, 25 ton thru 50 ton	AHU-02	05	MC	FL1021ZZ-05-Mechanical Equipment Room	YORK	CS402SHAF D	91-824636H
FL1021ZZ-000000013	Air Handling Unit, 25 ton thru 50 ton	AHU-02	06	MC	FL1021ZZ-06-Mechanical Equipment Room	YORK	CS402SHAF	91-824636I
FL1021ZZ-000000014	Air Handling Unit, 25 ton thru 50 ton	AHU-02	07	MC	FL1021ZZ-07-Mechanical Equipment Room	YORK	N/A	N/A
FL1021ZZ-000000015	Air Handling Unit, 25 ton thru 50 ton	AHU-02	08	MC	FL1021ZZ-08-Mechanical Equipment Room	YORK	CS4402SHAF	91-824636K
FL1021ZZ-000000016	Air Handling Unit, 25 ton thru 50 ton	AHU-02	09	MC	FL1021ZZ-09-Mechanical Equipment Room	YORK	N/A	N/A
FL1021ZZ-000000017	Air Handling Unit, 25 ton thru 50 ton	AHU-02	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room	YORK	CS490FOAF D	91-824636B
FL1021ZZ-000000018	Air Handling Unit, 25 ton thru 50 ton	AHU-02	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room	YORK	CS490FOAF D	91-824636C
FL1021ZZ-000000019	Air Handling Unit, 25 ton thru 50 ton	AHU-02	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room	YORK	CS490FOAF D	91-8246360
FL1021ZZ-000000020	Air Handling Unit, 25 ton thru 50 ton	AHU-02	GF	MC	FL1021ZZ-GF-Mechanical Equipment Room	MARATHON	XVJ213TTDR7026GP	N/A
FL1021ZZ-000000021	Air Handling Unit, 25 ton thru 50 ton	AHU-02	02	MC	FL1021ZZ-02-Mechanical Equipment Room	CENTURY ELEC	6-357725-01	N/A
FL1021ZZ-000000022	Air Handling Unit, 25 ton thru 50 ton	AHU-02	03	MC	FL1021ZZ-03-Mechanical Equipment Room	CENTURY ELEC	6-357724-03	N/A
FL1021ZZ-000000023	Air Handling Unit, 25 ton thru 50 ton	AHU-02	04	MC	FL1021ZZ-04-Mechanical Equipment Room	CENTURY ELEC	6-357725-01	N/A
FL1021ZZ-000000024	Air Handling Unit, 25 ton thru 50 ton	AHU-02	05	MC	FL1021ZZ-05-Mechanical Equipment Room	CENTURY ELEC	6-357725-01	N/A
FL1021ZZ-000000025	Air Handling Unit, 25 ton thru 50 ton	AHU-02	06	MC	FL1021ZZ-06-Mechanical Equipment Room	CENTURY ELEC	6-357725-01	N/A
FL1021ZZ-000000026	Air Handling Unit, 25 ton thru 50 ton	AHU-02	07	MC	FL1021ZZ-07-Mechanical Equipment Room	CENTURY ELEC	6-357725-01	N/A
FL1021ZZ-000000027	Air Handling Unit, 25 ton thru 50 ton	AHU-02	08	MC	FL1021ZZ-08-Mechanical Equipment Room	CENTURY ELEC	6-357725-01	N/A
FL1021ZZ-000000028	Air Handling Unit, 25 ton thru 50 ton	AHU-02	09	MC	FL1021ZZ-09-Mechanical Equipment Room	CENTURY ELEC	6-357725-01	N/A
FL1021ZZ-000000029	Air Handling Unit, 25 ton thru 50 ton	AHU-02	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room	CENTURY ELEC	6-357934-01	N/A
FL1021ZZ-000000030	Air Handling Unit, 25 ton thru 50 ton	AHU-02	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room	CENTURY ELEC	6-357934-01	N/A
FL1021ZZ-000000031	Air Handling Unit, 25 ton thru 50 ton	AHU-02	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room	CENTURY ELEC	6-357934-01	N/A

FL1021ZZ-000000032	Air Handling Unit, 25 ton thru 50 ton	AHU-02	RF	ST	FL1021ZZ-RF-South	TOSHIBA	A1506BQJ3BM	N/A
FL1021ZZ-000000033	Air Handling Unit, 25 ton thru 50 ton	AHU-02	RF	ST	FL1021ZZ-RF-South	TOSHIBA	A1506BQJ3BM	N/A
FL1021ZZ-000000034	Air Handling Unit, 25 ton thru 50 ton	AHU-02	RF	NT	FL1021ZZ-RF-North	WEG	03089ES3QDP32 4V	N/A
FL1021ZZ-000000035	Air Handling Unit, 25 ton thru 50 ton	AHU-02	RF	NT	FL1021ZZ-RF-North	WEG	03089ES3QDP32 4V	N/A
FL1021ZZ-000000039	Air Handling Unit, Computer Room	AHU-04	02	CC	FL1021ZZ-02-Control Center 227-Computer Room	LIEBERT SYST	DS070ARA0E198 0A	C09A8E0219
FL1021ZZ-000000323	Fire Detection and Alarm System	ALM	GF	CC	FL1021ZZ-GF-Control Center CSO's Office	SIMPLEX	4100-8009	
FL1021ZZ-000000324	Fire Detection and Alarm System	ALM	GF	CC	FL1021ZZ-GF-Control Center Computer Room	SIMPLEX	4100-82001	
FL1021ZZ-000000667	Switch, Automatic Transfer	ATS	GF	EE	FL1021ZZ-GF-Electrical Equipment Room Nort Wall	ZENITH	ZTSH160FC-7AAC	192237
FL1021ZZ-000000668	Switch, Automatic Transfer	ATS	GF		FL1021ZZ-GF-Fire Pump Room	HUBBELL	2501155P	212045-1-1
FL1021ZZ-000000040	Backflow Prevention Device	BFP	B1	PL	FL1021ZZ-B1-Parking Lot Near Custodial office	WATTS	N/A	176034
FL1021ZZ-000000041	Backflow Prevention Device	BFP	GF	OT	FL1021ZZ-GF-Outside North-East	WATTS	709 DCDA	105445
FL1021ZZ-000000042	Chiller, Centrifugal, water cooled, over 100 tons	CHL-CW2	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	YORK	YTJ3K3E1-CNF	YAAM838074
FL1021ZZ-000000043	Chiller, Centrifugal, water cooled, over 100 tons	CHL-CW2	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	YORK	YTJ3K3E1-CNF	YAAM838236
FL1021ZZ-000000001	Air Compressor	CMP	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	CHALENGE	ES-100A	AS07020157
FL1021ZZ-000000048	Cooling Tower	CTR	RF	NT	FL1021ZZ-RF-North	MARLEY	NC 8306H-255	N/A
FL1021ZZ-000000049	Cooling Tower	CTR	RF	NT	FL1021ZZ-RF-North	MARLEY	NC 8306H-2SS	N/A
FL1021ZZ-000000669	Switch, Disconnect	DCT	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	FURNAS	15CF32A71	N/A
FL1021ZZ-000000670	Switch, Disconnect	DCT	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	SQUARE D	3141100DTO	C
FL1021ZZ-000000671	Switch, Disconnect	DCT	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	SQUARE D	3141100DTO	C
FL1021ZZ-000000672	Switch, Disconnect	DCT	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	SQUARE D	SFG33	C
FL1021ZZ-000000673	Switch, Disconnect	DCT	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	SQUARE D	SFG33	C
FL1021ZZ-000000674	Switch, Disconnect	DCT	GF		FL1021ZZ-GF-Fuel Tank Room	SQUARE D	SDG34	C
FL1021ZZ-000000675	Switch, Disconnect	DCT	GF	MC	FL1021ZZ-GF-Mechanical Equipment Room Domestic Water Pump	HOFFMAN	3R	N/A
FL1021ZZ-000000676	Switch, Disconnect	DCT	GF		FL1021ZZ-GF-Fire Pump Room	FIRETROL	FTA1250-AA100B	N/A
FL1021ZZ-000000677	Switch, Disconnect	DCT	GF		FL1021ZZ-GF-Fire Pump Room	PEERLESS	Z-212263	N/A
FL1021ZZ-000000678	Switch, Disconnect	DCT	GF	PL	FL1021ZZ-GF-Parking Lot Parking North side	SQUARE D	SDG33	
FL1021ZZ-000000679	Switch, Disconnect	DCT	GF	SP	FL1021ZZ-GF-Sally Port South Wall	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000680	Switch, Disconnect	DCT	02	EE	FL1021ZZ-02-Electrical Equipment Room East Wall	SQUARE D	CP2525G10	1
FL1021ZZ-000000681	Switch, Disconnect	DCT	02	EE	FL1021ZZ-02-Electrical Equipment Room East Wall	SQUARE D	CPH2512G10	1
FL1021ZZ-000000682	Switch, Disconnect	DCT	02	EE	FL1021ZZ-02-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000683	Switch, Disconnect	DCT	02	EE	FL1021ZZ-02-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5

FL1021ZZ-000000684	Switch, Disconnect	DCT	02	EE	FL1021ZZ-02-Electrical Equipment Room East Wall	SQUARE D	PS4620G	4
FL1021ZZ-000000685	Switch, Disconnect	DCT	03	EE	FL1021ZZ-03-Electrical Equipment Room East Wall	SQUARE D	CP2525G10	1
FL1021ZZ-000000686	Switch, Disconnect	DCT	03	EE	FL1021ZZ-03-Electrical Equipment Room East Wall	SQUARE D	CPH2512G10	1
FL1021ZZ-000000687	Switch, Disconnect	DCT	03	EE	FL1021ZZ-03-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000688	Switch, Disconnect	DCT	03	EE	FL1021ZZ-03-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000689	Switch, Disconnect	DCT	03	EE	FL1021ZZ-03-Electrical Equipment Room East Wall	SQUARE D	PS4620G	4
FL1021ZZ-000000690	Switch, Disconnect	DCT	04	EE	FL1021ZZ-04-Electrical Equipment Room East Wall	SQUARE D	CP2525G10	1
FL1021ZZ-000000691	Switch, Disconnect	DCT	04	EE	FL1021ZZ-04-Electrical Equipment Room East Wall	SQUARE D	CPH2512G10	1
FL1021ZZ-000000692	Switch, Disconnect	DCT	04	EE	FL1021ZZ-04-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000693	Switch, Disconnect	DCT	04	EE	FL1021ZZ-04-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000694	Switch, Disconnect	DCT	04	EE	FL1021ZZ-04-Electrical Equipment Room East Wall	SQUARE D	PS4620G	4
FL1021ZZ-000000695	Switch, Disconnect	DCT	05	EE	FL1021ZZ-05-Electrical Equipment Room East Wall	SQUARE D	CP2525G10	1
FL1021ZZ-000000696	Switch, Disconnect	DCT	05	EE	FL1021ZZ-05-Electrical Equipment Room East Wall	SQUARE D	CPH2512G10	1
FL1021ZZ-000000697	Switch, Disconnect	DCT	05	EE	FL1021ZZ-05-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000698	Switch, Disconnect	DCT	05	EE	FL1021ZZ-05-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000699	Switch, Disconnect	DCT	05	EE	FL1021ZZ-05-Electrical Equipment Room East Wall	SQUARE D	PS4620G	4
FL1021ZZ-000000700	Switch, Disconnect	DCT	06	EE	FL1021ZZ-06-Electrical Equipment Room East Wall	SQUARE D	CP2525G10	1
FL1021ZZ-000000701	Switch, Disconnect	DCT	06	EE	FL1021ZZ-06-Electrical Equipment Room East Wall	SQUARE D	CPH2512G10	1
FL1021ZZ-000000702	Switch, Disconnect	DCT	06	EE	FL1021ZZ-06-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000703	Switch, Disconnect	DCT	06	EE	FL1021ZZ-06-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000704	Switch, Disconnect	DCT	06	EE	FL1021ZZ-06-Electrical Equipment Room East Wall	SQUARE D	PS4620G	4
FL1021ZZ-000000705	Switch, Disconnect	DCT	07	EE	FL1021ZZ-07-Electrical Equipment Room East Wall	SQUARE D	CP2525G10	1
FL1021ZZ-000000706	Switch, Disconnect	DCT	07	EE	FL1021ZZ-07-Electrical Equipment Room East Wall	SQUARE D	CPH2512G10	1

FL1021ZZ-000000707	Switch, Disconnect	DCT	07	EE	FL1021ZZ-07-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000708	Switch, Disconnect	DCT	07	EE	FL1021ZZ-07-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000709	Switch, Disconnect	DCT	07	EE	FL1021ZZ-07-Electrical Equipment Room East Wall	SQUARE D	PS4620G	4
FL1021ZZ-000000710	Switch, Disconnect	DCT	08	EE	FL1021ZZ-08-Electrical Equipment Room East Wall	SQUARE D	CP2525G10	1
FL1021ZZ-000000711	Switch, Disconnect	DCT	08	EE	FL1021ZZ-08-Electrical Equipment Room East Wall	SQUARE D	CPH2512G10	1
FL1021ZZ-000000712	Switch, Disconnect	DCT	08	EE	FL1021ZZ-08-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000713	Switch, Disconnect	DCT	08	EE	FL1021ZZ-08-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000714	Switch, Disconnect	DCT	08	EE	FL1021ZZ-08-Electrical Equipment Room East Wall	SQUARE D	PS4620G	4
FL1021ZZ-000000715	Switch, Disconnect	DCT	09	EE	FL1021ZZ-09-Electrical Equipment Room East Wall	SQUARE D	CP2525G10	1
FL1021ZZ-000000716	Switch, Disconnect	DCT	09	EE	FL1021ZZ-09-Electrical Equipment Room East Wall	SQUARE D	CPH2512G10	1
FL1021ZZ-000000717	Switch, Disconnect	DCT	09	EE	FL1021ZZ-09-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000718	Switch, Disconnect	DCT	09	EE	FL1021ZZ-09-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000719	Switch, Disconnect	DCT	09	EE	FL1021ZZ-09-Electrical Equipment Room East Wall	SQUARE D	PS4620G	4
FL1021ZZ-000000720	Switch, Disconnect	DCT	10	EE	FL1021ZZ-10-Electrical Equipment Room East Wall	SQUARE D	CP2525G10	1
FL1021ZZ-000000721	Switch, Disconnect	DCT	10	EE	FL1021ZZ-10-Electrical Equipment Room East Wall	SQUARE D	CPH2512G10	1
FL1021ZZ-000000722	Switch, Disconnect	DCT	10	EE	FL1021ZZ-10-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000723	Switch, Disconnect	DCT	10	EE	FL1021ZZ-10-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000724	Switch, Disconnect	DCT	10	EE	FL1021ZZ-10-Electrical Equipment Room East Wall	SQUARE D	PS4620G	4
FL1021ZZ-000000725	Switch, Disconnect	DCT	11	EE	FL1021ZZ-11-Electrical Equipment Room East Wall	SQUARE D	CP2525G10	1
FL1021ZZ-000000726	Switch, Disconnect	DCT	11	EE	FL1021ZZ-11-Electrical Equipment Room East Wall	SQUARE D	CPH2512G10	1
FL1021ZZ-000000727	Switch, Disconnect	DCT	11	EE	FL1021ZZ-11-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000728	Switch, Disconnect	DCT	11	EE	FL1021ZZ-11-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000729	Switch, Disconnect	DCT	11	EE	FL1021ZZ-11-Electrical Equipment Room East Wall	SQUARE D	PS4620G	4

FL1021ZZ-000000730	Switch, Disconnect	DCT	12	EE	FL1021ZZ-12-Electrical Equipment Room East Wall	SQUARE D	CP2525G10	1
FL1021ZZ-000000731	Switch, Disconnect	DCT	12	EE	FL1021ZZ-12-Electrical Equipment Room East Wall	SQUARE D	CPH2512G10	1
FL1021ZZ-000000732	Switch, Disconnect	DCT	12	EE	FL1021ZZ-12-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000733	Switch, Disconnect	DCT	12	EE	FL1021ZZ-12-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000734	Switch, Disconnect	DCT	12	EE	FL1021ZZ-12-Electrical Equipment Room East Wall	SQUARE D	PS4620G	4
FL1021ZZ-000000735	Switch, Disconnect	DCT	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room AHU-10 Mechanical Room	SQUARE D	SBG-33-PER	C
FL1021ZZ-000000736	Switch, Disconnect	DCT	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room AHU-10 Mechanical Room	SQUARE D	SBG-33-PER	C
FL1021ZZ-000000737	Switch, Disconnect	DCT	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room AHU-10 Mechanical Room	SQUARE D	40274-301-01	C
FL1021ZZ-000000738	Switch, Disconnect	DCT	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room Not in Use (old equipment)	SQUARE D	40274-301-01	N/A
FL1021ZZ-000000739	Switch, Disconnect	DCT	RF	RF	FL1021ZZ-RF-Roof / Roof Installed Item Stairwell-1	SQUARE D	SBA43	3141100DRO
FL1021ZZ-000000740	Switch, Disconnect	DCT	RF	RF	FL1021ZZ-RF-Roof / Roof Installed Item Stairwell-2	SQUARE D	SBA43	3141100DRO
FL1021ZZ-000000741	Switch, Disconnect	DCT	RF	ET	FL1021ZZ-RF-East	SQUARE D	N/A	N/A
FL1021ZZ-000000742	Switch, Disconnect	DCT	RF	WT	FL1021ZZ-RF-West	SQUARE D	B-40274-855-01	N/A
FL1021ZZ-000000743	Switch, Disconnect	DCT	RF	NT	FL1021ZZ-RF-North	SQUARE D	B-40274-554-01	N/A
FL1021ZZ-000000744	Switch, Disconnect	DCT	RF	ET	FL1021ZZ-RF-East	SQUARE D	SBG33	3141100D00
FL1021ZZ-000000745	Switch, Disconnect	DCT	RF	ST	FL1021ZZ-RF-South	SQUARE D	B-40274-269-01	N/A
FL1021ZZ-000000746	Switch, Disconnect	DCT	RF	ST	FL1021ZZ-RF-South	SQUARE D	B-40274-269-01	N/A
FL1021ZZ-000000747	Switch, Disconnect	DCT	RF	NT	FL1021ZZ-RF-North	SQUARE D	N/A	N/A
FL1021ZZ-000000748	Switch, Disconnect	DCT	RF	NT	FL1021ZZ-RF-North	SQUARE D	N/A	N/A
FL1021ZZ-000000050	Deaerator Tank	DEA	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room		N/A	N/A
FL1021ZZ-000000753	Transformer, Dry	DTT	GF	EE	FL1021ZZ-GF-Electrical Equipment Room West Wall	SQUARE D	33349-17212-055	79TS22C
FL1021ZZ-000000754	Transformer, Dry	DTT	GF	EE	FL1021ZZ-GF-Electrical Equipment Room West Wall	SQUARE D	32749-17212-022	15T3H
FL1021ZZ-000000755	Transformer, Dry	DTT	GF	EE	FL1021ZZ-GF-Electrical Equipment Room West Wall	SQUARE D	33349-17212-055	79TS22C
FL1021ZZ-000000756	Transformer, Dry	DTT	GF	EE	FL1021ZZ-GF-Electrical Equipment Room Nort Wall	SQUARE D	32749-17212C-022	79TS22C
FL1021ZZ-000000757	Transformer, Dry	DTT	GF	EE	FL1021ZZ-GF-Electrical Equipment Room Nort Wall	SQUARE D	32749-17212C-022	79TS22C
FL1021ZZ-000000758	Transformer, Dry	DTT	02	EE	FL1021ZZ-02-Electrical Equipment Room West Wall	SQUARE D	32749-12212-036	79TS22C

FL1021ZZ-000000759	Transformer, Dry	DTT	02	EE	FL1021ZZ-02-Electrical Equipment Room East Wall	SQUARE D	34349-17212-064	69TS22C
FL1021ZZ-000000760	Transformer, Dry	DTT	03	EE	FL1021ZZ-03-Electrical Equipment Room West Wall	SQUARE D	32749-12212-036	79TS22C
FL1021ZZ-000000761	Transformer, Dry	DTT	03	EE	FL1021ZZ-03-Electrical Equipment Room East Wall	SQUARE D	34349-17212-064	69TS22C
FL1021ZZ-000000762	Transformer, Dry	DTT	04	EE	FL1021ZZ-04-Electrical Equipment Room West Wall	SQUARE D	32749-12212-036	79TS22C
FL1021ZZ-000000763	Transformer, Dry	DTT	04	EE	FL1021ZZ-04-Electrical Equipment Room East Wall	SQUARE D	34349-17212-064	69TS22C
FL1021ZZ-000000764	Transformer, Dry	DTT	05	EE	FL1021ZZ-05-Electrical Equipment Room West Wall	SQUARE D	32749-12212-036	79TS22C
FL1021ZZ-000000765	Transformer, Dry	DTT	05	EE	FL1021ZZ-05-Electrical Equipment Room East Wall	SQUARE D	34349-17212-064	69TS22C
FL1021ZZ-000000766	Transformer, Dry	DTT	06	EE	FL1021ZZ-06-Electrical Equipment Room West Wall	SQUARE D	32749-12212-036	79TS22C
FL1021ZZ-000000767	Transformer, Dry	DTT	06	EE	FL1021ZZ-06-Electrical Equipment Room East Wall	SQUARE D	34349-17212-064	69TS22C
FL1021ZZ-000000768	Transformer, Dry	DTT	07	EE	FL1021ZZ-07-Electrical Equipment Room West Wall	SQUARE D	32749-12212-036	79TS22C
FL1021ZZ-000000769	Transformer, Dry	DTT	07	EE	FL1021ZZ-07-Electrical Equipment Room East Wall	SQUARE D	34349-17212-064	69TS22C
FL1021ZZ-000000770	Transformer, Dry	DTT	08	EE	FL1021ZZ-08-Electrical Equipment Room West Wall	SQUARE D	32749-12212-036	79TS22C
FL1021ZZ-000000771	Transformer, Dry	DTT	08	EE	FL1021ZZ-08-Electrical Equipment Room East Wall	SQUARE D	34349-17212-064	69TS22C
FL1021ZZ-000000772	Transformer, Dry	DTT	09	EE	FL1021ZZ-09-Electrical Equipment Room West Wall	SQUARE D	32749-12212-036	79TS22C
FL1021ZZ-000000773	Transformer, Dry	DTT	09	EE	FL1021ZZ-09-Electrical Equipment Room East Wall	SQUARE D	34349-17212-064	69TS22C
FL1021ZZ-000000774	Transformer, Dry	DTT	10	EE	FL1021ZZ-10-Electrical Equipment Room West Wall	SQUARE D	32749-12212-036	79TS22C
FL1021ZZ-000000775	Transformer, Dry	DTT	10	EE	FL1021ZZ-10-Electrical Equipment Room East Wall	SQUARE D	34349-17212-064	69TS22C
FL1021ZZ-000000776	Transformer, Dry	DTT	11	EE	FL1021ZZ-11-Electrical Equipment Room West Wall	SQUARE D	32749-12212-036	79TS22C
FL1021ZZ-000000777	Transformer, Dry	DTT	11	EE	FL1021ZZ-11-Electrical Equipment Room East Wall	SQUARE D	34349-17212-064	69TS22C
FL1021ZZ-000000778	Transformer, Dry	DTT	12	EE	FL1021ZZ-12-Electrical Equipment Room West Wall	SQUARE D	32749-12212-036	79TS22C
FL1021ZZ-000000779	Transformer, Dry	DTT	12	EE	FL1021ZZ-12-Electrical Equipment Room East Wall	SQUARE D	34349-17212-064	69TS22C
FL1021ZZ-000000780	Transformer, Dry	DTT	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room AHU-11/12 Mechanical Room	SQUARE D	33749-17212-055	79TS22C

FL1021ZZ-000000075	Emergency Diesel Generator	EMG-01	GF	EG	FL1021ZZ-GF-Emergency Generator Room	CATERPILLAR	SR4	6NA02958
FL1021ZZ-000000498	Panelboard, Power Distribution	EPB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room Nort Wall	SQUARE D	3441100-PO	C-934046
FL1021ZZ-000000499	Panelboard, Power Distribution	EPB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room Nort Wall	SQUARE D	3441100-PO	C-934047
FL1021ZZ-000000500	Panelboard, Power Distribution	EPB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room South Wall	SQUARE D	314100	C-934050
FL1021ZZ-000000501	Panelboard, Power Distribution	EPB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room South Wall	SQUARE D	314100	C-931133
FL1021ZZ-000000502	Panelboard, Power Distribution	EPB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room South Wall	SQUARE D	314100	C-934058
FL1021ZZ-000000503	Panelboard, Power Distribution	EPB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room South Wall	SQUARE D	314100	C-934048
FL1021ZZ-000000504	Panelboard, Power Distribution	EPB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room South Wall	SQUARE D	314100	C-931132
FL1021ZZ-000000505	Panelboard, Power Distribution	EPB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room South Wall	SQUARE D	314100	C-934059
FL1021ZZ-000000506	Panelboard, Power Distribution	EPB	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room AHU-10 Mechanical Room	SQUARE D	12-3141100-RO	E1
FL1021ZZ-000000051	Drinking Fountain, Packaged	EWC	02	RRM	FL1021ZZ-02-Restroom Near Restroom	HAWS	HWBF8SS	92509077
FL1021ZZ-000000052	Drinking Fountain, Packaged	EWC	02	CA	FL1021ZZ-02-Near Cafeteria	HAWS	HCR8	92143236
FL1021ZZ-000000053	Drinking Fountain, Packaged	EWC	03	RRM	FL1021ZZ-03-Restroom Near Restroom	HAWS	HWBF8SS	92509048
FL1021ZZ-000000054	Drinking Fountain, Packaged	EWC	03		FL1021ZZ-03-Near Room-322	HAWS	HCR8	N/A
FL1021ZZ-000000055	Drinking Fountain, Packaged	EWC	04	RRM	FL1021ZZ-04-Restroom Near Restroom	HAWS	HWBF8SS	92509079
FL1021ZZ-000000056	Drinking Fountain, Packaged	EWC	04		FL1021ZZ-04-Near Room-422	HAWS	HCR8	93143002
FL1021ZZ-000000057	Drinking Fountain, Packaged	EWC	05	RRM	FL1021ZZ-05-Restroom Near Restroom	HAWS	HWBF8SS	95509078
FL1021ZZ-000000058	Drinking Fountain, Packaged	EWC	05		FL1021ZZ-05-Near Room-521	HAWS	HCR8	95271465
FL1021ZZ-000000059	Drinking Fountain, Packaged	EWC	06	RRM	FL1021ZZ-06-Restroom Near Restroom	HAWS	HWBF8SS	95509010
FL1021ZZ-000000060	Drinking Fountain, Packaged	EWC	06		FL1021ZZ-06-Near Room-622	HAWS	HCR8	93042041
FL1021ZZ-000000061	Drinking Fountain, Packaged	EWC	07	RRM	FL1021ZZ-07-Restroom Near Restroom	HAWS	HWBF8SS	N/A
FL1021ZZ-000000062	Drinking Fountain, Packaged	EWC	07		FL1021ZZ-07-Near Room-721	HAWS	HCR8	93042025
FL1021ZZ-000000063	Drinking Fountain, Packaged	EWC	08	RRM	FL1021ZZ-08-Restroom Near Restroom	HAWS	HWBF8SS	92509022
FL1021ZZ-000000064	Drinking Fountain, Packaged	EWC	08		FL1021ZZ-08-Near Room-821	HAWS	HCR8	93042030
FL1021ZZ-000000065	Drinking Fountain, Packaged	EWC	08		FL1021ZZ-08-Near Room-861	HAWS	HCR8	93042029
FL1021ZZ-000000066	Drinking Fountain, Packaged	EWC	09	RRM	FL1021ZZ-09-Restroom Near Restroom	HAWS	HWBF8SS	95509077
FL1021ZZ-000000067	Drinking Fountain, Packaged	EWC	09	AH	FL1021ZZ-09-Near Air Handler Mechanical Room	HAWS	HCR8	93042028
FL1021ZZ-000000068	Drinking Fountain, Packaged	EWC	09		FL1021ZZ-09-Near Assambley Room	HAWS	HCR8	93042023

FL1021ZZ-000000069	Drinking Fountain, Packaged	EWC	10		FL1021ZZ-10-Near Room 1036	HAWS	HCR8	93042020
FL1021ZZ-000000070	Drinking Fountain, Packaged	EWC	10	RRM	FL1021ZZ-10-Restroom Near Restroom	HAWS	HWBF8SS	920828874
FL1021ZZ-000000071	Drinking Fountain, Packaged	EWC	11	RRM	FL1021ZZ-11-Restroom Near Restroom	HAWS	HWBF8SS	920828876
FL1021ZZ-000000072	Drinking Fountain, Packaged	EWC	11		FL1021ZZ-11-Near Room-1135	HAWS	HCR8	93042027
FL1021ZZ-000000073	Drinking Fountain, Packaged	EWC	12	RRM	FL1021ZZ-12-Restroom Near Restroom	HAWS	HWBF8SS	N/A
FL1021ZZ-000000074	Drinking Fountain, Packaged	EWC	12		FL1021ZZ-12-Near Room-1223	HAWS	HWFRC8	T10R92H26
FL1021ZZ-000000076	Exit Signs	EXS	B1	EV	FL1021ZZ-B1-Elevator Lobby	UDEC	USE-100	N/A
FL1021ZZ-000000077	Exit Signs	EXS	B1	EV	FL1021ZZ-B1-Elevator Lobby	UDEC	USE-100	N/A
FL1021ZZ-000000078	Exit Signs	EXS	B1	EV	FL1021ZZ-B1-Elevator Lobby	UDEC	USE-100	N/A
FL1021ZZ-000000079	Exit Signs	EXS	B1	EV	FL1021ZZ-B1-Elevator Lobby	UDEC	USE-100	N/A
FL1021ZZ-000000080	Exit Signs	EXS	B1	SW	FL1021ZZ-B1-Stairwell #1 Stair 1	UDEC	USE-100	N/A
FL1021ZZ-000000081	Exit Signs	EXS	B1	SW	FL1021ZZ-B1-Stairwell #2 Stair 2	UDEC	USE-100	N/A
FL1021ZZ-000000082	Exit Signs	EXS	B1	SW	FL1021ZZ-B1-Stairwell #2 Stair 2	UDEC	USE-100	N/A
FL1021ZZ-000000083	Exit Signs	EXS	B1	SW	FL1021ZZ-B1-Stairwell #2 Stair 2	UDEC	USE-100	N/A
FL1021ZZ-000000084	Exit Signs	EXS	B1	CD	FL1021ZZ-B1-East Corridor	UDEC	USE-100	N/A
FL1021ZZ-000000085	Exit Signs	EXS	B1	CD	FL1021ZZ-B1-East Corridor	UDEC	USE-100	N/A
FL1021ZZ-000000086	Exit Signs	EXS	GF	LB	FL1021ZZ-GF-Lobby North	UDEC	USE-100	N/A
FL1021ZZ-000000087	Exit Signs	EXS	GF	LB	FL1021ZZ-GF-Lobby North	UDEC	USE-100	N/A
FL1021ZZ-000000088	Exit Signs	EXS	GF	LB	FL1021ZZ-GF-Lobby south	UDEC	USE-100	N/A
FL1021ZZ-000000089	Exit Signs	EXS	GF	DR	FL1021ZZ-GF-Front Door	UDEC	USE-100	N/A
FL1021ZZ-000000090	Exit Signs	EXS	GF	DR	FL1021ZZ-GF-East Door	UDEC	USE-100	N/A
FL1021ZZ-000000091	Exit Signs	EXS	GF	MS	FL1021ZZ-GF-Marshall's Ofice	UDEC	USE-100	N/A
FL1021ZZ-000000092	Exit Signs	EXS	GF	MS	FL1021ZZ-GF-Marshall's Ofice	UDEC	USE-100	N/A
FL1021ZZ-000000093	Exit Signs	EXS	GF	OF	FL1021ZZ-GF-CSO's Office	UDEC	USE-100	N/A
FL1021ZZ-000000094	Exit Signs	EXS	GF		FL1021ZZ-GF-Near safety room	UDEC	USE-100	N/A
FL1021ZZ-000000095	Exit Signs	EXS	GF		FL1021ZZ-GF-Near Pump Room	UDEC	USE-100	N/A
FL1021ZZ-000000096	Exit Signs	EXS	GF	EN-ST	FL1021ZZ-GF-South Entrance	UDEC	USE-100	N/A
FL1021ZZ-000000097	Exit Signs	EXS	GF	CD	FL1021ZZ-GF-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000098	Exit Signs	EXS	GF	CD	FL1021ZZ-GF-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000099	Exit Signs	EXS	GF	CD	FL1021ZZ-GF-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000100	Exit Signs	EXS	GF	CF-NT	FL1021ZZ-GF-North Conference Room	UDEC	USE-100	N/A
FL1021ZZ-000000101	Exit Signs	EXS	GF	CD	FL1021ZZ-GF-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000102	Exit Signs	EXS	GF	CD	FL1021ZZ-GF-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000103	Exit Signs	EXS	GF	CD	FL1021ZZ-GF-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000104	Exit Signs	EXS	02	SW-1	FL1021ZZ-02-Stair 1	UDEC	USE-100	N/A

FL1021ZZ-000000105	Exit Signs	EXS	02	SW-2	FL1021ZZ-02-Stair 2	UDEC	USE-100	N/A
FL1021ZZ-000000106	Exit Signs	EXS	02	RE	FL1021ZZ-02-Reception	UDEC	USE-100	N/A
FL1021ZZ-000000107	Exit Signs	EXS	02	ST	FL1021ZZ-02-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000108	Exit Signs	EXS	02	ST	FL1021ZZ-02-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000109	Exit Signs	EXS	02	CD	FL1021ZZ-02-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000110	Exit Signs	EXS	02	CD	FL1021ZZ-02-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000111	Exit Signs	EXS	02	ST	FL1021ZZ-02-South Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000112	Exit Signs	EXS	02	ST	FL1021ZZ-02-South Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000113	Exit Signs	EXS	02	EN	FL1021ZZ-02-East Entrance	UDEC	USE-100	N/A
FL1021ZZ-000000114	Exit Signs	EXS	02	EN-ST	FL1021ZZ-02-South Entrance	UDEC	USE-100	N/A
FL1021ZZ-000000115	Exit Signs	EXS	02	CD	FL1021ZZ-02-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000116	Exit Signs	EXS	02	CD	FL1021ZZ-02-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000117	Exit Signs	EXS	02	CD	FL1021ZZ-02-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000118	Exit Signs	EXS	02	CF-NT	FL1021ZZ-02-North Conference Room	UDEC	USE-100	N/A
FL1021ZZ-000000119	Exit Signs	EXS	02	CD	FL1021ZZ-02-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000120	Exit Signs	EXS	02	CD	FL1021ZZ-02-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000121	Exit Signs	EXS	02	CD	FL1021ZZ-02-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000122	Exit Signs	EXS	03	SW-1	FL1021ZZ-03-Stair 1	UDEC	USE-100	N/A
FL1021ZZ-000000123	Exit Signs	EXS	03	SW-2	FL1021ZZ-03-Stair 2	UDEC	USE-100	N/A
FL1021ZZ-000000124	Exit Signs	EXS	03	RE	FL1021ZZ-03-Reception	UDEC	USE-100	N/A
FL1021ZZ-000000125	Exit Signs	EXS	03	ST	FL1021ZZ-03-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000126	Exit Signs	EXS	03	ST	FL1021ZZ-03-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000127	Exit Signs	EXS	03	CD	FL1021ZZ-03-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000128	Exit Signs	EXS	03	CD	FL1021ZZ-03-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000129	Exit Signs	EXS	03	ST	FL1021ZZ-03-South Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000130	Exit Signs	EXS	03	ST	FL1021ZZ-03-South Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000131	Exit Signs	EXS	03	EN	FL1021ZZ-03-East Entrance	UDEC	USE-100	N/A
FL1021ZZ-000000132	Exit Signs	EXS	03	EN-ST	FL1021ZZ-03-South Entrance	UDEC	USE-100	N/A
FL1021ZZ-000000133	Exit Signs	EXS	03	CD	FL1021ZZ-03-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000134	Exit Signs	EXS	03	CD	FL1021ZZ-03-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000135	Exit Signs	EXS	03	CD	FL1021ZZ-03-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000136	Exit Signs	EXS	03	CF-NT	FL1021ZZ-03-North Conference Room	UDEC	USE-100	N/A
FL1021ZZ-000000137	Exit Signs	EXS	03	CD	FL1021ZZ-03-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000138	Exit Signs	EXS	03	CD	FL1021ZZ-03-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000139	Exit Signs	EXS	03	CD	FL1021ZZ-03-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000140	Exit Signs	EXS	04	SW-1	FL1021ZZ-04-Stair 1	UDEC	USE-100	N/A
FL1021ZZ-000000141	Exit Signs	EXS	04	SW-2	FL1021ZZ-04-Stair 2	UDEC	USE-100	N/A

FL1021ZZ-000000142	Exit Signs	EXS	04	RE	FL1021ZZ-04-Reception	UDEC	USE-100	N/A
FL1021ZZ-000000143	Exit Signs	EXS	04	ST	FL1021ZZ-04-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000144	Exit Signs	EXS	04	ST	FL1021ZZ-04-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000145	Exit Signs	EXS	04	CD	FL1021ZZ-04-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000146	Exit Signs	EXS	04	CD	FL1021ZZ-04-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000147	Exit Signs	EXS	04	ST	FL1021ZZ-04-South Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000148	Exit Signs	EXS	04	ST	FL1021ZZ-04-South Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000149	Exit Signs	EXS	04	EN	FL1021ZZ-04-East Entrance	UDEC	USE-100	N/A
FL1021ZZ-000000150	Exit Signs	EXS	04	EN-ST	FL1021ZZ-04-South Entrance	UDEC	USE-100	N/A
FL1021ZZ-000000151	Exit Signs	EXS	04	CD	FL1021ZZ-04-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000152	Exit Signs	EXS	04	CD	FL1021ZZ-04-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000153	Exit Signs	EXS	04	CD	FL1021ZZ-04-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000154	Exit Signs	EXS	04	CF-NT	FL1021ZZ-04-North Conference Room	UDEC	USE-100	N/A
FL1021ZZ-000000155	Exit Signs	EXS	04	CD	FL1021ZZ-04-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000156	Exit Signs	EXS	04	CD	FL1021ZZ-04-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000157	Exit Signs	EXS	04	CD	FL1021ZZ-04-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000158	Exit Signs	EXS	05	SW-1	FL1021ZZ-05-Stair 1	UDEC	USE-100	N/A
FL1021ZZ-000000159	Exit Signs	EXS	05	SW-2	FL1021ZZ-05-Stair 2	UDEC	USE-100	N/A
FL1021ZZ-000000160	Exit Signs	EXS	05	RE	FL1021ZZ-05-Reception	UDEC	USE-100	N/A
FL1021ZZ-000000161	Exit Signs	EXS	05	ST	FL1021ZZ-05-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000162	Exit Signs	EXS	05	ST	FL1021ZZ-05-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000163	Exit Signs	EXS	05	CD	FL1021ZZ-05-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000164	Exit Signs	EXS	05	CD	FL1021ZZ-05-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000165	Exit Signs	EXS	05	ST	FL1021ZZ-05-South Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000166	Exit Signs	EXS	05	ST	FL1021ZZ-05-South Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000167	Exit Signs	EXS	05	EN	FL1021ZZ-05-East Entrance	UDEC	USE-100	N/A
FL1021ZZ-000000168	Exit Signs	EXS	05	EN-ST	FL1021ZZ-05-South Entrance	UDEC	USE-100	N/A
FL1021ZZ-000000169	Exit Signs	EXS	05	CD	FL1021ZZ-05-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000170	Exit Signs	EXS	05	CD	FL1021ZZ-05-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000171	Exit Signs	EXS	05	CD	FL1021ZZ-05-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000172	Exit Signs	EXS	05	CF-NT	FL1021ZZ-05-North Conference Room	UDEC	USE-100	N/A
FL1021ZZ-000000173	Exit Signs	EXS	05	CD	FL1021ZZ-05-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000174	Exit Signs	EXS	05	CD	FL1021ZZ-05-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000175	Exit Signs	EXS	05	CD	FL1021ZZ-05-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000176	Exit Signs	EXS	06	SW-1	FL1021ZZ-06-Stair 1	UDEC	USE-100	N/A
FL1021ZZ-000000177	Exit Signs	EXS	06	SW-2	FL1021ZZ-06-Stair 2	UDEC	USE-100	N/A

FL1021ZZ-000000178	Exit Signs	EXS	06	RE	FL1021ZZ-06-Reception	UDEC	USE-100	N/A
FL1021ZZ-000000179	Exit Signs	EXS	06	ST	FL1021ZZ-06-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000180	Exit Signs	EXS	06	ST	FL1021ZZ-06-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000181	Exit Signs	EXS	06	CD	FL1021ZZ-06-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000182	Exit Signs	EXS	06	CD	FL1021ZZ-06-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000183	Exit Signs	EXS	06	ST	FL1021ZZ-06-South Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000184	Exit Signs	EXS	06	ST	FL1021ZZ-06-South Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000185	Exit Signs	EXS	06	EN	FL1021ZZ-06-East Entrance	UDEC	USE-100	N/A
FL1021ZZ-000000186	Exit Signs	EXS	06	EN-ST	FL1021ZZ-06-South Entrance	UDEC	USE-100	N/A
FL1021ZZ-000000187	Exit Signs	EXS	06	CD	FL1021ZZ-06-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000188	Exit Signs	EXS	06	CD	FL1021ZZ-06-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000189	Exit Signs	EXS	06	CD	FL1021ZZ-06-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000190	Exit Signs	EXS	06	CF-NT	FL1021ZZ-06-North Conference Room	UDEC	USE-100	N/A
FL1021ZZ-000000191	Exit Signs	EXS	06	CD	FL1021ZZ-06-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000192	Exit Signs	EXS	06	CD	FL1021ZZ-06-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000193	Exit Signs	EXS	06	CD	FL1021ZZ-06-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000194	Exit Signs	EXS	07	SW-1	FL1021ZZ-07-Stair 1	UDEC	USE-100	N/A
FL1021ZZ-000000195	Exit Signs	EXS	07	SW-2	FL1021ZZ-07-Stair 2	UDEC	USE-100	N/A
FL1021ZZ-000000196	Exit Signs	EXS	07	RE	FL1021ZZ-07-Reception	UDEC	USE-100	N/A
FL1021ZZ-000000197	Exit Signs	EXS	07	ST	FL1021ZZ-07-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000198	Exit Signs	EXS	07	ST	FL1021ZZ-07-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000199	Exit Signs	EXS	07	CD	FL1021ZZ-07-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000200	Exit Signs	EXS	07	CD	FL1021ZZ-07-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000201	Exit Signs	EXS	07	ST	FL1021ZZ-07-South Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000202	Exit Signs	EXS	07	ST	FL1021ZZ-07-South Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000203	Exit Signs	EXS	07	EN	FL1021ZZ-07-East Entrance	UDEC	USE-100	N/A
FL1021ZZ-000000204	Exit Signs	EXS	07	EN-ST	FL1021ZZ-07-South Entrance	UDEC	USE-100	N/A
FL1021ZZ-000000205	Exit Signs	EXS	07	CD	FL1021ZZ-07-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000206	Exit Signs	EXS	07	CD	FL1021ZZ-07-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000207	Exit Signs	EXS	07	CD	FL1021ZZ-07-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000208	Exit Signs	EXS	07	CF-NT	FL1021ZZ-07-North Conference Room	UDEC	USE-100	N/A
FL1021ZZ-000000209	Exit Signs	EXS	07	CD	FL1021ZZ-07-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000210	Exit Signs	EXS	07	CD	FL1021ZZ-07-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000211	Exit Signs	EXS	07	CD	FL1021ZZ-07-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000212	Exit Signs	EXS	08	SW-1	FL1021ZZ-08-Stair 1	UDEC	USE-100	N/A
FL1021ZZ-000000213	Exit Signs	EXS	08	SW-2	FL1021ZZ-08-Stair 2	UDEC	USE-100	N/A

FL1021ZZ-000000214	Exit Signs	EXS	08	RE	FL1021ZZ-08-Reception	UDEC	USE-100	N/A
FL1021ZZ-000000215	Exit Signs	EXS	08	ST	FL1021ZZ-08-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000216	Exit Signs	EXS	08	ST	FL1021ZZ-08-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000217	Exit Signs	EXS	08	CD	FL1021ZZ-08-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000218	Exit Signs	EXS	08	CD	FL1021ZZ-08-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000219	Exit Signs	EXS	08	ST	FL1021ZZ-08-South Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000220	Exit Signs	EXS	08	ST	FL1021ZZ-08-South Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000221	Exit Signs	EXS	08	EN	FL1021ZZ-08-East Entrance	UDEC	USE-100	N/A
FL1021ZZ-000000222	Exit Signs	EXS	08	EN-ST	FL1021ZZ-08-South Entrance	UDEC	USE-100	N/A
FL1021ZZ-000000223	Exit Signs	EXS	08	CD	FL1021ZZ-08-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000224	Exit Signs	EXS	08	CD	FL1021ZZ-08-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000225	Exit Signs	EXS	08	CD	FL1021ZZ-08-East Corridor offices	UDEC	USE-100	N/A
FL1021ZZ-000000226	Exit Signs	EXS	08	CF-NT	FL1021ZZ-08-North Conference Room	UDEC	USE-100	N/A
FL1021ZZ-000000227	Exit Signs	EXS	08	CD	FL1021ZZ-08-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000228	Exit Signs	EXS	08	CD	FL1021ZZ-08-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000229	Exit Signs	EXS	08	CD	FL1021ZZ-08-North Corridor Offices	UDEC	USE-100	N/A
FL1021ZZ-000000230	Exit Signs	EXS	09	SW-1	FL1021ZZ-09-Stair 1	UDEC	USE-100	N/A
FL1021ZZ-000000231	Exit Signs	EXS	09	SW-2	FL1021ZZ-09-Stair 2	UDEC	USE-100	N/A
FL1021ZZ-000000232	Exit Signs	EXS	09	LI	FL1021ZZ-09-Library	UDEC	USE-100	N/A
FL1021ZZ-000000233	Exit Signs	EXS	09	ST	FL1021ZZ-09-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000234	Exit Signs	EXS	09	ST	FL1021ZZ-09-South Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000235	Exit Signs	EXS	09	CD	FL1021ZZ-09-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000236	Exit Signs	EXS	09	CD	FL1021ZZ-09-North Corridor Public	UDEC	USE-100	N/A
FL1021ZZ-000000237	Exit Signs	EXS	09	902	FL1021ZZ-09-902	UDEC	USE-100	N/A
FL1021ZZ-000000238	Exit Signs	EXS	09	902	FL1021ZZ-09-902	UDEC	USE-100	N/A
FL1021ZZ-000000239	Exit Signs	EXS	09	JU	FL1021ZZ-09-Grand Jury Room # 1	UDEC	USE-100	N/A
FL1021ZZ-000000240	Exit Signs	EXS	09	JU	FL1021ZZ-09-Grand Jury Room # 2	UDEC	USE-100	N/A
FL1021ZZ-000000241	Exit Signs	EXS	09	JU	FL1021ZZ-09-Grand Jury Room # 3	UDEC	USE-100	N/A
FL1021ZZ-000000242	Exit Signs	EXS	09	JU	FL1021ZZ-09-Grand Jury Room # 4	UDEC	USE-100	N/A
FL1021ZZ-000000243	Exit Signs	EXS	09	933	FL1021ZZ-09-933	UDEC	USE-100	N/A
FL1021ZZ-000000244	Exit Signs	EXS	10	SW-1	FL1021ZZ-10-Stair 1	UDEC	USE-100	N/A
FL1021ZZ-000000245	Exit Signs	EXS	10	SW-2	FL1021ZZ-10-Stair 2	UDEC	USE-100	N/A
FL1021ZZ-000000246	Exit Signs	EXS	10	CD	FL1021ZZ-10-East Corridor	UDEC	USE-100	N/A
FL1021ZZ-000000247	Exit Signs	EXS	10	CD	FL1021ZZ-10-East Corridor	UDEC	USE-100	N/A
FL1021ZZ-000000248	Exit Signs	EXS	10	CD-WT	FL1021ZZ-10-West Corridor	UDEC	USE-100	N/A
FL1021ZZ-000000249	Exit Signs	EXS	10	CD-WT	FL1021ZZ-10-West Corridor	UDEC	USE-100	N/A
FL1021ZZ-000000250	Exit Signs	EXS	10	CR	FL1021ZZ-10-Courtroom # 1	UDEC	USE-100	N/A
FL1021ZZ-000000251	Exit Signs	EXS	10	CR	FL1021ZZ-10-Courtroom # 1	UDEC	USE-100	N/A

FL1021ZZ-000000252	Exit Signs	EXS	10	CR	FL1021ZZ-10-Courtroom # 2	UDEC	USE-100	N/A
FL1021ZZ-000000253	Exit Signs	EXS	10	CR	FL1021ZZ-10-Courtroom # 2	UDEC	USE-100	N/A
FL1021ZZ-000000254	Exit Signs	EXS	10	CR	FL1021ZZ-10-Courtroom # 3	UDEC	USE-100	N/A
FL1021ZZ-000000255	Exit Signs	EXS	10	CR	FL1021ZZ-10-Courtroom # 3	UDEC	USE-100	N/A
FL1021ZZ-000000256	Exit Signs	EXS	10	1067	FL1021ZZ-10-1067	UDEC	USE-100	N/A
FL1021ZZ-000000257	Exit Signs	EXS	10	1067	FL1021ZZ-10-1067	UDEC	USE-100	N/A
FL1021ZZ-000000258	Exit Signs	EXS	10	1027	FL1021ZZ-10-1027	UDEC	USE-100	N/A
FL1021ZZ-000000259	Exit Signs	EXS	10	1027	FL1021ZZ-10-1027	UDEC	USE-100	N/A
FL1021ZZ-000000260	Exit Signs	EXS	10	1035	FL1021ZZ-10-1035	UDEC	USE-100	N/A
FL1021ZZ-000000261	Exit Signs	EXS	10	1035	FL1021ZZ-10-1035	UDEC	USE-100	N/A
FL1021ZZ-000000262	Exit Signs	EXS	11	SW-1	FL1021ZZ-11-Stair 1	UDEC	USE-100	N/A
FL1021ZZ-000000263	Exit Signs	EXS	11	SW-2	FL1021ZZ-11-Stair 2	UDEC	USE-100	N/A
FL1021ZZ-000000264	Exit Signs	EXS	11	CD	FL1021ZZ-11-East Corridor	UDEC	USE-100	N/A
FL1021ZZ-000000265	Exit Signs	EXS	11	CD	FL1021ZZ-11-East Corridor	UDEC	USE-100	N/A
FL1021ZZ-000000266	Exit Signs	EXS	11	CD-WT	FL1021ZZ-11-West Corridor	UDEC	USE-100	N/A
FL1021ZZ-000000267	Exit Signs	EXS	11	CD-WT	FL1021ZZ-11-West Corridor	UDEC	USE-100	N/A
FL1021ZZ-000000268	Exit Signs	EXS	11	CR	FL1021ZZ-11-Courtroom # 4	UDEC	USE-100	N/A
FL1021ZZ-000000269	Exit Signs	EXS	11	CR	FL1021ZZ-11-Courtroom # 4	UDEC	USE-100	N/A
FL1021ZZ-000000270	Exit Signs	EXS	11	CR	FL1021ZZ-11-Courtroom # 5	UDEC	USE-100	N/A
FL1021ZZ-000000271	Exit Signs	EXS	11	CR	FL1021ZZ-11-Courtroom # 5	UDEC	USE-100	N/A
FL1021ZZ-000000272	Exit Signs	EXS	11	CR	FL1021ZZ-11-Courtroom # 6	UDEC	USE-100	N/A
FL1021ZZ-000000273	Exit Signs	EXS	11	CR	FL1021ZZ-11-Courtroom # 6	UDEC	USE-100	N/A
FL1021ZZ-000000274	Exit Signs	EXS	11	1167	FL1021ZZ-11-1167	UDEC	USE-100	N/A
FL1021ZZ-000000275	Exit Signs	EXS	11	1167	FL1021ZZ-11-1167	UDEC	USE-100	N/A
FL1021ZZ-000000276	Exit Signs	EXS	11	1127	FL1021ZZ-11-1127	UDEC	USE-100	N/A
FL1021ZZ-000000277	Exit Signs	EXS	11	1127	FL1021ZZ-11-1127	UDEC	USE-100	N/A
FL1021ZZ-000000278	Exit Signs	EXS	11	1135	FL1021ZZ-11-1135	UDEC	USE-100	N/A
FL1021ZZ-000000279	Exit Signs	EXS	11	1135	FL1021ZZ-11-1135	UDEC	USE-100	N/A
FL1021ZZ-000000280	Exit Signs	EXS	12	SW-1	FL1021ZZ-12-Stair 1	UDEC	USE-100	N/A
FL1021ZZ-000000281	Exit Signs	EXS	12	SW-2	FL1021ZZ-12-Stair 2	UDEC	USE-100	N/A
FL1021ZZ-000000282	Exit Signs	EXS	12	CD	FL1021ZZ-12-East Corridor	UDEC	USE-100	N/A
FL1021ZZ-000000283	Exit Signs	EXS	12	CD	FL1021ZZ-12-East Corridor	UDEC	USE-100	N/A
FL1021ZZ-000000284	Exit Signs	EXS	12	CD-WT	FL1021ZZ-12-West Corridor	UDEC	USE-100	N/A
FL1021ZZ-000000285	Exit Signs	EXS	12	CD-WT	FL1021ZZ-12-West Corridor	UDEC	USE-100	N/A
FL1021ZZ-000000286	Exit Signs	EXS	12	A	FL1021ZZ-12-Court of Apeal	UDEC	USE-100	N/A
FL1021ZZ-000000287	Exit Signs	EXS	12	A	FL1021ZZ-12-Court of Apeal	UDEC	USE-100	N/A
FL1021ZZ-000000288	Exit Signs	EXS	12	1212	FL1021ZZ-12-1212	UDEC	USE-100	N/A
FL1021ZZ-000000289	Exit Signs	EXS	12	1212	FL1021ZZ-12-1212	UDEC	USE-100	N/A
FL1021ZZ-000000290	Exit Signs	EXS	12	1265	FL1021ZZ-12-1265	UDEC	USE-100	N/A
FL1021ZZ-000000291	Exit Signs	EXS	12	1235	FL1021ZZ-12-1235	UDEC	USE-100	N/A
FL1021ZZ-000000292	Exit Signs	EXS	12	1235	FL1021ZZ-12-1235	UDEC	USE-100	N/A
FL1021ZZ-000000293	Exit Signs	EXS	12	1222	FL1021ZZ-12-1222	UDEC	USE-100	N/A
FL1021ZZ-000000294	Exit Signs	EXS	12	1222	FL1021ZZ-12-1222	UDEC	USE-100	N/A
FL1021ZZ-000000295	Exit Signs	EXS	12	1227	FL1021ZZ-12-1227	UDEC	USE-100	N/A
FL1021ZZ-000000296	Exit Signs	EXS	12	1227	FL1021ZZ-12-1227	UDEC	USE-100	N/A
FL1021ZZ-000000297	Exit Signs	EXS	RF	1227	FL1021ZZ-RF-1227	UDEC	USE-100	N/A

FL1021ZZ-000000298	Expansion Tank	EXT	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	ACO	CA-300-3	91183
FL1021ZZ-000000299	Expansion Tank	EXT	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room	AMTROL	WX-350	N/A
FL1021ZZ-000000300	Fan, Axial	FAN-01	GF		FL1021ZZ-GF-Fuel Tank Room	TOSHIBA	B0254BLJ1BM	N/A
FL1021ZZ-000000301	Fan, Axial	FAN-01	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room	NOT AVAILABLE	A1506BLJ3BM	AC58558-1
FL1021ZZ-000000302	Fan, Axial	FAN-01	RF	ET	FL1021ZZ-RF-East	N/A	S2607002F4010	N/A
FL1021ZZ-000000303	Fan, Axial	FAN-01	RF	ST	FL1021ZZ-RF-South	WOODS	920324J-10T017P/A12	N/A
FL1021ZZ-000000304	Fan, Axial	FAN-01	RF	ST	FL1021ZZ-RF-South	WOODS	920324J-10T017P/A12	N/A
FL1021ZZ-000000305	Fan, Centrifugal	FAN-02	GF	PL	FL1021ZZ-GF-Parking Lot Parking North side	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000306	Fan, Centrifugal	FAN-02	GF	SP	FL1021ZZ-GF-Sally Port West Side of the Building	LOREN COOK COMPANY	N/A	N/A
FL1021ZZ-000000307	Fan, Centrifugal	FAN-02	RF	RF	FL1021ZZ-RF-Roof / Roof Installed Item Stairwell-1	LOREN COOK COMPANY	N/A	N/A
FL1021ZZ-000000308	Fan, Centrifugal	FAN-02	RF	RF	FL1021ZZ-RF-Roof / Roof Installed Item Stairwell-2	LOREN COOK COMPANY	N/A	N/A
FL1021ZZ-000000309	Fan, Centrifugal	FAN-02	RF	ET	FL1021ZZ-RF-East	CARNES	VLBK36C1G1UL20S-W1	649511001
FL1021ZZ-000000310	Fan, Centrifugal	FAN-02	RF	WT	FL1021ZZ-RF-West	LOREN COOK COMPANY	180 SQIB	305 S33126000 0193 0002
FL1021ZZ-000000311	Fan, Centrifugal	FAN-02	RF	NT	FL1021ZZ-RF-North	LOREN COOK COMPANY	N/A	N/A
FL1021ZZ-000000325	Fire Extinguishers	FEX	B1	PL	FL1021ZZ-B1-Parking Lot Near Elevator Lobby	AMEREX	20MB-2H	JX-064721
FL1021ZZ-000000326	Fire Extinguishers	FEX	GF	MC	FL1021ZZ-GF-Mechanical Equipment Room Diesel Tank Room	AMEREX	A456	HL-459806
FL1021ZZ-000000327	Fire Extinguishers	FEX	GF	EG	FL1021ZZ-GF-Emergency Generator Room Emergency Generator Room	AMEREX	A456	VN-788952
FL1021ZZ-000000328	Fire Extinguishers	FEX	GF	EE	FL1021ZZ-GF-Electrical Power Distribution Center (Primary Switchgear) Swithchgear Room	AMEREX	A456	HL-459808
FL1021ZZ-000000329	Fire Extinguishers	FEX	GF	SP	FL1021ZZ-GF-Sally Port Receiving Sally Port	AMEREX	A500	LW-678688
FL1021ZZ-000000330	Fire Extinguishers	FEX	GF	SP	FL1021ZZ-GF-Sally Port Vehicle Sallyport	AMEREX	A500	JV-187722
FL1021ZZ-000000331	Fire Extinguishers	FEX	GF		FL1021ZZ-GF-Near Room 112	AMEREX	A456	HL-459832
FL1021ZZ-000000332	Fire Extinguishers	FEX	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	AMEREX	A456	KC-212980
FL1021ZZ-000000333	Fire Extinguishers	FEX	GF	CC	FL1021ZZ-GF-Control Center Near Room 124 (CSO's Office)	AMEREX	A500	SH-587003
FL1021ZZ-000000334	Fire Extinguishers	FEX	GF		FL1021ZZ-GF-Fire Pump Room	AMEREX	20MB-2H	FS-512082
FL1021ZZ-000000335	Fire Extinguishers	FEX	GF	SW	FL1021ZZ-GF-Stairwell #2 North Stairwell	AMEREX	20MB-2H	KH-182464
FL1021ZZ-000000336	Fire Extinguishers	FEX	GF	OF	FL1021ZZ-GF-Office Machine Room	AMEREX	A456	GA-256991
FL1021ZZ-000000337	Fire Extinguishers	FEX	GF	EV	FL1021ZZ-GF-Elevator / Mechanical Penthouse 11th Floor Elevator Mechanical Room	AMEREX	A456	NH-367865

FL1021ZZ-000000338	Fire Extinguishers	FEX	02	FC	FL1021ZZ-02-Food Service, Kitchen Cafeteria	AMEREX	A500	LU-570836
FL1021ZZ-000000339	Fire Extinguishers	FEX	02		FL1021ZZ-02-Near Room 234	AMEREX	A500	LU-570848
FL1021ZZ-000000340	Fire Extinguishers	FEX	02		FL1021ZZ-02-Near Room 216	AMEREX	A500	LU-586288
FL1021ZZ-000000341	Fire Extinguishers	FEX	02		FL1021ZZ-02-Near Room 217	AMEREX	A500	MD-702866
FL1021ZZ-000000342	Fire Extinguishers	FEX	02	MC	FL1021ZZ-02-Mechanical Room	AMEREX	A500	LU-570853
FL1021ZZ-000000343	Fire Extinguishers	FEX	02	CA	FL1021ZZ-02-Near Cafeteria	AMEREX	A500	JH-588130
FL1021ZZ-000000344	Fire Extinguishers	FEX	02	227	FL1021ZZ-02-227	AMEREX	A500	LU-570857
FL1021ZZ-000000345	Fire Extinguishers	FEX	03	SW	FL1021ZZ-03-Southwest Hallway	AMEREX	A500	LU-570771
FL1021ZZ-000000346	Fire Extinguishers	FEX	03		FL1021ZZ-03-Near Room 311	AMEREX	A500	NZ-774027
FL1021ZZ-000000347	Fire Extinguishers	FEX	03		FL1021ZZ-03-Near Room 322	AMEREX	A500	KT-306879
FL1021ZZ-000000348	Fire Extinguishers	FEX	03	MC	FL1021ZZ-03-Mechanical Room	AMEREX	A500	LU-570846
FL1021ZZ-000000349	Fire Extinguishers	FEX	03		FL1021ZZ-03-Near Room 330	AMEREX	A500	LU-570831
FL1021ZZ-000000350	Fire Extinguishers	FEX	03		FL1021ZZ-03-Near Room 303	AMEREX	A500	LU-586272
FL1021ZZ-000000351	Fire Extinguishers	FEX	04	SW	FL1021ZZ-04-Southwest Hallway	AMEREX	A500	LU-570843
FL1021ZZ-000000352	Fire Extinguishers	FEX	04		FL1021ZZ-04-Near Room 411	AMEREX	A500	SH-587747
FL1021ZZ-000000353	Fire Extinguishers	FEX	04		FL1021ZZ-04-Near Room 422	AMEREX	A500	LU-586222
FL1021ZZ-000000354	Fire Extinguishers	FEX	04	MC	FL1021ZZ-04-Mechanical Room	AMEREX	A500	LU-586287
FL1021ZZ-000000355	Fire Extinguishers	FEX	04		FL1021ZZ-04-Near Room 430	AMEREX	A500	NZ-772964
FL1021ZZ-000000356	Fire Extinguishers	FEX	04		FL1021ZZ-04-Near Room 403	AMEREX	A500	LU-570815
FL1021ZZ-000000357	Fire Extinguishers	FEX	05	SW	FL1021ZZ-05-Southwest Hallway	AMEREX	A500	LU-570858
FL1021ZZ-000000358	Fire Extinguishers	FEX	05		FL1021ZZ-05-Near Room 510	AMEREX	A500	LU-586244
FL1021ZZ-000000359	Fire Extinguishers	FEX	05		FL1021ZZ-05-Near Room 521	AMEREX	A500	LU-570820
FL1021ZZ-000000360	Fire Extinguishers	FEX	05	MC	FL1021ZZ-05-Mechanical Room	AMEREX	A500	RC-576961
FL1021ZZ-000000361	Fire Extinguishers	FEX	05		FL1021ZZ-05-Near Room 529	AMEREX	A500	LU-570841
FL1021ZZ-000000362	Fire Extinguishers	FEX	05		FL1021ZZ-05-Near Room 502	AMEREX	A500	LU-586274
FL1021ZZ-000000363	Fire Extinguishers	FEX	06	SW	FL1021ZZ-06-Southwest Hallway	AMEREX	A500	LUN-570842
FL1021ZZ-000000364	Fire Extinguishers	FEX	06		FL1021ZZ-06-Near Room 611	AMEREX	A500	NZ-772970
FL1021ZZ-000000365	Fire Extinguishers	FEX	06		FL1021ZZ-06-Near Room 622	AMEREX	A500	LU-570832
FL1021ZZ-000000366	Fire Extinguishers	FEX	06	MC	FL1021ZZ-06-Mechanical Room	AMEREX	A500	LU-586206
FL1021ZZ-000000367	Fire Extinguishers	FEX	06		FL1021ZZ-06-Near Room 530	AMEREX	A500	LU-586269
FL1021ZZ-000000368	Fire Extinguishers	FEX	06		FL1021ZZ-06-Near Room 603	AMEREX	A500	LU-586223
FL1021ZZ-000000369	Fire Extinguishers	FEX	07	SW	FL1021ZZ-07-Southwest Hallway	AMEREX	A500	MU-607083
FL1021ZZ-000000370	Fire Extinguishers	FEX	07		FL1021ZZ-07-Near Room 710	AMEREX	A500	LU-570827
FL1021ZZ-000000371	Fire Extinguishers	FEX	07		FL1021ZZ-07-Near Room 721	AMEREX	A500	LU-570837

FL1021ZZ-000000372	Fire Extinguishers	FEX	07	MC	FL1021ZZ-07-Mechanical Room	AMEREX	A500	LU-586206
FL1021ZZ-000000373	Fire Extinguishers	FEX	07		FL1021ZZ-07-Near Room 729	AMEREX	A500	LU-570851
FL1021ZZ-000000374	Fire Extinguishers	FEX	07		FL1021ZZ-07-Near Room 702	AMEREX	A500	LU-570844
FL1021ZZ-000000375	Fire Extinguishers	FEX	08	SW	FL1021ZZ-08-Southwest Hallway	AMEREX	A500	LU-570807
FL1021ZZ-000000376	Fire Extinguishers	FEX	08		FL1021ZZ-08-Near Room 803	AMEREX	A500	HU-219611
FL1021ZZ-000000377	Fire Extinguishers	FEX	08		FL1021ZZ-08-Near Room 861	AMEREX	A500	LU-570812
FL1021ZZ-000000378	Fire Extinguishers	FEX	08	MC	FL1021ZZ-08-Mechanical Room	AMEREX	A500	LU-586271
FL1021ZZ-000000379	Fire Extinguishers	FEX	08		FL1021ZZ-08-Near Room 821	AMEREX	A500	LU-570849
FL1021ZZ-000000380	Fire Extinguishers	FEX	08		FL1021ZZ-08-Near Room 810	AMEREX	A500	LU-570847
FL1021ZZ-000000381	Fire Extinguishers	FEX	09	SW	FL1021ZZ-09-Near Stairwell South	AMEREX	A500	LU-570805
FL1021ZZ-000000382	Fire Extinguishers	FEX	09	NE	FL1021ZZ-09-Northeast hallway	AMEREX	A500	LU-570803
FL1021ZZ-000000383	Fire Extinguishers	FEX	09	MC	FL1021ZZ-09-Mechanical Room	AMEREX	A500	LU570870
FL1021ZZ-000000384	Fire Extinguishers	FEX	09	JU	FL1021ZZ-09-Jury Room 911	AMEREX	A500	LU-570828
FL1021ZZ-000000385	Fire Extinguishers	FEX	09	NW	FL1021ZZ-09-Nothrwest hallway	AMEREX	A500	LU-570840
FL1021ZZ-000000386	Fire Extinguishers	FEX	09	PR	FL1021ZZ-09-Public Telephone 902	AMEREX	A500	LU-586255
FL1021ZZ-000000387	Fire Extinguishers	FEX	10		FL1021ZZ-10-Near Room 1076	AMEREX	A500	LU-570862
FL1021ZZ-000000388	Fire Extinguishers	FEX	10		FL1021ZZ-10-Near Room 1036	AMEREX	A500	LU-570863
FL1021ZZ-000000389	Fire Extinguishers	FEX	10		FL1021ZZ-10-Near Room 1047	AMEREX	A500	LU-586224
FL1021ZZ-000000390	Fire Extinguishers	FEX	11		FL1021ZZ-11-Near Room 1135	AMEREX	A500	NZ-772998
FL1021ZZ-000000391	Fire Extinguishers	FEX	11		FL1021ZZ-11-Near Room 1170	AMEREX	A500	LU-570838
FL1021ZZ-000000392	Fire Extinguishers	FEX	11		FL1021ZZ-11-Near Room 1144	AMEREX	A500	NZ-772981
FL1021ZZ-000000393	Fire Extinguishers	FEX	12		FL1021ZZ-12-Near Room 1213	AMEREX	A500	LU-570861
FL1021ZZ-000000394	Fire Extinguishers	FEX	12		FL1021ZZ-12-Near Room 1223	AMEREX	A500	LU-570816
FL1021ZZ-000000395	Fire Extinguishers	FEX	12		FL1021ZZ-12-Near Room 1255	AMEREX	A500	LU-570856
FL1021ZZ-000000396	Fire Extinguishers	FEX	12		FL1021ZZ-12-Near Room 1266	AMEREX	A500	JH-670635
FL1021ZZ-000000397	Fire Extinguishers	FEX	12	HW-WT	FL1021ZZ-12-West Hallway	AMEREX	A500	MD-699822
FL1021ZZ-000000398	Fire Extinguishers	FEX	RF	EV	FL1021ZZ-RF-Elevator / Mechanical Penthouse Southwest Elevator Room	AMEREX	A500	LU-586266
FL1021ZZ-000000399	Fire Extinguishers	FEX	RF	SW	FL1021ZZ-RF-Southwest Mechanical Room	AMEREX	A500	LU-586204
FL1021ZZ-000000400	Fire Extinguishers	FEX	RF	MC	FL1021ZZ-RF-North Mechanical Room	AMEREX	A500	LU-570818
FL1021ZZ-000000401	Fire Extinguishers	FEX	RF	EV	FL1021ZZ-RF-Elevator / Mechanical Penthouse Elevator # 7 Room	AMEREX	A500	HY-217128
FL1021ZZ-000000312	Fire and Smoke Dampers	FSD	02	MC	FL1021ZZ-02-Mechanical Equipment Room	NOT AVAILABLE	N/A	N/A

FL1021ZZ-000000313	Fire and Smoke Dampers	FSD	03	MC	FL1021ZZ-03-Mechanical Equipment Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000314	Fire and Smoke Dampers	FSD	04	MC	FL1021ZZ-04-Mechanical Equipment Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000315	Fire and Smoke Dampers	FSD	05	MC	FL1021ZZ-05-Mechanical Equipment Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000316	Fire and Smoke Dampers	FSD	06	MC	FL1021ZZ-06-Mechanical Equipment Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000317	Fire and Smoke Dampers	FSD	07	MC	FL1021ZZ-07-Mechanical Equipment Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000318	Fire and Smoke Dampers	FSD	08	MC	FL1021ZZ-08-Mechanical Equipment Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000319	Fire and Smoke Dampers	FSD	09	MC	FL1021ZZ-09-Mechanical Equipment Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000320	Fire and Smoke Dampers	FSD	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000321	Fire and Smoke Dampers	FSD	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000322	Fire and Smoke Dampers	FSD	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000405	Fuel-Gas Detection Sensors	GDS	B1	PL	FL1021ZZ-B1-Parking Lot Shop	PNEUMERCATOR	LC 1003	R3252-1
FL1021ZZ-000000402	Fire Hose / Hose Connections	HSE	GF	OT	FL1021ZZ-GF-Outside North-East Corner	POWHATAN	175PSI	N/A
FL1021ZZ-000000403	Fire Hose / Hose Connections	HSE	GF	OT	FL1021ZZ-GF-Outside East Sidewalk	STANDPIPE & AUTO	175PSI	N/A
FL1021ZZ-000000404	Fire Hose / Hose Connections	HSE	GF	OT	FL1021ZZ-GF-Outside East Sidewalk	STANDPIPE & AUTO	175PSI	N/A
FL1021ZZ-000000409	Motor Control Center	MCC	B1	PL	FL1021ZZ-B1-Parking Lot Shop	ELECTRICAL CONTROLS INC	J1946	N/A
FL1021ZZ-000000410	Motor Control Center	MCC	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	WESTINGHOUSE	C7F1G104T3V4Y3	PHY32321-1
FL1021ZZ-000000411	Motor Control Center	MCC	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	WESTINGHOUSE	C7F1G104T3V4Y3	PHY32322-1
FL1021ZZ-000000406	Motor	MOT	GF	PL	FL1021ZZ-GF-Parking Lot Entrance	EMERSON	20-3200C-4	R68735B
FL1021ZZ-000000407	Motor	MOT	GF	PL	FL1021ZZ-GF-Parking Lot Exit	BALDOR	VM 3538	N/A
FL1021ZZ-000000408	Motor	MOT	GF	SP	FL1021ZZ-GF-Sally Port Sally Port	A.O. SMITH	20-3100C-4P	P66876F21
FL1021ZZ-000000412	Motor, Pump	MOT-02	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	U. S. ELECTR	E906AU11U231R10	N/A
FL1021ZZ-000000413	Motor, Pump	MOT-02	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	U. S. ELECTR	E906AU11U231R10	N/A
FL1021ZZ-000000414	Motor, Pump	MOT-02	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	U.S. ELECTRI	T05T026R104-13623	N/A
FL1021ZZ-000000415	Motor, Pump	MOT-02	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	U.S. ELECTRI	T05T026R104-13623	N/A
FL1021ZZ-000000416	Motor, Pump	MOT-02	GF	MC	FL1021ZZ-GF-Mechanical Equipment Room Domestic Water Pump	Baldor	JMM3219T	3GH823Y804
FL1021ZZ-000000417	Motor, Pump	MOT-02	GF	MC	FL1021ZZ-GF-Mechanical Equipment Room Domestic Water Pump	Baldor	JMM3219T	N/A
FL1021ZZ-000000418	Motor, Pump	MOT-02	GF		FL1021ZZ-GF-Fire Pump Room	LINCOLN MOTO	365TS	V1921001542

FL1021ZZ-000000419	Motor, Pump	MOT-02	GF		FL1021ZZ-GF-Fire Pump Room	GRUNDFOS	N/A	35815-873F5
FL1021ZZ-000000507	Powered Doors	PDR	GF	PL	FL1021ZZ-GF-Parking Lot Entrance	LIFT MASTER	N/A	N/A
FL1021ZZ-000000508	Powered Doors	PDR	GF	PL	FL1021ZZ-GF-Parking Lot Exit	MANARAS	GH	BR-00017
FL1021ZZ-000000509	Powered Doors	PDR	GF	SP	FL1021ZZ-GF-Sally Port Vehicle Sally Port	DOERR	N/A	N/A
FL1021ZZ-000000510	Powered Doors	PDR	GF	SP	FL1021ZZ-GF-Sally Port Sally Port	LIFT MASTER	GH1043M	3207N3463
FL1021ZZ-000000511	Powered Doors	PDR	GF	LB	FL1021ZZ-GF-Lobby West Side	HORTON AUTOMATICS	C9100	KAF66LP
FL1021ZZ-000000512	Powered Doors	PDR	GF	LB	FL1021ZZ-GF-Lobby West Side	HORTON AUTOMATICS	N/A	N/A
FL1021ZZ-000000513	Powered Doors	PDR	GF	LB	FL1021ZZ-GF-Lobby East Side	HORTON AUTOMATICS	C9100	KAF66LP
FL1021ZZ-000000514	Powered Doors	PDR	GF	LB	FL1021ZZ-GF-Lobby East Side	HORTON AUTOMATICS	N/A	N/A
FL1021ZZ-000000515	Pump, Centrifugal	PMP-01	GF	MC	FL1021ZZ-GF-Mechanical Equipment Room Domestic Water Pump	GOULD	5BF-17535-1	2237179
FL1021ZZ-000000516	Pump, Centrifugal	PMP-01	GF	MC	FL1021ZZ-GF-Mechanical Equipment Room Domestic Water Pump	GOULD	5BF-17535-1	2271086
FL1021ZZ-000000517	Pump, Centrifugal	PMP-01	GF		FL1021ZZ-GF-Fire Pump Room	PEERLESS	5AEF11G	473033
FL1021ZZ-000000518	Pump, Centrifugal	PMP-01	GF		FL1021ZZ-GF-Fire Pump Room	GRUNDFOS	N/A	N/A
FL1021ZZ-000000519	Pump, Chilled Water	PMP-02	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	WEINMAN	4K4A-200P14G-D	184793-1
FL1021ZZ-000000520	Pump, Chilled Water	PMP-02	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	WEINMAN	4K4A-200P14G-D	184793-2
FL1021ZZ-000000521	Pump, Condenser	PMP-06	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	WEINMAN	6K4A500P144G-D	184794-1
FL1021ZZ-000000522	Pump, Condenser	PMP-06	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	WEINMAN	6K4A500P144G-D	184794-2
FL1021ZZ-000000420	Panelboard, Lighting & Appliance	PNB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room West Wall	SQUARE D	NEHB-230435-1CU	E1
FL1021ZZ-000000421	Panelboard, Lighting & Appliance	PNB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room West Wall	SQUARE D	3720286-AO	E2
FL1021ZZ-000000422	Panelboard, Lighting & Appliance	PNB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room West Wall	SQUARE D	3141100-AVO	E2
FL1021ZZ-000000423	Panelboard, Lighting & Appliance	PNB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room West Wall	SQUARE D	3141100-AVO	E1
FL1021ZZ-000000424	Panelboard, Lighting & Appliance	PNB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room West Wall	SQUARE D	A70031-455-01	
FL1021ZZ-000000425	Panelboard, Lighting & Appliance	PNB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room West Wall	SQUARE D	B141100-AW0	E2
FL1021ZZ-000000426	Panelboard, Lighting & Appliance	PNB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room West Wall	GENERAL ELEC	CR260L26JA122	300
FL1021ZZ-000000427	Panelboard, Lighting & Appliance	PNB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room Nort Wall	SQUARE D	NEHB-18429-ACU	E1
FL1021ZZ-000000428	Panelboard, Lighting & Appliance	PNB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room Nort Wall	SQUARE D	3441100-CRO	E2
FL1021ZZ-000000429	Panelboard, Lighting & Appliance	PNB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room Nort Wall	SQUARE D	NEHB12426-1CU	E1

FL1021ZZ-000000430	Panelboard, Lighting & Appliance	PNB	GF	EE	FL1021ZZ-GF-Electrical Equipment Room Nort Wall	SQUARE D	3441100-AU0	E2
FL1021ZZ-000000431	Panelboard, Lighting & Appliance	PNB	02	EE	FL1021ZZ-02-Electrical Equipment Room West Wall	SQUARE D	NEHB-22441-2CU	E1
FL1021ZZ-000000432	Panelboard, Lighting & Appliance	PNB	02	EE	FL1021ZZ-02-Electrical Equipment Room West Wall	SQUARE D	NQOD442L225CU	E2
FL1021ZZ-000000433	Panelboard, Lighting & Appliance	PNB	02	EE	FL1021ZZ-02-Electrical Equipment Room West Wall	SQUARE D	NQOD454L22CU	E2
FL1021ZZ-000000434	Panelboard, Lighting & Appliance	PNB	02	EE	FL1021ZZ-02-Electrical Equipment Room West Wall	GENERAL ELEC	TL24415C	N/A
FL1021ZZ-000000435	Panelboard, Lighting & Appliance	PNB	02	EE	FL1021ZZ-02-Electrical Equipment Room East Wall	SQUARE D	12-3141100	E2
FL1021ZZ-000000436	Panelboard, Lighting & Appliance	PNB	02	EE	FL1021ZZ-02-Electrical Equipment Room East Wall	SQUARE D	NEHB12426-1CU	E1
FL1021ZZ-000000437	Panelboard, Lighting & Appliance	PNB	03	EE	FL1021ZZ-03-Electrical Equipment Room West Wall	SQUARE D	NEHB-22441-2CU	E1
FL1021ZZ-000000438	Panelboard, Lighting & Appliance	PNB	03	EE	FL1021ZZ-03-Electrical Equipment Room West Wall	SQUARE D	NQOD442L225CU	E2
FL1021ZZ-000000439	Panelboard, Lighting & Appliance	PNB	03	EE	FL1021ZZ-03-Electrical Equipment Room West Wall	SQUARE D	NQOD454L22CU	E2
FL1021ZZ-000000440	Panelboard, Lighting & Appliance	PNB	03	EE	FL1021ZZ-03-Electrical Equipment Room East Wall	SQUARE D	12-3141100	E2
FL1021ZZ-000000441	Panelboard, Lighting & Appliance	PNB	03	EE	FL1021ZZ-03-Electrical Equipment Room East Wall	SQUARE D	NEHB12426-1CU	E1
FL1021ZZ-000000442	Panelboard, Lighting & Appliance	PNB	04	EE	FL1021ZZ-04-Electrical Equipment Room West Wall	SQUARE D	NEHB-22441-2CU	E1
FL1021ZZ-000000443	Panelboard, Lighting & Appliance	PNB	04	EE	FL1021ZZ-04-Electrical Equipment Room West Wall	SQUARE D	NQOD442L225CU	E2
FL1021ZZ-000000444	Panelboard, Lighting & Appliance	PNB	04	EE	FL1021ZZ-04-Electrical Equipment Room West Wall	SQUARE D	NQOD454L22CU	E2
FL1021ZZ-000000445	Panelboard, Lighting & Appliance	PNB	04	EE	FL1021ZZ-04-Electrical Equipment Room East Wall	SQUARE D	12-3141100	E2
FL1021ZZ-000000446	Panelboard, Lighting & Appliance	PNB	04	EE	FL1021ZZ-04-Electrical Equipment Room East Wall	SQUARE D	NEHB12426-1CU	E1
FL1021ZZ-000000447	Panelboard, Lighting & Appliance	PNB	05	EE	FL1021ZZ-05-Electrical Equipment Room West Wall	SQUARE D	NEHB-22441-2CU	E1
FL1021ZZ-000000448	Panelboard, Lighting & Appliance	PNB	05	EE	FL1021ZZ-05-Electrical Equipment Room West Wall	SQUARE D	NQOD442L225CU	E2
FL1021ZZ-000000449	Panelboard, Lighting & Appliance	PNB	05	EE	FL1021ZZ-05-Electrical Equipment Room West Wall	SQUARE D	NQOD454L22CU	E2
FL1021ZZ-000000450	Panelboard, Lighting & Appliance	PNB	05	EE	FL1021ZZ-05-Electrical Equipment Room East Wall	SQUARE D	12-3141100	E2
FL1021ZZ-000000451	Panelboard, Lighting & Appliance	PNB	05	EE	FL1021ZZ-05-Electrical Equipment Room East Wall	SQUARE D	NEHB12426-1CU	E1
FL1021ZZ-000000452	Panelboard, Lighting & Appliance	PNB	06	EE	FL1021ZZ-06-Electrical Equipment Room West Wall	SQUARE D	NEHB-22441-2CU	E1

FL1021ZZ-000000453	Panelboard, Lighting & Appliance	PNB	06	EE	FL1021ZZ-06-Electrical Equipment Room West Wall	SQUARE D	NQOD442L225CU	E2
FL1021ZZ-000000454	Panelboard, Lighting & Appliance	PNB	06	EE	FL1021ZZ-06-Electrical Equipment Room West Wall	SQUARE D	NQOD454L22CU	E2
FL1021ZZ-000000455	Panelboard, Lighting & Appliance	PNB	06	EE	FL1021ZZ-06-Electrical Equipment Room East Wall	SQUARE D	12-3141100	E2
FL1021ZZ-000000456	Panelboard, Lighting & Appliance	PNB	06	EE	FL1021ZZ-06-Electrical Equipment Room East Wall	SQUARE D	NEHB12426-1CU	E1
FL1021ZZ-000000457	Panelboard, Lighting & Appliance	PNB	07	EE	FL1021ZZ-07-Electrical Equipment Room West Wall	SQUARE D	NEHB-22441-2CU	E1
FL1021ZZ-000000458	Panelboard, Lighting & Appliance	PNB	07	EE	FL1021ZZ-07-Electrical Equipment Room West Wall	SQUARE D	NQOD442L225CU	E2
FL1021ZZ-000000459	Panelboard, Lighting & Appliance	PNB	07	EE	FL1021ZZ-07-Electrical Equipment Room West Wall	SQUARE D	NQOD454L22CU	E2
FL1021ZZ-000000460	Panelboard, Lighting & Appliance	PNB	07	EE	FL1021ZZ-07-Electrical Equipment Room East Wall	SQUARE D	12-3141100	E2
FL1021ZZ-000000461	Panelboard, Lighting & Appliance	PNB	07	EE	FL1021ZZ-07-Electrical Equipment Room East Wall	SQUARE D	NEHB12426-1CU	E1
FL1021ZZ-000000462	Panelboard, Lighting & Appliance	PNB	08	EE	FL1021ZZ-08-Electrical Equipment Room West Wall	SQUARE D	NEHB-22441-2CU	E1
FL1021ZZ-000000463	Panelboard, Lighting & Appliance	PNB	08	EE	FL1021ZZ-08-Electrical Equipment Room West Wall	SQUARE D	NQOD442L225CU	E2
FL1021ZZ-000000464	Panelboard, Lighting & Appliance	PNB	08	EE	FL1021ZZ-08-Electrical Equipment Room West Wall	SQUARE D	NQOD454L22CU	E2
FL1021ZZ-000000465	Panelboard, Lighting & Appliance	PNB	08	EE	FL1021ZZ-08-Electrical Equipment Room East Wall	SQUARE D	12-3141100	E2
FL1021ZZ-000000466	Panelboard, Lighting & Appliance	PNB	08	EE	FL1021ZZ-08-Electrical Equipment Room East Wall	SQUARE D	NEHB12426-1CU	E1
FL1021ZZ-000000467	Panelboard, Lighting & Appliance	PNB	09	EE	FL1021ZZ-09-Electrical Equipment Room West Wall	SQUARE D	NEHB-22441-2CU	E1
FL1021ZZ-000000468	Panelboard, Lighting & Appliance	PNB	09	EE	FL1021ZZ-09-Electrical Equipment Room West Wall	SQUARE D	NQOD442L225CU	E2
FL1021ZZ-000000469	Panelboard, Lighting & Appliance	PNB	09	EE	FL1021ZZ-09-Electrical Equipment Room West Wall	SQUARE D	NQOD454L22CU	E2
FL1021ZZ-000000470	Panelboard, Lighting & Appliance	PNB	09	EE	FL1021ZZ-09-Electrical Equipment Room East Wall	SQUARE D	12-3141100	E2
FL1021ZZ-000000471	Panelboard, Lighting & Appliance	PNB	09	EE	FL1021ZZ-09-Electrical Equipment Room East Wall	SQUARE D	NEHB12426-1CU	E1
FL1021ZZ-000000472	Panelboard, Lighting & Appliance	PNB	10	EE	FL1021ZZ-10-Electrical Equipment Room West Wall	SQUARE D	NEHB-22441-2CU	E1
FL1021ZZ-000000473	Panelboard, Lighting & Appliance	PNB	10	EE	FL1021ZZ-10-Electrical Equipment Room West Wall	SQUARE D	NQOD442L225CU	E2
FL1021ZZ-000000474	Panelboard, Lighting & Appliance	PNB	10	EE	FL1021ZZ-10-Electrical Equipment Room West Wall	SQUARE D	NQOD454L22CU	E2
FL1021ZZ-000000475	Panelboard, Lighting & Appliance	PNB	10	EE	FL1021ZZ-10-Electrical Equipment Room East Wall	SQUARE D	12-3141100	E2

FL1021ZZ-000000476	Panelboard, Lighting & Appliance	PNB	10	EE	FL1021ZZ-10-Electrical Equipment Room East Wall	SQUARE D	NEHB12426-1CU	E1
FL1021ZZ-000000477	Panelboard, Lighting & Appliance	PNB	11	EE	FL1021ZZ-11-Electrical Equipment Room West Wall	SQUARE D	NEHB-22441-2CU	E1
FL1021ZZ-000000478	Panelboard, Lighting & Appliance	PNB	11	EE	FL1021ZZ-11-Electrical Equipment Room West Wall	SQUARE D	NQOD442L225CU	E2
FL1021ZZ-000000479	Panelboard, Lighting & Appliance	PNB	11	EE	FL1021ZZ-11-Electrical Equipment Room West Wall	SQUARE D	NQOD454L22CU	E2
FL1021ZZ-000000480	Panelboard, Lighting & Appliance	PNB	11	EE	FL1021ZZ-11-Electrical Equipment Room East Wall	SQUARE D	12-3141100	E2
FL1021ZZ-000000481	Panelboard, Lighting & Appliance	PNB	11	EE	FL1021ZZ-11-Electrical Equipment Room East Wall	SQUARE D	NEHB12426-1CU	E1
FL1021ZZ-000000482	Panelboard, Lighting & Appliance	PNB	12	EE	FL1021ZZ-12-Electrical Equipment Room West Wall	SQUARE D	NEHB-22441-2CU	E1
FL1021ZZ-000000483	Panelboard, Lighting & Appliance	PNB	12	EE	FL1021ZZ-12-Electrical Equipment Room West Wall	SQUARE D	NQOD442L225CU	E2
FL1021ZZ-000000484	Panelboard, Lighting & Appliance	PNB	12	EE	FL1021ZZ-12-Electrical Equipment Room West Wall	SQUARE D	NQOD454L22CU	E2
FL1021ZZ-000000485	Panelboard, Lighting & Appliance	PNB	12	EE	FL1021ZZ-12-Electrical Equipment Room West Wall	GENERAL ELEC	NP1578000D	A
FL1021ZZ-000000486	Panelboard, Lighting & Appliance	PNB	12	EE	FL1021ZZ-12-Electrical Equipment Room West Wall	GENERAL ELEC	AQF3421ABX	A
FL1021ZZ-000000487	Panelboard, Lighting & Appliance	PNB	12	EE	FL1021ZZ-12-Electrical Equipment Room North wall	GENERAL ELEC	ADF3302MBX	A
FL1021ZZ-000000488	Panelboard, Lighting & Appliance	PNB	12	EE	FL1021ZZ-12-Electrical Equipment Room East Wall	SQUARE D	12-3141100	E2
FL1021ZZ-000000489	Panelboard, Lighting & Appliance	PNB	12	EE	FL1021ZZ-12-Electrical Equipment Room East Wall	SQUARE D	NEHB12426-1CU	E1
FL1021ZZ-000000490	Panelboard, Lighting & Appliance	PNB	12	EE	FL1021ZZ-12-Electrical Equipment Room East Wall	SQUARE D	PS4620G	5
FL1021ZZ-000000491	Panelboard, Lighting & Appliance	PNB	12	EE	FL1021ZZ-12-Electrical Equipment Room East Wall	SQUARE D	PIK34225GN	3
FL1021ZZ-000000492	Panelboard, Lighting & Appliance	PNB	12	EE	FL1021ZZ-12-Electrical Equipment Room East Wall	SQUARE D	PTMH36800GN	3
FL1021ZZ-000000493	Panelboard, Lighting & Appliance	PNB	12	EE	FL1021ZZ-12-Electrical Equipment Room East Wall	SQUARE D	PQ4606G	4
FL1021ZZ-000000494	Panelboard, Lighting & Appliance	PNB	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room AHU-11/12 Mechanical Room	SQUARE D	NQOD424L100CU	E2
FL1021ZZ-000000495	Panelboard, Lighting & Appliance	PNB	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room AHU-11/12 Mechanical Room	SQUARE D	NEHB30435-CU	E1
FL1021ZZ-000000496	Panelboard, Lighting & Appliance	PNB	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room AHU-11/12 Mechanical Room	SQUARE D	N/A	N/A

FL1021ZZ-000000497	Panelboard, Lighting & Appliance	PNB	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room AHU-11/12 Mechanical Room	SQUARE D	NQOD430M1100 CU	E2
FL1021ZZ-000000523	Smoke Detection Sensors	SDS	B1	EV	FL1021ZZ-B1-Elevator Lobby	SIMPLEX	2098-9202	N/A
FL1021ZZ-000000524	Smoke Detection Sensors	SDS	B1	PL	FL1021ZZ-B1-Parking Lot South	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000525	Smoke Detection Sensors	SDS	B1	PL	FL1021ZZ-B1-Parking Lot South	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000526	Smoke Detection Sensors	SDS	B1	PL	FL1021ZZ-B1-Parking Lot North	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000527	Smoke Detection Sensors	SDS	B1	PL	FL1021ZZ-B1-Parking Lot North	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000528	Smoke Detection Sensors	SDS	B1	OF	FL1021ZZ-B1-Office South	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000529	Smoke Detection Sensors	SDS	B1	PL	FL1021ZZ-B1-Parking Lot East Corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000530	Smoke Detection Sensors	SDS	B1	PT	FL1021ZZ-B1-Pit Elevator 1,2,3 Shaft	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000531	Smoke Detection Sensors	SDS	B1	PT	FL1021ZZ-B1-Pit Elevator 4,5,6 Shaft	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000532	Smoke Detection Sensors	SDS	B1	PT	FL1021ZZ-B1-Pit East Corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000533	Smoke Detection Sensors	SDS	B1	PT	FL1021ZZ-B1-Pit East Corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000534	Smoke Detection Sensors	SDS	GF	EV	FL1021ZZ-GF-Elevator Lobby	SIMPLEX	2098-9202	N/A
FL1021ZZ-000000535	Smoke Detection Sensors	SDS	GF	MS	FL1021ZZ-GF-Marshall's Ofice	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000536	Smoke Detection Sensors	SDS	GF	CC	FL1021ZZ-GF-Control Center CSO's Office	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000537	Smoke Detection Sensors	SDS	GF	EB	FL1021ZZ-GF-Building North side	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000538	Smoke Detection Sensors	SDS	GF	EB	FL1021ZZ-GF-Building North side	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000539	Smoke Detection Sensors	SDS	02	SW-1	FL1021ZZ-02-Stair 1	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000540	Smoke Detection Sensors	SDS	02	SW-2	FL1021ZZ-02-Stair 2	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000541	Smoke Detection Sensors	SDS	02	SN	FL1021ZZ-02-Coffee Shop	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000542	Smoke Detection Sensors	SDS	02	OF-ST	FL1021ZZ-02-South office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000543	Smoke Detection Sensors	SDS	02	OF-WT	FL1021ZZ-02-West office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000544	Smoke Detection Sensors	SDS	02	OF-WT	FL1021ZZ-02-West office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000545	Smoke Detection Sensors	SDS	02	OF	FL1021ZZ-02-East office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000546	Smoke Detection Sensors	SDS	02	OF	FL1021ZZ-02-East office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000547	Smoke Detection Sensors	SDS	02	OF-NT	FL1021ZZ-02-North office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000548	Smoke Detection Sensors	SDS	02	AH	FL1021ZZ-02-AHU-2 Supply Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000549	Smoke Detection Sensors	SDS	02	AH	FL1021ZZ-02-AHU-2 Return Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000550	Smoke Detection Sensors	SDS	02	EV	FL1021ZZ-02-Elevator Lobby	SIMPLEX	2098-9202	N/A
FL1021ZZ-000000551	Smoke Detection Sensors	SDS	03	SW-1	FL1021ZZ-03-Stair 1	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000552	Smoke Detection Sensors	SDS	03	SW-2	FL1021ZZ-03-Stair 2	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000553	Smoke Detection Sensors	SDS	03	OF-ST	FL1021ZZ-03-South office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000554	Smoke Detection Sensors	SDS	03	OF-WT	FL1021ZZ-03-West office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000555	Smoke Detection Sensors	SDS	03	OF-WT	FL1021ZZ-03-West office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000556	Smoke Detection Sensors	SDS	03	OF	FL1021ZZ-03-East office corridor	SIMPLEX	2098-9201	N/A

FL1021ZZ-000000557	Smoke Detection Sensors	SDS	03	OF	FL1021ZZ-03-East office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000558	Smoke Detection Sensors	SDS	03	OF-NT	FL1021ZZ-03-North office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000559	Smoke Detection Sensors	SDS	03	AH	FL1021ZZ-03-AHU-3 Supply Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000560	Smoke Detection Sensors	SDS	03	AH	FL1021ZZ-03-AHU-3 Return Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000561	Smoke Detection Sensors	SDS	03	EV	FL1021ZZ-03-Elevator Lobby	SIMPLEX	2098-9202	N/A
FL1021ZZ-000000562	Smoke Detection Sensors	SDS	04	SW-1	FL1021ZZ-04-Stair 1	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000563	Smoke Detection Sensors	SDS	04	SW-2	FL1021ZZ-04-Stair 2	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000564	Smoke Detection Sensors	SDS	04	OF-ST	FL1021ZZ-04-South office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000565	Smoke Detection Sensors	SDS	04	OF-WT	FL1021ZZ-04-West office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000566	Smoke Detection Sensors	SDS	04	OF-WT	FL1021ZZ-04-West office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000567	Smoke Detection Sensors	SDS	04	OF	FL1021ZZ-04-East office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000568	Smoke Detection Sensors	SDS	04	OF	FL1021ZZ-04-East office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000569	Smoke Detection Sensors	SDS	04	OF-NT	FL1021ZZ-04-North office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000570	Smoke Detection Sensors	SDS	04	AH	FL1021ZZ-04-AHU-4 Supply Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000571	Smoke Detection Sensors	SDS	04	AH	FL1021ZZ-04-AHU-4 Return Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000572	Smoke Detection Sensors	SDS	04	EV	FL1021ZZ-04-Elevator Lobby	SIMPLEX	2098-9202	N/A
FL1021ZZ-000000573	Smoke Detection Sensors	SDS	05	SW-1	FL1021ZZ-05-Stair 1	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000574	Smoke Detection Sensors	SDS	05	SW-2	FL1021ZZ-05-Stair 2	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000575	Smoke Detection Sensors	SDS	05	OF-ST	FL1021ZZ-05-South office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000576	Smoke Detection Sensors	SDS	05	OF-WT	FL1021ZZ-05-West office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000577	Smoke Detection Sensors	SDS	05	OF-WT	FL1021ZZ-05-West office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000578	Smoke Detection Sensors	SDS	05	OF	FL1021ZZ-05-East office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000579	Smoke Detection Sensors	SDS	05	OF	FL1021ZZ-05-East office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000580	Smoke Detection Sensors	SDS	05	OF-NT	FL1021ZZ-05-North office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000581	Smoke Detection Sensors	SDS	05	AH	FL1021ZZ-05-AHU-5 Supply Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000582	Smoke Detection Sensors	SDS	05	AH	FL1021ZZ-05-AHU-5 Return Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000583	Smoke Detection Sensors	SDS	05	EV	FL1021ZZ-05-Elevator Lobby	SIMPLEX	2098-9202	N/A
FL1021ZZ-000000584	Smoke Detection Sensors	SDS	06	SW-1	FL1021ZZ-06-Stair 1	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000585	Smoke Detection Sensors	SDS	06	SW-2	FL1021ZZ-06-Stair 2	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000586	Smoke Detection Sensors	SDS	06	OF-ST	FL1021ZZ-06-South office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000587	Smoke Detection Sensors	SDS	06	OF-WT	FL1021ZZ-06-West office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000588	Smoke Detection Sensors	SDS	06	OF-WT	FL1021ZZ-06-West office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000589	Smoke Detection Sensors	SDS	06	OF	FL1021ZZ-06-East office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000590	Smoke Detection Sensors	SDS	06	OF	FL1021ZZ-06-East office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000591	Smoke Detection Sensors	SDS	06	OF-NT	FL1021ZZ-06-North office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000592	Smoke Detection Sensors	SDS	06	AH	FL1021ZZ-06-AHU-6 Supply Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000593	Smoke Detection Sensors	SDS	06	AH	FL1021ZZ-06-AHU-6 Return Duct	SIMPLEX	2098-9201	N/A

FL1021ZZ-000000594	Smoke Detection Sensors	SDS	06	EV	FL1021ZZ-06-Elevator Lobby	SIMPLEX	2098-9202	N/A
FL1021ZZ-000000595	Smoke Detection Sensors	SDS	07	SW-1	FL1021ZZ-07-Stair 1	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000596	Smoke Detection Sensors	SDS	07	SW-2	FL1021ZZ-07-Stair 2	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000597	Smoke Detection Sensors	SDS	07	OF-ST	FL1021ZZ-07-South office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000598	Smoke Detection Sensors	SDS	07	OF-WT	FL1021ZZ-07-West office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000599	Smoke Detection Sensors	SDS	07	OF-WT	FL1021ZZ-07-West office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000600	Smoke Detection Sensors	SDS	07	OF	FL1021ZZ-07-East office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000601	Smoke Detection Sensors	SDS	07	OF	FL1021ZZ-07-East office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000602	Smoke Detection Sensors	SDS	07	OF-NT	FL1021ZZ-07-North office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000603	Smoke Detection Sensors	SDS	07	AH	FL1021ZZ-07-AHU-7 Supply Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000604	Smoke Detection Sensors	SDS	07	AH	FL1021ZZ-07-AHU-7 Return Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000605	Smoke Detection Sensors	SDS	07	EV	FL1021ZZ-07-Elevator Lobby	SIMPLEX	2098-9202	N/A
FL1021ZZ-000000606	Smoke Detection Sensors	SDS	08	SW-1	FL1021ZZ-08-Stair 1	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000607	Smoke Detection Sensors	SDS	08	SW-2	FL1021ZZ-08-Stair 2	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000608	Smoke Detection Sensors	SDS	08	OF-ST	FL1021ZZ-08-South office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000609	Smoke Detection Sensors	SDS	08	OF-WT	FL1021ZZ-08-West office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000610	Smoke Detection Sensors	SDS	08	OF-WT	FL1021ZZ-08-West office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000611	Smoke Detection Sensors	SDS	08	OF	FL1021ZZ-08-East office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000612	Smoke Detection Sensors	SDS	08	OF	FL1021ZZ-08-East office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000613	Smoke Detection Sensors	SDS	08	OF-NT	FL1021ZZ-08-North office corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000614	Smoke Detection Sensors	SDS	08	AH	FL1021ZZ-08-AHU-8 Supply Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000615	Smoke Detection Sensors	SDS	08	AH	FL1021ZZ-08-AHU-8 Return Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000616	Smoke Detection Sensors	SDS	08	EV	FL1021ZZ-08-Elevator Lobby	SIMPLEX	2098-9202	N/A
FL1021ZZ-000000617	Smoke Detection Sensors	SDS	09	SW-1	FL1021ZZ-09-Stair 1	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000618	Smoke Detection Sensors	SDS	09	SW-2	FL1021ZZ-09-Stair 2	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000619	Smoke Detection Sensors	SDS	09	ST	FL1021ZZ-09-South Public corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000620	Smoke Detection Sensors	SDS	09	WT	FL1021ZZ-09-West Public corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000621	Smoke Detection Sensors	SDS	09	JU	FL1021ZZ-09-Jury Room 1	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000622	Smoke Detection Sensors	SDS	09	JU	FL1021ZZ-09-Jury Room 2	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000623	Smoke Detection Sensors	SDS	09	JU	FL1021ZZ-09-Jury Room 3	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000624	Smoke Detection Sensors	SDS	09	JU	FL1021ZZ-09-Jury Room 4	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000625	Smoke Detection Sensors	SDS	09	LI	FL1021ZZ-09-Library	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000626	Smoke Detection Sensors	SDS	09	LI	FL1021ZZ-09-Library	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000627	Smoke Detection Sensors	SDS	09	AH	FL1021ZZ-09-AHU-9 Supply Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000628	Smoke Detection Sensors	SDS	09	AH	FL1021ZZ-09-AHU-9 Return Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000629	Smoke Detection Sensors	SDS	09	933	FL1021ZZ-09-933	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000630	Smoke Detection Sensors	SDS	09	902	FL1021ZZ-09-902	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000631	Smoke Detection Sensors	SDS	09	902	FL1021ZZ-09-902	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000632	Smoke Detection Sensors	SDS	09	901	FL1021ZZ-09-901	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000633	Smoke Detection Sensors	SDS	09	EV	FL1021ZZ-09-Elevator Lobby	SIMPLEX	2098-9202	N/A

FL1021ZZ-000000634	Smoke Detection Sensors	SDS	10	SW-1	FL1021ZZ-10-Stair 1	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000635	Smoke Detection Sensors	SDS	10	SW-2	FL1021ZZ-10-Stair 2	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000636	Smoke Detection Sensors	SDS	10	ET	FL1021ZZ-10-East Public corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000637	Smoke Detection Sensors	SDS	10	ET	FL1021ZZ-10-East Public corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000638	Smoke Detection Sensors	SDS	10	WT	FL1021ZZ-10-West Public corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000639	Smoke Detection Sensors	SDS	10	NT	FL1021ZZ-10-North Public corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000640	Smoke Detection Sensors	SDS	10	AH	FL1021ZZ-10-AHU-10 Supply Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000641	Smoke Detection Sensors	SDS	10	AH	FL1021ZZ-10-AHU-10 Return Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000642	Smoke Detection Sensors	SDS	10	EV	FL1021ZZ-10-Elevator Lobby	SIMPLEX	2098-9202	N/A
FL1021ZZ-000000643	Smoke Detection Sensors	SDS	11	SW-1	FL1021ZZ-11-Stair 1	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000644	Smoke Detection Sensors	SDS	11	SW-2	FL1021ZZ-11-Stair 2	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000645	Smoke Detection Sensors	SDS	11	ET	FL1021ZZ-11-East Public corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000646	Smoke Detection Sensors	SDS	11	ET	FL1021ZZ-11-East Public corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000647	Smoke Detection Sensors	SDS	11	WT	FL1021ZZ-11-West Public corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000648	Smoke Detection Sensors	SDS	11	NT	FL1021ZZ-11-North Public corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000649	Smoke Detection Sensors	SDS	11	AH	FL1021ZZ-11-AHU-11 Supply Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000650	Smoke Detection Sensors	SDS	11	AH	FL1021ZZ-11-AHU-11 Return Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000651	Smoke Detection Sensors	SDS	11	EV	FL1021ZZ-11-Elevator Lobby	SIMPLEX	2098-9202	N/A
FL1021ZZ-000000652	Smoke Detection Sensors	SDS	12	SW-1	FL1021ZZ-12-Stair 1	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000653	Smoke Detection Sensors	SDS	12	SW-2	FL1021ZZ-12-Stair 2	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000654	Smoke Detection Sensors	SDS	12	ET	FL1021ZZ-12-East Public corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000655	Smoke Detection Sensors	SDS	12	WT	FL1021ZZ-12-West Public corridor	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000656	Smoke Detection Sensors	SDS	12	1212	FL1021ZZ-12-1212	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000657	Smoke Detection Sensors	SDS	12	AH	FL1021ZZ-12-AHU-12 Supply Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000658	Smoke Detection Sensors	SDS	12	AH	FL1021ZZ-12-AHU-12 Return Duct	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000659	Smoke Detection Sensors	SDS	12	EV	FL1021ZZ-12-Elevator Lobby	SIMPLEX	2098-9202	N/A
FL1021ZZ-000000660	Smoke Detection Sensors	SDS	RF	EV	FL1021ZZ-RF-Elevator / Mechanical Penthouse Elevator From 1-6 Mechanical room	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000661	Smoke Detection Sensors	SDS	RF	EV	FL1021ZZ-RF-Elevator / Mechanical Penthouse Elevator 7 Mechanical Room	SIMPLEX	2098-9201	N/A
FL1021ZZ-000000662	Sump Pump	SMP	B1	PL	FL1021ZZ-B1-Parking Lot Near Storage Room	HOFFMAN	N/A	N/A
FL1021ZZ-000000663	Sump Pump	SMP	B1	PL	FL1021ZZ-B1-Parking Lot Near Storage Room	HOFFMAN	N/A	N/A
FL1021ZZ-000000664	Sump Pump	SMP	B1	PT	FL1021ZZ-B1-Pit Elevator 1,2,3 Shaft	HOFFMAN	N/A	N/A
FL1021ZZ-000000665	Sump Pump	SMP	B1	PT	FL1021ZZ-B1-Pit Elevator 4,5,6 Shaft	HOFFMAN	N/A	N/A
FL1021ZZ-000000666	Sump Pump	SMP	B1	PT	FL1021ZZ-B1-Pit Elevator 4,5,6 Shaft	HOFFMAN	N/A	N/A
FL1021ZZ-000000749	Tank, Fuel	TNK-01	GF	EG	FL1021ZZ-GF-Emergency Generator Room	SIMPLX	SST	N/A
FL1021ZZ-000000750	Tank, Fuel	TNK-01	GF		FL1021ZZ-GF-Fuel tank Room	CONVAULT FLORIDA	N/A	N/A

FL1021ZZ-000000751	Tank, Water	TNK-04	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	FEND-ALL	23000	70570
FL1021ZZ-000000752	Tank, Water	TNK-04	GF	EG	FL1021ZZ-GF-Emergency Generator Room	FEND-ALL	23000	335876
FL1021ZZ-000000823	VAV (Variable Air Volume Boxes)	VAV	B1	ET	FL1021ZZ-B1-East Side of the Building	ENVIROTECH	LMHS8	N/A
FL1021ZZ-000000824	VAV (Variable Air Volume Boxes)	VAV	GF	ET	FL1021ZZ-GF-East Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000000825	VAV (Variable Air Volume Boxes)	VAV	GF	ET	FL1021ZZ-GF-East Side of the Building	ENVIROTECH	LMHS16	N/A
FL1021ZZ-000000826	VAV (Variable Air Volume Boxes)	VAV	GF	ET	FL1021ZZ-GF-East Side of the Building	ENVIROTECH	LMHS9	N/A
FL1021ZZ-000000827	VAV (Variable Air Volume Boxes)	VAV	GF	WT	FL1021ZZ-GF-West Side of the Building	ENVIROTECH	LMHS9	N/A
FL1021ZZ-000000828	VAV (Variable Air Volume Boxes)	VAV	GF	WT	FL1021ZZ-GF-West Side of the Building	ENVIROTECH	LMHS8	N/A
FL1021ZZ-000000829	VAV (Variable Air Volume Boxes)	VAV	GF	WT	FL1021ZZ-GF-West Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000830	VAV (Variable Air Volume Boxes)	VAV	GF	WT	FL1021ZZ-GF-West Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000000831	VAV (Variable Air Volume Boxes)	VAV	GF	WT	FL1021ZZ-GF-West Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000000832	VAV (Variable Air Volume Boxes)	VAV	02	WT	FL1021ZZ-02-West Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000833	VAV (Variable Air Volume Boxes)	VAV	02	WT	FL1021ZZ-02-West Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000834	VAV (Variable Air Volume Boxes)	VAV	02	ET	FL1021ZZ-02-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000835	VAV (Variable Air Volume Boxes)	VAV	02	WT	FL1021ZZ-02-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000836	VAV (Variable Air Volume Boxes)	VAV	02	WT	FL1021ZZ-02-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000837	VAV (Variable Air Volume Boxes)	VAV	02	WT	FL1021ZZ-02-West Side of the Building	ENVIROTECH	QFV8	N/A
FL1021ZZ-000000838	VAV (Variable Air Volume Boxes)	VAV	02	WT	FL1021ZZ-02-West Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000839	VAV (Variable Air Volume Boxes)	VAV	02	WT	FL1021ZZ-02-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000840	VAV (Variable Air Volume Boxes)	VAV	02	WT	FL1021ZZ-02-West Side of the Building	ENVIROTECH	QFV8	N/A
FL1021ZZ-000000841	VAV (Variable Air Volume Boxes)	VAV	02	WT	FL1021ZZ-02-West Side of the Building	ENVIROTECH	QFV8	N/A
FL1021ZZ-000000842	VAV (Variable Air Volume Boxes)	VAV	02	ET	FL1021ZZ-02-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000843	VAV (Variable Air Volume Boxes)	VAV	02	ET	FL1021ZZ-02-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000844	VAV (Variable Air Volume Boxes)	VAV	02	ET	FL1021ZZ-02-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000845	VAV (Variable Air Volume Boxes)	VAV	02	ET	FL1021ZZ-02-East Side of the Building	ENVIROTECH	QFV8	N/A
FL1021ZZ-000000846	VAV (Variable Air Volume Boxes)	VAV	02	WT	FL1021ZZ-02-West Side of the Building	ENVIROTECH	QVF12	N/A
FL1021ZZ-000000847	VAV (Variable Air Volume Boxes)	VAV	02	WT	FL1021ZZ-02-West Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000848	VAV (Variable Air Volume Boxes)	VAV	02	WT	FL1021ZZ-02-West Side of the Building	ENVIROTECH	LMHS14	N/A
FL1021ZZ-000000849	VAV (Variable Air Volume Boxes)	VAV	02	WT	FL1021ZZ-02-West Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000000850	VAV (Variable Air Volume Boxes)	VAV	02	ET	FL1021ZZ-02-East Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000000851	VAV (Variable Air Volume Boxes)	VAV	02	ET	FL1021ZZ-02-East Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000000852	VAV (Variable Air Volume Boxes)	VAV	02	ET	FL1021ZZ-02-East Side of the Building	ENVIROTECH	LMHS9	N/A
FL1021ZZ-000000853	VAV (Variable Air Volume Boxes)	VAV	02	ET	FL1021ZZ-02-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000854	VAV (Variable Air Volume Boxes)	VAV	03	ET	FL1021ZZ-03-East Side of the Building	ENVIROTECH	QFV10	N/A

FL1021ZZ-000000855	VAV (Variable Air Volume Boxes)	VAV	03	ET	FL1021ZZ-03-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000856	VAV (Variable Air Volume Boxes)	VAV	03	ET	FL1021ZZ-03-East Side of the Building	ENVIROTECH	LMHS9	N/A
FL1021ZZ-000000857	VAV (Variable Air Volume Boxes)	VAV	03	ET	FL1021ZZ-03-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000858	VAV (Variable Air Volume Boxes)	VAV	03	ET	FL1021ZZ-03-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000859	VAV (Variable Air Volume Boxes)	VAV	03	ET	FL1021ZZ-03-East Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000000860	VAV (Variable Air Volume Boxes)	VAV	03	ET	FL1021ZZ-03-East Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000000861	VAV (Variable Air Volume Boxes)	VAV	03	WT	FL1021ZZ-03-West Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000862	VAV (Variable Air Volume Boxes)	VAV	03	WT	FL1021ZZ-03-West Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000000863	VAV (Variable Air Volume Boxes)	VAV	04	WT	FL1021ZZ-04-West Side of the Building	ENVIROTECH	QVF12	N/A
FL1021ZZ-000000864	VAV (Variable Air Volume Boxes)	VAV	04	WT	FL1021ZZ-04-West Side of the Building	ENVIROTECH	QVF10	N/A
FL1021ZZ-000000865	VAV (Variable Air Volume Boxes)	VAV	04	WT	FL1021ZZ-04-West Side of the Building	ENVIROTECH	QVF14	N/A
FL1021ZZ-000000866	VAV (Variable Air Volume Boxes)	VAV	04	WT	FL1021ZZ-04-West Side of the Building	ENVIROTECH	QVF14	N/A
FL1021ZZ-000000867	VAV (Variable Air Volume Boxes)	VAV	04	WT	FL1021ZZ-04-West Side of the Building	ENVIROTECH	QVF12	N/A
FL1021ZZ-000000868	VAV (Variable Air Volume Boxes)	VAV	04	WT	FL1021ZZ-04-West Side of the Building	ENVIROTECH	QVF10	N/A
FL1021ZZ-000000869	VAV (Variable Air Volume Boxes)	VAV	04	WT	FL1021ZZ-04-West Side of the Building	ENVIROTECH	QVF12	N/A
FL1021ZZ-000000870	VAV (Variable Air Volume Boxes)	VAV	04	WT	FL1021ZZ-04-West Side of the Building	ENVIROTECH	QVF10	N/A
FL1021ZZ-000000871	VAV (Variable Air Volume Boxes)	VAV	04	WT	FL1021ZZ-04-West Side of the Building	ENVIROTECH	QVF12	N/A
FL1021ZZ-000000872	VAV (Variable Air Volume Boxes)	VAV	04	WT	FL1021ZZ-04-West Side of the Building	ENVIROTECH	QVF14	N/A
FL1021ZZ-000000873	VAV (Variable Air Volume Boxes)	VAV	04	ET	FL1021ZZ-04-East Side of the Building	ENVIROTECH	QVF14	N/A
FL1021ZZ-000000874	VAV (Variable Air Volume Boxes)	VAV	04	ET	FL1021ZZ-04-East Side of the Building	ENVIROTECH	QVF10	N/A
FL1021ZZ-000000875	VAV (Variable Air Volume Boxes)	VAV	04	ET	FL1021ZZ-04-East Side of the Building	ENVIROTECH	QVF12	N/A
FL1021ZZ-000000876	VAV (Variable Air Volume Boxes)	VAV	04	WT	FL1021ZZ-04-West Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000877	VAV (Variable Air Volume Boxes)	VAV	04	WT	FL1021ZZ-04-West Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000000878	VAV (Variable Air Volume Boxes)	VAV	04	WT	FL1021ZZ-04-West Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000879	VAV (Variable Air Volume Boxes)	VAV	04	ET	FL1021ZZ-04-East Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000000880	VAV (Variable Air Volume Boxes)	VAV	04	ET	FL1021ZZ-04-East Side of the Building	ENVIROTECH	LMHS9	N/A
FL1021ZZ-000000881	VAV (Variable Air Volume Boxes)	VAV	04	ET	FL1021ZZ-04-East Side of the Building	ENVIROTECH	LMHS5	N/A
FL1021ZZ-000000882	VAV (Variable Air Volume Boxes)	VAV	04	ET	FL1021ZZ-04-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000883	VAV (Variable Air Volume Boxes)	VAV	05	WT	FL1021ZZ-05-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000884	VAV (Variable Air Volume Boxes)	VAV	05	WT	FL1021ZZ-05-West Side of the Building	ENVIROTECH	QFV8	N/A
FL1021ZZ-000000885	VAV (Variable Air Volume Boxes)	VAV	05	WT	FL1021ZZ-05-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000886	VAV (Variable Air Volume Boxes)	VAV	05	WT	FL1021ZZ-05-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000887	VAV (Variable Air Volume Boxes)	VAV	05	WT	FL1021ZZ-05-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000888	VAV (Variable Air Volume Boxes)	VAV	05	WT	FL1021ZZ-05-West Side of the Building	ENVIROTECH	QFV10	N/A

FL1021ZZ-000000889	VAV (Variable Air Volume Boxes)	VAV	05	WT	FL1021ZZ-05-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000890	VAV (Variable Air Volume Boxes)	VAV	05	WT	FL1021ZZ-05-West Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000891	VAV (Variable Air Volume Boxes)	VAV	05	WT	FL1021ZZ-05-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000892	VAV (Variable Air Volume Boxes)	VAV	05	WT	FL1021ZZ-05-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000893	VAV (Variable Air Volume Boxes)	VAV	05	WT	FL1021ZZ-05-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000894	VAV (Variable Air Volume Boxes)	VAV	05	ET	FL1021ZZ-05-East Side of the Building	ENVIROTECH	QFV8	N/A
FL1021ZZ-000000895	VAV (Variable Air Volume Boxes)	VAV	05	ET	FL1021ZZ-05-East Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000896	VAV (Variable Air Volume Boxes)	VAV	05	ET	FL1021ZZ-05-East Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000000897	VAV (Variable Air Volume Boxes)	VAV	05	ET	FL1021ZZ-05-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000898	VAV (Variable Air Volume Boxes)	VAV	05	ET	FL1021ZZ-05-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000899	VAV (Variable Air Volume Boxes)	VAV	05	ET	FL1021ZZ-05-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000900	VAV (Variable Air Volume Boxes)	VAV	05	ET	FL1021ZZ-05-East Side of the Building	ENVIROTECH	LMHS8	N/A
FL1021ZZ-000000901	VAV (Variable Air Volume Boxes)	VAV	05	ET	FL1021ZZ-05-East Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000000902	VAV (Variable Air Volume Boxes)	VAV	05	ET	FL1021ZZ-05-East Side of the Building	ENVIROTECH	LMHS5	N/A
FL1021ZZ-000000903	VAV (Variable Air Volume Boxes)	VAV	05	ET	FL1021ZZ-05-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000904	VAV (Variable Air Volume Boxes)	VAV	06	WT	FL1021ZZ-06-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000905	VAV (Variable Air Volume Boxes)	VAV	06	WT	FL1021ZZ-06-West Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000906	VAV (Variable Air Volume Boxes)	VAV	06	WT	FL1021ZZ-06-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000907	VAV (Variable Air Volume Boxes)	VAV	06	WT	FL1021ZZ-06-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000908	VAV (Variable Air Volume Boxes)	VAV	06	WT	FL1021ZZ-06-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000909	VAV (Variable Air Volume Boxes)	VAV	06	WT	FL1021ZZ-06-West Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000910	VAV (Variable Air Volume Boxes)	VAV	06	WT	FL1021ZZ-06-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000911	VAV (Variable Air Volume Boxes)	VAV	06	WT	FL1021ZZ-06-West Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000912	VAV (Variable Air Volume Boxes)	VAV	06	WT	FL1021ZZ-06-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000913	VAV (Variable Air Volume Boxes)	VAV	06	WT	FL1021ZZ-06-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000914	VAV (Variable Air Volume Boxes)	VAV	06	ET	FL1021ZZ-06-East Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000915	VAV (Variable Air Volume Boxes)	VAV	06	ET	FL1021ZZ-06-East Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000916	VAV (Variable Air Volume Boxes)	VAV	06	ET	FL1021ZZ-06-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000917	VAV (Variable Air Volume Boxes)	VAV	06	WT	FL1021ZZ-06-West Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000918	VAV (Variable Air Volume Boxes)	VAV	06	WT	FL1021ZZ-06-West Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000000919	VAV (Variable Air Volume Boxes)	VAV	06	ET	FL1021ZZ-06-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000920	VAV (Variable Air Volume Boxes)	VAV	06	ET	FL1021ZZ-06-East Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000000921	VAV (Variable Air Volume Boxes)	VAV	06	ET	FL1021ZZ-06-East Side of the Building	ENVIROTECH	LMHS9	N/A
FL1021ZZ-000000922	VAV (Variable Air Volume Boxes)	VAV	06	ET	FL1021ZZ-06-East Side of the Building	ENVIROTECH	LMHS5	N/A

FL1021ZZ-000000923	VAV (Variable Air Volume Boxes)	VAV	06	ET	FL1021ZZ-06-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000924	VAV (Variable Air Volume Boxes)	VAV	07	WT	FL1021ZZ-07-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000925	VAV (Variable Air Volume Boxes)	VAV	07	WT	FL1021ZZ-07-West Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000926	VAV (Variable Air Volume Boxes)	VAV	07	WT	FL1021ZZ-07-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000927	VAV (Variable Air Volume Boxes)	VAV	07	WT	FL1021ZZ-07-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000928	VAV (Variable Air Volume Boxes)	VAV	07	WT	FL1021ZZ-07-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000929	VAV (Variable Air Volume Boxes)	VAV	07	WT	FL1021ZZ-07-West Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000930	VAV (Variable Air Volume Boxes)	VAV	07	WT	FL1021ZZ-07-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000931	VAV (Variable Air Volume Boxes)	VAV	07	WT	FL1021ZZ-07-West Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000932	VAV (Variable Air Volume Boxes)	VAV	07	WT	FL1021ZZ-07-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000933	VAV (Variable Air Volume Boxes)	VAV	07	WT	FL1021ZZ-07-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000934	VAV (Variable Air Volume Boxes)	VAV	07	ET	FL1021ZZ-07-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000935	VAV (Variable Air Volume Boxes)	VAV	07	ET	FL1021ZZ-07-East Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000936	VAV (Variable Air Volume Boxes)	VAV	07	ET	FL1021ZZ-07-East Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000937	VAV (Variable Air Volume Boxes)	VAV	07	WT	FL1021ZZ-07-West Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000938	VAV (Variable Air Volume Boxes)	VAV	07	WT	FL1021ZZ-07-West Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000000939	VAV (Variable Air Volume Boxes)	VAV	07	ET	FL1021ZZ-07-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000940	VAV (Variable Air Volume Boxes)	VAV	07	ET	FL1021ZZ-07-East Side of the Building	ENVIROTECH	LMHS9	N/A
FL1021ZZ-000000941	VAV (Variable Air Volume Boxes)	VAV	07	ET	FL1021ZZ-07-East Side of the Building	ENVIROTECH	LMHS8	N/A
FL1021ZZ-000000942	VAV (Variable Air Volume Boxes)	VAV	07	ET	FL1021ZZ-07-East Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000000943	VAV (Variable Air Volume Boxes)	VAV	07	ET	FL1021ZZ-07-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000944	VAV (Variable Air Volume Boxes)	VAV	08	WT	FL1021ZZ-08-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000945	VAV (Variable Air Volume Boxes)	VAV	08	WT	FL1021ZZ-08-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000946	VAV (Variable Air Volume Boxes)	VAV	08	WT	FL1021ZZ-08-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000947	VAV (Variable Air Volume Boxes)	VAV	08	WT	FL1021ZZ-08-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000948	VAV (Variable Air Volume Boxes)	VAV	08	WT	FL1021ZZ-08-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000949	VAV (Variable Air Volume Boxes)	VAV	08	WT	FL1021ZZ-08-West Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000950	VAV (Variable Air Volume Boxes)	VAV	08	WT	FL1021ZZ-08-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000951	VAV (Variable Air Volume Boxes)	VAV	08	WT	FL1021ZZ-08-West Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000952	VAV (Variable Air Volume Boxes)	VAV	08	WT	FL1021ZZ-08-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000953	VAV (Variable Air Volume Boxes)	VAV	08	WT	FL1021ZZ-08-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000954	VAV (Variable Air Volume Boxes)	VAV	08	ET	FL1021ZZ-08-East Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000955	VAV (Variable Air Volume Boxes)	VAV	08	ET	FL1021ZZ-08-East Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000956	VAV (Variable Air Volume Boxes)	VAV	08	ET	FL1021ZZ-08-East Side of the Building	ENVIROTECH	QFV12	N/A

FL1021ZZ-000000957	VAV (Variable Air Volume Boxes)	VAV	08	WT	FL1021ZZ-08-West Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000000958	VAV (Variable Air Volume Boxes)	VAV	08	WT	FL1021ZZ-08-West Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000959	VAV (Variable Air Volume Boxes)	VAV	08	ET	FL1021ZZ-08-East Side of the Building	ENVIROTECH	LMHS9	N/A
FL1021ZZ-000000960	VAV (Variable Air Volume Boxes)	VAV	08	ET	FL1021ZZ-08-East Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000000961	VAV (Variable Air Volume Boxes)	VAV	08	ET	FL1021ZZ-08-East Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000000962	VAV (Variable Air Volume Boxes)	VAV	08	ET	FL1021ZZ-08-East Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000000963	VAV (Variable Air Volume Boxes)	VAV	08	ET	FL1021ZZ-08-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000964	VAV (Variable Air Volume Boxes)	VAV	09	WT	FL1021ZZ-09-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000965	VAV (Variable Air Volume Boxes)	VAV	09	WT	FL1021ZZ-09-West Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000966	VAV (Variable Air Volume Boxes)	VAV	09	WT	FL1021ZZ-09-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000967	VAV (Variable Air Volume Boxes)	VAV	09	WT	FL1021ZZ-09-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000968	VAV (Variable Air Volume Boxes)	VAV	09	WT	FL1021ZZ-09-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000969	VAV (Variable Air Volume Boxes)	VAV	09	WT	FL1021ZZ-09-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000970	VAV (Variable Air Volume Boxes)	VAV	09	ET	FL1021ZZ-09-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000971	VAV (Variable Air Volume Boxes)	VAV	09	ET	FL1021ZZ-09-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000972	VAV (Variable Air Volume Boxes)	VAV	09	ET	FL1021ZZ-09-East Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000973	VAV (Variable Air Volume Boxes)	VAV	09	ET	FL1021ZZ-09-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000974	VAV (Variable Air Volume Boxes)	VAV	09	ET	FL1021ZZ-09-East Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000975	VAV (Variable Air Volume Boxes)	VAV	09	ET	FL1021ZZ-09-East Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000000976	VAV (Variable Air Volume Boxes)	VAV	09	ET	FL1021ZZ-09-East Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000977	VAV (Variable Air Volume Boxes)	VAV	09	ET	FL1021ZZ-09-East Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000000978	VAV (Variable Air Volume Boxes)	VAV	09	WT	FL1021ZZ-09-West Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000979	VAV (Variable Air Volume Boxes)	VAV	09	WT	FL1021ZZ-09-West Side of the Building	ENVIROTECH	LMHS9	N/A
FL1021ZZ-000000980	VAV (Variable Air Volume Boxes)	VAV	09	WT	FL1021ZZ-09-West Side of the Building	ENVIROTECH	LMHS9	N/A
FL1021ZZ-000000981	VAV (Variable Air Volume Boxes)	VAV	09	WT	FL1021ZZ-09-West Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000000982	VAV (Variable Air Volume Boxes)	VAV	09	ET	FL1021ZZ-09-East Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000000983	VAV (Variable Air Volume Boxes)	VAV	09	ET	FL1021ZZ-09-East Side of the Building	ENVIROTECH	LMHS9	N/A
FL1021ZZ-000000984	VAV (Variable Air Volume Boxes)	VAV	09	ET	FL1021ZZ-09-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000000985	VAV (Variable Air Volume Boxes)	VAV	10	WT	FL1021ZZ-10-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000986	VAV (Variable Air Volume Boxes)	VAV	10	WT	FL1021ZZ-10-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000987	VAV (Variable Air Volume Boxes)	VAV	10	WT	FL1021ZZ-10-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000988	VAV (Variable Air Volume Boxes)	VAV	10	WT	FL1021ZZ-10-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000989	VAV (Variable Air Volume Boxes)	VAV	10	WT	FL1021ZZ-10-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000990	VAV (Variable Air Volume Boxes)	VAV	10	WT	FL1021ZZ-10-West Side of the Building	ENVIROTECH	QFV14	N/A

FL1021ZZ-000000991	VAV (Variable Air Volume Boxes)	VAV	10	WT	FL1021ZZ-10-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000992	VAV (Variable Air Volume Boxes)	VAV	10	ET	FL1021ZZ-10-East Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000000993	VAV (Variable Air Volume Boxes)	VAV	10	ET	FL1021ZZ-10-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000994	VAV (Variable Air Volume Boxes)	VAV	10	ET	FL1021ZZ-10-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000995	VAV (Variable Air Volume Boxes)	VAV	10	ET	FL1021ZZ-10-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000996	VAV (Variable Air Volume Boxes)	VAV	10	ET	FL1021ZZ-10-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000000997	VAV (Variable Air Volume Boxes)	VAV	10	ET	FL1021ZZ-10-East Side of the Building	ENVIROTECH	LMHS8	N/A
FL1021ZZ-000000998	VAV (Variable Air Volume Boxes)	VAV	10	ET	FL1021ZZ-10-East Side of the Building	ENVIROTECH	LMHS9	N/A
FL1021ZZ-000000999	VAV (Variable Air Volume Boxes)	VAV	10	WT	FL1021ZZ-10-West Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000001000	VAV (Variable Air Volume Boxes)	VAV	10	WT	FL1021ZZ-10-West Side of the Building	ENVIROTECH	LMHS8	N/A
FL1021ZZ-000001001	VAV (Variable Air Volume Boxes)	VAV	10	WT	FL1021ZZ-10-West Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000001002	VAV (Variable Air Volume Boxes)	VAV	10	WT	FL1021ZZ-10-West Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000001003	VAV (Variable Air Volume Boxes)	VAV	10	WT	FL1021ZZ-10-West Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000001004	VAV (Variable Air Volume Boxes)	VAV	10	WT	FL1021ZZ-10-West Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000001005	VAV (Variable Air Volume Boxes)	VAV	10	WT	FL1021ZZ-10-West Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000001006	VAV (Variable Air Volume Boxes)	VAV	10	ET	FL1021ZZ-10-East Side of the Building	ENVIROTECH	LMHS9	N/A
FL1021ZZ-000001007	VAV (Variable Air Volume Boxes)	VAV	10	ET	FL1021ZZ-10-East Side of the Building	ENVIROTECH	LMHS8	N/A
FL1021ZZ-000001008	VAV (Variable Air Volume Boxes)	VAV	10	ET	FL1021ZZ-10-East Side of the Building	ENVIROTECH	LMHS8	N/A
FL1021ZZ-000001009	VAV (Variable Air Volume Boxes)	VAV	10	ET	FL1021ZZ-10-East Side of the Building	ENVIROTECH	LMHS8	N/A
FL1021ZZ-000001010	VAV (Variable Air Volume Boxes)	VAV	10	ET	FL1021ZZ-10-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000001011	VAV (Variable Air Volume Boxes)	VAV	11	WT	FL1021ZZ-11-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000001012	VAV (Variable Air Volume Boxes)	VAV	11	WT	FL1021ZZ-11-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000001013	VAV (Variable Air Volume Boxes)	VAV	11	WT	FL1021ZZ-11-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000001014	VAV (Variable Air Volume Boxes)	VAV	11	WT	FL1021ZZ-11-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000001015	VAV (Variable Air Volume Boxes)	VAV	11	WT	FL1021ZZ-11-West Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000001016	VAV (Variable Air Volume Boxes)	VAV	11	WT	FL1021ZZ-11-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000001017	VAV (Variable Air Volume Boxes)	VAV	11	WT	FL1021ZZ-11-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000001018	VAV (Variable Air Volume Boxes)	VAV	11	ET	FL1021ZZ-11-East Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000001019	VAV (Variable Air Volume Boxes)	VAV	11	ET	FL1021ZZ-11-East Side of the Building	ENVIROTECH	QFV14	N/A
FL1021ZZ-000001020	VAV (Variable Air Volume Boxes)	VAV	11	ET	FL1021ZZ-11-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000001021	VAV (Variable Air Volume Boxes)	VAV	11	ET	FL1021ZZ-11-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000001022	VAV (Variable Air Volume Boxes)	VAV	11	ET	FL1021ZZ-11-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000001023	VAV (Variable Air Volume Boxes)	VAV	11	ET	FL1021ZZ-11-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000001024	VAV (Variable Air Volume Boxes)	VAV	11	ET	FL1021ZZ-11-East Side of the Building	ENVIROTECH	LMHS7	N/A

FL1021ZZ-000001025	VAV (Variable Air Volume Boxes)	VAV	11	WT	FL1021ZZ-11-West Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000001026	VAV (Variable Air Volume Boxes)	VAV	11	WT	FL1021ZZ-11-West Side of the Building	ENVIROTECH	LMHS8	N/A
FL1021ZZ-000001027	VAV (Variable Air Volume Boxes)	VAV	11	WT	FL1021ZZ-11-West Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000001028	VAV (Variable Air Volume Boxes)	VAV	11	WT	FL1021ZZ-11-West Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000001029	VAV (Variable Air Volume Boxes)	VAV	11	WT	FL1021ZZ-11-West Side of the Building	ENVIROTECH	LMHS7	N/A
FL1021ZZ-000001030	VAV (Variable Air Volume Boxes)	VAV	11	WT	FL1021ZZ-11-West Side of the Building	ENVIROTECH	LMHS10	N/A
FL1021ZZ-000001031	VAV (Variable Air Volume Boxes)	VAV	11	WT	FL1021ZZ-11-West Side of the Building	ENVIROTECH	LMHS9	N/A
FL1021ZZ-000001032	VAV (Variable Air Volume Boxes)	VAV	11	ET	FL1021ZZ-11-East Side of the Building	ENVIROTECH	LMHS8	N/A
FL1021ZZ-000001033	VAV (Variable Air Volume Boxes)	VAV	11	ET	FL1021ZZ-11-East Side of the Building	ENVIROTECH	LMHS8	N/A
FL1021ZZ-000001034	VAV (Variable Air Volume Boxes)	VAV	11	ET	FL1021ZZ-11-East Side of the Building	ENVIROTECH	LMHS8	N/A
FL1021ZZ-000001035	VAV (Variable Air Volume Boxes)	VAV	11	ET	FL1021ZZ-11-East Side of the Building	ENVIROTECH	LMHS8	N/A
FL1021ZZ-000001036	VAV (Variable Air Volume Boxes)	VAV	11	ET	FL1021ZZ-11-East Side of the Building	ENVIROTECH	LMHS	N/A
FL1021ZZ-000001037	VAV (Variable Air Volume Boxes)	VAV	12	WT	FL1021ZZ-12-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000001038	VAV (Variable Air Volume Boxes)	VAV	12	WT	FL1021ZZ-12-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000001039	VAV (Variable Air Volume Boxes)	VAV	12	WT	FL1021ZZ-12-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000001040	VAV (Variable Air Volume Boxes)	VAV	12	WT	FL1021ZZ-12-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000001041	VAV (Variable Air Volume Boxes)	VAV	12	WT	FL1021ZZ-12-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000001042	VAV (Variable Air Volume Boxes)	VAV	12	WT	FL1021ZZ-12-West Side of the Building	ENVIROTECH	QFV8	N/A
FL1021ZZ-000001043	VAV (Variable Air Volume Boxes)	VAV	12	WT	FL1021ZZ-12-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000001044	VAV (Variable Air Volume Boxes)	VAV	12	ET	FL1021ZZ-12-East Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000001045	VAV (Variable Air Volume Boxes)	VAV	12	ET	FL1021ZZ-12-East Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000001046	VAV (Variable Air Volume Boxes)	VAV	12	ET	FL1021ZZ-12-East Side of the Building	ENVIROTECH	QFV8	N/A
FL1021ZZ-000001047	VAV (Variable Air Volume Boxes)	VAV	12	ET	FL1021ZZ-12-East Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000001048	VAV (Variable Air Volume Boxes)	VAV	12	ET	FL1021ZZ-12-East Side of the Building	ENVIROTECH	QFV8	N/A
FL1021ZZ-000001049	VAV (Variable Air Volume Boxes)	VAV	12	ET	FL1021ZZ-12-East Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000001050	VAV (Variable Air Volume Boxes)	VAV	12	WT	FL1021ZZ-12-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000001051	VAV (Variable Air Volume Boxes)	VAV	12	WT	FL1021ZZ-12-West Side of the Building	ENVIROTECH	QFV10	N/A
FL1021ZZ-000001052	VAV (Variable Air Volume Boxes)	VAV	12	WT	FL1021ZZ-12-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000001053	VAV (Variable Air Volume Boxes)	VAV	12	WT	FL1021ZZ-12-West Side of the Building	ENVIROTECH	QFV12	N/A
FL1021ZZ-000001054	VAV (Variable Air Volume Boxes)	VAV	12	WT	FL1021ZZ-12-West Side of the Building	ENVIROTECH	LMHS9	N/A
FL1021ZZ-000001055	VAV (Variable Air Volume Boxes)	VAV	12	ET	FL1021ZZ-12-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000001056	VAV (Variable Air Volume Boxes)	VAV	12	ET	FL1021ZZ-12-East Side of the Building	ENVIROTECH	LMHS12	N/A
FL1021ZZ-000001057	VAV (Variable Air Volume Boxes)	VAV	12	ET	FL1021ZZ-12-East Side of the Building	ENVIROTECH	LMHS14	N/A
FL1021ZZ-000001058	VAV (Variable Air Volume Boxes)	VAV	12	ET	FL1021ZZ-12-East Side of the Building	ENVIROTECH	LMHS12	N/A

FL1021ZZ-000000810	Variable Frequency Drive	VFD	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	SQUARE D	H10R16D14E07615P16	3141100DBO
FL1021ZZ-000000811	Variable Frequency Drive	VFD	02	MC	FL1021ZZ-02-Mechanical Equipment Room	SQUARE D	H10R16D14E07G15P16F16C12E13	3141100000
FL1021ZZ-000000812	Variable Frequency Drive	VFD	03	MC	FL1021ZZ-03-Mechanical Equipment Room	SQUARE D	H10R16D14E07G15P16F16C12E13	3141100DGO
FL1021ZZ-000000813	Variable Frequency Drive	VFD	04	MC	FL1021ZZ-04-Mechanical Equipment Room	SQUARE D	H10R16D14E07G15P16F16C12E13	3141100DEO
FL1021ZZ-000000814	Variable Frequency Drive	VFD	05	MC	FL1021ZZ-05-Mechanical Equipment Room	SQUARE D	H10R16D14E07G15P16F16C12E13	3141100DEO
FL1021ZZ-000000815	Variable Frequency Drive	VFD	06	MC	FL1021ZZ-06-Mechanical Equipment Room	SQUARE D	H10R16D14E07G15P16F16C12E13	3141100DEO
FL1021ZZ-000000816	Variable Frequency Drive	VFD	07	MC	FL1021ZZ-07-Mechanical Equipment Room	SQUARE D	H10R16D14E07G15P16F16C12E13	3141100DEO
FL1021ZZ-000000817	Variable Frequency Drive	VFD	08	MC	FL1021ZZ-08-Mechanical Equipment Room	SQUARE D	H10R16D14E07G15P16F16C12E13	3141100DEO
FL1021ZZ-000000818	Variable Frequency Drive	VFD	09	MC	FL1021ZZ-09-Mechanical Equipment Room	SQUARE D	H10R16D14E07G15P16F16C12E13	3141100DEO
FL1021ZZ-000000819	Variable Frequency Drive	VFD	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room	DANFOSS DRIVES	VLT AQUA Drive FC 200	3141100DFO
FL1021ZZ-000000820	Variable Frequency Drive	VFD	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room	SQUARE D	H10R16D14E07G15P16F16C12E13	3141100DFO
FL1021ZZ-000000821	Variable Frequency Drive	VFD	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room	SQUARE D	H10R16D14E07G15P16F16C12E13	3141100DFO
FL1021ZZ-000000822	Variable Frequency Drive	VFD	RF	MC	FL1021ZZ-RF-Mechanical Equipment Room	SQUARE D	N/A	N/A
FL1021ZZ-000001059	Voltage Regulator	VLT	GF	EG	FL1021ZZ-GF-Emergency Generator Room	LA MARCHE	A46-6-24V-A1	L-1845-3
FL1021ZZ-000000781	Valves	VLV	GF	MC	FL1021ZZ-GF-Mechanical Equipment Room Domestic Water Pump	WATTS	N/A	1115-3-1291
FL1021ZZ-000000782	Valves	VLV	GF	MC	FL1021ZZ-GF-Mechanical Equipment Room Domestic Water Pump	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000783	Valves	VLV	GF	PL	FL1021ZZ-GF-Parking Lot Center North side of the building.	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000784	Valves	VLV	GF	SP	FL1021ZZ-GF-Sally Port Receiving Sally Port Front of Cargo Elevator	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000785	Valves	VLV	GF	CB-E	FL1021ZZ-GF-Prisoner holding cells and movement areas North-West (Stairwell 2 Ground Level)	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000786	Valves	VLV	GF	CB-E	FL1021ZZ-GF-Prisoner holding cells and movement areas North-West (Stairwell 2 Ground Level)	NOT AVAILABLE	N/A	N/A

FL1021ZZ-000000787	Valves	VLV	GF	CB-E	FL1021ZZ-GF-Prisoner holding cells and movement areas North-West (Stairwell 2 Ground Level)	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000788	Valves	VLV	GF	CB-E	FL1021ZZ-GF-Prisoner holding cells and movement areas North-West (Stairwell 2 Ground Level)	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000789	Valves	VLV	GF	CB-E	FL1021ZZ-GF-Prisoner holding cells and movement areas North-West (Stairwell 2 Ground Level)	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000790	Valves	VLV	GF	CB-E	FL1021ZZ-GF-Prisoner holding cells and movement areas North-West (Stairwell 2 Ground Level)	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000791	Valves	VLV	GF	CB-E	FL1021ZZ-GF-Prisoner holding cells and movement areas North-West (Stairwell 2 Ground Level)	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000792	Valves	VLV	GF	CB-E	FL1021ZZ-GF-Prisoner holding cells and movement areas North-West (Stairwell 2 Ground Level)	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000793	Valves	VLV	GF	CB-E	FL1021ZZ-GF-Prisoner holding cells and movement areas North-West (Stairwell 2 Ground Level)	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000794	Valves	VLV	02	RR	FL1021ZZ-02-Restroom Custodial Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000795	Valves	VLV	03	RR	FL1021ZZ-03-Restroom Custodial Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000796	Valves	VLV	04	RR	FL1021ZZ-04-Restroom Custodial Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000797	Valves	VLV	05	RR	FL1021ZZ-05-Restroom Custodial Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000798	Valves	VLV	06	RR	FL1021ZZ-06-Restroom Custodial Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000799	Valves	VLV	07	RR	FL1021ZZ-07-Restroom Custodial Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000800	Valves	VLV	08	RR	FL1021ZZ-08-Restroom Custodial Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000801	Valves	VLV	09	RR	FL1021ZZ-09-Restroom Grand Jury Room # 1 ceiling	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000802	Valves	VLV	11	RR	FL1021ZZ-11-Restroom Custodial Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000803	Valves	VLV	12	RR	FL1021ZZ-12-Restroom Custodial Room	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000804	Valves	VLV	RF	NT	FL1021ZZ-RF-North	BELIMO	SY3-120MFT	N/A
FL1021ZZ-000000805	Valves	VLV	RF	NT	FL1021ZZ-RF-North	BELIMO	SY3-120MFT	N/A
FL1021ZZ-000000806	Valves	VLV	RF	NT	FL1021ZZ-RF-North	BELIMO	SY3-120MFT	N/A
FL1021ZZ-000000807	Valves	VLV	RF	NT	FL1021ZZ-RF-North	BELIMO	SY3-120MFT	N/A
FL1021ZZ-000000808	Valves	VLV	RF	NT	FL1021ZZ-RF-North	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000000809	Valves	VLV	RF	NT	FL1021ZZ-RF-North	NOT AVAILABLE	N/A	N/A
FL1021ZZ-000001060	Water Heater, Electric	WHT-01	02	RR	FL1021ZZ-02-Restroom Custodial Room	RELIANCE	640DOLNS	A07A131071
FL1021ZZ-000001061	Water Heater, Electric	WHT-01	02	FC	FL1021ZZ-02-Food Service, Break Room Cafeterria	GENERAL ELEC	GE10P6A	GE0399313247
FL1021ZZ-000001062	Water Heater, Electric	WHT-01	05	RR	FL1021ZZ-05-Restroom Custodial Room	RHEEM	RHESPR030-2	RH0999F02552

FL1021ZZ-000001063	Water Heater, Electric	WHT-01	08	RR	FL1021ZZ-08-Restroom Custodial Room	RUDD	PES40-2	RU 0692806778
FL1021ZZ-000001064	Water Heater, Electric	WHT-01	11	RR	FL1021ZZ-11-Restroom Custodial Room	LOCHINVAR	LSK040KK	AD4544978
FL1021ZZ-000001065	Water Treatment (Chemical)	WTM	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room West wall	ADVANTAGE CONTROLS	MCFB-EY	DC-426

Date Run:

7/15/2014 2:19:14 PM

Notes:

Please Update

FL1021ZZ-000000042	Chiller, Centrifugal, water cooled, over 100 tons	CHL-CW2	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	TRANE	CVHE500	L14B00825
FL1021ZZ-000000043	Chiller, Centrifugal, water cooled, over 100 tons	CHL-CW2	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	TRANE	CVHE500	L14B00838
FL1021ZZ-000001065	Water Treatment (Chemical)	WTM	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room West wall	FLOWZONE SERVICES	CT-800	CT-80021010-138
FL1021ZZ-000000408	Motor	MOT	GF	SP	FL1021ZZ-GF-Sally Port Sally Port	MANARAS	OGH	140113044

Please add

	Valves	VLV	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	BRAY	E40-L-18	N/A
	Valves	VLV	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	BRAY	E30-L-17	N/A
	Valves	VLV	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	BRAY	E40-L-18	N/A
	Valves	VLV	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	BRAY	E30-L-17	N/A
	Fan, Axial	FAN-01	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	LOREN COOK COMPANY	1617AFDC	305SFI3414-00/0000701
	Motor Control Center	MCC	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	SIEMENS	N/A	N/A

Please Remove

FL1021ZZ-000000410	Motor Control Center	MCC	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	WESTINGHOUSE	C7F1G104T3V4Y3	PHY32321-1
FL1021ZZ-000000411	Motor Control Center	MCC	GF	CH	FL1021ZZ-GF-Chiller Mechanical Room	WESTINGHOUSE	C7F1G104T3V4Y3	PHY32322-1

Sydney M. Arnovitz United States Courthouse FL0019ZZ O&M, Janitorial, Landscape
301 Simonton St.
Key West, FL 33040
53248 rentable square feet (rsf)

Equipment List by Building and Equipment ID - Detail

Total Record Counts: 78

Building: FL0019ZZ

Equipment ID	Equipment Description	Equipment Type	Floor	Room	Location	Manufacturer	Model No.	Serial No.
FL0019ZZ-AHU-01-005	Air Handling Unit, 3 ton thru 24 ton	AHU-01	01	MC	Floor 01 Mechanical Equipment Room			
FL0019ZZ-AHU-01-AHU1	Air Handling Unit, 3 ton thru 24 ton	AHU-01	02	MC	Floor 02 Mechanical Equipment Room	PETRA	PAHHC50C6	50207/0101/01
FL0019ZZ-AHU-01-AHU3	Air Handling Unit, 3 ton thru 24 ton	AHU-01	02	MC	FLOOR 02 Mechanical Equipment Room	PETRA	PAHHC62C6	50207/0301/01
FL0019ZZ-AHU-01-AHU4	Air Handling Unit, 3 ton thru 24 ton	AHU-01	01	EE	Floor 01 ELECTRICAL ROOM	PETRA	PAHHC150C6	50207/0401/01
FL0019ZZ-AHU-01-AHU5	Air Handling Unit, 3 ton thru 24 ton	AHU-01	MZ	MC	MEZZANINE Mechanical Equipment Room	PETRA	PAHHC100C4	50207/0501/01
FL0019ZZ-ALM-001	Fire Detection and Alarm System	ALM	GF	LB	Ground Floor Lobby			
FL0019ZZ-ALM-002	Fire Detection and Alarm System	ALM	GF	LB	Ground Floor Lobby			
FL0019ZZ-ATS-001	Switch, Automatic Transfer	ATS	B1	CH	Basement, 1st Level Chiller Mechanical Room			
FL0019ZZ-ATS-002	Switch, Automatic Transfer	ATS	B1	CH	Basement, 1st Level Chiller Mechanical Room			
FL0019ZZ-BAS-01-001	Building Automation System, DDC	BAS-01	GF	OF	Ground Floor Office O&M Office			
FL0019ZZ-CHL-CW1-CHL1	Chiller, Centrifugal, water cooled, up to 100 tons	CHL-CW1	BS	CH	BASEMENT Chiller Mechanical Room	TRANE	CVHE028FA4A0 PCE2133K9B4JB A0000000J00G0 00LS00001D10	L05A00521
FL0019ZZ-CRAC-001	Computer Room A.C.1 (CRAC Unit)	CRAC	02	CC	Floor 02 Control Center			
FL0019ZZ-CTR-001	Cooling Tower	CTR	PK	CG	GROUND FLOOR PARKING LOT CAGED AREA	MARLEY	NCCLASS	NC8306AL1SS
FL0019ZZ-DAV-001	Davits/Roof Anchors/Fall Protection	DAV	RF	OT	Roof Outside			
FL0019ZZ-DTT-001	Transformer, Dry	DTT	GF		Ground Floor General Building			
FL0019ZZ-DTT-002	Transformer, Dry	DTT	02	HC	Floor 02 Prisoner holding cells and movement areas			
FL0019ZZ-DTT-003	Transformer, Dry	DTT	02		Floor 02 General Building			
FL0019ZZ-EMG-01-001	Emergency Diesel Generator	EMG-01	GF	PL	GROUND FLOOR PARKING LOT CAGED AREA	Perkins		YB50298*U519811 U*
FL0019ZZ-EPB-001	Panelboard, Power Distribution	EPB	B1	CH	Basement, 1st Level Chiller Mechanical Room			
FL0019ZZ-EWC-001	Drinking Fountain, Packaged	EWC	GF	RR	Ground Floor Restroom			
FL0019ZZ-EWC-002	Drinking Fountain, Packaged	EWC	02	RR	Floor 02 Restroom			
FL0019ZZ-EWC-003	Drinking Fountain, Packaged	EWC	GF	SP	Ground Floor Sally Port			

FL0019ZZ-EXS-001	Exit Signs	EXS	B1	CH	Basement, 1st Level Chiller Mechanical Room			
FL0019ZZ-EXS-002	Exit Signs	EXS	GF	LB	Ground Floor Lobby			
FL0019ZZ-EXS-003	Exit Signs	EXS	PK		Ground Floor Parking Lot			
FL0019ZZ-EXS-004	Exit Signs	EXS	PH	EV	Penthouse Elevator / Mechanical Penthouse			
FL0019ZZ-EXS-005	Exit Signs	EXS	RF		Roof Roof / Roof Installed Item			
FL0019ZZ-EXS-006	Exit Signs	EXS	01		Floor 01 General Building			
FL0019ZZ-EXS-007	Exit Signs	EXS	01		Floor 01 General Building			
FL0019ZZ-EXS-008	Exit Signs	EXS	01	OF	Floor 01 Office			
FL0019ZZ-EXS-009	Exit Signs	EXS	02	JC	Floor 02 Judges chambers			
FL0019ZZ-EXS-010	Exit Signs	EXS	02	CB	Floor 02 Cell Block			
FL0019ZZ-FEX-001	Fire Extinguishers	FEX	B1	MC	Basement, 1st Level Mechanical Equipment Room			
FL0019ZZ-FEX-002	Fire Extinguishers	FEX	B2	MC	Basement, 2nd Level Mechanical Equipment Room			
FL0019ZZ-FEX-003	Fire Extinguishers	FEX	PH	EV	Penthouse Elevator / Mechanical Penthouse			
FL0019ZZ-FEX-004	Fire Extinguishers	FEX	GF	SP	Ground Floor Sally Port			
FL0019ZZ-FEX-005	Fire Extinguishers	FEX	PK		Floor 01 Parking			
FL0019ZZ-FEX-006	Fire Extinguishers	FEX	01	OF	Floor 01 Office			
FL0019ZZ-FEX-007	Fire Extinguishers	FEX	01	SR	Floor 01 Shipping and Receiving			
FL0019ZZ-FEX-008	Fire Extinguishers	FEX	01	MC	Floor 01 Mechanical Equipment Room			
FL0019ZZ-FEX-009	Fire Extinguishers	FEX	02	HC	Floor 02 Prisoner holding cells and movement areas			
FL0019ZZ-FEX-010	Fire Extinguishers	FEX	02	CF	Floor 02 Conference Room			
FL0019ZZ-FEX-011	Fire Extinguishers	FEX	02	CR	Floor 02 Courtroom			
FL0019ZZ-FEX-012	Fire Extinguishers	FEX	02	CB	Floor 02 Cell Block			
FL0019ZZ-FEX-013	Fire Extinguishers	FEX	GF	LB	Ground Floor Lobby			
FL0019ZZ-FEX-014	Fire Extinguishers	FEX	02	MC	Floor 02 Mechanical Equipment Room			
FL0019ZZ-FEX-015	Fire Extinguishers	FEX	02	CC	Floor 02 Control Center Marshal Security room			
FL0019ZZ-FNG-001	Fences and Gates	FNG	PK		Ground Floor Parking Lot			
FL0019ZZ-FNG-002	Fences and Gates	FNG	PK		Ground Floor Parking Lot exit			
FL0019ZZ-FSP-01-001	Wet-Pipe Sprinkler Systems	FSP-01	GF	MC	Ground Floor Mechanical Equipment Room			
FL0019ZZ-MCC-001	Motor Control Center	MCC	B1	EE	Basement, 1st Level Electrical Equipment Room			
FL0019ZZ-PAG-001	Parking Arm Gates	PAG	PK	EN	Ground Floor Parking entrance			
FL0019ZZ-PMP-001	Pump, Chemical Feed	PMP	BS	CH	BASEMENT Chiller Mechanical Room	LMI	DC4500-11A	07102449286-1
FL0019ZZ-PMP-02-001	Pump, Chilled Water	PMP-02	BS	CH	BASEMENT Chiller Mechanical Room	AURORA		
FL0019ZZ-PMP-02-002	Pump, Chilled Water	PMP-02	BS	CH	BASEMENT Chiller Mechanical Room	AURORA		
FL0019ZZ-PMP-06-001	Pump, Condenser	PMP-06	BS	CH	BASEMENT Chiller Mechanical Room	AURORA	D5-1171532-1	
FL0019ZZ-PMP-06-002	Pump, Condenser	PMP-06	BS	CH	BASEMENT Chiller Mechanical Room	AURORA	D51171532-2	

FL0019ZZ-RTU-001	Package Unit, Air Cooled	RTU	GF	SR	Ground Floor Shipping and Receiving mail room			
FL0019ZZ-SMP-SP1	Sump Pump	SMP	BS	CH	BASEMENT Chiller Mechanical Room	AURORA	D5-1171661-1	
FL0019ZZ-SMP-SP2	Sump Pump	SMP	BS	CH	BASEMENT Chiller Mechanical Room	AURORA	D5-1171661-2	
FL0019ZZ-SWB-001	Switchboard, Electrical	SWB	BS	CH	BASEMENT Chiller Mechanical Room	CUTLER HAMMER	1495D80G73	
FL0019ZZ-TNK-01-001	Tank, Size=500, Contents: Diesel, Used for:	TNK-01	01	TK		AST - class C		
FL0019ZZ-TNK-01-002	Tank, Fuel	TNK-01	B1	CH	Basement, 1st Level Chiller Mechanical Room			
FL0019ZZ-UPS-001	UPS (Uninterruptable Power Supply)	UPS	02	CC	Floor 02 Control Center			
FL0019ZZ-VAV-001	VAV (Variable Air Volume Boxes)	VAV	01	CB	Floor 01 Prisoner holding cells and movement areas			
FL0019ZZ-VAV-002	VAV (Variable Air Volume Boxes)	VAV	01	OF	Floor 01 Office			
FL0019ZZ-VAV-003	VAV (Variable Air Volume Boxes)	VAV	02	HC	Floor 02 Prisoner holding cells and movement areas			
FL0019ZZ-VAV-004	VAV (Variable Air Volume Boxes)	VAV	02	CC	Floor 02 Control Center			
FL0019ZZ-VAV-005	VAV (Variable Air Volume Boxes)	VAV	02	JC	Floor 02 Judges chambers			
FL0019ZZ-VAV-006	VAV (Variable Air Volume Boxes)	VAV	02	CR	Floor 02 Courtroom			
FL0019ZZ-VAV-007	VAV (Variable Air Volume Boxes)	VAV	02	CR	Floor 02 Courtroom			
FL0019ZZ-VFD-002	Variable Frequency Drive	VFD	01	MC	Floor 01 Mechanical Equipment Room			
FL0019ZZ-VFD-003	Variable Frequency Drive	VFD	01	MC	Floor 01 Mechanical Equipment Room			
FL0019ZZ-VFD-004	Variable Frequency Drive	VFD	02	MC	Floor 02 Mechanical Equipment Room			
FL0019ZZ-VFD-005	Variable Frequency Drive	VFD	02	MC	Floor 02 Mechanical Equipment Room			
FL0019ZZ-VFD-AHU5	Variable Frequency Drive	VFD	MZ	MC	MEZZANINE Mechanical Equipment Room	TECO	PA73002010-N1	B7A801-005
FL0019ZZ-WHT-01-001	Water Heater, Electric	WHT-01	B1	MC	Basement, 1st Level Mechanical Equipment Room			
FL0019ZZ-WTM-001	Water Treatment (Chemical)	WTM	B1	MC	Basement, 1st Level Mechanical Equipment Room			

Date Run:

9/26/2014 10:54:09 AM