AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE	OF	PAGES
J	1		12

2. AMENDMENT/MODIFICATION NUMBER	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQUISITION NUMBER	5. PROJECT NUMBER *(If applicable)*
0001	09 SEP 2026		

6. ISSUED BY	CODE	7. ADMINISTERED BY *(If other than Item 6)*	CODE
W07V ENDIST N ORLEANS KO CONTRACTING DIVISION, 7400 LEAKE AVE NEW ORLEANS, LA 70118-3651 UNITED STATES JASON MEYERS, EMAIL: JASON.B.MEYERS@USACE.ARMY.MIL TELEPHONE: (504) 862-1016	W912P8	SCD: PAS:	

8. NAME AND ADDRESS OF CONTRACTOR *(Number, street, county, State and ZIP Code)*	(X)	9A. AMENDMENT OF SOLICITATION NUMBER
	☒	W912P826QA034
		9B. DATED *(SEE ITEM 11)*
		31 AUG 2026
	☐	10A. MODIFICATION OF CONTRACT/ORDER NUMBER
		10B. DATED *(SEE ITEM 13)*
CODE / FACILITY CODE		

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☒ is extended. ☐ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:
(a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted;
or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER.
If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA *(If required)*

SEE SECTION G - CONTRACT ADMINISTRATION DATA

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.

CHECK ONE	
☐	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: *(Specify authority)* THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.
☐	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES *(such as changes in paying office, appropriation data, etc.)* SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
☐	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
☐	D. OTHER *(Specify type of modification and authority)*

E. IMPORTANT: Contractor ☐ is not ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (*Organized by UCF section headings, including solicitation/contract subject matter where feasible.)*

Revised SOW.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER *(Type or print)*		16A. NAME AND TITLE OF CONTRACTING OFFICER *(Type or print)*	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
_____ *(Signature of person authorized to sign)*		_____ *(Signature of Contracting Officer)*	

Previous edition unusable

STANDARD FORM 30 (REV. 11/2016)
Prescribed by GSA FAR (48 CFR) 53.243

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

Solicitation/Contract Form

The following changes have been made:

INFORMATION	FROM	TO
Response Due Time	02:00 PM	01:00 PM
Response Due Date	04 Sep 2026	14 Sep 2026

Description/Specifications/Statement of Work

Miscellaneous text in this section has been modified from:

USACE-MVN-OPERATIONS DIV. 26 Feb 2026

Technical Support Branch Structures Support Function

MOBILE OFFICE RENTAL ("RANGER OFFICE") BONNET CARRE SPILLWAY, ST. CHARLES PARISH, LA

USACE-MVN-OPERATIONS DIV. June 29, 2021

Technical Support Branch Structures Support Function

SPECIFICATIONS

1. SCOPE OF WORK: The Contractor shall provide all labor, supervision, tools, materials, equipment,

and transportation to supply Bonnet Carre' Spillway Park Rangers and Natural Resource Management

Specialists with a temporary mobile office trailer in accordance with these specifications herein. In addition, the contract shall be responsible for connecting the trailer's electrical, water and sewer lines to sites existing utilities. The contract will be for one base year with four option years. The Bonnet Carre Spillway is located in Norco, Louisiana.

2. RENTAL DESCRIPTION/SPECIFICATIONS:

2.1 BUILDING SIZE and FEATURES:

a. Single-Wide.

b. Box Size: Width 12 ft, Length 56 ft. to 60 ft, Height 8 ft.

c. Two lockable steel exterior doors, with steps for access.

d. Sliding windows.

e. Fluorescent or LED lighting

2.2 CLIMATE CONTROL:

a. Central electric heating and AC with thermostat.

b. Insulated windows, ceilings, and floor.

c. New air intake filter(s) shall be fitted at delivery.

2.3 FURNISHINGS:

a. Building is to be fitted with 2 side offices and one main office area.

b. Each side office shall include two built-in or 2 moveable desk workstations per office.

c. Each workstation will be provided with a lap drawer and a minimum of 2 desk type drawers, 2 separate power outlets, and a wall shelf.

d. The open office area shall contain 1 moveable desk or workstation. A conference area table with 10 chairs shall be included in the open office area.

e. One fully useable, lockable closet (not shared with a water heater).

f. One bathroom with sink, toilet, and cabinet.

2.4 BUILDING CONDITION:

a. The mobile office shall be in new or near new condition and less than 2 years old.

b. The contractor shall provide proof of manufacture or original delivery.

c. Prior to shipment, the Government shall approve the mobile office trailer to verify that it meets the specified requirements and condition.

3. PERSONNEL:

a. The contractor shall furnish all personnel to accomplish work required by this contract including delivery, installation, connections, and removal. Periodic cleaning, sanitation, or garbage removal will not be required under this contract.

b. The contractor shall provide periodic maintenance to the trailer including replacement of floor tiles, ceiling panels, door adjustments and repair any leaks or air conditioner/heater repairs.

4. DELIVERY & INSTALLATION: Delivery and installation shall be coordinated with the Bonnet Carre'

Spillway Project Manager. Delivery and installation include as a minimum, the following items:

Tie-downs

Skirting "Vinyl"

Hitch Removal

Block and level

Step installation

Delivery freight

AC/Heater check.

Utility installations / testing

5. CONNECTIONS:

5.1 ELECTRICAL:

Provide the services of a qualified licensed electrician to connect the office trailer to the available electrical box power source. Connections to any communication lines are the responsibility of the Government.

5.2 WATER SUPPLY, SEWAGE and WATER DRAINAGE:

The contractor shall connect the office trailer to an available water supply and an on-site sewage holding tank/treatment plant.

6. INSPECTION AND ACCEPTANCE:

a. The office trailer will be inspected upon delivery to ensure compliance with the contract specifications.

b. A final inspection and formal acceptance of the office trailer will be conducted once all connections are complete.

c. Inspection will be conducted under the general direction of the Bonnet Carre' Spillway Project Manager.

7. RETURN FRIEGHT - TRAILER REMOVAL:

Removal of the office trailer is to be accomplished at end of lease period or cancellation of contract. Return freight and trailer removal includes the following items:

Removal of connections above

Removal of tie-downs

Skirt removal

Hitch installation

Tear down

Return freight

8. UTILITIES:

The Government shall make all reasonably required amounts of utilities available to the Contractor from existing outlets and supplies. The Contractor shall carefully conserve any utilities furnished without charge. Any additional utilities required shall be furnished by the Contractor.

9. RIGHTS OF ENTRY:

All on-site work shall be performed on a U.S. Government owned reservation. Rights of entry for on-site construction purposes will be furnished by the Government, without cost to the Contractor. Upon completion of the contract work, any right of entry provided by the Government will be restored to a condition satisfactory to the Contracting Officer.

10. GENERAL SAFETY PROVISIONS:

The Contractor shall take measures to ensure safety and health requirements comply with EM 385-1-1

in performing work under this Contract. Contractor shall meet with the Contracting Officer, or designated Government Representative, to develop a mutual understating relative to administration

of the safety plan.

Contractor is subject to applicable Federal, State, and local laws, regulations, ordinances, codes, and orders relating to safety and health in effect on the date of this Contract. During the performance of work under this Contract, the Contractor shall comply with procedures prescribed for

control and safety of persons visiting the project site. Contractor is responsible for his personnel and for familiarizing each of his/her sub-contractors with safety requirements. Contractor shall advise the Contracting Officer, or designated Government Representative, of any special safety restrictions he/she has established while performing work under this Contract so onsite Government personnel can be notified of these restrictions.

11. PERIOD OF PERFORMANCE:

The Contractor shall deliver the trailer and complete all connections in accordance with these specifications within 30 days after Notice to Proceed.

12. CONTRACT DURATION:

The base contract shall be for one-year with a four-year option.

13. DELIVERY LOCATION/LOCATION OF WORK:

The trailer shall be delivered and setup at the Bonnet Carre Spillway's office reservation located at the address specified below:

U.S. Army Corps of Engineers Bonnet Carre Spillway

16302 River Rd.

Norco, La 70079

14. INVOICING:

Submit electronic monthly invoices to the Bonnet Carre' Spillway Project Manager, and mail the original invoice to:

USACE - FINANCE CENTER 5722 INTEGRITY DRIVE

MILLINGTON, TN 38054-5005

15. BONNET CARRE' SPILLWAY PROJECT MANAGER:

John Fogarty - (504)628-5054

16. TECHNICAL POC:

Stephen Dalferes - (504)862-1815

17. SUSTAINABLE ACQUISITION:

In accordance with USACE regulations, the following sustainable acquisition requirements are applicable to this procurement.

18. EPA DESIGNATED (CPG):

Under the Comprehensive Procurement Guidelines (CPG) program, the Environmental Protection Agency

(EPA) designates products that are or can be made with recovered materials, and recommends practices for buying these products. Any designated product that is being offered or supplied under this contract shall meet the minimum recommended content levels as identified under the CPG program. Visit http://www.epa.gov/epawaste/conserve/tools/cpg/products for a complete list of designated products and the associated recommended

content levels. Offerors must be able to demonstrate that each offered product meets minimum content levels upon request.

19. BIO-BASED:

The United States Department of Agriculture (USDA) designates certain biobased products for federal

procurement and specifies minimum biobased content levels for those products. Any designated product that is being offered or supplied under this contract shall meet USDA BioPreferred's minimum biobased content level. Visit the BioPreferred web site for the complete list of designated products and the associated minimum biobased content level requirements.

20. SECURITY:

Pre-screen candidates using E-Verify Program. "The Contractor must pre-screen Candidates using the

E-verify Program (http://www.uscis.gov/e-verify) website to meet the established employment eligibility requirements. The Vendor must ensure that the Candidate has two valid forms of Government issued identification prior to enrollment to ensure the correct information is entered into the E-verify system. An initial list of verified/eligible Candidates must be provided to the COR no later than 3 business days after the initial contract award." *When contracts are with individuals, the individuals will be required to complete a Form I-9, Employment Eligibility

Verification, with the designated Government representative. This Form will be provided to the

Contracting Officer and shall become part of the

official contract file.

To:

9 SEPTEMBER 2026

STATEMENT OF WORK

Mobile Office Rental ("Ranger Office")

Bonnet Carre Spillway, St. Charles Parish, LA

1. GENERAL: The purpose of this contract is to furnish a mobile office trailer to serve as a temporary office facility for the Bonnet Carre' Spillway Park Rangers and Natural Resource Management Specialists. The contract will be for one base year and four option years. The Bonnet Carre Spillway is located in Norco, Louisiana.

2. RENTAL DESCRIPTION/SPECIFICATIONS:

A. Existing Trailer Rental Option:

- An existing temporary trailer is located at the project site. The bidders may pursue the option of utilizing the existing trailer for this contract in lieu of furnishing a new trailer. Existing trailer is owned by BOXX Modular Inc., Geismar, Louisiana

B. New Trailer Rental Option:

BUILDING SIZE and FEATURES:

- Single-Wide. Box Size: Width 12 ft, Length 56 ft. to 60 ft, Height 8 ft.

- Two lockable steel exterior doors, with steps for access.

- Sliding windows.

- Fluorescent or LED lighting

CLIMATE CONTROL: Central electric heating and AC with thermostat; Insulated windows, ceilings and floor. New air intake filter(s) shall be fitted at delivery.

FURNISHINGS:

- Building is to be fitted with 2 side offices and one main office area. Each side office shall include two built-in or 2 moveable desk workstations per office. Each workstation will be provided with a lap drawer and a minimum of 2 desk type drawers, 2 separate power outlets, and a wall shelf.

- The open office area shall contain 1 moveable desk or workstation. A conference area table with 10 chairs shall be included in the open office area.

- One fully useable, lockable closet (not shared with a water heater).

- One bathroom with sink, toilet and cabinet.

BUILDING CONDITION: The mobile office shall be in new or near new condition and less than 2 years old. The contractor shall provide proof of manufacture or original delivery. Prior to shipment, Government shall approve the mobile office trailer to verify condition.

3. PERSONNEL: The contractor shall furnish all personnel to accomplish work required by this contract including delivery, installation, connections and removal. Periodic cleaning, sanitation, or garbage removal will not be required under this contract.

The contractor shall provide periodic maintenance to the trailer including replacement of floor tiles, ceiling panels, door adjustments and repair any leaks or air conditioner/heater repairs.

4. DELIVERY & INSTALLATION: Delivery and installation shall be coordinated with the Bonnet Carre' Spillway Project Manager, 16302 River Road, Norco, Louisiana 70079. Delivery and installation include as a minimum, the following items:

- Tie-downs

- Skirting "Vinyl"

- Hitch Removal

- Block and level

- Step installation

- Delivery freight

- AC/Heater check.

- Utility installations / testing

5. CONNECTIONS:

ELECTRICAL - Provide the services of a qualified electrician to connect the trailer to the available electrical box power source. Connections to any communication lines are the responsibility of the Corps of Engineers.

WATER SUPPLY, SEWAGE and WATER DRAINAGE - The contractor shall connect the trailer to an available water supply and an on-site sewage holding tank/treatment plant.

6. RETURN FRIEGHT - TRAILER REMOVAL: Removal of the office trailer is to be accomplished at end of lease period or cancellation of contract. Return freight and trailer removal includes the following items:

- Removal of connections above

- Removal of tie-downs

- Skirt removal

- Hitch installation

- Tear down

- Return freight

7. INVOICING:

Submit electronic monthly invoices to the Bonnet Carre' Spillway Project Manager, and mail the original invoice to:

USACE - FINANCE CENTER

5722 INTEGRITY DRIVE

MILLINGTON, TN 38054-5005