USACE-MVN-OPERATIONS DIV. 26 Feb 2026
Technical Support Branch
Structures Support Function

MOBILE OFFICE RENTAL
(“RANGER OFFICE”)
BONNET CARRÉ SPILLWAY,
ST. CHARLES PARISH, LA

CLIN	Description	QTY	Unit	Quote	
				Price	Total
0001	Delivery, Set-up & Connect Utilities	1	Job	$	$
0002	Base Year Lease	12	Month	$	$
0003	Utility Disconnection & Removal	1	Job	$	$
				Subtotal	$
0004	Option Year 1	12	Month	$	$
0005	Option Year 2	12	Month	$	$
0006	Option Year 3	12	Month	$	$
0007	Option Year 4	12	Month	$	$
				TOTAL	$

STATEMENT OF WORK

Mobile Office Rental ("Ranger Office")

Bonnet Carré Spillway, St. Charles Parish, LA

1. GENERAL: The purpose of this contract is to furnish a mobile office trailer to serve as a temporary office facility for the Bonnet Carre' Spillway Park Rangers and Natural Resource Management Specialists. The contract will be for one base year and four option years. The Bonnet Carré Spillway is located in Norco, Louisiana.

2. RENTAL DESCRIPTION/SPECIFICATIONS:

A. Existing Trailer Rental Option:

- An existing temporary trailer is located at the project site. The bidders may pursue the option of utilizing the existing trailer for this contract in lieu of furnishing a new trailer. Existing trailer is owned by BOXX Modular Inc., Geismar, Louisiana

B. New Trailer Rental Option:

BUILDING SIZE and FEATURES:
- Single-Wide. Box Size: Width 12 ft, Length 56 ft. to 60 ft, Height 8 ft.
- Two lockable steel exterior doors, with steps for access.
- Sliding windows.
- Fluorescent or LED lighting

CLIMATE CONTROL: Central electric heating and AC with thermostat; Insulated windows, ceilings and floor. New air intake filter(s) shall be fitted at delivery.

FURNISHINGS:
- Building is to be fitted with 2 side offices and one main office area. Each side office shall include two built-in or 2 moveable desk workstations per office. Each workstation will be provided with a lap drawer and a minimum of 2 desk type drawers, 2 separate power outlets, and a wall shelf.
- The open office area shall contain 1 moveable desk or workstation. A conference area table with 10 chairs shall be included in the open office area.
- One fully useable, lockable closet (not shared with a water heater).
- One bathroom with sink, toilet and cabinet.

BUILDING CONDITION: The mobile office shall be in new or near new condition and less than 2 years old. The contractor shall provide proof of manufacture or original delivery. Prior to shipment, Government shall approve the mobile office trailer to verify condition.

3. PERSONNEL: The contractor shall furnish all personnel to accomplish work required by this contract including delivery, installation, connections and removal. Periodic cleaning, sanitation, or garbage removal will not be required under this contract.

The contractor shall provide periodic maintenance to the trailer including replacement of floor tiles, ceiling panels, door adjustments and repair any leaks or air conditioner/heater repairs.

4. DELIVERY & INSTALLATION: Delivery and installation shall be coordinated with the Bonnet Carre' Spillway Project Manager, 16302 River Road, Norco, Louisiana 70079. Delivery and installation include as a minimum, the following items:

- Tie-downs
- Skirting "Vinyl"
- Hitch Removal
- Block and level
- Step installation
- Delivery freight
- AC/Heater check.
- Utility installations / testing

5. CONNECTIONS:

ELECTRICAL – Provide the services of a qualified electrician to connect the trailer to the available electrical box power source. Connections to any communication lines are the responsibility of the Corps of Engineers.

WATER SUPPLY, SEWAGE and WATER DRAINAGE – The contractor shall connect the trailer to an available water supply and an on-site sewage holding tank/treatment plant.

6. RETURN FRIEGHT – TRAILER REMOVAL: Removal of the office trailer is to be accomplished at end of lease period or cancellation of contract. Return freight and trailer removal includes the following items:

- Removal of connections above
- Removal of tie-downs
- Skirt removal
- Hitch installation
- Tear down
- Return freight

7. INVOICING:
Submit electronic monthly invoices to the Bonnet Carre' Spillway Project Manager, and mail the original invoice to:

USACE – FINANCE CENTER
5722 INTEGRITY DRIVE
MILLINGTON, TN 38054-5005